













Methuen's Colonial Library



## THE COMPLETE PHOTOGRAPHER

**UNIFORM WITH THIS VOLUME**

**THE COMPLETE MOTORIST**

**THE COMPLETE GOLFER**

**THE COMPLETE CRICKETER**

**THE COMPLETE RUGBY FOOTBALLER**

**THE COMPLETE OARSMAN**

**THE COMPLETE LAWN TENNIS PLAYER**

**THE COMPLETE SHOT**

**THE COMPLETE MOUNTAINEER**

**THE COMPLETE COOK**

# THE COMPLETE PHOTOGRAPHER

BY

R. CHILD BAYLEY

EDITOR OF "PHOTOGRAPHY"

AUTHOR OF "PHOTOGRAPHY IN COLOURS," ETC.

WITH OVER ONE HUNDRED ILLUSTRATIONS

THIRD EDITION, REVISED

METHUEN & CO.  
36 ESSEX STREET W.C.  
LONDON

*Colonial Library*

*First Published* . . . . . *October 1906.*  
*Second Edition* . . . . . *March 1907.*  
*Third Edition, Revised* . . . . . *June 1908.*  
~~Fourth Edition~~ . . . . . *1909.*  
*Fourth Edition*

## PREFACE

NOBODY who has once come under the spell of the camera, and has so far penetrated into the mysteries of photography as to be able to expose with a reasonably quiet conscience as to the ultimate nature of his negatives, can ever thereafter free himself completely from its fascination. As a hobby, its claims over nearly all others are twofold. With fresh subjects it is forever fresh, and its pursuit is as delightful abroad as at home. I have been under that spell for more than twenty years, but my camera is as good a companion as ever, and photography is as entertaining in 1906 as it was in 1885. And incalculably easier also. I shall be glad if I am able to pass on some of the pleasure to fellow-photographers, or to incite others to enjoy it.

In "The Complete Photographer" I have made no attempt to compete with the many books on photography that have already been published. These, in the main, divide themselves into two classes: scientific treatises upon the principles underlying the practice, and elaborated instruction manuals—"how-to-do" books, in short. Without going so far as to omit formulæ altogether, they will be found to be very few, and then only such as are not dealt with in the maker's instructions enclosed in every box of plates and packet of paper. Too many have stuck hopelessly amongst prescriptions, going from one to the other in the hope of finding some magic fluid that shall dissolve all the obstacles in their path, not realizing that it is not the formula but its use that is at fault. It is their application to



photography that has formed my topic, and in that respect I hope "The Complete Photographer" may find a place on the shelves of its namesakes.

I owe much on the subject of colour-photography to the help of Sir William Abney, which of late years has had so large a share of his attention. General Waterhouse I have to thank for many valuable suggestions and for revising the chapter on the Evolution of Photography, and Mr. Mummery for an account of gum-bichromate as he works it. M. Demachy of Paris, and my friend Mr. Stieglitz of New York, greatly helped me on the subject of pictorial photography. Besides these acknowledgments, I have to thank the many workers, some personal friends, others known to me only by name, but all showing that friendly readiness to help, which I venture to think is one of the results of the practice of photography, who have enabled me to illustrate the book with so choice a collection of pictures, representative, as far as is possible within its limits, of photography as an art.

R. C. B.

THE TEMPLE, E.C.

*August, 1906*

## NOTE TO THE THIRD EDITION

ADVANTAGE has been taken of the rapid exhaustion of two editions, to bring the third up to date, and it is significant of the rate of photographic progress that this has involved considerable alteration, although the book is less than two years old. Ozobrome, Bromoil, Carbograph, the Autochrome plate, and lastly the Donisthorpe process are amongst the additions, while those parts which refer to the older methods have come in for revision in the light of later knowledge.

R. C. B.

*April, 1908*

# CONTENTS

## CHAPTER I

### THE EVOLUTION OF PHOTOGRAPHY

	PAGE
The twofold nature of photography—Roger Bacon's speculum—Barbaro's first camera obscura with lens—Marshall's sciopticks—Chester More Hall and the achromatic lens—The legend of Fabricius—Schulze discovers the sensitiveness of silver nitrate to light—Beccari and horn silver—Charles the aéronaut and the alleged silhouettes—The Wedgwood circle—The elder Niepce and bitumen—Daguerre discovers daguerreotype—Talbot—Photography an accomplished fact—Wet collodion—The first dry plates—Developments with bichromated gelatine—Willis's platinotype—Vogel discovers orthochromatism—The gelatine dry plate—Bromide paper and P.O.P.—The first Kodak—Celluloid film—The evolution of the modern lens . . . . .	I

## CHAPTER II

### THE CAMERA

The camera and lens separately selected—The camera in outline—Rigidity the first essential—Testing for light-tightness—Ghosts—Stray light in the camera—The rising, falling, and cross front—The different forms of rising front compared—The camera extension—Focussing methods—The swing back—The reversing back—The ground glass—Dark slides—Carriers—Metal dark slides—The Mackenzie-Wishart slides—Magazines and changing boxes—Film carriers—The Premo Film Pack—Roll holders—Stands—Studio stands—Tripods—Sizes of plates—Choosing a camera—The degree of extension needed—Large direct work <i>v.</i> small work enlarged—Patterns of cameras—Dust in the camera—Care of the camera . . . . .	27
---	----

## CHAPTER III

### THE LENS IN PRINCIPLE

The myth of the wonderful lens—Fancy prices for lenses—The description of lenses—Focus and its measurement—Principal focus—Back focus—The stop—Systems of marking stops—Stops and exposure—Effective aperture—Selecting a lens—Defects—Striæ—Centring—Covering and defining power—Curvature of the field—Astigmatism—Curvilinear distortion—Spherical aberration—Flare spot—Achromatism—The fallacy of examples of work . . . . .	42
---	----

## CHAPTER IV

## PINHOLE 'PHOTOGRAPHY

Pinhole work—The character of the definition—Making pinholes—Measuring them—The sizes of needles—The camera extension—Arranging the subject—Over-exposure possible—Working out the exposure—Some advantages of pinhole work . . . . .	PAGE 56
---	------------

## CHAPTER V

## THE DRAWING OF A PHOTOGRAPH

No essential difference in perspective between a photograph and a painting—View point the ruling condition—Impossible view points—Pugin—Wide angles suggest distortion—Suitable lenses to avoid the appearance of strained perspective—The centre of the picture plane—Different appearances from the same standpoint—Plane perspective—Panoramic or cylindrical perspective . . . . .	61
--	----

## CHAPTER VI

## THE SELECTION OF A LENS

The uncorrected single lens—Corrected single lenses—Rectilinears and symmetricals—The wide-angle rectilinear—The advantages of the anastigmat—The Petzval portrait lens—Dallmeyer's modification; with the arrangement for diffusion of focus—Abbe and Schott and the Jena glasses—Anastigmats—Costly lenses—A nocturnal expedition—The Grün lens—The Hypergon—Telephotographic lenses—The Adon—The Dallmeyer-Bergheim lenses for pictorial work . . . . .	68
--	----

## CHAPTER VII

## THE LENS IN USE

The portrait lens—Single lenses—Using half a doublet lens—"Convertible" anastigmats of two and three foci—Rectilinears—The value of stops—The importance of parallelism—Focussing from the back or front—Copying—Depth of focus—Selection of a stop—Focussing landscapes—Interiors—Focussing by scale—Copying to scale . . . . .	81
--	----

## CHAPTER VIII

## PLATES AND FILMS

Glass v. Celluloid—Paper for negative work—The Cristoid film—Commercial plates, British and foreign—Different kinds of the same make—High rapidity—Orthochromatic plates—Halation, its cause—Prevention—The manufacture of caramel—Development and halation—All halation not a defect . . . . .	88
---	----

# CONTENTS

ix

## CHAPTER IX THE DARK ROOM

	PAGE
The dark room should be a room, but not dark—Necessity for occasional daylight—Illumination—Light filters—Coloured glass—The "Geka" filters—Light for different purposes—For orthochromatic plates—Fabrics—Testing the light—The sink and water supply—Splash preventers—Shelves—Dishes, porcelain or otherwise—For large work—Measures and scales—A light-tight drawer . . . . .	97

## CHAPTER X EXPOSURE

Gradation the test of exposure—Hurter and Driffield's "perfect negative"—The latitude in plates—Over-exposure at first only causes fog—The factors which influence exposure—Strength of light—The influence of the lens—The speed of plates—The Hurter and Driffield, Watkins and Wynne numbers—Their translation—The subject—Exposures indoors—Meters and tables—The Actinograph—The Watkins meter—The secret of success with the Watkins meter—Exposures in sunny climes—A little haze no drawback	109
--	-----

## CHAPTER XI DEVELOPMENT

The latent image, theory and practice—The speed of plates considered a matter of development—Control in development—The Kodak developing machine—The appearance of the picture—The problem, how far to develop—Solved by inspection—By the Watkins method—By time—Developers—Removing the backing—Fixing—Acid hypo baths—Washing—Hypo eliminators—The ideal washer—Varnishing . . . . .	123
---	-----

## CHAPTER XII INTENSIFICATION AND REDUCTION

Intensification—Different processes required by different forms of thinness—Fog—Different reduction methods—Wellington's silver process—Mercury-ammonia—Mercury-ferrous-oxalate—Mercuric iodide—Monckhoven's intensifier—Sanzol—Ammonium persulphate—Ferricyanide and hypo—Namias' permanganate reducer—All such processes are only makeshifts .	142
--	-----

## CHAPTER XIII THE HAND-CAMERA

Detective cameras—Distinctive features of hand-camera work—Focussing devices—Depth of focus—Infinity—Magnifiers—Finders—Shutters—Efficiency in shutters—Control of speed—Levels—Plate-changing mechanism—Dark slides—Films—Daylight loading—The Kodak—Holding the camera—Reflector cameras—Estimating distance—Pictorial photography and the hand-camera—The exposure problem—Boats—Street scenes—"Press-the-button" photographers . . . . .	147
--	-----

## CHAPTER XIV

## THE PRINT

P.O.P.—Sensitiveness—Most suitable negatives—Vignetting—Washing and toning—Separate or combined baths—Self-toning papers—Double tones—Developing partially printed P.O.P.—Platinum toning—Fixing—Washers—Squeegeeing—Mounts—Dry mounting—Masking—Wasted advice . . . 174

## CHAPTER XV

## PLATINUM PRINTING

Simplicity of the process—Care of the paper—Damp—Artificial light for printing—Suitable negatives—Development—Warm tones—The acid baths—Development with glycerine—Permanence—Gold intensified platinum prints—Packham's process—Restoring discoloured prints—Printing on fabrics—Defects . . . . . 192

## CHAPTER XVI

## THE CARBON PROCESS

Tissue—The necessity for transferring—Ready sensitized tissue—Its storage—Measuring the printing—Actinometers—Sensitizing tissue—Bennett's formula—Drying tissue—The safe edge—Development—Single transfer—Stripping negatives—Double transfer—Double printing—Spotting—Carbon transparencies—Bichromate poisoning—Ozotype—Gum-bichromate—Mr. Mummery's method—Multiple gum—Single coatings—Gum ozotype . . . 206

## CHAPTER XVII

## BROMIDE PAPERS

Machine-printed bromides—Qualities of paper—Exposing—Gauging exposures—Development—Lighting the dark room—Developer formulæ—Washing—Carbograph—Gaslight papers—Toning—Hypo-alum—The Blake-Smith process—Intensifying bromide prints—Ferguson's copper toning—Uranium toning—Blue tones—Ozobrome . . . . . 242

## CHAPTER XVIII

## ENLARGING, REDUCING, SLIDE MAKING

Enlarging—Illumination of the negative—Diffusers and condensers—The optical arrangements—Daylight—Curing distortion—Exposing on bromide paper—On dry plates—Developing—Slide making—By contact—A lantern-slide printing frame—Slide cameras—Development—For warm tones—Intensifying slides—Clouds—Dodging slides—Mounting and spotting—Masking—The lantern screen—Small displays . . . . . 254

# CONTENTS

xi

## CHAPTER XIX

### ORTHOCHROMATIC AND THREE-COLOUR PHOTOGRAPHY

PAGE

Insensitiveness to yellow and red not altogether an evil—Colour contrast—Pure and impure colours—Two chief classes of orthochromatic plates—Light filters—Adapting them to plates—Dyed films—Measuring the effect of light filters—Colour photography—The Lipmann process—What are not colour photographs—Colour vision—The Young-Helmholtz theory—Three-colour work—Direct processes—The Autochrome—The preparation of the starch grain—Development and reversal—Copying autochromes—Uto paper . . . . . 275

## CHAPTER XX

### DODGING AND "FAKING"

Selective focussing—Physical reduction—Baskett's reducer—The use of matt varnish—Work on the negative—Sensational effects—Printing in clouds—Work on enlarged negatives—A printing board—The Cherrill frame—Spotting—Sunning down—Softening definition—Modifications when enlarging—Combination printing—Retouching—Vignetting by reduction—Guide prints—The misuse of dodging . . . . . 292

## CHAPTER XXI

### LANDSCAPE PHOTOGRAPHY

Pure landscape characteristically British—Size of camera—The lens—Films and plates—A view meter—Exposure meters—What not to take—The disappointment of panoramic views—Where to find subjects—Woodland scenes and tree studies—The fashion in subjects—Shipping and marine—Wave studies—The rendering of movement—The hilly road—Snow and frost pictures . . . . . 308

## CHAPTER XXII

### ARCHITECTURAL PHOTOGRAPHY

Cathedrals and churches—Interiors—The use of the exposure meter—Backed plates and halation—Perspective and point of view—Wide-angle lenses—The level—Most suitable type of camera—Anastigmats—Focussing dark interiors—Supplementary illumination—Living-rooms—Views through windows—Permissions to photograph—Their abuse . . . . . 319

## CHAPTER XXIII

### PORTRAITURE

The necessities—Neither studio nor "portrait lens" essential—Diffusion of focus—Type of camera—Backgrounds—Niagara Falls as a background—

Portraits in ordinary rooms—Position of the sitter—Reducing exposures—Sunshine effects—Under-exposure and over-development—Dress—Outdoor portraits—Groups—The hands—Artificial light—Magnesium—"Smokeless" powders—Retouching—Animal photography . . . . .	PAGE 329
--	-------------

## CHAPTER XXIV

## PICTORIAL PHOTOGRAPHY

John Richard Green on photography—Distinction between pictorial and technical work—The picturesque in nature—Subject and treatment—Laws of "composition"—Chiaroscuro—Breadth—Composite printing—Clouds—Aërial perspective—Truth of tone—Key—Early pictorial workers—Hill—Rejlander—Mrs. Cameron—H. P. Robinson—Davison—Emerson and "Naturalistic Photography"—Present position of pictorial photography—The R.P.S. and the Linked Ring—Position in the United States—The Photo Secession—"Camera Work"—Stieglitz—Position on the Continent—The German workers—M. Demachy on pictorial photography in France . . . . .	343
---	-----

## CHAPTER XXV

## EXHIBITIONS AND SOCIETIES

The display of prints—Albums—Exhibiting—The question of size—Framing— <i>Passe partout</i> —Mounting in the American manner—The autumn and winter exhibitions—Copyright—How to register a photograph—Selling the right to reproduce—Prices of pictures—Prints suitable for reproduction—Amateur or professional—Photographic societies—Postal clubs—Journals and text-books—Photographic classes—City and Guilds examinations . . . . .	366
---	-----

## CHAPTER XXVI

## PHOTOGRAPHY AND THE PRINTING PRESS

Printing is of two kinds, intaglio and relief—Photogravure—Laying the ground—Printing the resist—Etching—Rendering half-tone—Line processes—The half-tone process—Ruled screens—Woodbury type—Collotype—Oil printing—Bromoil . . . . .	380
L'ENVOI . . . . .	392
INDEX . . . . .	399

## IN THE TEXT

FIG.	PAGE
1. AN EARLY CAMERA, AND DIAGRAMS SHOWING THE ANALOGY BETWEEN IT AND THE EYE. ("Leçons de Physique." Nolet. Paris: 1755) . . . . .	6
2. THE CAMERA USED BY DAGUERRE . . . . .	17
3. APPARATUS FOR DEVELOPING A DAGUERREOTYPE PLATE . . . . .	18
4. CENTRAL SWING TO THE CAMERA . . . . .	31
5. BOTTOM SWING . . . . .	31
6. LANDSCAPE PATTERN CAMERA . . . . .	40
7. DIAGRAM ILLUSTRATING DISTORTION . . . . .	51
8. PLANE PERSPECTIVE—PANORAMIC OR CYLINDRICAL PERSPECTIVE . . . . .	67
9. FORMS OF LENSES—SOME WELL-KNOWN TYPES . . . . .	70
10. A TYPICAL TELEPHOTOGRAPHIC LENS . . . . .	77
11. THE LIGHT WHICH CAUSES HALATION . . . . .	93
12. THE HALATION IMAGE . . . . .	95
13. THE ACTINOGRAPH . . . . .	119
14. WATKINS BEE EXPOSURE METER . . . . .	120
15. TRIMMING A PRINT TO ENSURE PARALLELISM. . . . .	187
16. SECTION OF CARBON TISSUE . . . . .	208
17. SECTION OF CARBON TISSUE WHEN TRANSFERRING . . . . .	208
18. A REVERSING PRISM . . . . .	220
19. HOG-HAIR SOFTENER—CAMEL-HAIR MOP . . . . .	235
20. GUM-BICHROMATE PRINTING-BOARD . . . . .	237
21. SPRAY DIFFUSER IN BOTTLE . . . . .	239
22. MARION'S PRINT-TESTING FRAME . . . . .	247
23. DIAGRAM OF THE FUNCTION OF A CONDENSER . . . . .	255
24. DIAGRAM OF THE FUNCTION OF A CONDENSER . . . . .	255
25. DIAGRAM OF THE FUNCTION OF A DIFFUSER . . . . .	258
26. ILLUMINATION BY MEANS OF A REFLECTOR . . . . .	258
27. AN ENLARGING LANTERN . . . . .	259
28. A PARABOLIC REFLECTOR FOR ENLARGING . . . . .	260
29. ARRANGEMENT FOR ENLARGING WITH A CAMERA . . . . .	260
30. ENLARGING BY DAYLIGHT WITH A CAMERA . . . . .	262
31. DIAGRAM SHOWING THE CURE OF DISTORTION . . . . .	263
32. A PORTABLE LANTERN SCREEN . . . . .	273





PRESENTED BY  
ABANI NATH MUKHARJI  
OF UTTARPARA.

# THE COMPLETE PHOTOGRAPHER

## CHAPTER I

### THE EVOLUTION OF PHOTOGRAPHY

The twofold nature of photography—Roger Bacon's speculum—Barbaro's first camera obscura with lens—Marshall's scioptricks—Chester More Hall and the achromatic lens—The legend of Fabricius—Schulze discovers the sensitiveness of silver nitrate to light—Beccari and horn silver—Charles the aéronaut and the alleged silhouettes—The Wedgwood circle—The elder Niépce and bitumen—Daguerre discovers daguerreotype—Talbot—Photography an accomplished fact—Wet collodion—The first dry plates—Developments with bichromated gelatine—Willis's platinotype—Vogel discovers orthochromatism—The gelatine dry plate—Bromide paper and P.O.P.—The first Kodak—Celluloid film—The evolution of the modern lens.

THE telegraph, the steam-engine, the dynamo, the motor car, most notable applications of the great forces of nature to the service of man, are the product, not of the single inspiration of brilliant genius, but of toiling and plodding on the part of many often obscure and unrecognized inventors. The photograph, as we have it to-day, is no exception. It is the final outcome of two distinct chains of invention, each with its beginning hidden in the mist of antiquity. The forging of their links has been the work of many hands, and the credit of the production of either, much less of the result of their union, the photograph, must be shared by a score or more at the very fewest. But just as in the case of the telegraph, where the work of Wheatstone and Cooke suddenly crystallized into practical form the results of a long series of discoveries, of Porta and Galvani and Volta, of Oersted and Weber and Faraday, so the processes of Daguerre and Talbot, based on the work of Schulze, Scheele, and Wedgwood in one line, and of Aristotle, Euclid, Alhazen, Bacon, Barbaro, Porta, Kepler,

as well as less-known physicists, in the other, enable us to fix the "discovery of photography," in the popular sense, as taking place some time between 1834 and 1837. The reservation "in the popular sense" is necessary, as, in the strict etymological sense, "photographs"—that is, "light-drawings"—were made in 1727 or earlier; but a photograph in common parlance means a picture produced by the camera, and those of Schultz were made by contact, while some of Niépce's bitumen plates bore negative images obtained in the camera it is true, but scarcely pictures. Great as was the step made by Daguerre, its importance was hardly recognized at the time, if we are to judge from the fact that the French Government awarded an annual pension of £240 to him, and of £160 to his partner Niépce, in return for which princely remuneration, the discovery was to be thrown open to the world. To form a correct notion of his work, and that of his contemporaries, notably Talbot and Herschel, we must turn to the earlier pages of the record.

## I

The operations which constitute photography are twofold—first, the formation of a light-image by the lens and camera; and, second, the fixing or recording of that image by chemical means. The discovery that images could be seen of necessity preceded the search for a chemical method of recording them, and, as a matter of fact, we find that the camera obscura was familiar for centuries before there is any evidence of an attempt to fix its pictures.

In Eastern lands, where science had its earliest votaries, houses are dark within while the scene without is bright. How early in point of time it was noticed that when one small hole in a darkened room allowed the light to enter, a picture of what was going on outside was visible on the opposite wall, it is impossible to say. But where the conditions were so favourable it must have attracted the attention of such close observers of nature as the Chaldean and Egyptian sages. Aristotle notes that when the sun shines through a square hole upon some surface at a distance from it, the spot of light is not the shape of the hole, but is circular, and that during an eclipse the spot takes the shape of the sun for the time being.

Euclid also combined instruction with amusement when demonstrating to his pupils the rectilinear passage of light, by the projection of images of outside objects in a darkened room, through an aperture in the window shutter. These cases are parallel to that of a camera provided with a pinhole instead of a lens, still often used by photographers. From the room with its accidental chink and whitened wall, to a structure made for the express purpose of showing such images, cannot have been a great step; but no trace remains of the man who made the first intentional stride towards photography. Firm ground is only reached when we get to Roger Bacon's "Perspectiva," written about 1267, wherein he describes, not very clearly it is true, an apparatus with a speculum, by which it is possible to see images of what is going on in the street, so that "those looking will run to the image and think the things are there when there is nothing but merely an apparition." Bacon speaks of a "speculum," or mirror, and one of the earliest forms of camera used in photography actually had a mirror instead of a lens, although for practical purposes, except in celestial photography, the mirror was soon abandoned for the lens. The first record of a box for viewing or projecting pictures is of one constructed in 1437 by L. B. Alberti, which was probably a rough form of camera obscura or magic lantern. Leonardo da Vinci, who was well versed in optics and in the theory of vision, has left unpublished manuscripts, now in the Bibliothèque Nationale at Paris, which contain a very distinct account of a pinhole camera, with a diagram; but he does not claim it as his invention, nor even as a novelty. As Leonardo da Vinci died in 1519, it is clear that at whatever period of his life this was written, it must have been long before the time of Giovanni Battista della Porta. Porta is, however, generally quoted as the inventor of the camera obscura, which he describes in his "Magica Naturalis" published in Naples in 1558. In this book the camera is provided with a "speculum"—*i.e.* a mirror—and it was left for Daniello Barbaro to give the first account of a camera with a lens, which he did in a work on perspective, published at Venice in 1568. Barbaro not only describes a camera and lens, but actually alludes to the use of a stop in sharpening up the picture. The passage is remarkable enough to quote in full.

"Having made a hole in the window of the room from which you wish to observe, as large as a spectacle-glass, then take an old man's glass convex on both sides, not concave, like the glasses of youths with short sight, and when it is fixed in the hole, shut all the doors and windows of the room so that no light may enter except by the lens. Now take a sheet of paper and place it in front of the glass, so that you see clearly all that is outside the house. This takes place most distinctly at a determinate distance, found by bringing the paper nearer to or farther from the glass till you have found the proper position. Here you will see the images on the paper as they are, and the gradations, colours, shadows, movements, clouds, the rippling of water, birds flying, and everything that can be seen. For this experiment the sun must be clear and bright, because the sunlight has greater power in bringing out the visible images. When it pleases you to make the experiment, you should choose the glasses which do best, and should cover the glass so much that you leave a little of the circumference in the middle which should be clear and open, and you will see a still brighter effect. (This seems to be the first mention of the use of a diaphragm in sharpening the image.) Seeing, therefore, on the paper the outline of things, you can draw with a pencil all the perspective, and the shading and colouring, according to nature, holding the paper tightly till you have finished the drawing." \*

Not Barbaro only, but another Venetian, Benedetti, refers to the use of a camera and lens some years before it was published by Porta in the second edition of the work to which reference has already been made. The early history of the camera has been the subject of a long and painstaking investigation by Major-General Waterhouse, and it is curious to notice that he was led to anticipate that the invention might very likely be found to proceed from Venice, from the fact that the seat of glass manufacture in those times was there. He seems to have left no room for doubt that Porta not only was anticipated by Bacon, Da Vinci, and others in

\* "*La Pratica, della Perspettiva*," by Monsignor Daniel Barbaro, eletto Patriarcha d'Aquileia, Venice, 1568. Translation in "*Notes on the Early History of the Camera Obscura*," by Major-General Waterhouse. The *Photographic Journal*, N.S., xxv. pp. 270 *et seq.*, from which much in this chapter has been taken.

the description of a darkened room and pinhole, which had been utilized by Maurolycus, Reinhold, and others for observing eclipses from 1520 onwards, but also by Barbaro and Benedetti with the camera and lens. Another link with Venice is found in the biography of the Venetian painter Canaletto, who seems to have been the first artist to make use of the camera in obtaining the outlines of his subjects. The man who really turned the camera obscura to practical use as a sketching instrument, and laid down the optical principles on which the projection of images by single lenses or combinations of them depended, was the great astronomer, Johann Kepler, in his optical treatise "Dioptrice" (1611). When Sir W. Wotton visited Kepler in 1620, he saw a landscape drawing executed by the aid of a portable camera, and wrote a quaint description of it to Lord Bacon, from which an extract was published in a book called "Graphice; or, The Most Excellent Art of Painting," printed for R. Crofts in 1658.

"The draught of a landskip mathematicall; they that have leasure, and desire thereto, may make experiment. A Landskip. Set up a little black tent in a field, made easie, portable and convertible, as a windmill, to all quarters at pleasure; capable of no more than one man with little ease; exactly close and dark, save at one hole, an inch and a half diameter, to which apply a long prospective trunck, with a convex glasse; fitted to the said hole, and the concave taken out at the other end, which extendeth into (about) the middle of this erected tent, through which the visible radiations of all the objects without, are intermitted, falling upon a paper which is accommodated to receive them, and so trace them with pen in their naturall appearance, turning this your little tent round by degrees, till you have designed the whole aspect of the place. There is good use hereof in chorography; but *to make lundskips hereby were too illiberall.* Surely no painter could exceed the preciseness<sup>e</sup> of these."

The "Scioptrick ball" was a wooden globe pierced and fitted at one end of the opening with a lens. The ball was so held that it could be turned about, and a camera fitted with it was sold in 1704 by Mr. Marshall at "the Archimedes" on Ludgate Hill. Such cameras were called "Scioptricks." In the latter half of the eighteenth century the camera seems to

have become quite common, both as a show and for sketching purposes. There were many besides Canaletto who did not hold with Crofts that its use "were too illiberall." Some were made with mirrors to get over the difficulty of the picture




FIG. 1.—AN EARLY CAMERA, AND DIAGRAMS SHOWING THE ANALOGY BETWEEN IT AND THE EYE ("Leçons de Physique." Nollet. Paris: 1755.)

being reversed or wrong way about, some were large and the observers got inside, others small and portable and fitted with a mirror within, which reflected the image on to a horizontal screen on the top of the box. Such an instrument is figured in "Leçons de Physique," by the Abbe Nollet, published in Paris

*in 1755, and the plate, which we reproduce, is of interest, as demonstrating the analogy between the camera and the eye, and the fact that the nearer the object is brought to the lens, the further away on the other side of the lens is the sharp image.*

A discovery which ultimately had a very important bearing on photography had in the mean time been made by an Essex gentleman, an astronomer, Mr. Chester More Hall. He, like all other users of lenses, had been inconvenienced by their want of what is now spoken of as "achromatism." Any lens made of a single piece of glass not only refracts or bends aside the light which passes through it, but bends each colour to a different extent. The result is that images with such lenses appear to have coloured edges or fringes surrounding them, especially when the lenses are used as they are in telescopes. It was generally supposed, on no less an authority than that of Sir Isaac Newton, that this defect was insurmountable. In his "Optics" Newton stated that "refraction could not be produced without colour," for which reason "no improvement could be expected in the refracting telescope." Hall, however, found that, contrary to Newton's supposition, all glass, while bending or refracting the light, did not separate the colours to the same extent, and that it was possible by combining lenses of two different kinds of glass (crown and flint) to make a compound or "achromatic" lens, which should form an image without separating the different colours at all, or at least perceptibly. He took no pains to make his invention public, however, and the discovery of the achromatic lens is, therefore, often attributed to John Dollond, an optician, who described to the Royal Society in 1758 how it was possible to remedy both "chromatic aberration" and "spherical aberration" by making lenses of more kinds of glass than one. This was the foundation stone on which all modern lenses for the microscope and telescope as well as for the camera, with their exquisite perfection of design, construction, and performance, have been made. Lenses made on this principle to give the best results to the eye, as in the telescope, are not the best suited to photographic uses; and the construction of a properly corrected photographic lens was not put in hand until the demands of photography called it forth; but the principle of Hall's



discovery was none the less important, and when lenses for photography were wanted, it was only necessary to modify the glasses and their curvatures to accommodate the lens to the new requirements.

This has brought us down to the latter part of the eighteenth century, when the first recorded attempt was made to fix the images obtained in the camera, by applying the existing knowledge of the chemical action of light. But before we can understand the nature of this attempt, we must retrace our steps, and see what the chemists had done while the physicists were evolving the camera.

## II

It must have been noticed at a very early date indeed that light affected certain bodies in an unmistakable manner. Probably the first of its effects to attract observation was the fading of dyed fabrics. The famous Tyrian purple we now know to have been anything but a permanent colour, and some of the cheaper and commoner dye-stuffs of the ancients were similarly fleeting. The greatest of all the manifestations of light-action, the conversion of carbonic acid and moisture in the air into vegetable matter by means of the chlorophyll in the leaves of plants, escaped observation until comparatively recent years, but very primitive gardeners must have noticed that by heaping earth round the stems of plants, the parts so protected remained colourless or nearly so, whence the deduction that in some way the colour is due to light is simple and direct. Changes in the colours of fruit and flowers by solarization are noticed by Aristotle.

The beginnings of photographic chemistry are generally attributed to the alchemists. These early metallurgists, giving much of their time to the investigation of the precious metals, undoubtedly succeeded in making silver nitrate and possibly silver chloride; but if they noticed that fabrics treated with either substances turned dark when exposed to light, they have not recorded the fact.

The first accounts of silver ores and native silver chloride, or "horn silver," which were sometimes observed to change

colour after being extracted from the mines, are found in the metallurgical writings of Agricola, Fabricius, Kentmann, and others living in the Saxon mining districts round Meissen, and familiar with the minerals found there. Fabricius, a Saxon scholar and poet of the sixteenth century, who wrote a short supplement to Agricola's great work on metals and mining, has generally, but quite erroneously, been looked upon as an alchemist, and has been the subject of a curious legend, started apparently by a French historian of photography. Fabricius, so it is said, not only prepared silver chloride, but found that "it became suddenly black as soon as a ray of sunlight fell on its surface"—which it certainly does not—and acting on the hint this phenomenon afforded, he projected upon the surface of silver chloride the image formed by a glass lens, which imprinted itself thereupon, and so made the first photograph. Unfortunately, an examination of the works of Fabricius reveals no account of any experiment so remarkable; he refers to a semi-transparent, horn-coloured ore of silver, or to the form of silver chloride known as "horn silver," but apparently he was not aware of its most remarkable characteristic of changing colour in light. The writings of the alchemists have many references to silver nitrate, and Porta, who did not invent the camera, was certainly familiar with this salt, though he did not know that it was sensitive to light. He observes that it is possible to disguise one's self by applying a solution of silver nitrate all over the body—a most effective method, no doubt.

The actual discovery that light was the active agent in causing this darkening of silver nitrate was made by Johann Heinrich Schulze, and, like many another, was purely accidental. He tells us that, wishing to treat some chalk with nitric acid, he happened to use acid he had at hand in which a little silver had been dissolved. Mixing this with the chalk, and working near a window, he was surprised to find that the mixture in the dish turned dark where the direct rays of the sun fell upon it, but was unaltered in the parts not reached by the sunlight. The fact that struck him most was that the result of the action of light should be darkness. We have to view the experiment through the theories of a couple of centuries ago, to realize how strange this must have seemed to Schulze. It attracted

his attention so strongly that he laid aside the work on which he was engaged, to follow up the clue thus accidentally acquired. Friends suggested that the change was due to heat and not to light, but this he disproved by showing that it was possible to make a bottle of the mixture so hot in front of a fire that the hand could not bear it, and yet not get the darkening that sunlight soon brought about. He thought at first that his sensitive material was made by the mixture of chalk and aqua fortis, but failed to get any darkening when these substances were used. It was only after many experiments that he recollected that there was silver in the acid he had first used, and then by saturating acid with silver he got more marked results than at first. He cut out letters and figures from sheets of opaque paper, and putting these round bottles of the mixture and exposing them to light, he obtained true photographic impressions, but written, if not in sand, in still less stable material. For we must not forget that Schulze's bottles contained nothing but a kind of chalky sludge, and it needed but a swirl to mix the contents up and the images disappeared in a moment. None the less, for the first time he had produced images by means of light, and intentionally ; and that first step, if not taking him far on the road towards photography as we know it, was at least the first step, and a notable one. He published an account of his experiments in the *Acta* of the Cæsarean Academy for 1727; and there seems every reason to believe that it was from an account of Schulze's experiments that Wedgwood got the suggestion for his own.

The sensitive material in Schulze's experiments was silver nitrate, and it is possible that the effect of light upon it was noticed before his time ; for he himself remarks, in the paper in which he published an account of them, that he had "often found a solution of silver made with aqua fortis does not get dark in a quite dark place, while when exposed to the sun a dark red colour is induced, verging afterwards towards blue." The chalk was only a vehicle, and he found that magnesia, "ceruss of lead," and other substances could be employed in a similar manner. Silver chloride, or luna cornea, it was long known, gradually darkened in colour when exposed ; but it was assumed, as by Robert Boyle, that the darkening was due



ON THE ARUN  
BY CHARLES JOH



to the air. Thirty years after Schulze, Beccari of Bologna suspected that this change was due to light. He enclosed some of the luna cornea in a glass vessel and placed it in front of a window, but some distance within the room. He soon found that the side turned towards the window had changed to violet, while the back remained white. On the vessel, over parts of the unaltered chloride, he stuck black paper, and exposed it to light until the following day, when he found that the substance had turned violet everywhere except where the paper had protected it.

Schulze's experiments were repeated by Dr. William Lewis of Kingston-on-Thames, who carried his investigations into the action of light much further. He found that ivory, bone, wood, and stone, treated with nitrate darkened in sunshine, and observed that compounds of bismuth, of gold, and of mercury were light-sensitive. At the death of Dr. Lewis in 1781 his manuscript note-books were purchased by Josiah Wedgwood, the potter, who also took his assistant, Mr. Chicholm, Chisholm, or Chisolm into his service, as secretary and chemical assistant; but in this we are anticipating.

The next stage was an important one, and was made at the other end of Europe. Carl Wilhelm Scheele, of Stralsund, knowing doubtless of the discovery of Schulze, and that silver chloride as well as silver nitrate was affected by light, set himself to find out the nature of the change, and to ascertain whether all kinds of light affected the silver salt equally. By a series of experiments he convinced himself that silver chloride in sunshine was converted into metallic silver, which was the dark-coloured product, and that if it were exposed under water, the water subsequently contained muriatic acid. Liquor ammonia, the alchemists knew, was a solvent of silver chloride. Scheele found that it did not dissolve the darkened product obtained by exposing silver chloride to light. It does not appear that he realized from this that it might possibly act as what we now describe as a "fixing" agent; and in the subsequent experiments of Wedgwood there is no mention of ammonia being tried for this purpose, though he found he was quite unable to fix his pictures. Throwing upon a surface sensitized with silver chloride the band of coloured light from a prism, Scheele found that the darkening action took place

more quickly in the violet than in the other colours. He must have performed this experiment in a very casual manner, as he failed to notice that quite half of his visible band of colours, the green probably and the yellow and red certainly, had no effect on the chloride at all. Scheele published an account of his work in 1777. In 1801, Ritter, repeating these experiments more carefully, found that not only was the sensitive substance unaffected by red, yellow, and green light, but that there existed invisible radiations—now known as the ultra-violet—which changed it even more powerfully and quickly than violet light itself.

Prof. Jacques Alexandre Cesar Charles, a public lecturer on physics in Paris, is said by Frenchmen (on extremely doubtful grounds) to have made silhouettes by casting the shadow of a person's profile on paper made sensitive with a salt of silver. Charles was a notable man in his time. He was the first to ascend in a free balloon; and he fought and wounded Marat, with whom he had some difference on a scientific subject. No record whatever of his alleged experiments seems to exist, and the basis for the claim is an assertion made in 1839 by Arago. He dated the experiments as being made in "the first years of the nineteenth century."

This sketch has now brought us down to the end of the eighteenth century. By that time scientific men at least were familiar with the fact that some mineral compounds were sensitive to light, and that minute holes, mirrors, and lenses were each capable of forming an image of external objects on a suitably placed surface. It remained to apply the one process to the other to produce a camera picture, and the attempts, unsuccessful and successful, to do this form the third stage in photographic history.

### III

Pre-photographic legends of pictures made by natural or by magical means are in existence, the Chinese, of course, having a tradition of this kind; but the most explicit accounts are to be found in the two French works "*Un Voyage Supposé*," by Fenelon, published in 1690, and "*Giphantie*," by Tiphaigne de

la Roche, published in 1760. These are curious anticipations of photographic processes, but are not sufficiently definite even to suggest the problem to an experimenter, and it is not at all likely that either was known to those who subsequently took up the task of making photography possible.

In the latter part of the eighteenth century a remarkable group of men were living in the Midlands, scattered about, it is true, but meeting from time to time, frequently corresponding, and constantly in sympathy, if not always in agreement. The best known of the group are Dr. Priestley, Josiah Wedgwood, James Watt and Matthew Boulton his partner, and Dr. Erasmus Darwin, a naturalist himself, and grandfather of a still more famous one. In 1771 was born to Josiah and Sarah Wedgwood a fourth son and fifth child, Thomas. Dr. Priestley, in 1772, published his "History of Discoveries relating to Light Vision and Colour," in which are described the experiments of Schulze and of Beccari already referred to. In 1782, we have seen that Chisolm, who had been Dr. Lewis's assistant, came to Josiah Wedgwood at Etruria, and amongst his other duties, he seems to have had much to do with the education of "Tom" Wedgwood. It is not surprising that a lad reared under these conditions, if of scientific taste at all—and Tom Wedgwood's tastes were markedly scientific—should have his attention drawn very strongly to these experiments with salts of silver. Wedgwood's scientific experimenting began before he was of age, and there is some reason for supposing that the work described to the Royal Institution in 1802 was performed in or about 1790-1792.

The great merit of Wedgwood as a photographic pioneer lay in the fact that he was the first to realize that it might be possible to use the light-sensitive properties of substances to make permanent the images given by the camera obscura. He was a confirmed invalid, dying at the age of thirty-four, and the latter years of his life were almost entirely spent in travel in search of health. Hence the extremely casual and unsatisfactory way in which the report of his photographic work has come down to us. It is contained in the first and only volume of the "Journals of the Royal Institution," and is entitled "An account of a method of copying paintings upon glass, and of making Profiles, by the agency of Light upon Nitrate of



silver. Invented by T. Wedgwood, Esq. With observations by H. Davy." In this account, which seems to have been written by Davy, we are told that white paper or white leather moistened with solution of silver nitrate speedily changes colour on being exposed to light. Red rays have very little effect on it, yellow and green are more efficacious, but blue and violet light produce the most decided and powerful effects. The leather he found more readily acted upon than the paper, an observation in which lay the germ of "development." The phrase "paintings on glass" in the title refers to originals so prepared, from which copies could be printed on the sensitive paper or leather, in the method now so well known. Wedgwood failed in his attempts to fix these prints. Repeated washings would not remove the unaltered silver compounds sufficiently to prevent the white parts darkening when exposed to daylight afterwards. Varnish was tried without avail, and these copies therefore had to be kept in the dark, and examined only by the light of candles or lamps. The following extract describes the first recorded attempt to obtain camera pictures :—

"The images formed by means of a camera obscura have been found too faint to produce, in any moderate time, an effect upon the nitrate of silver. To copy these images was the first object of Mr. Wedgwood in his researches on the subject, and for this purpose he first used the nitrate of silver, which was mentioned to him by a friend as a substance very sensible to the influence of light ; but all his numerous experiments as to their primary end proved unsuccessful. In following these processes, I (Davy) have found that the images of small objects, produced by means of the solar microscope, may be copied without difficulty on prepared paper. However, it is necessary that the paper be placed at but a small distance from the lens."

Here ended Wedgwood's invention: the fixing difficulty seemed to be insurmountable. Yet several substances were available had he known, and the universally used fixing agent "hypo" had been discovered by Chaussier in 1799. This difficulty discouraged others from working at the process, and Talbot himself, nearly fifty years afterwards, said that he learnt of the property of hypo before he read of Wedgwood's work, or he too might have been discouraged. The light-sensitiveness

of silver compounds was neglected from the date of the publication of Wedgwood and Davy's account for more than a quarter of a century. Wedgwood himself died July 10, 1805.

The next stage is curious, because it ignored almost all that had gone before, and started on a completely fresh line. Joseph Nicéphore Niépce, a middle-aged country gentleman living at Gras, near Chalon-sur-Saone, in South-Eastern France, was interested in the then novel process of lithography. His lithographic experiments commenced in 1813, and led him from the use of stones to that of metal plates, which he coated with various "varnishes." From this stage he was tempted to try to transfer to the plates, by the action of light, the line pictures which formed his originals. By 1816 he had succeeded in doing so, although in all probability, when so transferred, he could not copy them by "lithography" or any of its modifications. Two years later, as shown by his published correspondence, he was trying to get camera pictures by his method. He succeeded, although the exact date when he did so is uncertain. His great originality lay in the abandonment of silver salts as sensitisers, and in the use of resinous substances instead. Of these he found, in 1826, that "bitumen of Judea" was the most satisfactory. This mineral pitch or asphaltum he discovered to be soluble in oil of lavender except where light had acted on it. By giving a thin coating of the bitumen to a metal plate, exposing this to light under an engraving or design, and then washing the surface of the plate with certain essential oils—oil of lavender being the best for the purpose—the bitumen where the light had not acted washed away, where it had acted it remained. The result was a copy of the engraving, the lines being represented by bare metal, the clear spaces by bitumen.


The designs Niépce obtained in this way he called "heliographs," and many efforts were made by him both to make them more easily visible and to find some means of printing from these metal plates. The most promising methods were by acting upon the bare metal in those parts whence the bitumen had been washed away; this he did with various acids, and with iodine (which had been discovered in 1812 by Curtois). In the Chalon museum is an old print, oiled to make it translucent, and a number of proofs from it, which are said to have been printed from an engraved plate made in this

manner in 1826. This process of Niépce is remarkable, in that it is even now in extensive use, much of the modern half-tone and line work being printed on copper or zinc by a process to all intents and purposes that worked out at Chalon eighty years ago. The bitumen process is like some of the simpler organisms in nature: it has outlasted many of the more complex and elaborate methods of later date, and for the purposes to which it is applied it is not easy to see how it is to be improved.


In the mean time a reputation had been made which extended far beyond its centre, Paris, by a very clever stage artist—he was much more than a scene-painter—named Louis Jacques Mandé Daguerre. He showed himself remarkably skilful in scenic effects, which reached their highest point in the Diorama, an entertainment he devised which was popular for many years. Daguerre had few of the characteristics of the conventional inventor; he was a gay man-about-town, and his career, to put it very mildly, would hardly commend itself to the worthy Dr. Smiles. He must have had much originality, however, and undoubted patience. Somewhere about 1824 he first entertained the idea of fixing the images of the camera obscura, an instrument he used in his scene paintings. He heard of the work of Niépce in 1826, wrote him, and the two inventors met in 1827. Two years later they entered into an agreement for ten years to work at the subject for their joint advantage, each communicating his results to the other. Until the death of Niépce in 1833, Daguerre seems to have worked on the lines of the bitumen process, in the details of which he effected some improvements. After that date, however, acting very possibly on a hint given to him by attempts to etch silver plates with iodine, he took up a distinctly novel line, which gave promising results in 1835, and in 1837 was sufficiently perfected to be the subject of a fresh agreement with the son of the first Niépce. The process, after an unsuccessful attempt to form a company, was given to the world in return for a pension from the French Government. •

Daguerre's process was an immense advance in sensitiveness on everything which had gone before it; when details had been modified a little, it was even capable of being used for portraiture from life. It was, moreover, a positive process, not

a, negative one, and was more strikingly original than any other method, introduced before or since. A highly polished silver plate was submitted to the fumes of iodine until it was coated with a fine layer of silver iodide, and was then exposed in the camera. The plate was next transferred to a box in which it was held over a metal dish of mercury, heated from beneath by a spirit lamp. The vapour of mercury ascended, and the metal adhered to those parts which had been exposed to light, in proportion to the strength of the light. The



Horizontal section.



Vertical section.

FIG. 2.—THE CAMERA USED BY DAGUERRE.

"A is a ground glass by which the focus is adjusted; it is then removed and the photographic plate substituted, as in C. B is a mirror for observing the effects of objects, and selecting the best points of view. It is inclined at an angle of  $45^{\circ}$  by means of the support L. To adjust the focus, the mirror is lowered, and the piece of ground glass A used. The focus is easily adjusted by sliding the box D out or in, as represented in the plate. When the focus is adjusted, it is retained in its place by means of the screw H. The object glass J is achromatic and periscopic; its diameter is about one inch, and its focal distance rather more than 14 inches. M is a stop a short distance from the lens, the object of which is to cut off all those rays of light which do not come directly from the object, to which the camera is directed. This instrument reverses the objects; this can be remedied by using a mirror outside, as at KJ. ("Photography." By Robert Hunt. 1853.)

unaltered iodide was dissolved away by means of a solution of salt—hypo was subsequently used for the same purpose—and the final result was a brilliant, well-defined picture, reversed as regards right and left, but with its lights the light-coloured mercury compound, and its shadows the polished silver surface, which, if held so as to reflect only dark objects, appeared dark, and so made the result a "positive," and not a "negative;"

though these terms were not introduced until the following year, when Herschel employed them "to avoid circumlocution."




FIG. 3.—APPARATUS FOR DEVELOPING A DAGUERRETYPE PLATE.

The plate H in a wooden holder, B, was introduced by means of the lid A. Mercury, C, was then volatilized by means of the lamp D, the support for which, I, was adjustable. A thermometer partly shown at FJ enabled the heat to be regulated, while the progress of development was watched by means of a candle or other feeble light through the window G. ("Photography." By Robert Hunt.)

The process was termed Daguerreotype, and except for the application of bromine to the silver plate along with the iodine, made by Goddard in 1840, by which its sensitiveness was much increased, and a method of depositing gold on the image, introduced by Fizeau, which gave it more vigour and greater permanence, it was not modified or improved. It had a great vogue for portraiture from 1840 to 1851, when the wet collodion plate speedily made daguerreotype obsolete. Its exceptional character is shown by the fact that no other process originated in it, or borrowed anything from it. Daguerreotype, like its brilliant discoverer, stands alone and independent. Daguerre launched upon an astonished world a complete and practical photographic process—the first. It existed unmodified until made obsolete by a totally dissimilar method, when it died almost as suddenly as it appeared.

It is time we got back to Wedgwood, and took up the silver nitrate and chloride thread again, which we dropped at his death. Nothing of note can be recorded until 1819, when Sir John Herschel (Herschel II.) published in the *Edinburgh Philosophical Journal* an account of his investigation into "hyposulphurous acid and its compounds." One of these is the now universally used "hypo" (hyposulphite of soda, or more correctly sodium thiosulphate), whose solvent properties on silver chloride were then not only pointed out, but thoroughly examined and described. It was in that paper that Herschel drew attention to a fact that many photographers even now

ignore—that to ensure the complete solution of the silver salt there must be a large excess of hypo present!

We now come to the work of William Henry Fox Talbot, an English gentleman of ancient lineage and scientific tastes, who is known not only for his photographic discoveries, but as one of the first decipherers of the cuneiform inscriptions and as a pioneer in modern illustrative methods: the photogravure process of to-day also is essentially his invention. He tells us in the "Pencil of Nature" that the idea of fixing the camera images occurred to him in 1833, and that he began experimenting in 1834. Daguerre's process was made public in the first fortnight in 1839; on January 25 of the same year Faraday exhibited prints by Talbot, and on January 31 Talbot read an account of his process to the Royal Society. We can accordingly settle on January, 1839, as the period when photography, as we understand it, though still imperfect, first became known to be practical. Talbot followed the lines of Wedgwood and Davy, but obtained greater sensitiveness by forming his silver chloride in the paper in such a way that there was left with it an excess of silver nitrate. It was by the presence of this silver nitrate that the speed of the paper was increased to such an extent that camera pictures became possible. During the brilliant summer of 1835, he tells us in the work already quoted, he had succeeded in getting camera pictures of his own house, Lacock Abbey, on paper sensitized by alternate washes of solutions of salt and of silver nitrate. The publication early in 1839 of Daguerre's method frustrated his hope of being the first to announce a practical photographic process, but there is no doubt that for some years both he and Daguerre, on different lines, had been making pictures in the camera—Daguerre by an original, and it is said accidental, discovery, Talbot by a method a direct outcome of that of Wedgwood and Davy. Talbot's first camera pictures, however, were not developments of a latent image; but the photograph—a negative one, of course—was printed right out in the camera. The discovery that a comparatively short exposure to light would give an image, but an invisible one, in a fraction of the time taken to print it out visibly, was made by Daguerre; although his development by mercury vapour bears no known relation to any other development

process, and was quite inapplicable to the paper process of Talbot.

#### IV

From the time of Talbot and Daguerre the stream of invention swept on in an ever-widening flood. The same year that marked the publication of their processes saw the discovery by Mungo Ponton,\* that paper soaked in potassium bichromate was sensitive to light, that it underwent a change of colour on exposure, and that the image so obtained could not be washed out of the paper, although the bichromate could. This observation, to all appearances a curiosity and little more, laid the foundation of the carbon process, of gum bichromate, of ozotype, of collotype, of photogravure, of Woodburytype, and of some of the half-tone block processes, and, in the variety of the methods which sprang from it, has been absolutely unrivalled in photographic research. This was in 1839. The next year Sir John Herschel made photographs on glass plates by depositing silver chloride on them, but as there was nothing to hold the chloride to the glass and to act as a "sensitizer," the results were interesting, but no more.

The calotype process of Talbot must not be confused with his first method, in which there was no such thing as development. Calotype was patented in 1841, and, Daguerre's being first, was the second in which development played any part. The development of a calotype is the direct ancestor of the development of to-day. Wedgwood had noticed that white leather treated with silver nitrate was more sensitive than white paper. In 1839, the Rev. J. B. Reade was making pictures with the "solar microscope"† on paper sensitized with silver nitrate. To take advantage of Wedgwood's observation, Mr. Reade used all the white kid gloves the household authorities could spare, and, the supply falling far short of his requirements, thought he would try and "tan" paper. Accordingly

\* The fact that paper treated with chromic acid had been sensitive to light was known long before Ponton published his discovery.

† The solar microscope was an instrument in principle like a magic lantern, arranged so that a beam of sunlight could pass through the microscope in an otherwise darkened room, and project a picture of the object on a small screen suitably placed.



GROUP  
BY C. FLYG





he treated paper with gallic acid, and found at once that he got greater sensitiveness. What he did not note, however, was that this action of the gallic acid was exercised during as well as after exposure, and that it was, in fact, a "development" of the latent image. Reade mentioned his discovery to Ross, the celebrated optician, who in turn told Talbot, in whose hands the observation of Reade rapidly became the "calotype" or "Talbotype" process. Paper in which silver iodide had been formed by alternate treatment with silver nitrate and potassium iodide, was washed over with a solution of silver nitrate and gallic and acetic acids. After this second application, it was highly sensitive, but soon spoilt. On exposure in the camera an image rapidly appeared, and was then developed up to full vigour by further treatment with the "gallo-nitrate of silver." A solution of common salt was suggested by Talbot for fixing purposes, but was seldom employed, hypo being already known in that capacity.

The same year that saw the patenting of "calotype" saw another patent granted, to Claudet, for the use of red or yellow light to illuminate the dark room, which hitherto had been lit only by very feeble artificial white light, such as is given by a candle some distance away from the sensitive substance.

Daguerreotype was largely practised for professional portraiture from 1840 to 1852 or 1853, while calotype became for a time quite the fashionable craze. Queen Victoria and Prince Albert had a studio and dark room at Windsor, and thousands of photographers took landscapes with quaint leather-hinged folding cameras, and exposures of anything up to an hour or more. With calotype, in spite of its slowness—to modern eyes—and its difficulties, good work was done; and its insensitiveness did not prevent its use for portraiture, although direct sunshine was generally used to cut down exposures as much as possible. Some of the work done in 1844 and 1845 by J. D. O. Hill is still in existence, and has pictorial quality which enables it to hold its own with work of the present day. The "waxed paper process," a later modification of calotype, was popular for landscape work as an amateur's process for a very long time.

While daguerreotype and calotype flourished, collodion was discovered by Prof. Schonbein of Basle, and seemed to

offer what photographers had been wanting—namely, a film which could be applied to glass and sensitized. Daguerreotypes could not be “printed ;” while although this was possible with “calotypes,” they gave prints with some degree of coarseness, owing to the fibre of the paper which formed the support of the negative. Scott Archer, in 1851, invented the “wet plate,” or “wet collodion” process. A glass plate was coated with collodion containing metallic iodides, immersed in a solution of silver nitrate, exposed while still wet, developed with a solution of pyrogallic and acetic acids, and fixed in hypo. A negative so obtained gave results equal in fineness of definition to anything that can be got to-day, and the wet plate process, very slightly modified from the condition in which it left the hands of Archer, is used enormously at the present time for photo-mechanical work. Probably the great majority of illustrations in this volume are printed from plates prepared with the help of wet collodion.

The wet plate was vastly more sensitive than either the calotype or the daguerreotype, but only while it was wet. If dried, the silver nitrate solution crystallized in the film and spoilt it, or if it were washed out, most of the sensitiveness went with it. Various ingenious methods were devised to meet this difficulty, the most successful being the Taupenot, tannin, and collodio-albumen methods, but not till 1864 was an emulsion dry plate made. In that year Sayce and Bolton described how it was possible to make “collodion emulsion”—collodion containing silver bromide in suspension, which could be poured on to glass and allowed to dry. The plates so prepared would keep indefinitely. Collodio-bromide was never as sensitive as wet collodion, but it was fast enough, and with its other advantages was popular as an amateur’s process. It is still made for process work, and is occasionally used by enthusiasts for lantern-slide making, yielding transparencies that for richness and brilliancy have never been surpassed.

There was no great change in negative processes until the late “seventies,” though investigation was constantly going on, and photographic bypaths were explored and opened up. For example, Poitevin, in 1855, used Mungo Ponton’s discovery that gelatine treated with bichromate became insoluble in hot water after exposure to light, and succeeded in making prints

by means of it ; but he failed to get half-tones, although blacks and whites were yielded readily enough. In 1858 Pouncy invented the process now known as gum-bichromate, though it dropped out of sight again for many years. Burnett, Blair, and Fargier improved upon Poitevin's attempts, until Joseph Wilson Swan, in 1864, patented the carbon process, which, with slight but valuable modifications introduced by Johnson in 1869 and Sawyer in 1874, is the process as we know it to-day. Amongst other inventions of Poitevin was the method recently revived under the name of oil printing.

On another line, also, work was steadily progressing. Herschel, in 1842, published the fact that several iron salts were sensitive to light, and shortly afterwards based certain printing processes upon it. Some of these survive as the "blue printing" methods used by engineers and others for copying tracings ; the others are obsolete. Hunt, in the fifties, attempted to turn the iron in the Herschel pictures into platinum, but failed to get a practical result, and it was left for W. Willis, in 1873, to patent a process, in which the image was composed, to all intents and purposes, of metallic platinum, and therefore was as permanent as could well be desired. This process he improved in 1878 and 1880, when platinotype as known to-day became an accomplished fact, though the prints had to be developed in a hot solution of oxalate, the "cold bath platinotype" not being introduced until 1892.

A discovery was made in 1873 by Prof. H. W. Vogel of Berlin, the full significance of which it took very many years to appreciate ; in fact, it is only to-day that its importance is being realized, and, what is more, utilized by photographers. We have seen that Scheele a hundred years before had noticed that all colours did not affect the sensitive substance equally, and that yellow, and especially red, seemed to have but little effect upon it. Of all colours yellow is the brightest to the eye, yet in a photograph yellow appeared quite dark, green appeared darker than it should do, and a pure red appeared black. Acting on earlier observations by Herschel and Draper, that colour sensitiveness of photographic plates and papers was dependent upon the absorption of coloured rays by the sensitive substance, Vogel found that by adding certain dyes to the sensitive plate, it could be made to respond to the colours to

which hitherto it had been insensitive. Thus he laid the foundation of orthochromatic photography, and cleared the ground for "thréé-colour" and other processes intended to give photographs in the colours of nature. The clue once provided, the action of thousands of dye-stuffs has since been investigated, and although nothing, so far, has been found which will make the sensitiveness of a plate to colours correspond with the sensitiveness of our eyes, it has been found possible to make plates sensitive to some extent to all colours, so that by using them with a coloured screen to cut off some of the rays to which the plate is disproportionately sensitive, we can obtain a close approximation to a true monochromatic rendering.

The wet collodion and the collodion emulsion processes were regarded as marvels of sensitiveness, "instantaneous" work was done with the former, and the latter was as convenient a tourist's method as photographers could then conceive. Attempts were made, however, to find some other and more convenient vehicle than collodion, which compelled the use of ether and alcohol as solvents, and gave a film which, if sensitive and structureless, was extremely tender and destroyed by a touch. Gelatine seemed to be what was wanted, and Maddox in 1871 succeeded in making negatives by a process very much like that of Sayce and Bolton, but substituting gelatine for collodion. It was imperfect, however, and offered no advantages as far as could then be seen. As collodion emulsion for coating plates had been put on the market, Kennett, in 1874, prepared gelatine "pellicle"—dried emulsion—which was soaked in water, dissolved by heat, and poured on the plate. The great merit of the gelatine process was discovered by Charles Bennett in 1878, when he found that by keeping the emulsion gently heated for some hours or even days, it attained a degree of sensitiveness so far in advance of the highest reached by the wet plate process, that most of its first users failed through their plates being fogged by the dark room lights, which for collodion had been safe enough. What Bennett did at a gentle heat in days, Mansfield and Bolton rendered possible in a few minutes by boiling, and Monckhoven without extra heat by the mere addition of ammonia. By 1880 gelatine dry plates were fairly on the market, exposures had

been reduced to fractions of a second and modern photography had "arrived."

The eighties saw an immense growth both in commercial and in amateur photography. Swan showed that the same preparation ~~that~~ was applied to glass for negatives could be applied to paper for prints, giving us bromide paper. The original silver paper of Talbot had undergone little modification except that by coating the paper with white of egg, a fine surface had been given on which to form a picture, thus getting "albumenized paper," which held its own for nearly fifty years, and is responsible for most of the faded portraits in family albums. It was found that just as silver bromide could be "emulsified" in gelatine and applied to paper, so could silver chloride, and paper prepared with this and certain other silver salts was long supplied by Obernetter. The Ilford Company, in 1891, started its manufacture on a large scale under the name of P.O.P. (printing-out paper), and the impetus thus given to it soon sufficed to make albumenized paper almost a thing of the past.

One other development remains to be noted. George Eastman, an American plate-maker, early realized the commercial possibilities of a hand-camera provided with a roll of flexible sensitive material instead of glass, and sold the first Kodak, which used bromide paper, somewhere about 1886. Soon afterwards celluloid was substituted, and this was followed by "the daylight loading cartridge." In this advantage was taken of a device introduced nearly half a century before for the negative paper used by amateurs in those days. With the film or paper a strip of black paper was rolled, both longer and wider than the band of sensitive material. By this means it was possible to load and unload a camera with a roll of film in daylight.

The limits imposed by a work of this character prevent reference being made to many ingenious appliances and original methods worked out from time to time by inventors; and this sketch of the growth of photography has necessarily been limited to a demonstration of the way in which the methods most popular to-day have been evolved. Side by side with the evolution of processes there had gone on a perfecting of apparatus, in its way as remarkable, but to follow which would take too long. Cameras have altered less than might be

supposed ; the simplicity of their functions has not entailed any elaborate development of design. This is far from being the case with lenses, and it is no exaggeration, but almost an underestimate, to say that the anastigmat at the beginning of the twentieth century, though in a legitimate line of descent, is as far removed from the lenses available to Daguerre and Talbot in 1839 as the modern dry plate is from the processes of those pioneers. But an acquaintance with the history of the lens, though interesting, is not of much help towards its successful use, and we must forego even opening so large a subject, especially as to follow it up demands a familiarity with physical science not required by those who only utilize the tools which that knowledge places at their disposal. Let it suffice to say that the names of Petzval, Andrew and Thomas Ross, J. H. Dallmeyer, Steinheil, Abbe and Schott, Rudolph, Schroeder, Von Hough, Voigtlander, T. R. Dallmeyer, Aldis and Dennis Taylor form as brilliant a list as those of their fellow-workers whose labours have been set forth in this sketch.

So has photography grown, sometimes slowly, sometimes by leaps and bounds, but every step that has been taken has started from some earlier work, and in tracing the progress backwards, we are led further and further until the trail is lost in the darkness of antiquity. It is no one man's discovery, nor yet that of ten nor of a hundred men, but the product of many brains and many years. The greatest steps of all were taken, undoubtedly, by Wedgwood and Daguerre, but Wedgwood's did not lead him to a practical process, and if Daguerre's took him far, it took him at right angles to the main road that has come down to our own time. To show to what that road has led, is the purpose of what follows.

## CHAPTER II

### THE CAMERA

The camera and lens separately selected—The camera in outline—Rigidity the first essential—Testing for light-tightness—Ghosts—Stray light in the camera—The rising, falling, and cross front—The different forms of rising front compared—The camera extension—Focussing methods—The swing back—The reversing back—The ground glass—Dark slides—Carriers—Metal dark slides—The Mackenzie-Wishart slide—Magazines and changing boxes—Film-carriers—The Premo Film Pack—Roll holders—Stands—Studio stands—Tripods—Sizes of plates—Choosing a camera—The degree of extension needed—Large direct work *v.* small work enlarged—Patterns of cameras—Dust in the camera—Care of the camera.

THE chief instrument of the photographer consists of two parts, the camera and the lens. These two parts are so distinct, that in many cases the makers of lenses do not make cameras, and *vice versa*; and in all except the cheaper patterns of hand-camera and stand-camera "complete sets," the camera and lens are selected separately, and the lens is attached to the camera after purchase by the dealer who sells it.

The camera performs three functions—it holds the lens, it holds the sensitive plate in the proper position with regard to the lens, and it excludes all light from the plate except that which has come through the lens. The part of the camera holding the lens is always referred to as the front, but the term "back" is loosely used, either for the entire opposite end of the camera to the front, or for a detachable receptacle in which the plates, usually two, are carried. It wants no very elaborate mechanism to perform these functions; and the photographic camera, for the results it yields, is one of the most simple pieces of apparatus that can be imagined. The idea which so many people entertain, that a good photograph is necessarily the outcome of a "good" camera, or that it is in any way possible to judge of the excellence of the camera by looking at pictures



taken with it, is altogether mistaken. Some of the qualities of the lens may possibly be revealed in the work done with it, but then only to an expert, as we shall see later on ; but of the camera, none. The great merits of a good camera are the convenience with which it can be used, and the way in which it can be adjusted to meet the special requirements of each particular case.

The first essential is that it shall hold both lens and plate firmly in the desired position. When the camera is extended as it would be for taking a photograph, and the top of the front is held in one hand and the top of the back in the other no looseness should be felt between them. There should be no play at all, when the stays provided have been put into position and screwed up.

Then, of course, it should be light-tight. The effects of light leaking into a camera are twofold. The common result is a general fogginess or greyness of the negative, except where the plate has been protected by the edges of the dark slide. This is the case when the light does not shine straight on to the plate from one small opening, but is scattered about the interior of the camera by reflection. A less frequent result, but still one which is responsible for some of the most absurd fancies, is that of a "ghost." A typical case of this sort was submitted to the Royal Photographic Society many years ago. A photograph of a snow-covered scene in the Himalayas bore on it the ghostly images of two coolies, through whose bodies the scenery was clearly visible. It was suggested at the time that in the locality of the Mahatmas some supernatural forces might not improbably be at work ; but the real cause of the figures was plain enough. The camera having been set up, the shutter of the slide was drawn a short time before the exposure was made. A pin-hole in the bellows or in the camera front threw a pin-hole picture of the two men on the plate, and silhouetted as they were against the white snow, it would not require a very long exposure for a distinct image to be recorded. They may have been at the side of the camera, or in front. If the latter, they were got out of the way before the real exposure was made, which by making some of the landscape visible through the image of their bodies would give rise to the ghostly effect. These ghosts are so often met with

that at least a dozen cases have been brought to the notice of the author in the last twelve months, due undoubtedly to minute holes in some part of the camera.

There is also stray light at times which has got in by the orthodox entrance, the lens. This has been scattered by reflection from the sides of the camera, and even from the plate itself. More trouble has arisen in recent years than formerly on this score, because modern lenses, as a rule, include a much wider angle of light. The result is that not only is the plate lit, but much light shines on the bellows of the camera, and from them is reflected on to the plate. The better the lens, the more likely is the trouble; with reflector cameras, where the very finest of lenses are generally used, it may be very rife. What is worse, it cannot be prevented. It can only be minimized. To do this, the interior of the camera is painted over with a dull black paint, so that as much of the light is absorbed and as little is reflected as possible. If dust is allowed to accumulate on the inside of the camera, much of the good done by the blackening is lost, as the dust is light coloured and reflective.

Only the very simplest forms of camera have the relative positions of the lens and plate fixed once for all; in most patterns they are capable of adjustment in several ways. The first is by means of the rising, falling, and cross front. The most useful adjustment of all is the rising front, by which, still keeping the front of the camera parallel with the plate, the lens can be raised so that its centre is no longer opposite the centre, but may be as high as or even higher than the top edge of the plate. For reasons which will be discussed later on, the back of the camera must usually be kept strictly upright. When photographing a high building from a standpoint that is comparatively near, with the lens in the centre of the plate, we may find nearly half the picture is nothing but foreground, while most of the building is not on the plate at all. By raising the lens, as is done with the rising front, still keeping the camera level and the back upright, we shall find that more of the building and less of the foreground are on the plate, until a point may be reached at which the entire building is in the picture. For outdoor photography, where nearly every subject is bounded by the ground only a few feet below the camera,

while extending indefinitely in the other direction, the rising front is so constantly of service, that it would be better to have the lens permanently fixed above the centre of the plate, so that we always used a certain amount of rise, than to have it in the centre, so that we could never have any at all. The falling front is for employment under precisely opposite circumstances, but is very seldom wanted. Many cameras are fitted with cross fronts, by which the lens can be shifted from side to side. In the cameras which only take the plate one way, and have to be turned bodily on their side to take it the other, this cross-front movement is important, because when the camera is turned it becomes a rising and falling front. It is serviceable also when a stereoscopic pair of pictures is required, on a half plate for example. A partition is fixed in the centre of the camera, and the lens slid sideways until it is opposite one half of the plate to give the first picture, and then slid across to the other side for the other. Apart from this the cross front is not of much use. It is convenient at times, when, after much elaborate arrangement for a difficult subject, everything is right except the position of the picture on the plate, which is just a trifle too much to one side or the other. The cross front can correct this without interfering with the other arrangements. But this is only a makeshift, and should not be used except to a very trifling extent, or it may introduce other troubles, from alteration in the perspective.

The movement next in importance is that which allows us to alter the distance between the lens and the plate, for focusing purposes, or to accommodate different lenses. The base of the camera being fixed, this can be done by moving on it either the front carrying the lens, the back carrying the focusing screen and plate, or both. Studio cameras intended to use heavy lenses generally focus by sliding the back only. This is also the most convenient pattern for copying. Portrait lenses are generally mounted in a tube with a rack and pinion, so that after focussing approximately by sliding the back of the camera, fine focussing is done by racking the lens in or out.

In some hand-cameras focussing is effected in a somewhat similar manner. The lens mount has a very coarse screw-thread on it, and runs in a jacket with a similar thread. The lens is then drawn in or out by merely turning it in its jacket.

For general purposes, and especially in most forms of landscape and hand-camera, it is the front that moves, and in the most adaptable of all both back and front can be moved. Whichever it is that slides, it ought to do so smoothly and evenly with no tendency to wobble sideways, and with as little play as can be expected from the kind of workmanship paid for.

We have already referred to the importance of keeping the back of the camera vertical. In order to do so when the camera itself is tipped up, as in the attempt to photograph a high building, most cameras are provided with a "swing-back;" that is to say, the back to which the bellows are attached is




FIG. 4.




FIG. 5.

not fastened directly to the baseboard, but swings on trunnions within a frame (Fig. 4), or else is pivotted on its bottom edge and fastened where desired by means of a strut (Fig. 5). The former method is easier to use, but there are constructional advantages—the camera is simpler—when the latter is employed, and the difference is not enough to trouble about. A camera that has to be turned bodily over to take a picture the other way of the plate should have a back which swings horizontally as well as vertically, as the one becomes the other when the camera is turned. If the camera has a "reversing back" there is no need to turn it, and no need for the horizontal swing whatever. It is sometimes said to be useful in

*focussing*, allowing one edge of the plate to be nearer to the lens than the other, when photographing a long row of objects that reach from the camera; and the purists point out that this introduces distortion or makes the perspective false, and condemn the practice accordingly. There seems to be no real reason why it should not be employed, when absolute literal truth is not the immediate object of the photograph—and this must be the case in ninety-nine per cent. of the exposures made at the very least. Our objection is rather that it is so seldom required as to be a needless complication.

Most stand-cameras are now made square at the back, and are fitted with a reversing back. In architectural work; particularly, it is convenient to be able to put the reversing back into the camera in any one of the four possible positions, because it often happens that every inch of room behind the camera is valuable. We have known a lot of time wasted in setting up a camera and getting everything ready to take the picture, only to find that a wall or pillar or some similar obstacle absolutely prevented the shutter of the dark slide from being drawn. If the back could have been turned half round, so that the slide was drawn out from the other side, this trouble would have been prevented.

The focussing screen is generally a piece of ground glass, though in some small cameras ground celluloid is used for lightness and to prevent risk of breakage. In all other respects glass is much to be preferred, and in everything above quarter-plate size is essential. It should be perfectly flat and very finely ground. Some cameras are fitted with such coarse screens that anything like fine focussing is impossible. Such a screen is best taken out and replaced by something better. Special finely ground flat glass is now sold for this particular purpose.

The American term "plate holder" is distinctly preferable to "dark slide," the name generally given in this country to the appliance by which the plate is carried about protected absolutely from light except at the moment of exposure. The early cameras made to take wet plates were usually fitted with a single dark slide to hold one plate only. Instead of having a reversing back, they had a square dark slide in which the plate could be put either vertically or horizontally. A good

*many such instruments are still in use in old-fashioned studios, and a very similar, but more elaborate, dark slide is employed in process cameras ; but for all ordinary purposes the old single wet-plate slide has been supplanted by the "double dark slide" or "double back."*

Double dark slides are generally made of one of two different patterns, known respectively as "book form" and "solid." The former are the more costly, and as a rule are better finished ; the latter are cheaper to make, and take up less room when opened—a consideration where the dark room is small.

The regulation number of double dark slides per camera is three, and in comparing the prices of different instruments, it is well to make sure that each price includes the same number of slides. With small cameras, it is often very convenient to have more than three ; as many as half a dozen, in fact, are useful. But dark slides, if the most convenient in use, are an extremely bulky way of carrying plates, and when many exposures are required some other means should be employed. Cases lined with flannel and made to hold one dark slide each can be purchased, and save scratching and other injury to a nicely finished slide, as well as acting as an additional safeguard against light-fog ; although the dark slide that needs this must be a very bad one, and a snare. Carriers or inner frames are supplied, which fit in the slides in the places occupied by the plates, and so enable a small plate to be used in place of a large one. These carriers can be got in nests fitting one inside the other, and taking a whole series of sizes.

Of late years there has been something like a revival of the single slide, several very compact forms having made their appearance, some of which, made of metal, are not much larger than the plates they enclose. The Mackenzie-Wishart plate holder is a single wooden slide, the plate being carried in a particular form of envelope, of celluloid and light-proof cloth. One of these being shut up in the slide, the act of drawing the shutter opens the envelope and exposes the plate to the camera. Replacing the shutter closes the envelope again, and it can then be taken out of the dark slide in daylight, and a fresh plate in another envelope inserted. This arrangement is extremely compact, and, if used with due care, is effective.

There is no limit to the number of envelopes that can be used, one single slide serving for all of them.

Ingenuity has been lavished on plate-holding devices, but to this day the dark slide, altered very little in design since the introduction of the dry plate, holds its own undisputed in larger sizes, and equalled, but not excelled, even for small plates. The magazine, usually holding a dozen plates, although excellent for quarter plates, five by four, and possibly half plates, is not very suitable for larger sizes, and even for small plates has drawbacks of its own. The failure of a dark slide from any cause only means that one plate or at the most two cannot be used ; but if the more elaborate changing mechanism of a magazine jams, the photographer relying on it finds his work completely stopped. For this reason, and because of its greater complication, nothing but the best of magazines is to be recommended. A cheap form of dark slide, if not elaborately finished, may nevertheless be perfectly efficient ; but a cheap magazine is to be shunned. The only form the author can recommend is the "N. & G.," in which the plates are carried in sheaths, twelve plates or twenty-four films in each box. The top of the box is a soft leather bag, into which the dark plate is raised by drawing up a "lifter." The plate in its sheath is then caught hold of through the bag, and is pushed down a slot into the front of the box, ready to receive the image as soon as the shutter is drawn. When it has been exposed, the next plate is raised, picked up, and pushed down, sliding in front of the first and pushing it back in so doing. This changing box is very efficient in small sizes, but has certain inconveniences. The exposed plates being in front of the others, and the box being loaded and emptied from the back, it is necessary to take all the plates out to get at the one or more that may have been exposed, for development. Moreover, the box must be handled carefully, and the sheaths must on no account be allowed to get bent, or they may jam and render the box useless until attended to in a dark room. In handling the plates, it must be done so that there is no risk of a sharp corner of glass piercing the leather bag, and the plate should be held sloping with its top away from the front of the box to avoid rubbing anything against the face of the plate. There are a number of devices for carrying plates

in the camera itself, but these all apply to hand-cameras only.

Those who use films instead of plates find the dark slide or changing-box problem much easier. In the first place, all apparatus without exception which will take glass plates will take cut films. In some cases no additional apparatus at all is required; in others some form of carrier or sheath must be used, applied to which the cut film becomes the same size as a plate and as stiff, and is treated throughout in the same way. The simplest carrier is a thin metal frame in which the film slips, a black card of the requisite thickness sliding in also and holding it in position. In another form the card is dispensed with, the sheath being simply a thin sheet of metal, with corrugations to stiffen it and give it the requisite thickness, and with its edges turned over to form grooves to hold the film. In large sizes, cut films mean a very great decrease in weight, and they can be used in dark slides without any carrier at all. The film is placed in the grooves just like a plate, and a piece of stout card the same size is placed on it, and the dark slide closed. The spring in the centre of the slide in such a case must be removed, or it will make the middle of the film bulge out. Another effective plan, which does away with the need of removing the spring, is to insert behind the film a light wooden frame, like a plate-carrier but without any catches. If the spring does not project beyond the thickness of the frame, it then does no harm, the author has used  $12 \times 10$  cut films in this way, without any sheath, quite successfully. If negative paper or bromide paper of large size is to be used, it has not the stiffness of a cut film, and may be attached by gummed paper strips to the wooden frame, to avoid any risk of it bulging into the camera.

But all these take no advantage of the great merit of the film—its flexibility. It is only when we come to the roll holder and the "film pack" that the celluloid film shows how readily it adapts itself to the requirements of the photographer, and especially to arrangements for daylight loading, dispensing entirely with all need of a dark room for filling or emptying slides or cameras, or indeed for developing. The best device for using cut films is that known as the "Premo" film pack, the invention of an Englishman, though made in the United



States at Rochester, New York, by the Eastman Kodak Company. The "Premo" film pack consists of two parts—the holder, which may be separate for insertion like a dark slide into the camera, or may be built into the camera itself, as is the case in some forms of hand-camera; and the film pack, which is sold ready loaded with a dozen films. Each film is attached to one end of a long strip of black paper, which is led round a roller at one end of the pack of films, up behind them, and ends in a numbered tab which hangs loose outside the pack. The film pack is put into its holder in daylight, exactly as bought, a label is broken, the holder is closed up, and on pulling the first tab, the first film is exposed in the holder ready to receive the picture. On pulling the next tab, the first film is drawn round the roller to the back, and the second is ready for exposure, and so on through the whole dozen. When the last tab is pulled, the holder may be opened and the pack taken out in daylight, and a new pack substituted, and so on.

A film pack may be opened, and one or more films taken out for development, and the pack closed up again for exposure of the rest; but, though possible, it is much better to avoid this all one can. The pack, when all are exposed, is easily opened, the films taken out for development, and the pack itself thrown away. As each film is carried round the roller to the back, there is a chance that its sensitive surface may get rubbed or scratched, the changing should therefore be done gently. Some workers seem particularly unfortunate in getting these scratches, others never or hardly ever meet with them; so that it looks as if they were due largely, if not entirely, to the personal factor. The author has exposed hundreds of films in the film pack, without more scratches than occur in the most perfect form of plate magazine, certainly without anything to counterbalance the very great advantage of this ingenious device. Its most serious drawback is a defect of its qualities. The very ease and simplicity of the changing, and the fact that the film packs are light, portable, and can be replaced in full daylight, are a great temptation to make more exposures than would be the case were the changing less facile.

For those who use roll film in lengths there is the roll holder. In spite of the fact that more roll film is used to-day

than ever, the roll holder, *qua* roll holder, is almost obsolete. The reason for this is that roll film is almost exclusively used in hand-cameras, or at least in cameras specially constructed to take the film. In other words, the roll holder is very seldom a separate fitting, but is usually part and parcel of the camera itself, and not separable from it. Separate roll holders can be bought, however, which can be used in place of dark slides, it being necessary to state, when ordering spools of film for them, that they are required for a roll holder. The only pattern now made is Eastman's, supplied by the Kodak Company in various sizes up to and including  $7 \times 5$  inches.

Beyond half plate, the conveniences of roll film are to a great extent lost, as it is not likely with large sizes that so many exposures will be required between each changing. The difference between the cost of film and glass is also more noticeable, and there is also the difficulty of keeping the thin flexible film flat. Even with half plate this is an important matter when modern high-class lenses are used, with which a very slight degree of unevenness in the plate or film means a loss of some of the advantages of the lens.

Camera stands may be divided into two classes, tripod and studio. The amateur as a general rule is content with a tripod stand, but for portraiture, for photographing such subjects as flowers, fruit, natural history specimens, and for copying—in short, for general work indoors, a studio stand, even if very simple and with few adjustments, will be found a very great convenience. It is a great nuisance to find, when all has been arranged, that the camera ought to be just an inch or two nearer to the subject, or *vice versa*, and that in consequence of a tripod being used, all the adjusting and levelling has to be done over again. For those who do not wish to have two stands, but yet appreciate the convenience of the stand on casters, there is an ingenious appliance called the "Folding tripod adapter," a three-armed wooden frame running on casters, with a place at the extremity of each arm to receive the tripod foot. This gives some of the advantages of the studio stand.


The tripod is the popular form of stand, and combines a maximum of rigidity with a minimum of weight. The weak point in most tripods is the attachment of the legs to the

tripod head, and when a stand is shaky, it will nearly always be found that the source of the trouble is at the top. The firmest tripod the author has ever used is the "Ashford," but this is a comparatively heavy pattern and in its most rigid form is only twofold, though a threefold pattern is made. Anything less than threefold is inconveniently long at times, and if the outfit is to be carried on a cycle a fourfold tripod is a convenience. However many the joints in the legs, one of them should be a sliding one, clamping with a screw. Other things being equal, the bigger the top the firmer the stand. Some tripods with very small tops, even if firm to start with, soon get so shaky that they are worse than useless. Tripod stands are sometimes made of metal, steel or aluminium usually. Each leg is tubular and telescopic. But such stands soon get very shaky, and a single blow will make the whole stand useless; so that, except under very special circumstances, legs made of good ash are to be preferred.

If the camera is to be used exclusively for work on the tripod, instead of having a tripod stand with a separate head, a "turn-table" may be let into the baseboard of the camera, to which the tripod legs are directly attached. There is a gain both in firmness and in portability by this means; but if any part of the turn-table project beyond the baseboard, as it does in some patterns, it makes the camera a very awkward one to use on a table, or on anything but its own tripod. All things considered, when the photographer has only one camera, it is better to have the tripod head separate altogether.

It is difficult to give any advice, other than generalities, on the subject of buying a camera, as so much must depend on the circumstances of each particular case. The standard sizes of plates in Great Britain and America are as follows:—

Inches.		
$3\frac{1}{4} \times 3\frac{1}{4}$	...	British lantern-plate size.
$4 \times 3\frac{1}{4}$	...	American " "
$4\frac{1}{2} \times 3\frac{1}{2}$	...	Quarter plate. The most popular British hand-camera size.
$5 \times 4$	...	The most popular American hand-camera size.
$6\frac{1}{2} \times 4\frac{1}{2}$	...	True half plate. (Now obsolete.)
$6\frac{1}{2} \times 4\frac{3}{4}$	...	Half plate. The most popular British stand-camera size (the size for cabinet prints).
$7 \times 5$	...	The most popular American stand-camera size.



THE WHITE SAIL  
BY ALEXANDER KEIGHTLY



Inches.		
$7\frac{1}{2} \times 5$	...	Occasionally used in Britain for landscape cameras.
$8\frac{1}{2} \times 6\frac{1}{2}$	...	Whole plate.
$10 \times 8$		
$12 \times 10$		
$15 \times 12$	...	The most popular of the "large" sizes.

Here, clearly, is plenty of room for choice. For a hand-camera, quarter plate has very many advantages over every other size. The plates are not heavy; they are sold everywhere, and so are easily obtainable, and more likely to be fresh than other sizes, except, perhaps, half plate. A quarter plate, if taken with a good lens, should be capable of enlargement up to  $15 \times 12$  with effect, and the condenser required to do this with artificial light is neither cumbrous nor expensive.

It should not be forgotten that the definition possible with small plates is better than is practicable with large ones. This opens up the question, Is it better to take a large photograph direct, or to take a small one and enlarge it? When the camera is to be carried about, the small negative and enlarging offer many advantages, while for studio and similar work direct photography on large plates is preferable. The author has used a quarter-plate camera for years for nearly every purpose, making direct enlargements on bromide paper or enlarged negatives when bigger pictures are wanted. There should be little in an enlargement  $15 \times 12$  inches, if it is on rough bromide paper, to show whether it is made by contact from a negative that size or enlarged from a quarter plate. Framed and hanging up, no one should detect any lack of detail from the fact that it was enlarged.

If a stand camera is to be used, a half-plate is as large as can be carried about far without discomfort. Half-plate has this against it—that prints that size are not very imposing, while enlarging means that daylight must be used, or else a very cumbersome condenser, 8 inches in diameter at least, must be employed. For these reasons, if the camera is not to be carried about very much, whole plate is a better size. Whole-plate prints are quite capable of holding their own at an exhibition, and the apparatus is still not unwieldy.  $10 \times 8$  is not very popular, being considerably heavier and more costly

than whole plate, without any very apparent gain in the importance of the prints, the next notable size to whole plate being  $12 \times 10$ . This gives a fine large print, but is not very manageable, and is certainly not portable.

In selecting a stand camera, if for use indoors, and weight is not very important, the square bellows pattern, with folding tailboard, the front fixed rigidly at right angles to the base-board, the back drawing out and clamping by means of two screws on the top of it, is old fashioned, but unsurpassed for rigidity, strength, and general convenience. Except to carry about, this form can hardly be improved upon. A half-plate camera of this type should have an extension of at least 16 inches from focussing screen to front; a whole plate should extend 22 inches. It is heavy, however, and does not extend so far as one of the lighter forms of "landscape" camera.

The most popular form of stand camera, one that has come to be more or less a standard pattern, is the taper bellows




FIG. 6.

form, extending back and front (Fig. 6). If properly made, it is convenient to use, light to carry, and remarkably rigid. We have already seen some of the tests to which it should be put; but if it is got from a reliable dealer, there ought to be no trouble either from lack of register, want of rigidity, or light leakage. It should either have a swing back or else a great rise of the front, as in the Sanderson. If

it has not this rise, which should be sufficient to bring the middle of the lens opposite the top of the plate when this is vertical, and even if it has this, unless a very high-class lens is to be used, a swing back is useful. A half-plate camera of this type should extend 18 inches from focussing screen to front, or if of "triple extension" it should extend to 22 inches.

Three double dark slides should form part of the outfit, and a leather case, to hold camera, slides, tripod head, focussing cloth, and lens, is certainly desirable. Waterproof canvas cases are supplied for this purpose, but they do not protect the camera

so efficiently, nor are they so cheap in the long run, for a good leather case will outlast three or four of them. The camera when not in use should be put away in its case, and kept in a dry place. If it gets damp it may work stiffly, or even refuse to work at all. Dust inside it is more than untidy; as already pointed out, it is harmful. Dark slides should be kept clean inside and out. Inside, dust causes minute spots which appear black on the prints; outside, it gets carried into the camera on the slide, wiped off on to the inside when the shutter is drawn, and so causes trouble. Sliding parts, where wood moves on wood or on metal, must not be greased, but may be lubricated, if they work hard, with a little fine black lead applied with the finger. The whole of the inside of camera and dark slides should be blackened and kept black. Matt black varnish is sold for the purpose, and a drop may be applied to any bright parts. The spring in the dark slides, where it touches the centre of the plate, wears bright in time, and we have seen very conspicuous black marks on negatives caused by nothing more than the reflection from it. A morsel of black court plaster will stop up a pinhole in the bellows. Properly taken care of, the camera should last out the photographer himself, and should not perceptibly deteriorate in efficiency, if its looks get a little the worse for wear. But this chapter is best finished, as begun, with a reminder that the quality of the work in no sense depends on the quality of the camera. The advantage a good instrument offers over a bad one is very great, immeasurable almost, but it lies entirely in convenience and comfort in use, and in adaptability to varying conditions of work; and so long as it can be made to keep the light out, as fine photographs can be made with a packing case as with the most expensive instrument ever constructed.



## CHAPTER III

### THE LENS IN PRINCIPLE

The myth of the wonderful lens—Fancy prices for lenses—The description of lenses—Focus and its measurement—Principal focus—Back focus—The stop—Systems of marking stops—Stops and exposure—Effective aperture—Selecting a lens—Defects—Striæ—Centring—Covering and defining power—Curvature of the field—Astigmatism—Curvilinear distortion—Spherical aberration—Flare spot—Achromatism—The fallacy of examples of work.

**I**T marks one stage further in photographic knowledge when a person says of a photograph, "That must have been taken with a wonderfully fine lens," instead of attributing the excellence of the product to the camera. Yet as in the case of the camera, so with regard to the lens, it is not possible, without knowing something of the conditions under which the photographer has to work, to say whether the lens was a magnificent instrument, or one of the most rubbishy and worthless character. This is not to suggest that there is no practical difference between them, or that a fine lens is not worth all the money charged for it, but only to say that the good qualities of a lens are not superficial ones, and that it takes a knowledge of photography to appreciate the excellence of the lens, and a good deal more than a knowledge of photography to make a critical examination of it, and to ascertain how close it comes to the ideal instrument.

There is another common misapprehension that it is well to remove before going any further, and that is one which has been called "the myth of the wonderful lens." In the dark ages of photography—ten years ago at the least—more was heard about the superlative qualities of some particular instrument or other than is the case to-day, and there is no doubt that in some cases there was just this foundation for the myth, that the lenses of the same type and by the same maker

often differed amongst themselves very considerably. With one or two exceptions, the lenses were made and tested by rule-of-thumb methods, which perhaps were all that were necessary at the time, but which made possible considerable difference in the qualities of different instruments allowed to go out into the market. The great improvements in lens design which have taken place in the last few years have made such methods of manufacture obsolete, or nearly so, and the makers have been obliged to employ refinements in manufacturing and testing which have done away with most of the old element of chance. One thing now is quite certain, and that is that in buying a modern lens by a reputable maker, one particular instrument of the type is practically as good as another, and all are far superior to the best productions of fifteen or twenty years ago. We can be sure that if a photographer gets some supremely fine results in the way of definition, he does so, not by the occult properties possessed by the particular lens he is using and not shared by others of its make and class, but by the care and skill with which he employs it, and the favourable conditions under which he is working.

A few years ago the apparatus of a well-known amateur photographer who had won many medals for his work, was put up to auction, and, to the amusement of those who knew better, the lenses he possessed—and he had a good few of them—fetched considerably higher prices than lenses of exactly the same sort and by the same maker could be bought for new. It has not transpired that the work they have since done has been so successful, and the whole thing was a good example of the mistaken notions which prevail as to the true causes of photographic success.

A lens is generally described as being of such and such "focus," working at such and such an aperture, and covering such and such a plate. The last term explains itself; the focus and aperture may need a word or two.

The "focus" of a lens, as that term is generally understood, is the distance from the plate or ground glass to the lens, when it is focussed on an object at such a distance that everything beyond it is also in focus. The measurement may be made to the diaphragm of a double lens or to the glass of a single lens, and will then be approximately correct. Or we may focus

sharply some object so that its image on the screen is exactly the same size as the original ; the lens will then be found to be equidistant from the plate and from the object, and the distance in each case is twice its focus. Further refinements are not needed in practical work.

The stops are never described by their actual dimensions, but by the relationship between the focus of the lens and the diameter of the stop. This is generally expressed as a fraction,  $F$  (the numerator) standing for the focus, and the number of times the diameter of the stop is contained in it being the denominator. Thus a stop 1 inch diameter, used with a lens of 8 inches focus, would be described as  $F/8$  ; this expression is generally referred to as the "F number."

With a great many modern lenses the largest stop employed has a diameter equal to one-eighth of the focus of the lens ; it is known, therefore, as  $F/8$ . The next size smaller to require twice the exposure is  $F/11\cdot3$ , the next  $F/16$ , the next  $F/22\cdot6$ , the next  $F/32$ , the next  $F/45$ , the next  $F/64$ . Beyond this very few lenses go ; in fact, few go as far as  $F/64$  now, although in the old rapid rectilinears this was always the smallest stop, and gave its name to a class of photographers who were noted for their fondness for the utmost definition, only obtained in those days by much stopping down ; hence the term " $F/64$  men" applied to these enthusiasts. Portrait lenses work at  $F/4$  or larger, and the series in their case becomes  $F/4$ ,  $F/5\cdot6$ ,  $F/8$ , and so on as above. The competition to make lenses with as large apertures as possible has led to the manufacture of many, the largest stops for which are of odd sizes such as  $F/6\cdot5$ ,  $F/6\cdot7$ ,  $F/7$ ,  $F/7\cdot7$ , and so on. With these, as a rule, the custom of making each stop require twice the exposure of the preceding one does not hold good with the two largest openings ; it is found most convenient for the largest opening to be whatever is the maximum working aperture, and the next to be  $F/8$ , after which the exposures double, as usual.

This arrangement makes it very easy for the photographer to go from one lens to another without getting wrong with his exposures. He knows, for example, that whatever lenses he be using, however big or however small, so long as he uses each with its stop marked  $F/8$ , the exposure with every lens will be the same. A word of caution is necessary here. The exposure

is only the same so long as the lens is being used at or near its principal focus. This is the case in most landscape and hand-camera work ; it is not so true when we come to interiors and portraits ; while in copying, if unintelligently applied, it would lead us altogether astray. For example, when copying the same size, the plate is distant from the lens twice the focal length of the latter ; the stop, therefore, which the optician has marked  $F/8$  is not for the time being one-eighth the focus, but one-sixteenth, and the exposure required is therefore four times as long. There are tables showing how, in copying, the extension of the camera affects the nominal value of the stop, and in doing work of this kind these tables should be consulted. For portrait work, interiors, and so on, the difference, though at times perceptible, is not great enough to introduce any serious difficulty, or to lead the photographer astray ; though if his exposure errs in the direction of insufficiency, this will help to make matters worse.

There are other ways of marking stops besides that of giving their "F values." The U.S., or "Uniform System," was put forward by the Royal Photographic Society many years ago, but was not received with any enthusiasm. At length, after many years, some of the most popular cameras had their lenses marked in this way—all Kodaks, for instance, are graduated on the U.S. The Society then, rather perversely, withdrew its recommendation ; but just as its advocacy had no perceptible effect on the adoption of the method, its withdrawal does not appear to have influenced its popularity.

The U.S. system starts with  $F/4$ , which at the time of its introduction was the speed of most portrait lenses.  $F/4$  is known then as 1 ;  $F/5.6$ , requiring twice the exposure of  $F/4$ , is called 2 ; and  $F/8$ , requiring twice that, is U.S. 4. The others are as follows :  $F/11.3 = \text{U.S. } 8$ ,  $F/16 = \text{U.S. } 16$ ,  $F/22.6 = \text{U.S. } 32$ ,  $F/32 = \text{U.S. } 64$ ,  $F/45 = \text{U.S. } 128$ , and  $F/64 = \text{U.S. } 256$ . The merit of these numbers is that they express directly the relative exposures which the different stops require. Thus we know that with  $F/64$  (U.S. 256) we must give 256 times as long as with  $F/4$  (U.S. 1). In actual practice, however, there is little or no advantage, as the simple relationship expressed by saying that each stop requires twice or half the exposure required by its neighbours, respectively,

answers all requirements of the photographer. It may be useful as an aid to memory if we point out that  $F/16$  is U.S. 16, and that the other U.S. numbers in order are each double or half the preceding number.

There are several other systems of marking stops; the simplest is the method used by Zeiss, when one iris diaphragm is to be used with two or more lenses. The aperture of the diaphragm and the focus of the lens are given in millimetres; the  $F/-$  number is the one divided by the other.

While it takes a skilful optician to test a lens exhaustively, the user can make a trial for himself which will at least show him some of its capabilities. And first a word of caution about appearances. Some parts of the best modern lenses are made of optical glass of a particular kind, one of whose peculiarities is that it is impossible to secure it quite free from minute bubbles. On looking through one of these lenses the bubbles, in all probability, will be the first things seen, and it may be supposed that they are defects. Of course it would be much better if they could be got rid of without impairing the other qualities of the instrument; but as they cannot, and as the damage which they do to the defining power of the lens is quite inappreciable, the photographer must just put up with them. If he means to avoid them he must get an inferior lens made of glasses in which they are avoidable.

The most serious defect which a lens can possess, which a casual examination will reveal, is the presence of "striæ" in the glass. These are little lumps or masses of uneven density. Perhaps the best explanation is to compare them with the striæ which are seen when a strong solution of hypo is mixed with water. They should always be looked for when buying a lens—just as when, negotiating for a horse, it should be noted that he has four legs—but they certainly should not be found. Striæ are seen by looking through the lens, holding it a few inches away from the eyes and near some printed matter.

The next thing to note is that the whole of the interior of the metal mount of the lens has been treated with some dead black, so that, could the eye be put at any position occupied by the glasses of the lens, or at any position inside the camera, no particle of bright metal could be seen.

The most beautifully designed and finished lens ever made

could be completely ruined by being put up badly in its mount. The different curves to which its glasses are ground are all parts of spheres, and the centre of every one of these spheres must lie upon the imaginary line running right through the middle of the lens, and called its axis. If this is not the case, if the lens, in other words, is not properly centred, it is worse than useless. The centring is all the more important to the purchaser, because apart from the reputation of the lens maker, there is always a possibility that the lens may have had some mechanical injury since it left his hands which has affected the centring. This is easily examined. If we hold up a lens a foot or two from the eye, and look through it at a candle-flame 10 or 15 feet away, by twisting the lens slightly out of the straight line joining the eye and the flame, we shall see a number of reflected images of the flame on the different glass surfaces of which the lens is composed. Watching these carefully, we swing the lens round until they all close up and overlap to form one image as we look straight through. If they come together gradually and regularly, and if all exactly overlap at the finish, so that only one image of the flame is to be seen, the centring is satisfactory.


Before putting the lens in the camera there are one or two other things which we may note. Its surfaces should be very highly polished ; there should, of course, be no sign of greyness or of imperfect polishing. If the lens projects beyond the metal of the mount, it should be examined for scratches and injury on the projecting surface, a very common defect in second-hand lenses which have been owned by those who did not know how to use them. A lens, of course, should not be cracked, but it may come as a surprise to many to know that the principal injury produced by a crack applies to its selling value, and not to its performance. If the same blow that caused the crack did not affect the centring, it is doubtful, unless the crack is very bad, whether its effects could be detected at all in the work done by the lens.

The mount of a lens generally prevents it from being used to quite the extent it might be otherwise. This is not necessarily a defect, and in at least one famous type, the mount was expressly arranged to prevent the lens from being used for purposes for which it was not intended, and so perchance

appearing inferior. Latterly, however, the tendency has been all the other way, and some lenses are not provided with sufficient mount to give them a reasonable protection from accidental injury. To ascertain if the mount of the lens gets in the way is very simple. Focussing some distant open view, the ground glass is removed, and the eye is brought to the position of one corner of it. In many cameras the corners of the ground glass are cut away, and in these all we have to do is to apply one eye to one of these openings and look into the lens, which must be at its largest opening. If the opening of the stop does not seem its proper shape from this view point the mount is cutting off, and smaller and smaller stops must be inserted until one is found which is seen in its true shape. This is then the largest stop which can be employed without the mount affecting the evenness of the illumination of the lens; and, other things being equal, the larger this stop is, the better is the lens in this respect.

So far the lens has been examined in the hand; it must next be placed in the camera and tried on the ground glass. In doing this, it is most important that the flange of the lens should be quite flat upon the camera front, as anything which tended to tip the lens however slightly to one side or the other, would deprive the test of all its value. This fixing is not so important when the lens is to be used temporarily on a camera, under conditions which are not likely to be trying. It is possible, if the hole in the camera front is too large for the temporary lens, that this can be fixed by cutting a hole in a piece of black card so that it just fits on the screw of the lens mount, pushing this through the card, and holding the lens to the card by screwing on the flange. The card is then fastened over the hole in the camera front. Such a make-shift, however, is quite unsuited for testing a lens, and would make the lens seem much worse than it really is. For the same reason, when trying a lens in the camera, it is of the very utmost importance that both the back and front of the camera shall be precisely at right angles to the base-board. Having seen to this, we shall be in a position to examine both the "covering power" and the "defining power" of the lens.

For testing purposes it is quite useless to employ such a subject as a person or a landscape, because its different parts



THE VILLAGE TREACHER  
IV JANUARY





are at different distances from the camera, and it is not possible to distinguish the want of definition due to this difference of distance from that caused by any shortcomings of the lens itself. For this reason a flat object must be employed, and nothing is better than a newspaper opened out as much as possible and pinned flat upon a wall. The larger the type on it, in reason, the better. Opposite such a subject, taking great care that the lens is opposite the middle of it, and that the camera is quite square with the wall, we take our stand. Covering the head with the focussing cloth, we proceed to focus the picture as sharply as possible, using the full aperture of the lens, and removing the camera from the subject, if possible, until we can see about half the newspaper on the ground glass. The first thing to note is the "covering power" of the lens—that is to say, whether it will give an image over the whole of the ground glass. To ascertain this we look to the corners. They may require focussing again, but the image should be visible there when the lens is opposite the centre of the focussing screen. If it is not visible, then the lens will not "cover" that size of plate at all, and is useless for it. But it ought to do more than this, because we are sure to want to use the rising front at some time or other. We raise the front now, little by little, looking at the bottom corners and refocussing when necessary, to ascertain how much the front can be raised before the corners are cut off. This test it is well to repeat on some landscape subject at the first opportunity, as, in consequence of the comparative nearness of the newspaper to the lens, the photographer may be led to suppose that he has a greater power of raising the lens than he will find to be the case when he comes to use it out-of-doors.

Unless the lens is one of the modern "flat-field" instruments, it will be found at once, on trying it in this way, that when the centre of the picture is sharp the edges are blurred, and *vice versa*. If it is of either the "single" or the "rectilinear" type, this curvature must be expected. It may not give any very great trouble, because such lenses are not likely to be used much for copying from the flat, as in the test subject; but if the lens is supposed to give a flat field, and there is found to be any need for refocussing to get the corners sharp after focussing on the centre, it is defective. If all the four corners come

sharp together, it may be taken that the wall and the ground glass are parallel, and that the test is a good one; if they do not, the apparatus must be re-arranged before the test can be considered conclusive. Curvature of the field is a serious matter when copying with large apertures, but for many other purposes is not at all important. It has the effect of requiring objects at the edge of the plate to be nearer to the camera than objects which fall on the centre of the picture; so that in many cases it is possible to arrange the subject accordingly; we can get the outside members of a group to come a little closer, for example. In landscape work this is not possible, though even then it is not often very troublesome. It can be remedied by the use of a small stop.

The same test subject will allow us to examine the lens for "astigmatism." We select some of the black lines on the newspaper which run parallel to each other, such as the "rules" that are placed between the columns, and focus these with full aperture as sharply as we possibly can. On examining lines that run in a direction at right angles to these, if the lens suffers from astigmatism, we shall find that they are not sharp. If we focus the second lot of lines, the first will become fuzzy. All the older forms of lens, portrait, rectilinear, etc., possess astigmatism, but the modern types should be capable of going through this test without revealing any trace of it to the unaided eye. It is a serious handicap when a lens has to be used for copying and similar work, and is a distinct drawback in architectural photography. For most ordinary purposes, however, except that the definition of a lens suffering from astigmatism is never quite so good as when it is free from it, it is possible to reduce it by the use of a smaller stop. The lenses where the photographer is most likely to encounter astigmatism are the rapid rectilinears, of which so many are now in use. These vary enormously in this respect; some do not show more than a trace of it at the corners of the field, with others it is easily seen almost as soon as we get away from the centre of the picture.

There is another defect which may be looked for while this test is in progress. Let the camera be so arranged that one of the aforesaid "column rules" is represented on the ground glass at the extreme edge of the plate. If we focus it sharply

and then apply a straight-edge to the ground glass, the line which was straight in the subject may appear curved in the image. With a portrait lens this is certain to be the case, and may be passed over, as this form of distortion is not important in the work to which such lenses are put. It is also inevitable in all single lenses, although some manifest it in a much higher degree than others. All rectilinear lenses, however, should be absolutely free from it—their very name implies this—and if not they should be returned forthwith to the maker. Modern high-class lenses, also, should show no signs of it, except when one-half of the complete lens is used by itself, and even then it should be difficult to detect the distortion. There is no cure for this defect at all; it is not remedied by stopping down, and it unfits a lens for most architectural photography and for copying. For landscape, portrait, and hand-camera work generally, its presence, to the slight extent generally met with, makes no difference.

Distortion has no effect at all on the centre of the picture and is due entirely to the position of the stop. In single




FIG. 7.

lenses the stop is generally placed in front of the lens, that is between the lens and the subject. If with this arrangement we photograph a square, as in A, Fig. 7, the distortion gives us a figure such as B, this is known as "barrel-shaped distortion." If the stop were put behind the lens, we should get the form shown in C, "cushion-shaped distortion." The further the stop is in each case from the lens, the better is the definition and the worse the distortion. When, as in a rectilinear, the stop is midway between two lenses, the one kind of distortion neutralizes the other, and an undistorted image should be the result. While no degree of stopping down will remedy distortion, it can be reduced by lessening the distance between the lens and the stop; this impairs the

*definition, which in its turn is remedied by the use of a smaller stop. It is possible when a negative shows distortion, to make an enlargement from it with a single lens, with the stop in the opposite position, so that by again distorting the picture, but the opposite way, an undistorted result is finally attained.*

Theroetically the curves of a lens should not be parts of spheres, but should have a parabolical form. Such a form, however, presents such immense difficulties in manufacture as to put it quite outside the sphere of practical optics, the consequence is that photographic lenses suffer to some extent from what is known as "spherical aberration"; although in the best forms, this is reduced to such a degree that it is not capable of detection in the ordinary way at all. To detect spherical aberration, a circle of black paper should be cut, the size of the front surface of the lens. Out of the centre of this should be cut another circle having a diameter of about two-thirds the first. This smaller circle is fastened in the centre of the front of the lens, with a drop of moisture, and the image is sharply focussed; thus using the edges of the lens only, to form the picture. Removing the circle, without shifting the lens, it is wiped clean, and the black ring substituted for the disc, thus using the centre of the lens only. If the image is still sharp, there is very little spherical aberration, but if it has to be focussed again, the defect is present. The extent to which focussing has to be performed is an indication of the spherical aberration present. It is to be met with in all the cheaper forms of single lenses, in rectilinears and in portrait lenses; but should not be noticeable in an anastigmat. It is reduced by stopping down.

However perfect a lens may be in all other respects, there is always a possibility that its good points may be neutralized entirely by what is known as a "flare spot." Given a sufficiently trying subject almost every lens can be made to yield a "flare"; but if it is to be of any use at all, the flare spot must, under all ordinary conditions, be conspicuous by its absence. To examine for it, the camera should be taken into a room where it can be set up at some distance from a bright object, such as a window. Arranging things so that the image of the window falls on one corner of the plate, we must look carefully all over the ground glass for a disc of light or

"ghost" of the image. If we do not see one at first, it may be visible when the camera is moved a little. It is to be sought on the opposite side of the centre of the field, to the image of the bright object. If it is present under these conditions the lens is of little or no use. Single lenses, as a rule, are free from flare spot, but the more separate surfaces of glass there are in a lens, and the steeper the curves of those surfaces, the more chance is there of trouble from this defect.

A "flare spot" is the term generally applied when the flare is well defined; when it is not so and is only present as a haze over the picture it is spoken of simply as flare. There must always be a certain amount of flare, but there should not be a flare spot. Before condemning a lens for flare, it is well to make quite sure the defect observed is not merely an image of some bright metal on the lens mount itself. The space between the combinations of a doublet lens, or the face of a stop turned towards the plate, if the black is worn off, may give rise to what is at first supposed to be flare, yet is nothing of the kind. The lens should also be examined to make sure each separate glass is screwed into its proper place; as in a carefully adjusted lens, a slight unscrewing of the one or other of its components may give rise to a flare spot, which disappears on the lens being properly screwed up.

One more possible defect concludes the list. In lenses composed of one kind of glass, the rays of light of different colours come to a focus at different distances from the lens. Thus, if with such a lens we were to focus sharply the red light of a railway signal, we should find when it changed to green that it was no longer sharp, while if it changed to blue or violet as some signals do, the fuzziness would be still more pronounced. All colours are bent aside by a prism to different degrees; in fact, we distinguish between them by saying that different coloured rays are of "different refrangibility," or bendability, to coin a word on the German system. Lenses to be used with the eye only, such as are employed in microscopes and telescopes, are "corrected" by the use of more kinds of glass than one, so that as many of the rays as possible come to a focus where the yellow rays do, yellow being the light to which the eye is most sensitive. In photographic lenses, much of the light to which the plate is sensitive is blue violet or even

*invisible, and this has to be taken into account when correcting lenses for use in photography. Lenses "corrected for colour" are said to be "achromatic."*

If we take an uncorrected lens and with it focus an image as sharply as possible, we shall find in consequence of the lack of correction, that the photograph is not sharp. As a matter of fact, the focus for those rays which most powerfully affect the plate is nearer to the lens than the sharpest position to the eye, by about one-fiftieth of the focal length. If, then, it is a 5-inch lens, and after focussing it is racked in one-tenth of an inch, the image on the negative will be sharper than if this is not done. (But even so, no uncorrected lens will give as sharp a picture as one that has been properly achromatized.) There are a number of "periscopic" lenses on the market (used in hand-cameras in which focussing is either not done at all, or is done by scale), which lenses are not achromatized, but the difference is allowed for in fixing them in the camera. These are only supplied in the very cheapest forms of apparatus, and the definition at best is very poor.

It may be taken that all photographic lenses, properly so called, should be achromatic. To test this properly, if we can only be quite certain that the plate and the ground glass come exactly into the same place, and without this the test is valueless, nothing more should be necessary than to focus sharply some one of a series of objects at different distances from the camera, and expose a plate. If the sharpest object in the negative is that upon which the camera was focussed, the lens is properly corrected for colour, but if some object a little further away is the sharper, then the lens is not properly corrected. This test is vitiated by any difference between the positions of the ground glass and plate respectively.

To avoid this, and other possible inaccuracies, the following method of performing the test is a good one. Seven white cards, each about 2 by 8 inches are taken, and a hole is punched out at the end of each so that they can all be stiffly carried on a cedar pencil. At the other extremity of each card a number should be written in bold characters with good black ink. The cards are arranged at intervals of 1 inch on the pencil, and the seven are placed round it, so that on looking at the whole arrangement from one end, all the numbers are seen

*in order, in a circle, each number being 1 inch behind the next lower one. The pencil is fixed up horizontally in this manner, and the camera a few feet away, is set up, so that the numbers appear in the middle of the picture. The ground glass is placed in the dark slide itself, which is opened for the purpose, and while held in position the card marked No. 4 is focussed as sharply as possible. A plate is then substituted for the ground glass and the exposure is made. Number 4 ought to be the sharpest in the negative also.*

As in nearly every case, photographic lenses are only corrected for those rays which are most active on the plate, as soon as we come to use orthochromatic plates, with deep yellow screens which cut off nearly all these rays, such lenses no longer give a sharp image. This is particularly noticeable in three-colour work, where the colour screens cut off the light so decidedly that very few lenses, none in fact, unless specially well corrected, will give three pictures equally sharp without being refocussed, except when the focus is very short. In all ordinary cases, therefore, when a colour screen and orthochromatic plate are being used, the focussing should be done with the screen in position.

A good many of these tests are such that the photographer may not feel that he has sufficient skill to make them, or knowledge to appreciate them when made; and under such circumstances, he will do best if he intends to get a first-class modern lens, to go direct to one of the good makers and take what they are prepared to supply. He cannot then go far wrong. If he wants a specimen of work done with it, on no account should he take a landscape, portrait, or even an architectural subject, but should have a negative of a flat test subject, such as has been here suggested, taken with the full aperture of the lens, and taken on a much reduced scale. This scale should be indicated. It is only under such conditions that the test negative will give any true indication of the qualities of the lens. Many of the specimens shown in shops are intended to catch the eye of those who are not in a position to know what a good lens should do; and are shown in the belief that those who are influenced by them will not know that good work may be done with a very poor instrument, if only the user knows how to make the most of it, and if the conditions are favourable.



## CHAPTER IV

### PINHOLE PHOTOGRAPHY

Pinhole work—The character of the definition—Making pinholes—Measuring them—The sizes of needles—The camera extension—Arranging the subject—Over-exposure possible—Working out the exposure—Some advantages of pinhole work.

THE simplest contrivance for forming an image is a pinhole, and for landscape work, where the long exposure is not going to be troublesome, the pinhole is still useful. It has this advantage, that the image can be got on any scale with it, as it is always equally sharp (or almost so) however the focussing screen is pushed in or out. If, therefore, some particular object is to occupy the greater part of the plate, we may extend the camera and get its image larger and larger until it is the size we want; and we may go nearer to or farther from the object, until we get the drawing we want. With a pinhole, also, while there is at no time any very fine definition, there is not that gradation from sharp to blur, that is given by a properly corrected lens used at a large aperture.

It was Dr. Emerson who first laid great stress on "differential focussing"—the sharpness of the image suited to the requirements of the picture, and blurring allowed to stifle obtrusive details. There is nothing to be said against the practice by pictorial photographers, but it is not as easy as it sounds. If the lens has a flat field, everything the same distance as the principal object will be sharp with it, whether it is wanted so or is to be subordinated by diffusion; while if the lens has not a flat field, the focussing may be more erratic, but it is no more under the control of the photographer. While Dr. Emerson used it at times with complete success, other instances may be selected from his own work to show the limitations it imposed upon him. The pinhole knows none of these distinctions of



RODIN - LE PENSEUR  
BY STEICHEN



definition. If none of its image has the critical sharpness demanded by the optician, none need have any pronounced blur ; and plenty of pinhole photographs exist which, put in an album with others taken with lenses, would not attract attention from any imperfection of definition. The fact is, there is a fine quality about the pinhole image which, were it not for the lengthy exposures, would render it very popular for many purposes. The actual softness depends on the diameter of the hole ; the smaller the pinhole, the sharper the picture, within limits.

Pieces of metal pierced with a hole of a definite size are on the market, and Watkins makes one which can be used, very conveniently, in connection with his exposure meter ; but there is no actual necessity to purchase a pinhole, or even to make one in metal before trying a pinhole picture. Very good pinhole work has been done by removing the glasses from a lens mount, and placing a piece of blackened card across the opening of the stop. In the centre of this card is a hole about a quarter of an inch in diameter, or less, closed by gumming over it a piece of the thinnest black opaque paper procurable. When dry and tight, a hole is perforated in the black paper with a red-hot needle, using only the point, and the hole is then enlarged with the cold needle, until this just passes through it. With a little care all burr on the edges can be avoided. Mr. Combe, who has done much good pinhole work, recommends that the pinhole should be punched in a piece of the thinnest sheet brass procurable, using the point of a needle, and placing the brass on a piece of glass with a sheet of paper between the two. The needle is just allowed to perforate the brass, and then the burr is rubbed off with a piece of fine emery-paper. It is pushed a little further, and the burr again rubbed off ; then a little further, and so on until the whole needle will just pass through the brass. The brass is then blackened.

The idea of making the hole so that the selected needle will just pass through it, is to allow the hole itself to be measured ; as unless we know its diameter it is not possible to calculate the exposure it will require. The easiest way to measure it is to take care to have plenty of needles of the size, or of the maker's number, used in piercing the hole. Two visiting-cards are then gummed down on a stouter card side by side, parallel

*and with exactly an inch between their nearest edges, and the needles are arranged between the two cards until the space is fully occupied, if forty needles are required to do this, the diameter of each must be one-fortieth of an inch, and this may be taken, with sufficient accuracy, as the diameter of the hole through which one of them will just pass. There is no absolute need for the cards to be an inch apart, half an inch or even a quarter may be sufficient to give the size of the needles. Another method is to pierce two holes in a piece of thin black paper with the needle that is to be measured, the holes being as accurately as possible an eighth of an inch apart. The paper is then put into an enlarging lantern and as big an image as possible is sharply focussed on a piece of white paper. The size of the image of the holes and their distance apart is marked on the paper with a sharp pencil, and measured at leisure. The actual distance apart in eighths of an inch gives the degree of magnification, and the diameter of the image of one of the holes divided by the degree of magnification gives the actual diameter of the hole. Rev. J. B. Thomson, who has done much pinhole work, points out that the three most useful sizes of holes are those made by No. 10, No. 11, and No. 12 needles, and that these are, approximately,  $\frac{1}{55}$ ,  $\frac{1}{63}$ , and  $\frac{1}{75}$  inch in diameter respectively. Of these, No. 10 is the most generally useful, but at times even No. 8,  $\frac{1}{45}$  inch, may be a convenience. By using these needles, the necessity for measuring the hole itself is avoided.*

Though there is no fixed position of the focussing screen in pinhole work corresponding to the focus of the lens, there are limits within which alone the pinhole can be used, though these are very wide limits, the angle included on the plate being at least as variable as with ordinary lenses. For reasons which need not detain us, there is a position for the focussing screen where the definition is at its best, but the improvement over other positions is not sufficiently great for that to be determined by trial, while the position given by theory is still a matter of discussion. Mr. Combe says that the best camera extension is that obtained by squaring the width of a hundred needles of the size employed to pierce the hole, and dividing the result by eight. If the plate is placed at this distance from the pinhole the maximum of sharpness is obtained. As the pinhole allows

very little light to enter the camera, it is hardly possible, except under quite unusual circumstances, to arrange the subject on the ground glass by means of it. Some pinhole workers carry a comparatively large hole which they use for this purpose, substituting the smaller hole when exposing. An alternative plan is to remove the focussing screen entirely, to turn the camera round until it points away from the subject, and then putting the eye to the pinhole, to arrange the picture in the opening formed by the frame that held the ground glass, racking this in or out until the proportions borne by the different parts of the subject are those required. By taking a sight along one angle of the camera, it should be possible, then, to turn it round until it is pointing in exactly the opposite direction, when the picture as seen through the pinhole, will be that which falls on the plate. This is not absolutely the case, unless the pinhole is exactly above the tripod screw on which the rotation was performed, but, provided the tripod top is level, it is quite true enough in all ordinary cases.

It has been said that it is impossible to over-expose with a pinhole; probably all that is meant is, that those who are accustomed to lens exposures and do not trouble to find out what the relative pinhole exposures should be, are not likely to over-expose. Otherwise over-exposure is just as easy as it is with a lens. Theoretically, the pinhole, aperture and extension considered, should be faster than a lens, as all glass absorbs a great deal of the invisible ultra-violet light to which the plate is sensitive; but it is not at all easy to detect any such extra rapidity, and it is certainly small enough to be ignored. The only satisfactory way of determining exposure with a pinhole is to calculate it out, at the time. The length of the exposure generally allows this to be done deliberately enough. The diameter of the hole being known, an extension of 1 inch has that as its F/- number. For instance, with a No. 10 needle which gives a hole  $\frac{1}{32}$  inch in diameter, when the plate is an inch from the hole, we are working at F/55. The exposure for F/55 is obtained exactly as if a lens at that opening were being used. Of course a much longer extension is employed, and the exposure is increased as the square of that extension. Thus if the distance from the hole to the plate is 8 inches, the exposure is eight times eight or sixty-four times that with F/55,

or may be regarded with sufficient accuracy in such a case as as many minutes as  $F/55$  needed seconds. There is no real difficulty about working out these exposures, as they can be done with pencil and paper after the exposure is started ; but by using the gauged pinhole supplied by Watkins, the application of the Watkins meter to pinhole work becomes still easier. A lens cap or shutter is not required for work of this character, the focussing cloth may be hung over the hole to obscure it while drawing the shutter of the dark slide, but even this is not often required.

In other respects, pinhole photography does not differ from that done with lenses. The drawing is the same as with any rectilinear lens. The swing back and rising and cross fronts serve the same purpose with both. The prolonged exposure is not always a drawback. In a crowded street, where buildings are wanted, and the traffic is a nuisance, by using a very small pinhole the exposure is so prolonged that all the moving parts are lost entirely, and the buildings appear without any sign of traffic before them. In landscape work, wind may be very troublesome, especially if it is a high wind, but a great deal of the trouble which one may experience with a lens, from the trembling of leaves when a faint breath passes over them, is missed together, the pinhole giving a sort of "average" position for leaves and branches, from which any momentary departure has not been recorded. Pinholes have been used for portraiture. The definition given by a fairly large pinhole in such a case is very agreeable, and the prolonged exposure is not without its good points also, in doing away to a large extent with fleeting expressions and getting an "average" result. But exposures usually run into several minutes, even under the most favourable conditions.

## CHAPTER V

### THE DRAWING OF A PHOTOGRAPH

No essential difference in perspective between a photograph and a painting—View point the ruling condition—Impossible view points—Pugin—Wide angles suggest distortion—Suitable lenses to avoid the appearance of strained perspective—The centre of the picture plane—Different appearances from the same standpoint—Plane perspective—Panoramic or cylindrical perspective.

THE idea that in some way or another the perspective of a photograph differs from the perspective of a painting goes deep into the painter's mind, and is possessed somewhat hazily, perhaps, but still possessed by the public and by many photographers. Yet any difference that there may be is due entirely to casual imperfections of the painting or of the photograph; the photographic image, with only reasonable care, is true every time, and the painting in all matters of perspective as closely resembles a photograph as the painter can get it. Later on we shall see exactly of what the supposed difference in drawing between the two representations consists; for the present it is well to recall exactly what it is that both photographer and painter try to obtain.

If a scene in nature is looked at through a window with one eye only, keeping the eye steadily in one place, everything visible through the glass can be referred to some place on the glass, so that if we had a steady hand and a brush set in a long handle we might sketch on the glass the outline of the scene in question; and so long as the eye, the glass, and the scene, were unmoved, the outlines of every detail would fall in exactly the same place on the glass. If the glass were vertical, the outline sketch so made would be identical in perspective with the drawing which a painter would try to make if he desired to represent the scene as viewed from the point occupied by the eye, and any difference between the two would be due to the painter's



want of ability. In the same way, a photograph taken with the lens in the position occupied by the eye would give identical drawing with that on the glass. The only difference would be if the plate in the camera were not vertical, or if a single lens were used under severe conditions, when some of the lines which were straight in the original might appear slightly curved in the photograph. Such a drawing as we have imagined would be said to be in true monocular perspective.

What then is the cause of the supposed difference between the "perspective" of the painter and of the photographer? It is twofold. In the first place, the photographic lens will include a much wider angle than the human eye, and if the photographer allows this wide angle to be included in his picture, he at once gets an apparent falsity. It is not a defect of the lens, but merely a superabundance, and can be corrected by trimming the print down. In the second place, the photographer must go to his standpoint and set up his camera there, or he cannot get the view as seen from that standpoint. The painter is under no such restrictions. He can sit and work in one place and make his drawing as if it were seen from another, which other may be inaccessible or even impossible. Thus, in Pugin's "Normandy," the interiors are drawn as if one of the sides of each building was removed, and the interior seen from a point some distance outside.\* Could the wall have been pulled down and the camera placed there, the photograph would have given precisely the same drawing as that at which the draughtsman aimed, but under the circumstances it could not, and the photographer has at least the consolation of knowing that no eye could ever see the building as it was drawn, and that the drawing, however well it may record the details and the proportions of the structure, does not and cannot give any true impression of that general effect at which the architect himself aimed. The result is that in every case the visitor whose ideas of the structure have been gathered from the drawings, has a feeling of disappointment when he first sees the reality. It looks narrowed and dwarfed.

It is generally only in portraiture and architecture that there is any suggestion of distortion about a photograph that includes too wide an angle; but in landscape, if it is not

\* Sherar's "Perspective Tables," p. 40. Sinclair: Edinburgh, 1905.

actually suggested, the error is there all the same, and is best avoided. Even photographic lenses of ordinary angles include too much to give the best effect, which, it will be found, can only be ensured by the width of the picture being kept down to a *maximum* of one and a half times the focus of the lens, less is better. This can be done, of course, simply by trimming the print ; but, as with a wide angle lens, this would mean that a great deal of the area of both plates and prints might be wasted ; it is better to obtain the same result by the use of a longer focus lens. Thus, if we wish every photograph to be free from suspicion of "strained perspective," a  $6\frac{1}{2}$ -inch lens would be the shortest focus to be used on a quarter plate, a 10-inch on a half plate, a 13-inch on a whole plate, and so on. Such lenses, though theoretically those which ought to be used, are fully long for many purposes, and photographers therefore generally use 5, 7, and 10-inch lenses or thereabouts on the sizes named. In most cases the difference is not very appreciable, but where the subject is of such a character as to show up any excessive angle, these generally used lenses will give results which, unless trimmed down, will look distinctly false.



The so-called distortion of photographs is, therefore, due to the selection of a standpoint which is unsuitable, and to the inclusion of too wide an angle in the picture. If such a lens as we have supposed were selected, and the photographer were limited in size to the plate for which it was designed, say a 10-inch lens on a half plate, none of the alleged distortion could exist, as he would be compelled to select the more distant point of view if he wanted to get as much of the subject on the plate as he would with a shorter focus lens. It would be a very simple way of preventing the apparent falsity, but would hamper him considerably in some classes of work, as he would often find the more distant view point inaccessible, as in the case of the Normandy interiors already cited.

The drawing of the lens, then, is the same as would be obtained by placing the eye at a position of the lens and a flat sheet of glass vertically between the eye and the subject, and tracing the outlines of the subject where they appeared to fall on the glass. The focus of the lens only decides the scale of the picture, the position of the eye decides the perspective. The position of the glass is also important. There has long

been a convention in drawing that all vertical lines in the subject shall be rendered in the perspective drawing as vertical too, and, therefore, parallel to each other. This is rendered necessary by our habit of regarding all pictures as hanging vertically, with the axis of the eye directed towards their centre. In order that this convention may be complied with, the sheet of glass on which our perspective picture is supposed to be traced must be vertical also. For the same reason the photographer's plate must be vertical, and if the camera is tipped up, the back must be swung to bring the plate so, or all upright lines in the subject in the picture will appear to fall together at the top. That this is purely a convention can be proved by those who care to take the trouble, by making such a distorted photograph, enlarging it, and then fixing it in a box in such a way that it can only be seen by applying the eye to a hole in a box in such a position that the bottom of the picture is much nearer to the eye than the top. A position can be found, without very much trouble, in which the most distorted picture will look perfectly natural.

There is another aspect of this perspective question which does not have the attention it deserves from photographers ; and that is the position of what Mr. Sherar, in the admirable little book already mentioned, calls "the centre of the picture plane." He is writing for draughtsmen ; but we may apply his argument to photography to our profit. A perpendicular to the imaginary sheet of glass may be dropped from the point of sight. This is "the perspective axis" or the "axis of the picture plane" and the point at which it cuts the surface of our imaginary sheet of glass is "the centre of the picture plane." It is well the sheet of glass is imaginary, as it may have to undergo considerable extension to be cut by the perspective axis at all. Now the appearance of the subject may vary enormously according to the position of the centre of the picture plane, which may be in the centre of the picture itself, or a long way outside it. This can hardly be better illustrated than in the three photographs which, by the courtesy of Mr. Sherar, we are enabled to reproduce from his book, "Perspective Tables." These were all taken from absolutely the same standpoint, and differ only in scale and in the position of the centre of the picture plane.





# THREE PHOTOGRAPHS FROM THE SAME STANDPOINT

(See p. 69)

REPRODUCED BY PERMISSION OF THE AUTHOR FROM "PERSPECTIVE TABLES" BY ROBERT E. SHERAR

Few photographers would suspect that all three pictures were taken without moving the tripod. They are, of course, not put forward as examples to follow, but as exaggerations to illustrate the effect. In Z we have the view of the building which the photographer would secure who turned his camera to face the building and then trimmed his print liberally on all sides. In the other two we have the pictures he would get by turning the camera away from the building till it was only just included on the edge of a picture obtained with a wide angle lens, one showing the result with the camera turned one way, one the result with the other. We could either take the two latter pictures each on a large plate, with the lens opposite its centre, and then trim more than half of each print off on one side, or we could slide the lens on the cross front until that part of the field of view which contained the building was central. The results of the two methods would not be appreciably different in drawing.

The photographer has little difficulty in determining the centre of his picture plane, as this must always be where the axis of the lens cuts the plate, provided the back and the front of the camera are parallel. If the back is swung at all, the centre of the picture plane is no longer on the axis of the lens, but is where a perpendicular from the optical centre of the lens would cut the plate or its prolongation. There is little need to know the position of the centre of the picture plane; what is important is to see that no very great distance separates it from the centre of the picture itself, if the effect is to look true. The two pictures X and Y only convey a truthful impression to the eye if viewed with the eye in a line perpendicular to A and B respectively at the distance AB. To get the eye as near as this and yet to see clearly requires a weak magnifying glass. As the spectator of a picture has little or no guide as to the proper position from which to view it in order to get a truthful effect, and as his tendency is to see it at such a distance as makes its width subtend an angle of from thirty to sixty degrees while standing approximately opposite to some part of it, and not opposite the wall beyond one of its edges, it has become a recognized convention that a greater angle than sixty degrees should not be included, and that the centre of the picture plane shall be within the picture itself. There is no

need for it to be in the centre of the picture, in fact, in very many cases it is better not to be so, but it ought not to be very far from the centre if the impression is to be a truthful one ; while another reason for a central position is that in any other, the lens is not being used at its best.

The difference in drawing which is obtained from different standpoints is often overlooked by the photographer, whose main concern seems to be "to get it all on" the plate ; and we often see one approach a subject with the sole idea of increasing its scale on the plate, although by doing so its perspective may suffer. Apart from the abruptness of the convergence of lines obtained in this way, the principal photographic effect is in the scale of the distance as compared with the foreground. The images of two men, one of whom is three or four yards further from the camera than the other, if photographed from a distance of say four yards will appear widely different in size. If they are taken with a much longer focus lens from a distance of twenty or thirty yards, they will be almost alike in size. Concentrating the attention on a near object, as is usually done when photographing, and getting it in each case of the same size on the plate, the nearer the camera is to it, the more the distance is dwarfed in size in proportion to the near object.

There is one other aspect of this question to be considered, and that has come into prominence of late years by the popularity of panoramic cameras, in which the film is curved and the lens rotates. The drawing obtained with such instruments is quite different from that which all other cameras yield. We no longer have the perspective of the subject as it would be delineated on a flat sheet of glass interposed between it and the eye ; but as it would appear if the glass were a portion of a cylinder having a radius equal to the focus of the lens, and placed vertically. There is no longer a picture plane, but a picture cylinder, and the centre of the picture plane has become a straight line. Consequently viewed as truthful representations of wide panoramas, such prints are unsatisfactory and false, unless seen under proper conditions. These are that the picture shall be curved to the same extent as was the film originally, and the eye placed at the centre of curvature. When this is done, the drawing appears as truthful

as the most accurate one on a flat surface ; and even when it is not, the panoramic picture is less objectionable by far than would be one including the same angle, if that were possible, and taken on a flat plate, because the curving surface of the film prevents the apparent distortion of objects viewed by the lens very obliquely. The movement of the lens also removes all difficulty from the falling off in illumination so noticeable in wide angle lenses as we approach the margin of the field.

Photographic perspective, then, is in no sense whatever different from the perspective of the painter or the draughtsman. Any blame for apparent distortion must be borne not by the camera, but by its user, who has neglected to select the best point of sight for his camera, or has at least chosen to





FIG. 8.

take it from an unsatisfactory view point rather than not at all, and has allowed too wide an angle to be included in his print. These faults are grave ones where pictorial work is concerned, or where it is important to convey a true impression even at the most superficial glance, but have no validity at any other time. As a scientific record, a photograph of a building taken with the hypergon and including an angle of  $130^\circ$  provided we know the standpoint, is no more untruthful or false or distorted than is a map of the world on Mercator's projection, which represents the poles as straight lines of length equal to that of the equator. Both are systematic and accurate representations of solid objects on a flat surface, and are only deceiving to those who cannot read their message aright.



## CHAPTER VI

### THE SELECTION OF A LENS

The uncorrected single lens—Corrected single lenses—Rectilinears and symmetricals—The wide-angle rectilinear—The advantages of the anastigmat—The Petzval portrait lens—Dallmeyer's modification; with the arrangement for diffusion of focus—Abbe and Schott and the Jena glasses—Anastigmats—Costly lenses—A nocturnal expedition—The Grün lens—The Hypergon—Telephotographic lenses—The Adon—The Dallmeyer-Bergheim lenses for pictorial work.

THE variety in design and construction of photographic lenses is very great, far greater, in fact, than in the character of the results obtained with them. This, from our point of view, which is that of the amateur photographer pure and simple, is something for which to be grateful, as the subject of lens calculation and design is hardly one to be taken up in a dilettante manner. It has been said to be the one occupation for which the education of a senior wrangler has fitted him, and it certainly demands a degree of mathematical knowledge which is not at all common. We can pass over all the intricacies of lens construction, therefore, and view them from a standpoint aptly described by a celebrated optician as that of the lens phrenologist, whose acquaintance with the inwardness of his instrument is limited to what can be got by feeling its bumps.

The simplest form, the uncorrected single lens, is still sometimes used by those who do not care for definition. When applied to another, as a "magnifier," it is usually so weak that its want of correction is slight enough in its influence on the combination to be ignored altogether, but a single lens to be used by itself will only give definition as good as that obtained with a pinhole by stopping it down very much. As it is not achromatized, the focus for the chemical rays will differ from that for the visual rays. After focussing on the screen with

such a lens, this has to be allowed for, by racking the back nearer to the lens after focussing by about one-fiftieth of that total distance. Some uncorrected single lenses are sold with a supplementary lens or magnifier which is inserted for focussing, and then is taken out, its absence making the allowance required. The aims and aspirations of those who use uncorrected lenses, however, are generally of such a kind that the subject of definition concerns them not at all.

Many fixed-focus hand-cameras are fitted with corrected single lenses, and excellent work can be done with them. Their largest aperture as a rule is  $F/11$ , or  $F/16$ , and except that there is always a certain amount of distortion, they are efficient, if not fast. For portrait work, particularly for large heads taken direct, a single lens may be used, and used at a large aperture,  $F/8$  or even  $F/6$ . It is said to give greater roundness than the portrait lens, and is also by no means so heavy or so expensive. A portrait lens of 15 or 20 inches focus needs not only a specially built camera but almost a specially constructed stand to carry it, whereas a single lens of that length is not at all unwieldy. The longer focus is essential if the drawing of the portrait is to be satisfactory. Most single lenses are of the "meniscus" type externally; that is to say, one surface is concave and the other convex. It is customary to employ them with the convex side turned towards the plate, and the stop placed some little distance away on the other side of the lens. The single lens reaches its highest point of perfection in those anastigmatic forms which are composed of one completely corrected combination of three or four glasses cemented together, made to be used either by itself or with another of a similar kind, as in the Zeiss "Protar," referred to later on. There perfect definition is the object, which of course, in the single lens for portraiture just referred to, is not the case.

Next to the single lens comes the "rectilinear," formed apparently of two single lenses placed with their concave surfaces towards each other and the stop between them. In certain very cheap forms, each of these two lenses is composed of a single glass. The lens is, therefore, uncorrected for colour and must be used in the way referred to earlier in this chapter. Such lenses are known as "periscopic" or as

"periscopes," and are not very satisfactory in any way, except that the distortion obtained with a single lens may be got rid of almost entirely with them. It should not be necessary to




FIG. 9.—FORMS OF LENSES—SOME WELL-KNOWN TYPES.

- |                                      |  |
|--------------------------------------|--|
| A. Corrected single lens (meniscus). | D. Wide-angle rectilinear or portable symmetrical. |
| B. Uncorrected doublet (periscope).  | E. Petzval portrait lens.                          |
| C. Rapid rectilinear or symmetrical. | F. Dallmeyer's modified Petzval lens.              |

point out that there is a distinct difference between "may be" and "is," when applied to the characteristics of lenses as well as of other commercial products. The glasses of the periscopic

lens are generally much thinner than those of the rectilinear. One form of the rectilinear had its glasses close together, and a comparatively small stop between them, and was known as the wide-angle rectilinear. The rapid rectilinear usually has  $F/8$  as its largest stop, but many have been made which could be used at  $F/6$ ; these are known as "Euryscopes." The wide angle rectilinear generally had  $F/16$  as its maximum opening. There is not necessarily any real advantage in getting a rapid rectilinear that is fitted with a stop as large as  $F/6$ , as it cannot be used at this opening with any satisfaction, unless its angle of view is comparatively small. It must not be supposed in buying a lens that it is of necessity any better because its maker has fitted it with a larger stop than another. In fact, it may even be worse, as an indication of a lower standard either of definition or of business morality. No finer "R.R." lenses were ever made than the Dallmeyer rapid rectilinears, and the maker adopted for these a standard opening of  $F/8$ , although in exceptional circumstances lenses with larger openings were made both by Dallmeyer and by Voigtlander.


The rapid and wide angle rectilinears for many years had an immense vogue. They represented the high-water mark of the optician, and were made by many under the most diverse names, though the most important syllables of "rectilinear" or "symmetrical" were usually worked into the greco-latin hybrids by which they were designated. They have now subsided into a type; they are no longer pre-eminent; their price has fallen; and if their reputation has not fallen too, it has at least dropped back relatively to that of rival forms. The Ross "Rapid Symmetricals" and "Portable Symmetricals" were practically rapid and wide angle rectilinears, and for long shared pre-eminence with the Dallmeyer R.R.'s, until the anastigmats by the same and other makers were introduced. A good rapid rectilinear lens is a very good all-round tool to-day, and may well satisfy those who cannot afford more expensive patterns. It may give results that are quite indistinguishable from those obtained with an anastigmat, provided it is used on work for which it is fitted—landscapes, architecture, and general photography. It is when it is employed at a large aperture, on subjects with very fine detail, and especially on flat objects as in copying, that the anastigmat begins to reveal its superiority; but except

where exposures must be very short, as in hand-camera work, there is no reason why any one should be able to detect from the prints that the lens employed was one and not the other. .

The fallacy of supposing that the older types, such as R.R., were as good as modern patterns still exists, and is not made any less absurd by the admissions in the previous paragraph. It is only held by those who either have not had an opportunity of critically comparing the two, or else from defective vision—mental or ocular—are incapable of appreciating fine definition. "If an R.R. lens works at F/8, what is the advantage of an anastigmat also working at F/8 and costing six or eight times as much?" the author was asked quite recently. The reply, of course, was that if F/8 were used with both, the definition given by the anastigmat would, on the whole, be finer, or, put another way, the anastigmat might often be used at F/8 when the rectilinear would have to be stopped down to F/16 to get as good a result. Closely examined, the definition of a well-constructed anastigmat is distinctly superior to that of the R.R., even when the latter is very much stopped down.

In the very earliest days of photography, in 1841, Professor Petzval, of Vienna, realizing the importance of reducing exposure as much as possible, an importance far greater then than now, constructed his portrait lens of the type shown on page 70. (The arrow in the case of all these lens diagrams points into the camera.) Most of the special portrait lenses used to-day are of this type, although modified in some respects. It will be seen that they are composed of three separate glasses. The front one is itself composed of two, cemented together. There is an air-space between the back pair, and if such a lens is taken to pieces, particular care should be taken to put each glass back in its proper place. To prevent all risk of confusion, a card should be cut to the curvature of each surface, and the position of that surface written on it as a record. Should the glasses then at any time get mixed, reference to the cards will enable the lens to be put together properly. Dallmeyer's "patent portrait lenses are a modification of the Petzval form. These lenses are so made that by unscrewing them at the back and so increasing the separation of the two glasses, a certain amount of "diffusion of focus," due to increased spherical aberration, can be obtained. Pictorial workers have found this a

A DUTCH CANAL.  
BY JAMES C. HATKIN.





great convenience. Many like to use it to whom anything like "blur" is objectionable, because it is a curious fact, but capable of explanation, that when a slight diffusion is introduced all over the picture the result may look less objectionably "fuzzy" than when there is extreme sharpness in one place, and when the whole is sharper than in the previous case. But this only applies to a slight degree of diffusion, and a great deal can be obtained when required with the Dallmeyer portrait lens. Quite recently an improved mounting allows the unscrewing to be done from outside the lens, in front of it, while other forms by means of rods and universal joints allow it to be done from the ground glass itself.

Most portrait lenses work at  $F/4$  or thereabouts, but they have been made to work at  $F/2$ , or even at larger apertures than that. The great increase in the speed of plates has made portraiture possible with lenses of much smaller aperture, and those of the "portrait" type, such as we have been discussing, are now used chiefly by professional photographers. The amateur will either use his landscape or R.R. lens for portraiture, or, if he is pictorially inclined, will favour a long focus single lens, or perhaps such an instrument as the Dallmeyer-Bergheim. A portrait lens, as a rule, makes a good enlarging lens and is also excellent in the optical lantern. Such lenses have been used in hand-cameras, and for instantaneous work of special kinds, such as the photography of express trains; but their limitations in this direction are great, and those who wish to take up high-speed work seriously must be prepared to pay the price for a very rapid anastigmat.

Many references to the anastigmat have been made already, and it is possible the reader has come to regard it as a definite type, very much as the rectilinear, but it is not so. In the eighties Abbe and Schott, financially assisted by the Prussian Government, which is untrammelled by any *laissez faire* theories, carried out a long investigation on the subject of optical-glass making, which until that date had been in the hands of Parisian and Birmingham makers almost completely. The result was the establishment of the world-famous Jena glass works, placing at the disposal of opticians ten or twenty times as many varieties of glass as were to be obtained before. Many of the new glasses possess most valuable qualities from



the lens-maker's point of view. One of these qualities made possible the reduction of the defect known as astigmatism to such an extent as to be practically non-existent, and lenses so made to take advantage of the new glasses were known as anastigmats. The methods of using the glasses to obtain this result are very varied, and the upshot of the change has been to substitute many widely differing designs for the comparatively simple R.R., wide-angle rectilinear, and portrait types, which occupied the whole field before the appearance of the anastigmats.

Little would be gained and a great deal of space would be occupied by an attempt to describe all these different forms. The firm of Zeiss alone has at least half a dozen patterns, and Goerz is not far behind. In most cases the lenses are doublets with the stop between them, and in some the two halves may be used separately, in others they cannot. The "Cooke," the "Aldis," the "Unar" and "Tessar" of Zeiss are examples of anastigmats of which the separate combinations cannot be used, except of course with an extremely small stop, when any lens can be used. The Cooke, which is the invention of Mr. H. Dennis Taylor of York, and is made by Messrs. Taylor Taylor and Hobson at one of the most perfect factories of the kind in the world, takes several forms. One, a very convenient hand-camera lens, is so arranged that the separation of the front and second glasses can be altered by turning a ring. This alters the focus of the lens, so that focussing for different distances can be carried out without any movement of the camera front or back. The "Aldis" is an extremely simple type of "anastigmat," which is comparatively cheap to make and is low priced but very efficient. The "Unar" is an anastigmat intended for use when a very large aperture is a necessity. In its smaller sizes it works at  $F/4.5$  and in half plate and larger at  $F/5$ , and, taking aperture into consideration, it is low in price.

The stigmatic of Dallmeyer is made in at least three distinct types, and is a very high-class anastigmat. The combinations *may* be used separately, and in this respect it occupies an intermediate position between those which have just been named and those which are to follow. That is to say, the single combinations of the stigmatic lens must be

stopped down to about  $F/22$  before they give as fine definition as that yielded by the complete instrument. One series of the stigmatics works at  $F/4$ , and is a most efficient portrait lens, especially where space is limited; though it is, of course, preferable to use as long a focus lens for the purpose as possible.

The last class of anastigmats includes the Homocentric of Ross, the Goerz, the "Protar" of Zeiss, and several others. These are all symmetrical, that is to say, they are composed of two lenses identical in construction and (sometimes) identical in size, placed back to back with the stop between them. Half the lens can be used by itself, the focus being then approximately doubled. Some of the lenses in this class represent the high-water mark of lens construction, and, incidentally, of lens price. The "Protars" of Zeiss in particular enjoy a reputation which is hardly attained by any other.

The question how far the quality which these high-class lenses possess is worth paying for, is not one that can be answered offhand. The writer's own practice is to buy just the very best he can afford, and his three cameras are fitted with a Zeiss "Protar," a Goerz "Double Anastigmat," and a Dallmeyer "Stigmatic" respectively. Even assuming, and it is a big assumption, that these instruments do not in most cases give an appreciably better result than lenses of a less costly nature, there is no doubt that they work at a bigger aperture, that under trying conditions they show their superiority, and also that they possess a market value as second-hand instruments very much nearer to their original cost price than would be the case were they of cheaper types. It is not an invariable rule by any means that the more expensive the lens the better it is; but as a rough guide price is not to be despised. Certainly it is not possible to make and supply at a low price a lens of both the quality and the adaptability of the modern symmetrical doublets; and the photographer who values definition and rapidity, will do well to buy the best lens to which his pocket will stretch. If he goes to any of the makers to whom we have alluded, he has at least the satisfaction of knowing that he gets an instrument made by a manufacturer with a high reputation to maintain,

and that at the worst he should be able to get two-thirds or more of its list price should he make up his mind to part with it.

There is one drawback about the use of costly lenses, which may be guessed from a nocturnal expedition at which we once assisted, fortunately 'only to the extent of holding a lantern. It was one chilly autumn night, after all the regular inhabitants had retired to rest, when a small party of photographers went down to a certain village bridge. After preliminary observations, one of the party plunged into the river, and disported himself mysteriously for about a quarter of an hour. At the end of that time he emerged, cold, moist, but triumphant, with the front half of his anastigmat rescued from a watery bed, whither he had consigned it in the course of the afternoon while trying to get a long focus view from the bridge itself.

The demand for more and more rapidity has led to the construction of curious lenses at different times, one of the most remarkable in appearance being the Grun, in which the space between two of the combinations was occupied by fluid. This was not the first "liquid" lens by any means, an ingenious form having been devised by Sutton nearly half a century ago for very wide angle views. These departures from recognized optical practice have proved more curious than successful; and the demand for an extremely rapid lens for cinematograph work, as the pictures needed were so small, has been met by the construction of modified forms of the portrait lens working at  $F/2$  or thereabouts, and giving remarkably good definition.

Another curious lens was the result of efforts to provide an extremely wide angle instrument. It is known as the "Hypergon," and is constructed by Goerz of Berlin. No other instrument will approach it in the angle it will embrace, including as it does  $135^\circ$ , and working at  $F/22$ . This means, that the lens will cover a plate whose diagonal is five times the focus. The difficulty with all wide angle lenses is the very rapid falling off in the illumination of the picture as the edges are approached; and with such an angle as that of the "Hypergon," it becomes absolutely necessary to counteract this in some way, and the means by which this is accomplished

are very ingenious. A little opaque disc, cut into the shape of a star, is delicately pivoted, so that it can be rotated in front of the lens by the air from a rubber bulb. The star obscures the centre of the lens, but allows more and more light to reach the parts of the lens as they are farther and farther from the centre. Were the whole exposure made with the star in position, the centre of the field would not be illuminated at all; so that when seven-eighths of the total exposure has been given, a spring is touched, and the star drops away from the lens altogether, the remaining eighth being given without it. For short exposures, the star is kept rotating by working the bulb; for long ones, such as in the case of interiors, there is no need to do this, the star may just be moved round a little at regular intervals. The drawing obtained with the "Hypergon" lens seems at first sight most unnatural, because of the extraordinary angle it includes. This quite unfits it for pictorial work; but for ordinary record purposes, the lens will do what no other instrument will, and it is possible to get photographs with it in confined spaces where, before the advent of the "Hypergon," photography seemed to be impossible.

The telephotographic lens differs in two respects from those that have been considered: first, it has no fixed focal length, as this depends upon the adjustments of the component parts of the combination; and, second, with the same camera extension it will give pictures on a much larger scale than will an ordinary lens. Telephotographic lenses are of two parts: one may be any lens of the ordinary kind, such as a portrait lens, an anastigmat, or a rectilinear; and the other, usually placed between the first and the plate, is a negative, or diminishing, and not a magnifying lens. The effect of using this negative lens is that that portion of the picture which, without it, would be rendered on a small scale in the centre of the plate, is enlarged so as to cover the whole area of the plate or more.




FIG. 10.—A TYPICAL TELEPHOTOGRAPHIC LENS.

With the telephotographic lens, as with one of the ordinary type, the size of the image depends upon the focus of the lens; and although in this case this may be varied by altering the

distance apart of the two components, and although the camera extension for the same size of image may be very much shorter with the telephotographic than with the ordinary instrument, this holds good just the same. The focus of a lens is measured from the ground glass to a certain point in the lens, sometimes, but not very accurately, called its "optical centre." This is generally somewhere within the limits of the mount of the lens itself; but in telephotographic lenses it is in the air in front of the lens, possibly some feet away from it.

Work with high-power telephotographic lenses is very specialized, and calls for a number of precautions which are not wanted ordinarily. Owing to the optical centre being so far away from the plate, photography as it were is being conducted at the end of a long lever, and the slightest motion of the shorter end—the lens—is greatly magnified on the plate. The apparatus, therefore, has to be particularly stiff and rigid. Owing to all distant pictures being seen through a great thickness of illuminated air, there is a haze or fog over them, which makes it difficult to develop up strong negatives when high magnifications are used, while the fluctuation in the density of the air itself makes long distance telephotography at times quite impossible.

Moderate power work is free from much of this trouble, and a negative attachment for use with one of the best of the ordinary lenses makes a valuable addition to the outfit of the stand photographer. It can be used for taking architectural details that are high up and out of reach of the ordinary lens on any important scale, and for subjects which only include a very narrow angle. In the hands of Mr. Ernest Marriage, one of the leading exponents of this work, the lens has given very successful results in the direction usually associated with the hand-camera. The scale of the image is such that a stand-camera may be used from a distance without the groups photographed being conscious of the fact that they are being photographed. As examples of successful work of this sort, we may refer to a number of pictures on the Thames Embankment, the groups being on the pavement beside the river, while the camera was on the curb on the other side of the road, and quite unnoticed. As in the case of the Hypergon, which, as far as results are concerned, is diametrically the opposite of

the telephotographic lens, the drawing obtained is practically the same as with any other lens used at the same standpoint, the advantage being that the telephotographic lens will give us a large image without an excessive camera extension, and, moreover, will allow us to vary the size of the image at will.

The popularity of the telephotographic lens, if not its actual first invention, about which there is a difference of opinion, is due to the late T. R. Dallmeyer, who devised a number of telephotographic combinations. One of these patterns is a very much simplified instrument, designed originally to fit on outside a hand-camera lens, and so to make a telephotographic lens of it which would work at the same speed as the lens without the attachment. All other forms of telephotographic lens have the negative lens placed between the positive lens and the plate, and the exposure is prolonged in proportion to the greater area over which the image of any particular part of the subject is spread. The simplified form, from its purpose, was called the "Adon," and was actually a complete telephotographic combination in itself. The application of the "Adon" to other lenses has never proved very popular, but many photographers have used the "Adon" by itself as a low-power telephotographic lens, with entire satisfaction.

The aim of the makers in all the lenses to which reference has been made, has been the production of an instrument which, in addition to its special features of angle or of aperture, shall give as perfect definition as possible. For pictorial purposes, this is not always desirable. Why not throw the image out of focus? some one may inquire. Unfortunately, throwing the image out of focus, while certainly preventing good definition, hardly does so in the way that is required. An image formed with a good lens, but out of focus, differs in the extent of the blurring of different parts, according to their relative distances from the camera. Instead of the eye being satisfied, therefore, with a pleasant softness of the image, it is worried by the differences in the definition of different parts, and by the curious shapes which some of the minute points of light assume when blurred in this manner. The first lens specially introduced to meet this case was the modified Dallmeyer

portrait lens, already referred to. Later on a number of uncorrected "spectacle" lenses were put on the market, but as these were hardly more than ordinary "glasses" mounted up for use on a camera, there is no need to refer to them specifically. The "Dallmeyer-Bergheim" lens is more than this, being a telephotographic combination of two uncorrected single lenses, designed for portraiture exclusively, and giving very soft and agreeable definition for large heads and similar work. It is essentially an amateur's lens, as the general public is hardly of sufficiently cultivated taste in photographic matters to appreciate and pay for work of the character which it produces; but in its own sphere it is particularly valuable. Not only is there a large variation possible in the quality of the definition, but its construction on the telephotographic principle means that its focus can be altered to suit the particular needs of the moment. It is made in two forms—one rigidly mounted, and so without the power of having its focus altered; the other with rack and pinion adjustment of the separation of the two lenses. In using a Dallmeyer-Bergheim lens, as there is no correction for colour, the definition on the plate is not the same as that seen on the focussing screen, unless, after focussing, the separation of lens and screen is altered to allow for this.

The Pulligny and other uncorrected lenses have been designed for pictorial work; but it is doubtful whether some of these, except the Dallmeyer-Bergheim, have any appreciable advantages for such purposes over cheap "magnifying glasses," which can often be obtained for a tenth or a twentieth of the price. Far more, in all such cases, depends upon the user than the tool, and in capable hands a simple set of spectacle lenses, with a mount to hold any selected one, such as is put on the market by several makers, seems to do all that is wanted.

THE Tenth YAKU  
Y. L.







## CHAPTER VII

### THE LENS IN USE

The portrait lens—Single lenses—Using half a doublet lens—"Convertible" anastigmats of two and three foci—Rectilinears—The value of stops—The importance of parallelism—Focussing from the back or front—Copying—Depth of focus—Selection of a stop—Focussing landscapes—Interiors—Focussing by scale—Copying to scale.

THE lens in use calls for an application of the principles which have been laid down in the preceding chapters. The distinguishing titles—"landscape" "portrait" "wide angle" and so on—are only indications of the purposes for which the instruments are best fitted, and must not be supposed to indicate that the lenses cannot be used indiscriminately by those who do not mind the drawbacks such use entails. A portrait lens is one which works at a very large aperture,  $F/4$  usually. As this means that the clear diameter of its lenses is one-fourth the distance of the lens from the plate, an 8-inch lens must be at least 2 inches in internal diameter, and so on in proportion. The portrait lens is therefore bulky and heavy. Apart from that, it works at a very large aperture, and therefore unless stopped down it has little depth of focus; but stopped down it makes a capital landscape lens, and, except for its distortion, it could be used even for architecture and for copying. For amateur purposes, the typical portrait lens is almost out of fashion, as the increased rapidity of plates has made it possible to do portrait work with much smaller stops than  $F/4$ , and consequently to take large heads and similar work direct with lenses which are neither excessively heavy nor large and therefore costly.

The single lens, which in its most elaborate and perfect form is composed of three or four distinct glasses cemented together, and works well at  $F/11$ , is perhaps the best all-round

instrument for its price that can be obtained ; but it is better to buy it in the form of a doublet, which may be either a rapid rectilinear if the pocket is limited, or an anastigmat if it can be afforded. Rectilinear lenses and most anastigmats can be used either as a whole, when they work at from  $F/4$  to  $F/8$ , or  $F/11$ , according to design, construction, and angle included, or one half may be unscrewed and the other used by itself. In rectilinear lenses, which work as a whole at  $F/8$ , the foci of the two halves are generally approximately equal, though hardly ever exactly the same. At least the difference between them is not marked enough for them to be regarded as giving the photographer much choice between them. It is customary to unscrew the front lens and use the back one, and this is easily done without taking the lens out of the camera. Even if the front lens is that used, it is better to put it between the stop and the plate than to leave it in its original position in front. Half the lens used in this way gives a picture on approximately twice as large a scale from the same standpoint, and this is often a great convenience. With "wide-angle rectilinears" there is usually a greater difference between the foci of the two halves ; but as this differs not only in different patterns, but even in individual lenses of the same pattern, the photographer must find out for himself whether the two are alike or not.

Some anastigmats are constructed so that the single lenses are corrected to such an extent that it is difficult to detect any difference in quality between the single lens and the combination of two, except as regards rapidity. This is the case with the Zeiss Protar lenses, which are sold as single lenses (Series VII.), or as pairs (Series VII. A.). If the two single lenses are equal in focus the combination will work at  $F/6.3$ , all the single lenses working at  $F/12.5$ . If the two single lenses are of different focus, the combination is not quite so rapid, being slower the greater the difference between the lenses. Thus we may have a 9-inch single and a 14-inch single, both working at  $F/12.5$ , the combination being one of  $6\frac{1}{2}$  inches, working at  $F/8$ . If instead we took two  $11\frac{1}{2}$ -inch lenses, the combination would have practically the same focus, but would work at  $F/6.3$ . The extra rapidity is worth having for some purposes, but unless hand-camera work is to be done, it would certainly be better economy to get the first pair, as it would give three lenses of

9, 14, and  $6\frac{1}{2}$  inch respectively, rather than two, an  $11\frac{1}{2}$  inch and a  $6\frac{1}{2}$  inch.

With such instruments, as with rapid rectilinears, straight lines in the original should be rendered as straight lines in the photograph when the double lens is used. With the single lens there will be a certain degree of distortion when such straight lines occur near the extreme edges of the plate. This is much less with the anastigmats than with the rectilinears, though with neither should it be noticeable unless looked for or the conditions are very trying. Such single lenses make excellent portrait lenses, when exposures can be long enough, and they will always cover at least as large a plate as the combination, generally one much larger. Thus the 9-inch lens just referred to is sold to cover a plate  $7\frac{1}{2} \times 5$  inches, the  $11\frac{1}{2}$  inch a whole plate, the 14 inch a  $10 \times 8$ , whereas either of the  $6\frac{1}{2}$  inch combinations is not fitted for use on anything larger than a half-plate unless stopped down.

Whether the lens be an anastigmat or a rectilinear, one thing must not be overlooked, and that is the alteration in the values of the stops and therefore in the exposures, when half the lens only is being used. If the focus of the single lens were exactly double that of the combination, all exposures with the former would require to be four times as long, since the stop of the combination marked  $F/8$  would be  $F/16$  with the single lens,  $F/11$  would be  $F/22$ , and so on. Such an exact doubling can hardly ever be the case, and it will therefore be well to find out the values of the different stops for the single lens, if they are not already marked for it. With an iris diaphragm it is better to have it separately engraved for the single lens and for the double, making the distinction between the two scales quite unmistakable to prevent accidents.

Whatever the lens be, its quality is quite wasted unless the camera front which bears it, and the camera back which carries the plate, are normally strictly parallel. This ought to be the case with every camera, unless of the most slop-made and shoddy construction; but to make sure as far as possible that it is so, the camera should be opened out, fixed on the tripod, and its front made as strictly vertical as it is possible to get it, plumbing it with a thread and bullet. In doing this the lens should be in position, lest its weight should throw things out again. When

the front is plumbed, the back tested in the same way should also be plumb. The camera may then be laid on its side, and the front again carefully made vertical. Wedges will probably have to be used, unless the camera is one that is turned on its side to reverse the way of the plate, as it will not be possible to screw it to the tripod. The back is then again tested in its new position.

To focus an object the camera is racked in and out. In most landscape patterns the front carrying the lens is moved by the rack, the back also having a sliding movement; but in square bellow patterns the back often moves and not the front. The difference is not unimportant. In landscape work, when the nearest objects are many times the focus of the lens away from the camera, the fact that when we rack the lens in or out we not only alter the distance between the lens and the plate, but also between the lens and the subject, does not make an appreciable difference. If we were copying or doing other work with the subject nearer to the camera, this alteration of the distance of the lens from the subject might be a great nuisance. For copying work, portraiture, etc., therefore, a camera which focusses by the movement of the back is to be preferred. Where the exact size of the image on the screen is not of very great importance, focussing can often be carried out more accurately by using the rack for rough focussing and sliding the camera to and fro to secure the final focus. In such work it is often a help to use a focussing glass, a little magnifier, which is adjusted by pressing it on the ground glass and screwing the lens of the magnifier in or out until the ground surface of the glass is seen at its sharpest. The magnifier must not be altered afterwards, and must be pressed against the focussing screen when it is in use.

Most of the defects which were dealt with in Chapter III. are remedied by the use of a small stop; but the stop plays an important part in another direction. We have seen that there is with every lens a position for the ground glass in which the image of an object at a certain distance from the lens is sharp, and that as the distance of the object varies so the distance of the ground glass must be altered. It would seem then that it is not possible for two objects at different distances to be sharp at the same time. Strictly speaking, this is so; but as "sharpness"

is a matter of degree, when one object is sharp another at a different distance will not be so sharp, but may still be well defined enough to appear equally sharp to our eyes. The more a lens is able to render near and distant objects equally sharp at the same time, the greater is said to be its "depth of focus." Unfortunately this most desirable quality is not a matter of design, but is dependent upon the focal length and the size of the stop. A salesman anxious to dispose of a lens will sometimes claim for it that it possesses "great depth of focus." He means nothing by it; it is only an idle boast. Did he mean anything, it could only be that the lens would not work at so large an aperture as another with less depth of focus. And aperture, *aperture*, APERTURE is what the optician is ever striving for. Not to make a "better" lens, but one as good that shall work at a larger aperture, is his constant aim.

Larger apertures in large lenses mean great lack of depth of focus. An example should make this plain. A lens of  $4\frac{1}{2}$ -inch focus working at F/8 will give us sharp images of objects at 11 feet and upwards to infinity. If we stop it down to F/16, objects 5 feet 3 inches and upwards will be sharp. But if instead of our  $4\frac{1}{2}$ -inch lens we have a 12-inch one and use it also at F/8 instead of getting everything sharp from 11 feet upwards, the nearest object that we can get sharp at the same time as the distance will be 75 feet from the camera, or at F/16—37 feet. Of course we can focus nearer objects by sacrificing the distance, but there will always be that wide disparity between the depth of focus of the lenses. This we must not forget is not a matter of the make of the lens, or the perfection of its design, but is a shortcoming of the ideally perfect lens, as much as, or even more than, of an inferior one. Because the worse the lens, the more likely is its want of depth to be lost sight of in its other imperfections.

We stop down, therefore, to reduce as much as possible the faults of the lens, and also to get the depth of focus which the subject demands. Next in importance to the operation of focussing is the selection of the stop. Many workers, beginners especially, in their desire to secure the sharpest possible definition, use much too small a stop. A good rule is to employ the largest aperture that will give the degree of sharpness required. The use of very small stops tends to make the negative flat and

lacking in contrast, and deprives the picture of a certain proportion of its relief, due to the rendering of the different planes with different degrees of sharpness, which with a large opening may be effective, even when the degree of blurring is not great enough for it to be noticed at all. Absurdly small stops introduce diffraction phenomena, and so make the definition worse instead of better; while with certain types of lens a change in the size of the stop introduces a change in the focus, and it is therefore necessary to focus with the stop that is to be used to take the picture. This is just what the "small stopper" tries to avoid; he does not like the responsibility of deciding by the eye alone whether the stop is small enough. Yet this ought always to be done, and the photographer should satisfy himself not only that his picture is as sharp as he wants it to be, but also that he is using the largest stop that will make it so.

Landscape subjects and architectural exteriors are the easiest to focus. Portraits are more difficult, and need watching to see that nothing which in the dark corners of the focussing screen is overlooked, will be offensively blurry in the brilliant print. Interiors are hardest of all, because, as a rule, they are so poorly lit that the importance of keeping the exposure short cannot be passed by, while the great difference in the relative distances of the different parts calls for careful focussing with the actual stop used.

Focussing by scale is considered in the hand-camera chapter, but with stand-cameras there is one form of scale which may be adopted. The usual lens being put in place, a distant object such as a lamp 300 or 400 yards away, should be sharply focussed with the open aperture, and the position of the moving part of the camera, front or back as the case may be, is marked with the blade of a knife and a little soot or other black rubbed in to make the cut easily visible. It is at times a convenience to be able to open out the camera to "infinity" without looking on the screen; and if we want a case in point we might take that of a heavy thunderstorm at night. The photographer suddenly realizes that he has a magnificent opportunity of getting some lightning photographs, he extends his camera to the mark, as we have described, he cannot focus, there is nothing on which to focus, he puts in a plate, uncaps the lens, and points it to the quarter of the sky

in which there seems the best chance of a flash. After one or two have taken place, the plate is changed, and the operation repeated as long as the supply of patience, plates, or lightning holds out.

A scale on the base board is also very useful when copying to some exact proportion has to be done. Without it the task becomes a very irritating one, because every alteration in the focus to get the subject sharp alters its size. When it is the right size it is not sharp,—we carefully focus it only to find that in doing so we have altered the dimension of the image ; we get this right, and then the picture is no longer sharp, and so it goes on. By marking the camera extension on the base board, once for all, for the usual copying lens for images of different proportions to the original, all we have to do is to open out the camera to the right mark and clamp it there, and then to focus by altering the distance between the camera and the subject.



## CHAPTER VIII

### PLATES AND FILMS

Glass *v.* Celluloid—Paper for negative work—The Cristoid film—Commercial plates, British and Foreign—Different kinds of the same make—High rapidity—Orthochromatic plates—Halation, its cause—Prevention—The manufacture of caramel—Development and halation—All halation not a defect.

THE ideal support for the sensitive coating which we expose in the camera is still in the future. Glass has many advantages; the ease with which it can be obtained smooth enough for the purpose, its cheapness, its inert behaviour in the different solutions used by the photographer, and its transparency. This last quality it does not possess to the extent many people imagine, and even to the eye clean glass cuts off much light, while to the photographic plate, which is sensitive to light the eye cannot appreciate, it cuts off a great deal more. On the other side of the account we have the rigidity of glass, an advantage or disadvantage according to circumstances; we have its brittleness, a decided drawback, its weight, and its thickness. This last is the prime cause of that bugbear of the photographer—halation.

The only serious rival which glass has at the present time is celluloid. This can be obtained clear enough for all ordinary photographic purposes, very thin, flexible, practically unbreakable, light, and—expensive. As regards the cost of celluloid, a stiff film is about fifty per cent. more than the glass plate with the same emulsion, while a roll film may be as much as three times the price of glass. So that some very great advantages indeed must be anticipated from the use of celluloid. For work away from home, these exist. The roll film with its facilities for daylight loading and daylight developing makes photography facile to a degree. The film takes up little room, is light, and travels safely by post. Its price is not its only

THE RIVER ARIEL AT LEEDS





drawback, however. It is a strange but well-attested fact, that it has not hitherto been possible to make roll films as rapid as plates. The same emulsion spread on glass and on celluloid is markedly more rapid in the former case. Moreover, volatile substances enter into the composition of celluloid, and though the precise nature of the action is not understood, celluloid films will not keep so well as plates, especially under trying climatic conditions. Celluloid also is highly electrical, and when circumstances are favourable, it may be caused to spark in such a way as to affect the sensitive coating on it. Rapid rolling or rubbing is most likely to bring this about, and in manufacture it has caused a great deal of trouble, especially in the early days of the industry. We hear of sparks a foot in length flashing about the coating-room as the film was stripped from the tables, where it must have acted like a great electrophorous. But forewarned is forearmed, and by handling roll film with reasonable gentleness, there should be no trouble from such a cause. Its inflammability is not so great as that of bare celluloid, the non-curling film, which has a coat of gelatine on both sides of it, being to some extent fireproofed thereby, although it will burn if a little trouble is taken to light it. Celluloid is not so inert as glass, and certain solutions which would not affect the latter, must on no account be applied to a film. Thus it is not practicable to dry celluloid film in a hurry by means of spirit; though this is the only case that need be mentioned. Celluloid films in large sizes are only kept flat with difficulty, and even in half plate a modern flat field lens, working at a large aperture and sharply focussed, would hardly be likely to give such crisp definition all over a film as it would on a glass plate. The inferiority would only just begin to be perceptible in this size, and in anything smaller it need not be taken into consideration.

While glass and celluloid divide between them the honours of the situation, they are not entirely alone. Paper, especially in large sizes, has its advocates. Some workers make their enlarged negatives on ordinary bromide paper, while others use this for outdoor work with the camera. The sensitive coating on ordinary bromide paper, however, is kept thin to suit the paper to its true purpose—printing and enlargement. When it is used for negative making, this thinness means that

the exposure must be exact if the negative is to be a good one, Some makers of bromide paper, therefore, have put a special "negative paper" on the market, which is essentially a bromide paper with a thicker coating of emulsion than usual. The cheapness and lightness of paper make it attractive to landscape photographers who work large sizes direct. The grain of the paper itself shows slightly in a print on a smooth surface; but in carbon or rough platinum it is not noticeable. The paper slows printing considerably—four or five times at least—unless it is waxed; but it is better not to wax it, as there is always a chance that it may take the wax irregularly and in spots. The best material for the purpose is a mixture of one part of Canada balsam and five parts of turpentine. This is rubbed into the paper with a small sponge, and the negative is then hung up for the turpentine to evaporate. One advantage of a paper negative is the ease with which one can work upon its back with pencil, stump, and brush; against this may be set the ease with which the paper will absorb noxious solutions and stain, when celluloid or glass would allow them, literally, to run "like water off a duck's back."

One more support for the sensitive film may be mentioned, if it is not a bull to speak of it as such, since the film is its own support. In the Cristoid film there is neither celluloid, glass, nor paper, the vehicle being gelatine such as holds the sensitive substance itself. As might be expected, such a film possesses ideal keeping properties, and has none of the drawbacks of glass or paper. On the other hand, it absorbs water throughout as soon as it is wetted, swells in consequence, and the finished negative is very considerably larger than the film which was exposed. Cristoid film has never enjoyed a wide popularity, but is highly appreciated in certain select circles, some of the most skilful pictorial photographers of the day using it to the exclusion of everything else.

Enough has surely been said to enable the reader to balance the *pros* and *cons* of films, plates, and papers. The author's own practice is to use plates exclusively for work at home, or where their weight is not prohibitive. As his photographic touring is limited to a few weeks in the year, he uses plates then, in spite of the difficulties of carrying about a supply. Films are used in a folding-camera on journeys

when photography is not the *raison d'être*, the compactness and portability of the outfit preventing it from being a serious addition to the luggage. Any one who uses the camera for travel purposes exclusively, would find the advantages of roll film almost irresistible. For professional photography, and for amateur work at home, the rigidity and perfection of glass, to say nothing of its economy, offer overwhelming advantages to those whose apparatus will admit of its employment.

At the present time there are many plates on the market ; amongst which the photographer can choose for himself, with little fear of making a bad selection. If the number of good plate makers is legion, the number of kinds of plates is at least half a dozen times as great, for every maker has several brands. One, usually at a higher price, is the fastest of all, and this is the plate which should always be used for hand-camera work. This is not to say that no other plate is possible ; but that, as the conditions cannot be foreseen, it is good policy to be prepared for the most unfavourable. In the early days of gelatine plates, fast plates were much more difficult to develop than slow ones ; they were sometimes only the slow ones fogged to make them seem fast, although this deception was quite an unconscious one on the part of the plate-maker. That reproach is now entirely removed ; and, except that there is more risk of fogging them by undue exposure to the light of the dark room, the fastest plates of all are as easy to develop as those of ordinary rapidity. Sir William Abney, who has photographed a great deal in Switzerland, recommends very fast plates for use there, on the ground that they yield a softer and more harmonious negative of subjects in which the contrasts are excessive, as is the case with Swiss landscapes. For portrait work the fastest possible plate should be used, because the lighting is often none too great, and it is always well to keep the actual duration of the exposure as short as possible, in the interests of the sitters themselves. Moreover, a portrait negative must on no account err on the side of excessive density, and this is less likely to occur with a fast than with a slow plate. Most photographers, who turn to portraiture from landscape, get their negatives too strong at first. The special plates made for portrait purposes are not different from others

in any respect except in the character of the gradation which they give, this usually being softer in the portrait plate.

Very rapid plates are not to be recommended except when their speed is a necessity. Slower plates have a more opaque film, an advantage referred to again later on, and they possess a greater "range." That is to say, assuming with a slow plate that an exposure of two seconds is the shortest that will give a correct negative, eight or even sixteen times that exposure may still give a correct negative, as will be considered when we come to discuss exposure. On the other hand, with a very fast plate, if two seconds is the shortest correct exposure, four times that is probably the greatest exposure that would also be correct, anything more giving rise to signs of over-exposure in the negative. For landscape and outdoor photography in general, when a stand camera is used, a plate of ordinary rapidity is all that is required. For interiors the slow plate is often an advantage in spite of the increased length of exposure, because of its greater range and thicker coating. In this respect the Cristoid films, already referred to, are remarkable. They are not composed of a single layer of emulsion of uniform character, but have a slow emulsion as a basis, a faster one on the top of that, and in some cases a third still faster on the top of all. These layers do not separate, and the finished negative shows no sign of them, but they help to make the film extremely opaque, and have a range which no single layer of emulsion can approach.

The question whether or not he should use orthochromatic plates is one which the photographer must settle for himself, according to the character of the work which he proposes to do. Theoretically, no doubt, in almost every case, they are superior to ordinary plates; in practice, this superiority is often quite incapable of detection.

- When a photograph is taken of some subject in which there are great extremes of light and shade, such as an interior with a brightly lit window which appears in the picture, a defect often makes its appearance in the form of light in the print, all round the bright object. There is a certain glare in the subject itself, caused by the illuminated air—or rather the illuminated dust in the air; but the photograph may show a great deal more than exists in Nature. The cause of this can

be understood from Fig. 11, which represents, very much magnified, a section through such a negative. A is the glass plate, and B the film on its surface. A ray of light, C, coming from the lens falls on the sensitive film at K, and some of it is absorbed. But a plate is not perfectly opaque, as we know, and some of the light passes through it to the glass, A. The top surface of the glass will reflect some of this light, as shown by D, the bottom surface will also reflect some, E, and the rest will pass out at the back of the plate towards F. The thicker and more opaque the coating B on the plate, the less light will get through it. Some of the light from C, on entering the film, will also be scattered in all directions by the particles of silver bromide, as shown by the finer lines G, G. It will be noticed at once that the reflected ray E reaches the film in a spot, H, some distance from K, that at which C struck it, and therefore while the true image is formed at K there will be a certain quantity of light-action at G and H also. As a matter of fact, light will be reaching the film all the way from K to H, owing to reflection and scattering; but the diagram has been kept simple for the sake of clearness.




FIG. 11.

A little consideration shows that as B is extremely thin, the reflected ray D will lie close to K while it is in the film, and so will not give rise to any serious spreading of the image. In the same way, little trouble is likely to arise from G, G, G. These are the only causes of halation in celluloid films, and consequently the defect is almost unknown with such materials. But with glass plates the case is different. The back surface of the glass at L is highly reflective, and, owing to the thickness of the glass, H is often at some distance from K, and the light reaching H causes a distinct fogging of the film there, and therefore in the print causes the glare which is only too familiar to photographers.

There are two methods by which halation can be attacked, and if both are invariably employed, it will entirely cease from



troubling. The first is by means of "backing." This is a preparation which is spread on the back of the plate at L, by which its power of reflecting light is destroyed. The action of backing is one which is more often misunderstood than almost any other photographic process. Many people suppose that any opaque substance spread upon the glass at L will answer the purpose. This is a complete mistake. Most of such substances will merely absorb the light which is passing away to F. But this light, if the plate is in a darkslide that is properly blackened inside, is already harmless, and whether it is absorbed by a coating on the plate or by the darkslide is quite immaterial. Black paper gummed to the glass, or black velvet laid against it, are some of the devices to prevent halation, which have been suggested from time to time by some who did not understand the nature of the problem. They are useless for the purpose. It must be remembered that the light which does the mischief at H never gets outside the glass A at all, and anything that is to attack it must do so from within, as it were. This is not so impossible as it seems at first sight. We can apply to the glass at L something which, by being almost identical optically with the glass itself, causes L to cease to exist as a reflective surface. To do this, the substance applied must have the same "refractive index" as glass, or as nearly the same as possible, and it must be applied in "optical contact" with the glass. It will then stop reflection from L, the light which would be reflected passing into the substance, whatever it is, where it must be absorbed if it is to be rendered harmless. There is one material which seems better fitted for backing than any other, and that is caramel. It is the basis of most of the preparations on the market, and is most efficient. Backing may be applied with a sponge, a brush, or a dabber made by tying up a tuft of cotton-wool in a piece of cambric. A little piece of artificial (rubber) sponge makes an excellent tool for the purpose. If many plates are to be coated a backing frame is convenient. It is easily made of card or wood, and is simply a board with a ledge just a trifle smaller than the plate, and on this ledge another into which the plate fits. The plate is supported in such a frame, face downwards, and except at the extreme edges its face is not in contact with anything, and therefore cannot be damaged. The backing is rubbed on, and

the plate placed in a rack for it to dry in the dark. If the plate has to be put into the camera at once, a piece of tissue-paper may be placed on the backing and rubbed into contact all over. A thick coating of backing is quite unnecessary, nor need it be even in thickness provided it goes all over the plate. The best workers use no plates, whether for direct negative work, for slide making, or for enlarged negatives, that have not first been backed.

There is still the second method of the prevention of halation, which is by suitable development. In the diagram which follows, Fig. 12, we have supposed the plate shown in Fig. 11 to have been fully developed, and the image in its magnified film is shown by the shading. The letters are the same in both, but the course of the rays of light is not marked by lines, being unnecessary. It

will be seen at once that the halation at G and H starts from the glass and works up into the film, while the true image at K starts at the surface and diminishes down-




FIG. 12.

wards. Hence, if we could plane off the under part of the film, say all below the dotted line, we could get rid of the halation almost entirely. These are not suppositions. Sections of films have been cut and examined in the microscope and the positions of the direct and halation images actually *seen*. Moreover it is possible, if not to plane off all below the dotted line, at least to keep the image mostly above it. This is done in exposure and development. The longer the exposure the more the image at H approaches the surface of the film, and the more the image at K extends down towards the glass. Over-exposure, therefore, tends to increase halation. Prolonged development also, by giving the developer time to diffuse down and act energetically on the glass side of the plate also helps to make halation more apparent. Hence developers, which contain bromide to any extent, give halation when otherwise it might be absent; while under-exposure, by inducing the photographer to go on developing in the futile hope of "bringing out detail," is as efficient a cause of halation as anything can be.

If a subject is likely to give rise to halation, therefore, we can prevent it from being troublesome—

1. By using a thickly coated plate—slow plates, as a rule, are more opaque than fast ones, and therefore appear more thickly coated, and actually are less liable to halation in consequence.

2. By using a properly backed plate.

3. By exposing correctly and developing without any restrainer.

A photograph taken under these conditions, however trying the subject, should show no more halation than is visible to the eye.



FRANK BRANGWYN  
BY ALVIN LANGDON COBURN



## CHAPTER IX

### THE DARK ROOM

The dark room should be a room, but not dark—Necessity for occasional daylight—Illumination—Light filters—Coloured glass—The “Geka” filters—Light for different purposes—For orthochromatic plates—Fabrics—Testing the light—The sink and water supply—Splash preventers—Shelves—Dishes, porcelain or otherwise—For large work—Measures and scales—A light-tight drawer.

**I**T is possible, by using roll-film and a developing machine, to dispense entirely with the dark room, but this is to impose very narrow limits upon the photographer, and a majority of those who use such appliances have probably some form of dark room. In a great many cases it is a place of such a character that good work becomes almost an impossibility. Narrow, cramped, ill lit, and worse ventilated, it is a prison from which the perspiring captive emerges with a sigh of relief, instead of the clean, comfortable, and (comparatively) brilliant room, which it might be. The idea that any little corner will do, provided it is dark, is responsible for much of the discomfort of the average room; and the truth is not realized, that it is better to turn an ordinary room into a temporary dark room when required, than to have a chamber from which all daylight is permanently excluded. Not only is a room which is never entered by daylight distinctly unhealthy, but it is almost certain that it will not be kept so clean, as if its dust and dirt revealed themselves under the searching influence of the sun. And dirt, using the term in its widest sense, is the greatest foe the photographer has to encounter.

Dirt in the camera, dust in the slides, chemical dust floating in the air of the dark room, invisible but by no means imperceptible dirt in dishes and measures, all lie in wait for him, and all make their presence felt by defects, whose precise

cause it may be difficult or impossible to trace. It is only when we deal with so exquisitely sensitive a thing as a plate, that we realize the true meaning of cleanliness. Let a spirit-lamp be burning with an almost invisible blue flame, and tap the table sharply. It starts into a yellow light for an instant, and the spectroscope tells us that we have jerked into the flame some of the ever-present dust containing sodium. The plate is not quite so sensitive as this, and sodium salts are not its worst foes; but few dark rooms are free from other chemicals in the form of dust, and one of the most prevalent, as it is the most deadly in its effects, is hypo. This salt, at once the photographer's best friend and worst enemy, has a most searching character, especially in solution. It is hardly too much to say that it is impossible to remove all the hypo from a porcelain dish in which a fixing solution has been left for four and twenty hours. At least it is only possible to do so by devices to which the photographer is not likely to resort. For this reason, dishes used for hypo should be used for nothing else. It may not affect the robust solutions generally employed for development, but a trace of it will put a gold toning bath out of action in a very little time.

If dust is a foe to the plate user, it is still more so to the plate maker, and we therefore see that plate factories are established in the country to get away as much as possible from the smoke-laden air of the towns. In the olden times, when photographers had to make their own plates, there was one process, the albumen, which was used for transparency making. It was said to be so sensitive to dust, that enthusiastic slide makers used to remove their garments, rub themselves all over with glycerine as if they were Grecian athletes, and grapple with the process in nature's garb alone. How far this is true, or whether it is one of those myths from which no early history is quite free, there is now no telling. Let us be thankful, especially in winter time, that the exigencies of modern methods are less exacting.

The power of flooding the dark room with daylight, then, is worth keeping as a guarantee against dirt. It should be roomy, to prevent semi-suffocation. The author has long held to the belief that no dark room at all is better than a small, ill-ventilated cupboard. As a rule, it is not difficult to

provide a frame covered with some light, opaque material, by which, without much exertion, a window can be blocked up when required. By limiting dark-room work to the evenings, even this may not be necessary. Moonlight shining into a room does no harm provided plates are not directly exposed to its rays. A water supply and a sink are the two most essential fittings, but even these can be extemporized. If much work is to be done, however, they must be provided.

It is difficult to lay down rules for fitting up a dark room, as the conditions of different cases are widely different; but a few general principles may be given. If the dark room is a large one, and electric light is used, there is not so great a need for special ventilating arrangements to act when the room is darkened; a fireplace and chimney will do most that is required. But small rooms lit by gas should have their ventilation looked after most particularly, or the photographer will suffer. There is a form of headache which many people think is brought on by working in the red light; it used to be attributed to the ammonia that was used for developing. Its real source is to be found, there can be no doubt, in a lack of sufficient pure air in the dark room. Many otherwise efficient ventilating systems are rendered almost useless by the light trap. Air should pass through the ventilator, but no light. Air can turn round corners and light cannot; therefore, a few corners in the ventilator are sufficient to prevent light from entering. But if air can turn corners, it requires a certain pressure to make it do so, and every corner tends to obstruct the passage, even for air. A light trap, therefore, if placed in a passage otherwise the right size, should be an expansion of that passage; or the fact that an opening is light trapped should be a reason for making it bigger than would otherwise be necessary. However well ventilated, in every good dark room it should be possible to fling open the windows and let in fresh air and daylight with no trouble at all. •

The illumination of the dark room must depend necessarily on the work to be done in it. The red lamps at present on the market are, almost without exception, too small; and are suitable only for temporary dark rooms and makeshifts. The user has to pore over his dish close to the lamp, or else work



in semi-darkness, which is most injurious to his eyes, and is demanded by very few plates. Moreover, the limited quantity of light makes it impossible to find anything not quite at hand, and is responsible for measures and bottles being knocked over and broken. Where electric light is available, an efficient and safe light is a very simple matter. Stained incandescent lamps are not satisfactory and should on no account be used. The heat of the lamp soon affects the coating, and its light causes the dye to fade, and the lamp becomes a danger. One of the circular glass jars which one sees in the windows of sweet-stuff shops forms as good an electric dark-room lamp as can be wished. The bottom and about an inch above it are made opaque by being covered with black paper or book-binder's cloth, and a cardboard lid, with an edge about an inch deep, is also fitted. Through the centre of this lid passes the flexible wire from which is suspended the incandescent lamp. The exterior surface of the jar may be covered with any selected flexible coloured medium, which may be provided so as to slip on and off, or be fixed in position. Or the jar may receive a coating of coloured varnish. If the lamp is enclosed in a smaller jar or bell-shaped globe, the space between the two may be filled with coloured liquid, which in theory at least, is the most satisfactory method of getting a safe light, which is light and not a mere modified darkness.

Let us consider for a moment what the problem of dark-room illumination presents to us. Plates, even non-orthochromatic, are sensitive to light of every colour that is perceptible to the eye, and very sensitive to "ultra-violet" light also, of which the eye is hardly conscious. We must not forget that even a "safe" red light will fog any plate in time. The light to which non-orthochromatic plates are least sensitive is deep pure red. Crimson often contains "ultra-violet," and may be most unsafe in consequence. To yellow light plates are a little more sensitive, to green they are a little less sensitive again, while by blue and violet they are immediately affected. Green, yellow, and red, therefore, are the three colours amongst which our choice may be made. Red, considered solely from the point of view of the plate, is safest, but the least luminous to the eye. Orange, which may be regarded as a mixture of green, yellow, and red, is in consequence favoured by many people. The

trouble about orange is that it is certainly not safe for the orthochromatic plates and films which are now coming into general use, and so far as the author is aware, there is not on the market any orange-light filter which has been worked out for the purpose of dark-room illumination, so as to give a light at once as bright and as safe as possible. This is not the case with red, and there are several forms of light filter of this colour, which have been fitted to the work they are required to perform, and not selected haphazard ; among these are the "Geka" light filters and Wratten and Wainwright's "Safe lights." They give the greatest quantity of light that is consistent with safety, and being made in several forms can be selected for the various requirements of the photographer. The "Geka" filters are made of a dyed gelatine or similar material. They must be enclosed between a couple of sheets of glass to protect them from injury, and should not be subjected to too great heat, or they will scorch. The light they pass is so much more brilliant than that of the ordinary materials employed, that the photographer at first might think them unsafe ; but a trial reassures him.

The first requirement is a light in which the fast non-orthochromatic plates which are the most used of all, can be changed and developed. The writer uses an incandescent gas lamp screened by a full size sheet of No. 2 Ruby "Geka" light filter for this purpose. It gives a profusion of light, so much that reading by it is not at all uncomfortable. But such a light must not be allowed to shine direct upon the plates. They must be loaded into the slides in the shadow of the body, and developed in a dish that is kept covered up. Those who prefer to work in a much feebler light rather than to take precautions, can use the No. 3 Ruby. The makers, anxious that their material shall not be condemned for giving foggy negatives which are actually due to its misuse, recommend the No. 3 for fast and the No. 2 for slow ordinary plates ; but, with care, the latter can be used for both and is certainly very much pleasanter. There is a yellow-medium, No. 1, which can be employed for lantern-slide making and for bromide printing ; but if bromide enlarging is to be done with the paper exposed all the time to the light of the dark room, No. 2 should be used. Orthochromatic plates of the ordinary yellow and green sensitive

kind may be developed with the light of the No. 3 Ruby by *using care ; but a deeper red, No. 4, is supplied for the purpose.* This also can be used for red sensitive plates ; but whatever the light used for these, the greatest care must be taken if fog is to be avoided. For the Cadett "Spectrum" and other plates strongly sensitive to red, a green light is often employed. A suitable one is made by Wratten and Wainwright.

So far nothing has been said about coloured glass for dark-room illumination. As a matter of fact, though it is widely used, it is not to be recommended. The ruby glass is "flashed," that is to say a thin film of red glass covers one side of a sheet of white glass. The colour is a good one for ordinary plates, but nearly all orthochromatic plates are distinctly sensitive to the light transmitted by ruby glass. In addition to this, pinholes in the ruby coating are not at all uncommon, and while they may not be visible to the eye, they help to make the light unsafe. Some ruby glass lets through a considerable proportion of ultra-violet light, and is most unsafe in consequence. Yellow glass, as such, does not exist. The yellow glass on sale is not yellow but brown, as can be seen by putting a piece of it down on a sheet of white paper. It is therefore darker than it need be, without being any the safer. It is "pot" glass, that is to say the yellow colour is not in a thin layer, but extends right through the glass. It is therefore not subject to pinholes. If glass is used in a lantern, a sheet of yellow and a sheet of ruby make a reasonably safe combination, though not a very light one. The yellow does not make the ruby seem much darker, but it makes the light distinctly safer. Whether the transparent "Geka" filters or glass be the material used, the lighting of the dark room is made much more pleasant by the use of a sheet of ground glass. This diffuses the light and throws it into corners otherwise quite dark, while it lessens at the same time the strength of the direct rays.

There are various fabrics on the market for dark-room illumination. Of these ruby and canary medium are well known. They are a stout woven material prepared with some coloured coating which makes them fairly safe when two or three thicknesses are used. One thickness is never safe, on account of pinholes, which are quite unavoidable. As they are comparatively cheap, they are often used to block up windows,

so as not to exclude all the light, and for this purpose they are well fitted. The author some years ago did a great deal of developing in a little dark room partitioned off an ordinary room. It was a light wooden frame, covered entirely to within 2 feet 8 inches of the ground with one layer of ruby and one of canary fabric, the doorway being closed with a curtain. A paraffin lamp stood on a table outside, and the light within was very pleasant and uniform, though not very strong. Another material often employed is known as "Ruby Christia." This is made both in paper and fabric, and can be used for the same purposes as the ruby and canary medium. Its colour is, if anything, better. The paper is an excellent material for tourists, as it takes up no room, and may be tied round an incandescent electric lamp like a bag, and held with an elastic band, thus providing a safe light for plate changing. Two thicknesses of it, shut into the porthole, will turn a cabin into a temporary dark room in the same way. For ordinary dark-room illumination, however, neither paper nor fabrics are altogether suitable, as they stop a good deal of the safe light as well as of the unsafe. They distribute the light over the dark room in a more pleasant manner, however ; as is done also by ground glass.

Two kinds of light are ample for most purposes : a yellow for bromide and lantern-slide work, which would also be suitable for wet collodion, were it ever to be used, which is not likely ; and a red for plates, which by being screened or by having the light turned down, may be made safe enough if orthochromatic plates are used occasionally. If they are constantly employed, the light should be a deeper red than otherwise. Brown and green have at times been suggested for the dark room, but they have never become popular, and to-day are scarcely used at all. Certainly they are not to be recommended.

When arranging for the lighting of a dark room, the light itself before screening should be as strong as possible. Many fail to recognize the difference between a strong light properly screened, and a feeble light with a weaker screen. Of course any light may be used if it is weak enough, and the author has changed the most sensitive plates, without the slightest trace of fog, in rooms in which there was light enough to see

everything distinctly after a minute or two. But this is not what is wanted. The larger the area of light screen and the more powerful the light, the better. In this way we can increase the visible light almost indefinitely, without making it unsafe for ordinary plates. No one who has ever worked in a properly lit dark room would ever consent to go back to the gloomy shades of the poor little oil lamp in an ill-ventilated lantern, screened by a few square inches of unsuitable ruby glass.

It is only necessary to add, that no one should use a light for more than the most temporary purposes without testing it. This is easily done by putting a plate in a dark slide, placing this where the plate is likely to be exposed to the light of the dark room, and leaving it there, with the shutter drawn half way out, for as long a time as it is likely the plate will ever be exposed to the dark-room illumination. The plate is then to be developed in the usual manner, fixed, washed, and dried. If on placing it down on a sheet of white paper there is a distinct difference between the exposed and the unexposed half, the light is not safe, and it must either be used at a greater distance or the light filter must be changed. The commonest defect of all, in everyday work, is a fogged negative. The commonest cause is unsafe light in the dark room, or undue exposure to it. Yet the simple experiment of testing the dark-room light is performed—how often?

After the light and the ventilation, the most important features of the dark room are the sink and water supply. Although some of the chemicals used in photography attack lead, a lead-lined sink, when everything is taken into consideration, is the best. Earthenware sinks are most costly, especially in big sizes, are heavy, and mean that every glass or porcelain article allowed to fall in the sink is to a certainty smashed. With lead this very seldom happens. And the most careful will knock over a bottle or measure now and then. The bench beside the sink, if the latter is lead lined, may be lead covered too, and provided with a fillet on its outer edge over which the lead is carried, while at the back the lead is turned up the wall for 3 or 4 inches. The bench is then easily cleaned down with a squeegee, a thing that should be done every time it is used.





The water tap is best fitted with a "splash preventer," by means of which it will give a smooth stream. It should be 15 inches above the bottom of the sink, so that the largest bottles can be filled at it, but it need not be higher than this. There are swing arm taps fitted with a rose and a bottle-filling jet, but the ordinary tap with a splash preventer answers every purpose. Two taps are better than one, and best about 8 inches apart. A negative can be placed under one of them to wash, while the other can be used in the ordinary work. A piece of clean linen or muslin about 3 inches wide and a foot or two in length, if wound round the nozzle of the tap so as to prolong it for a couple of inches, and fastened in place with a rubber band, forms a simple splash preventer, and turns the most violent rush into a gentle stream. In places where there is a system of heating by means of hot-water pipes, particular care must be used to see that the dark-room water-supply pipe is not brought alongside a pipe carrying hot water, or unexpected troubles may arise. Such a state of things is by no means uncommon, and has often been the cause of frilling and blistering of plates and papers, that seemed most mysterious until the reason for it was detected.

A few shelves for bottles, or better still a cupboard, a rack for dishes, a rail for dusters and towels, and a draining rack for negatives complete the list of indispensable dark-room fittings. Most plate-draining racks have too many grooves; they should be at least  $1\frac{1}{2}$  inches apart, or the plates will take a long time to dry, and disfiguring drying marks may be expected. Where one size of plate only is used, the hypo bath may be a grooved porcelain tank, as this takes up little room and the plates fix very quickly in a vertical position. The best dishes are undoubtedly granitine or porcelain; because the material of which they are made makes them easy to clean, and their colour makes dirt conspicuous. In course of time, however, and very quickly if solutions are left about for any time in them, the inside of the dishes becomes covered with little cracks. These cracks pass through the glaze, and allow the porous material beyond to absorb the solutions placed in the dish, and it is no longer possible to clean such dishes perfectly. They may then, if cleaned as well as possible, be used for



developing, for fixing and for washing plates, but should not be used for toning with gold and platinum, or for any operation about which the photographer does not feel that slight contamination does not matter. Vulcanite dishes are the most portable and light, but they are easily broken, cannot be used for any solutions that are not quite cold, nor for solutions containing alcohol or acetone, and it is not easy to see any dirt they may contain. Papier-mache is quite unbreakable, and for developing, fixing, etc., is very suitable; but it, too, does not show up dirt. A papier-mache dish answers well for hypo, and when it begins to look worn and dirty, may have a good scrubbing with hot water and soap, be well rinsed, dried thoroughly, and painted inside and out with Brunswick Black, when it is as good as ever again. Large dishes are heavy, fragile, and expensive, if made of porcelain. They are never perfectly flat; the plate therefore rocks on them, and they take more solution than should be necessary. For this reason for sizes larger than 15 by 12 inches, dishes made of a sheet of glass in a wooden frame are popular. The bottom of such dishes is absolutely flat, as the photographer finds out when he tries to pick up a large plate from such a dish, and ultimately has to take his knife to it. These dishes are fragile, but are comparatively cheap. Best of all for large sizes, is a dish constructed of thin wood, with stouter wood for its sides, well waxed within and without, and then lined with thin American cloth. The waxing may be done with a paraffin candle and a flat iron, the dishes being made by the local carpenter. A sheet of American cloth decidedly larger than the dish is then placed in it, neatly folded, and the edges outside tacked to the wood. By ironing the cloth into position, the wax is melted and cements it tightly into place, but not so tightly that when the inside gets dirty or worn, it is impossible to strip off the cloth and reline the dish. For occasional enlargements and similar work these dishes are excellent. They are light and cheap, while if they are not easily cleaned, their lining may be renewed from time to time without much expense or trouble. After use they should always be dried and hung up.

Measures are a necessity in the dark room. The larger ones are best of cylindrical shape; these have not got that

point at the bottom which is so difficult to clean. On the other hand, they can only be used for measuring quantities which nearly fill them, and for the smaller measurements they give only the roughest approximation. One of the small measures should therefore be of conical shape so that 10 or 20 minims can be got with reasonable accuracy. A jug holding a pint and another of two pints will be found useful. A funnel or two, of glass, must be at hand; and if sulphide solutions are to be mixed up, for toning purposes, a thin glass "boiling" flask will be required. The scales should weigh from 10 grains to 2 ozs., and should not be kept in the dark room unless in a cupboard or drawer, where they are not likely to be exposed to fumes. A packet or two of cut filter paper circles may be kept with the scales, a paper being put in each pan when weighing to secure cleanliness and accuracy.

It is a very bad plan to keep sensitive plates and papers in the dark room, as there must be no room in the house where they are so likely to be exposed to fumes that may injure them. The best place is in a drawer or cupboard, under lock and key, of course, in a passage or room that is not often used. Heat, gas and other fumes, and damp are as injurious to sensitive products as light itself. At the same time a light-tight drawer in the dark room is very convenient, as plates may be slipped into it, if daylight is to be let in for a little time. When enlarging also, it will hold the supply of bromide paper, if this had been sold in an envelope which fits it so tightly that putting the paper back after taking out a sheet is almost out of the question—not, by the way, an imaginary case. A most ingenious light-tight drawer is in the dark room of a friend of the author. It is constructed on the principle of the little boxes in which French wax matches are supplied. An inner lid fits on a ledge all round the top of the drawer. The back half of this lid is a fixture, but the front half is hinged to the back and is pushed up into a vertical position by a spring. On opening the drawer the lid flies up, on closing it, the lid is pushed down, thus making the drawer absolutely light-tight, which an ordinary drawer would not be.

No dark room is complete without a nail brush, soap, and a towel. Cleanliness, personal and instrumental, is an absolute

necessity in successful photography. As a final example of the way in which dirt lies in wait for the photographer, a case may be mentioned of a succession of spoiled prints which were traced to the accidental dipping first into one solution and then into another of the photographer's coat sleeve. Shirt-sleeves and an apron form the best dark-room uniform.

## CHAPTER X

### EXPOSURE

Gradation the test of exposure—Hurter and Driffeld's "perfect negative"—The latitude in plates—Over-exposure at first only causes fog—The factors which influence exposure—Strength of light—The influence of the lens—The speed of plates—The Hurter and Driffeld, Watkins and Wynne numbers—Their translation—The subject—Exposures indoors—Meters and tables—The Actinograph—The Watkins meter—The secret of success with the Watkins meter—Exposures in sunny climes—A little haze no drawback.

**E**XPOSURE is the crux of the photographic process. Beside it the other operations are comparatively simple, and can be definitely and fully prescribed. But the exposure of the plate must be governed by circumstances, which, in most cases, cannot be foretold, and some, even at the time, can only be estimated. In the early days of the dry plate, it was generally accepted that if the photographer exposed his plate incorrectly he could remedy it in development. In other words, it was said that he could "compensate for under or over exposure." That has long since been shown to be a fallacy; and although careful quantitative experiments indicate the possibility of errors in exposure being to some extent remedied by development modifications, such modifications are not those which photographers employ, nor indeed are they of real service in actual practice. The mistake lay in supposing that methods which make an over-exposed negative look—superficially—like one that has been correctly exposed, remedy the over-exposure. A negative is only a means to an end; that end is the print. If the remedy for over-exposure does not give a print that differs in any way from one obtained from a negative "unremedied," the remedy may fairly be considered as inoperative.

The beauty of photography is its power of rendering half-tone or gradation. Two photographs of the same subject may

differ very widely in this respect. They may both have the highest light equally white, and the deepest shadow in each may be an equally dark tone, yet everything else may be different. In one a tone in the original which lay about midway between those two extremes, may in the photograph be equally midway between the brightest and the darkest tones ; in the other the intermediate tone may be altered so as to be almost as dark as the darkest, or as light as the lightest. The result is that the latter print seems altogether wrong, though to the unpractised eye it is difficult, if not quite impossible, to say just how it is wrong. This defect is quite apart from the value of the gradations themselves ; it is not flatness nor harshness, which are qualities dependent upon the *actual* value of the gradations. It depends solely on their *relative* values. Whatever result the photographer may want to get in the end, he always aims—though sometimes very blindly—to get the relative gradations right in the negative. The actual conditions under which this is possible were first clearly laid down by Dr. Hurter, an eminent chemist, and Mr. V. C. Driffield, an engineer, who collaborated with him, in the most important photographic research of modern times.

This is not the place for a discussion of the experiments of Hurter and Driffield, or even for a recapitulation of the whole of their results. But the outcome to practical photographers may be summarized briefly, and is easily understood. A “perfect negative” they considered to be one which reproduced truthfully, but in negative form, all the tones of the subject—not one in which the intermediate tones were shifted nearer in value to the highest or the lowest tone. The degree of contrast in such a negative was governed by the printing process which was to be used with it—some processes require a “stronger” negative than others, as is well known ; but, whatever the contrast, the intermediate tones must all be in their proper proportions if the negative is to be considered perfect. Such a negative can only be obtained when the plate has been correctly exposed. If it is then developed with a developer which does not fog the plate, in the comparatively short time during which it is exposed to it, which developer is practically free from bromide, the result will be a perfect negative. If it is developed for a very short time, the negative will be a thin one, suitable for bromide enlarging

and other purposes for which much contrast is unnecessary. If it is developed longer, the negative gradually acquires more and more contrast, but it is still a "perfect negative," the relation between its different gradations being unaltered, although the extent of the difference keeps on increasing with development. This result is expressed by saying the density ratios are unaltered by development. A point is reached at length, beyond which development is unnecessary, the negative acquiring too much contrast for any printing process. If, therefore, we have a correctly exposed plate, and we apply to it a suitable developer, we can get a negative suitable for any printing process we like, according to the extent to which we allow the plate to develop.

*The "perfect negative" of Hurter and Driffield is the type of negative every photographer tries to get. It is a negative which can only be obtained by exposing the plate correctly.*

This would indeed have been sad news to photographers if it meant that they had to time their exposures to a nicety ; but, fortunately, it is not as it looks at first. The same researches showed that most plates possessed a good deal of "latitude in exposure," some an immense amount, and all had some. The meaning of the expression is made clear by an example. If it is found that a plate will give a "perfect negative" with a certain exposure, it will give an equally perfect negative with twice, four times, eight times, occasionally even thirty-two times as long. This latitude depends on the subject, the character of the emulsion on the plate, and the thickness of its coating. The thicker the plate is coated, within reason, the greater the latitude. The slower the plate, as a rule, the greater the latitude also ; though to this there are exceptions. The shorter the scale of light and shade in the subject, the greater the latitude also. So that we no longer have to hit upon the exact exposure, which would under most conditions be almost if not quite impossible, but have a margin, within which any exposure will be correct.

Every photographer knows that if he takes two plates, and gives one eight times the exposure of the other, he gets two widely differing negatives ; yet few would be able to state definitely in what manner the two negatives differ. If both were of the same subject, and both were correctly exposed, one,

let us say, having eight times the exposure of the other ; and if the two were developed side by side in the same dish for the same time, different as they would look to the eye, the prints which they would give would be identical. All that would be required would be to print one for a longer time than the other. The negative which had the longer exposure would be the exact counterpart of the other, except for a certain amount of fog. That fog is measurable. With proper appliances, it is quite easy to fog an unexposed plate, develop it to the required point, and then by putting it in contact with the negative which had the shorter exposure, to make it appear, and be, exactly identical in every respect with the negative which had the longer exposure. The fog would make the negative take longer to print, but would not otherwise have any effect upon it that we need consider in this place.

As time of printing is comparatively unimportant besides truthfulness of tone, it would appear that so long as the exposure is a correct one, it does not matter much whether it is a large correct or a small correct one. In many subjects it does matter, however, as has been shown in a previous chapter, when dealing with the subject of halation. The shortest possible correct exposure is that which gives the least risk of halation.

The importance of correct exposure, within the limits of the latitude of the plate, having thus been shown, it remains to consider the methods by which it can be obtained. Exposure is influenced by—

1. The strength of the light.
2. The focus and aperture of the lens.
3. The speed of the plate.
4. The nature of the subject.
5. The movement of the subject or of the camera.

This last factor is not limited to hand-camera work, but still is so largely a hand-camera consideration that we may pass it by for the present. The others make fearsome list enough by themselves. It was customary for photographers at one time to look at the brightness of the image on the ground glass, and to conclude from that the exposure required. It was a rule-of-thumb method, and resulted in many failures, until in time a kind of knack of guessing exposures was acquired. One

thing is quite certain, and that is that, consciously or unconsciously, the photographer was not influenced by what he saw on the ground glass. Such workers are still amongst us, and from their long experience are still some of the cleverest photographers, but a new generation is rapidly arising to which such "methods" are unknown. Photographers cannot now afford the time or the material to acquire the knack of judging exposure nearly half as well as it can be done mechanically, and amongst all but the hopelessly antiquated, the exposure meter reigns supreme.

The strength of the light at the time of making the exposure is influenced by three distinct things—the height of the sun, the state of the atmosphere (which means more than is usually understood by the weather), and the physical obstructions by which some of the total light is cut off from the subject photographed. Abney, Eder, La Baume Pluvinel, and others, compiled tables showing the fluctuation in daylight throughout the year, and at different times of the day. The best known of all was that of Dr. J. A. Scott. Other tables were drawn up to show the variation due to the weather, while yet a third table dealt with the different classes of subject, and the lens. By extracting from these tables the figures standing for the particular conditions of the moment, and multiplying them together, a figure was arrived at which was the exposure required by a particular speed of plate. Until towards the end of the eighties this was the only method of calculating the exposure that was available. It gave by no means an invariably correct result, and was used by comparatively few. Even guesswork, to most, seemed preferable.

At about that date the conclusion was reached of a long series of careful measurements, conducted during several years, by Messrs. Hurter and Drifffield. These showed that the influence of the height of the sun was a perfectly definite one, and enabled them to tabulate and to express in the form of curves the changes in the power of daylight due to this cause. These curves formed the basis of the "Actinograph," by which exposures could be estimated. The influence of the weather upon the strength of the daylight is not so great as might be imagined. The older tables gave it as one to five—that is to say, place, season, and time of day being the same, the light when



the weather is very bright is not more than five times as strong as when it is very dull. Hurter and Driffeld made it even less—one to four.

Besides the height of the sun, and the weather, there is an important modification of the daylight effected by the dust-laden atmosphere through which it passes. This is best seen at sunset, when the thickness of the atmosphere through which the sun is seen is greatest. The red colour of the light is then most pronounced, and red being the tint to which photographic plates are least sensitive, the light at such times is not as strong, photographically, as it seems.

The influence of the lens upon the exposure is easily expressed. It may be said to be governed entirely by the ratio which the diameter of the opening in the stop bears to the focal length, which photographers speak of as the  $F/$  number. So long as the other conditions remain the same, all lenses working at the same  $F/$  number require the same exposure. While this is quite accurate enough for all ordinary purposes, it is not absolutely true. The glass of which a lens is composed absorbs a certain quantity of the light entering it, and the thicker the glass, the more light it absorbs. If the glass has any trace of a yellow tinge, it is absorbing just that light which is most active on the plate. Some old lenses have this tinge of yellow, due to the action of light upon the particular glass of which they are made. Such lenses act to some extent as colour screens, and wonderful properties have been claimed for individual specimens from time to time. Needless to say, if a colour screen is to be used, it is better to have one made suited to the plate with which it is to be employed, than trust to the haphazard of a yellowed lens. Occasionally the balsam with which the different glasses of the lens are cemented together turns yellow and cuts off useful light.

Both these defects are very rare, and need not be taken into consideration at all as influencing exposure, but there is another circumstance whose power in that direction is often overlooked. A lens with a focus of 8 inches and a stop 1 inch in diameter has that stop marked  $F/8$ . This is only its true designation, however, so long as the focussing screen is 8 inches from the lens—that is to say, at its principal focus. To take an extreme case, suppose copying the same size as the original is

in hand. The stop is 1 inch in diameter, but to get the copy the right size and sharp, it will be found that the screen has to be 16 inches from the lens instead of 8, so that the stop marked F/8 is actually F/16, and the exposure must be altered accordingly. Under ordinary circumstances, the focussing screen is not moved so far from the principal focus as to necessitate any allowance on this account, but in portrait work and in copying it may be.

Another source of error that is sometimes overlooked is the use of one combination of a double lens only; this has been dealt with in Chapter VII.

The speed of the plate is the third factor to be considered in exposure calculations. Any one whose knowledge of plate speeds is derived from the marks on plate boxes will have a very erroneous idea as to their definite character. A case in point will make this clear. A good many years ago, the author was secretary to a committee appointed by the Royal Photographic Society to investigate the whole question of plate speeds in the hope that some definite system might be adopted. It fell to him to obtain a number of different plates, and to give two of each kind to each member of the committee, that he might work out their speed in his own method, not knowing what were the plates with which he was dealing. When the committee met and the results were compared, it was found that the experts which composed it were not even in agreement in the order in which they arranged the plates in point of speed, much less did they agree upon the figures denoting the speeds. Moreover, it was not found possible to agree even upon a definition of "the speed of a plate." The only method of ascertaining speed at one time was by means of a highly ingenious instrument called the Warnerke sensitometer, which had only one defect, and that was that its results were quite erroneous when tested in the light of actual practice. It compared plates according to the quantity of light action required to produce, on development, the faintest perceptible image on the plate. As such an image was quite unprintable, the reading given by the Warnerke sensitometer would only be correct if the exposure required to produce a printable image bore some definite relation to that which was sufficient to produce one barely visible on the negative. It does not. It was soon found

that of two plates, one might prove to be faster than the other in the sensitometer, while in actual negative making in the camera the positions were reversed. An attempt was made to get over this by reading, not the faintest visible image, but the feeblest printable image ; but this varied according to the judgment of the reader, and even then did not agree with the behaviour of the plates in practice.

It was Hurter and Driffield, in the memorable research to which reference has already been made, who first showed that it was necessary to take into consideration the exposure required to give, upon development, that rendering of the subject which they called a "perfect negative." There is no need to go into the methods by which this is done, as it is a matter for the plate maker rather than for the plate user ; but they worked out a complete system of plate testing, by means of which it is possible to express the speed of a plate as a number inversely proportional to the exposure that plate requires to give a "perfect negative" under definite conditions. This is now known by their initials, and plates are marked H. and D. 50, H. and D. 100, and so on, the latter requiring one-half the exposure of the former. A good many makers now mark their plates with the H. and D. numbers, but owing to differences in the manner of making the tests, the H. and D. numbers of one maker do not compare strictly with those of another, though they are reliable enough for the plates of different speeds by the same maker. Marion and Co., so far as the author is aware, are the only makers whose H. and D. numbers are obtained strictly on the lines laid down by Hurter and Driffield. The H. and D. Actinograph has already been mentioned.

Watkins and Wynne make exposure meters, in which it is necessary to denote plate speeds by means of a number, and each of these makers issues lists of plates giving the Watkins or the Wynne number for each, these numbers being obtained by actual tests of the plates, and checked from time to time. The use of them will be referred to later on. The following rules for converting H. and D. numbers into Watkins and Wynne numbers are given by Mr. Sterry :—

To obtain the Watkins number, multiply the H. and D. number by two ; and *vice versa*, to obtain the H. and D. number, halve the Watkins number.

To obtain the Wynne number, multiply the H. and D. number by sixty-four and take the square root ; and *vice versa*, to obtain the H. and D. number, square the Wynne number and divide by sixty-four.

As the H. and D. numbers on plate boxes are not strictly comparable, it is much better, whenever practicable, to obtain the lists of plates and speed numbers issued by Watkins or by Wynne, and to use those.

The nature of the subject is the only remaining factor to consider for the moment ; and, thanks to exposure meters, it is now the only factor which the photographer must furnish from his own judgment. If we can measure the light that falls on the subject, we need only consider its colour and distance. Dark-coloured objects, and those which are yellow or red, may require as much as twice the average exposure. Very light objects, on the other hand, may be fully exposed with one-half. If all the other conditions were unaltered, three photographers facing a whitewashed building, an ordinary grey stone building, and a blackened ivy-covered ruin respectively, would be within the mark if they gave exposures one-half and twice that given for the stone building. Those who have never used an exposure meter are surprised at the very little difference which the subject itself demands, but this is undoubtedly due to the fact that they have not been accustomed to consider separately the influence of each factor.

The distance of the most important part of the subject has far more influence. The nearer an object to the camera, the longer exposure will it require. The cause of this is that we see everything through a veil of air laden with dust and with moisture which reflects the light, and so makes the apparent darkness of any object get less and less as the thickness of the layer of air through which we view it increases. Authorities are agreed that the ratio of 1 : 10 represents the effect of distance upon exposure. That is to say, an object at the greatest distance at which it is likely to be photographed will require about one-tenth the exposure the same object would require close at hand. Thus the grey stone building just alluded to, which would be presumably within fifty or a hundred yards of the camera, would require about ten times the exposure that it would need were it on the horizon. The

only views often photographed at such distances are panoramas of sea and sky, and we are therefore safe in giving them about one-tenth that which would be given to buildings or landscapes of the ordinary character. On the other hand, objects which are much nearer to the camera than fifty yards are not affected to any noticeable extent by the intervening atmosphere, and the exposure need not be altered in consequence.

The exposures hitherto considered have been exclusively out-of-doors. But the conditions indoors are not greatly different, provided always we can measure the actual light falling upon the subject. The question of distance ceases to be troublesome. In the case of portraiture in a studio, exposures hardly present any difficulty at all; the conditions vary so little that the photographer soon acquires the knack of estimating them without using any meter or other appliance. There is another consideration here, which helps to make it easier. The scale of gradation in a portrait is usually very short. The highest light may be a collar or cuff, rarely, if ever, in sunshine; the deepest shadow the fold of a dark dress, illuminated by reflected light from the studio walls, and possibly from reflectors employed for the special purpose. In outdoor work we may have a whitewashed wall on which the sun shines, and a dark oak door in deep shadow. The range in the latter case may be four times as long as in the former, or even more. This means that if we have a plate which gives us a latitude in the case of the landscape of four times, it will give us a latitude of sixteen times with the portrait. As a matter of fact, many of the plates on the market will far exceed this.

A consideration of all these factors may make the problem of correct exposure seem almost insoluble, but this is very far from being the case. In fact, if it is approached the proper way, and a little trouble is taken to understand it at the outset, it becomes quite simple. There are a number of appliances by which exposures can be ascertained. These fall into two groups, exposure tables and exposure meters. The former give assistance in calculating approximately the power of the light, the latter directly measure it. This last would be perfect, if the sensitive preparation by which it was measured was affected by light in exactly the same way as the plate; but

theoretical perfection in this respect has not been reached. But in practice, except under special and infrequent conditions, when orthochromatic plates are used, the light measurers give indications upon which the photographer may implicitly rely. In his own work the author uses an exposure meter invariably.

There are various representatives of these two types of exposure aids, but a typical one of each need alone be mentioned. Amongst exposure tables, the "Actinograph" is at once the most perfect and the most widely applicable. It is a combination of the curves of light intensity, ascertained by Hurter and Driffield, with a slide rule, and its general appearance can be seen from the illustration. The card at the top

is pulled out until the top scale cuts it at the date on which the exposure is being made. This scale is then slid along until the figure representing the lens and stop employed comes against the black line on the card bearing the time of day. The lower sliding scale is then moved until the mark on it is against the figure which, in the




FIG. 13.—THE ACTINOGRAPH.

bottom graduation of all, stands for the H. and D. speed of the plate. We can then read off the exposure in seconds, according to the weather, "very dull, dull, mean, bright, of very bright," the last being one-fourth the first. The whole calculation need not take twenty seconds. The result is the exposure for an "ordinary landscape," which is not quite the same kind of object as what Watkins calls his standard subject, but is more of an open view. (The Watkins standard subject requires about one and a half times the exposure of the Actinograph "Ordinary landscape.") The number read off on the Actinograph is multiplied by two or three for close subjects or for subjects which have heavy shadows in the foreground; is halved, or even further diminished for

distant views. But it only has to be modified to suit the character of the subject, all the other factors having been taken into consideration by the little machine itself, and in this way the problem of correct exposure is very greatly simplified. The "Actinograph" has one drawback, which unfits it altogether for the globe-trotting photographer. As its light scales depend upon the height of the sun above the horizon, it is only applicable to exposures in the latitude for which they are arranged, and if the photographer travels much to the north or south thereof, he must either abandon the instrument or provide himself with light curves for other latitudes. The makers supply several of these; but the need for them must be recognized as a factor in the want of popularity from which the Actinograph has suffered.

No such limitation affects the Watkins exposure meter, which we may take as a type of those instruments which measure the light at the moment of exposure. This most useful tool is made in a variety of patterns, some of which are extremely simple and are low priced.



FIG. 14.—WATKINS "BEE" EXPOSURE METER.

The pattern that is most generally used is that known as the "Bee" meter and shown in Fig. 14. It is very simple in use. Watkins from time to time publishes lists of plates against which are given the speed numbers according to Watkins' system. Having ascertained the speed of the plates that are in use, and

the time taken for the sensitive paper to darken to the standard tint which is sold with it, the meter is held by the ring at the top, and then holding the glass and back between finger and thumb, we find we can rotate these together. We do so, until the figures on the inner dial marked "stop," which correspond to the stop which is being used, come against the number on the rim, marked "Plate," which represents the speed of the plate as given by Watkins. On the other side of the face of the meter on the dial we then find in the column marked "Light" the number of seconds which the meter paper took to darken, and then against this on the rim, in the column marked "Exp," is the exposure. The calculation with this form of meter

does not take half as long to perform as this paragraph takes to read.

Alterations on account of subject are not extensive. The exposure ascertained as just described is commonly correct. But it may be modified in four different degrees, at times, as given by Watkins in the following list :—

Sky, or sky and sea ... ..	S. 10, or $\frac{1}{10}$ the indicated exposure.
Snow and glacier scenes ; white, or black and white prints or objects ; sea view with shipping	} S. 25, or $\frac{1}{4}$ the indicated exposure.
Light coloured objects ; open land- scape (no foreground), lake or water scenes ; half-tone photo- graphs	
Very deep coloured objects, as old oak, old paintings	S. 150, or $1\frac{1}{2}$ the indicated exposure.

The indicated exposure referred to is that marked E, or that for the standard subject.

The whole secret of using the Watkins meter successfully lies in the testing of the light by its means. The meter is not held in sunlight, or even in diffused light by the camera, but the light to be measured must be that which falls upon the shadiest part of the subject in which full detail is required. The instrument is so held that it faces the sky under these conditions. To do this it does not mean that of necessity the meter must be carried to the shadiest part of the subject, and there exposed ; in most cases it is possible to extemporize a shadow to correspond. If the body is turned to face the same way as the shadow side of a house in a street scene, and the meter is held near the body and in its shadow, the reading will usually be near enough. If the view is an open landscape with no very deep shadows at all, the meter may be held further away from the body. A little familiarity with the instrument, if the results obtained with it are noted, will make its use quite simple and its indications almost if not quite infallible. In outdoor work, if the light is fairly constant, there will be no need to measure it for every exposure, as will soon be seen. With hand cameras, where there are only one or two speeds at which the shutter can be set, the meter can be used backwards, setting the exposure scale to one of the exposures



possible with the shutter, and finding out from the scale marked D the stop which with that exposure will be correct.

There is a belief about that success in photography depends upon a powerful light, and that countries with uninterrupted sunshine and cloudless skies are particularly favourable to the camera user. Like a good many more of the popular ideas on photography, it is a complete fallacy. Hand-camera work, where plenty of light is a necessity, can be carried on in sunny climes more days in the year and more hours in the day than it can in England. But that is the sum-total of the advantage. On a sunny spring or summer day in Britain, exposures will be found to be every bit as short as those in countries much further south, where the sun beats down from a cloudless sky. The reason is easy to understand. Exposures must be made for the shadows and not for those parts on which the sun falls directly, and the moisture-laden atmosphere of Britain causes the shadow to be lighter than the clear dry air of, say, a Spanish summer. Except in countries like Switzerland, where snow-covered mountains act as vast reflectors, sending light into shadows never reached by the sun itself, it will not ever be found that exposures are very much shorter than they need be on good summer light in this country ; while it need hardly be pointed out that, pictorially, the clear atmosphere presents a very real difficulty to the photographer instead of aiding him.

A few years ago, during the great coal strike in America, the author visited New York, and took some photographs as mementos of his visit. Several of the Americans he met assured him that owing to the smoke-laden atmosphere due to the soft coal they were then compelled to burn—it was about as smoke laden as Cumberland—they would give quite an unfavourable view of their city. On the other hand, it was infinitely more beautiful than it appeared a few weeks later, when the strike was over, the hard smokeless coal once more in use, and the distant New Jersey shore as clear cut and as near as the buildings in the next block. The atmosphere of London, whatever may be said of its hygienic properties, lends a charm to many of its prospects, which an artist cannot fail to appreciate.

## CHAPTER XI

### DEVELOPMENT

The latent image, theory and practice—The speed of plates considered a matter of development—Control in development—The Kodak developing machine—The appearance of the picture—The problem, how far to develop—Solved by inspection—By the Watkins method—By time—Developers—Removing the backing—Fixing—Acid hypo baths—Washing—Hypo eliminators—The ideal washer—Varnishing.

**I**F it were necessary to show how completely in photography practice has outrun theory, nothing more is required than to give the case of the latent image. We take a sensitive plate, and expose it in the camera. We know the result of that exposure is to bring about such a change in the film that on applying a suitable agent the silver bromide where the light has acted is reduced to metallic silver, while where the light has not acted reduction does not take place, at any rate so soon. Yet though the result is known, the nature of the change in the plate brought about by the action of light remains a complete mystery. There are two conflicting theories, and each has its supporters.

While our knowledge of the theory of the latent image is so imperfect, a great deal of light has been shed upon the practice of exposure and development, and here again we at once encounter the names of Hurter and Driffeld. We have already seen that until the publication of their great paper before the Society of Chemical Industry in 1891, it was universally believed by photographers<sup>1</sup> that they possessed the power of compensating for errors in exposure by modifications in development. So long as such a belief held sway it was manifestly impossible to express in any definite manner the "speed" of a plate, since it followed that this was entirely a question of developer. If a photographer could turn an under exposure into a correct exposure by a change in the developer, he made the plate

faster by so doing, and *vice versa*. The source of this error, for such it is now known to be, lay in the failure to recognize *gradation* as the true index of exposure.

While most plate makers, being pecuniarily interested, were quick to avail themselves of the work of Hurter and Driffield, plate users, trained in the earlier methods, were by no means so ready to apply that work to their own practice; and even to-day there are plenty of photographers who develop in the old way, adding alkali if they think a plate is under exposed, and bromide if the fault seems to be in the other direction, under the impression that they are compensating for such errors. Gradually, however, the truth is working its way amongst even the old style photographers, that the development of a plate should be almost as definite an operation as fixing itself, consisting of the application of the most powerful unrestrained developer the plate will stand, until it has done the required work in the film. This leaves one factor alone for control by the photographer, namely, the extent to which development should be carried.

Control of the extent of development can be exercised by controlling the proportions of the different ingredients of the developer, the temperature at which development is carried out, and the time during which the developer is allowed to act. Generally speaking, it is well not to change the first, unless the make of plate itself is changed, but to ascertain the composition of the developer which will do all that is required before it apparently acts upon the unexposed parts of the plate, and to use such a developer always. Control of the temperature is actually very simple, although few photographers care to regulate it directly by standardizing the temperature of their solutions by means of a thermometer. The most usual method of development is to ascertain the time taken for the first sign of the image to appear, and to develop for some multiple of that time. But it is quite easy, by making up a standard developer, warming it or cooling it to the standard temperature, and then applying it to the plate for a definite time, to produce uniform and excellent results. This is the principle upon which the Kodak Developing Machine and the Kodak Tank Developer are based, and the success with which those machines operate, astounding as it

often is to the photographer filled with the belief in his power of control, will no doubt play a very large part in bringing about the adoption of the same principle to the development of plates.

Having settled upon the composition of his developer, there are three methods open to the photographer, which we will consider in order. In the first, he applies the developer to the plate, rocking the dish the while, and watching the appearance of the image by the red light of the dark room; the second is the Watkins method; and the third, time development pure and simple.

There is no more wonderful or attractive experiment in the whole range of physical science than the gradual building up of that picture in metallic silver, on the slight and mysterious foundations laid, it may be in the thousandth of a second, by the impulse of light alone. It is an experiment which, to the reflective mind, can never lose its interest. There is the creamy coating on the plate without a sign to suggest in the faintest manner the wonderful potentialities that lie upon its surface. No test that we can apply, other than the developer itself, will even tell us whether it is in its pristine state of purity, or whether it has already had the magic touch which has given it the power to preserve through all time a minute and impeccable record of a state of things itself perhaps of the most transient character. We thoughtlessly snap off our camera at an express train as it dashes through a station. A hundred years afterwards, if the negative is preserved, it will not merely give us the impression of the train in its passage, it will show us the people on the platform, the signals with their message of safety or danger, the arrangement of the very bricks in the station walls. Nay, it will tell us the particular stalks of the particular plants in the porter's garden that at that moment bore flowers. What other everyday action can compare with this, either in the elaborate detail of the result, or in the simplicity of the means by which it has been brought about? And this is the miracle which takes place in the dark room of every photographer each time he develops a plate. How often do we spare a thought from the trivial anxieties of the moment to the marvellous character of the powers we are employing?

This change then is watched by the photographer, with his

mind as a rule, it is only reasonable to suppose, directed upon the immediate problem which confronts him. That problem is, how far to carry development. He watches the gradual emergence of the image on the film, notes how it darkens over in the most exposed portions first, until the details there are no longer perceptible, and how this darkening gradually extends to the shadows also. If all is as it should be, the edges of the plate where the light has not acted at all, whatever happens, should not perceptibly change colour; but if the exposure has been the shortest correct one, there will be a distinct darkening in even the deepest shadows. If these remain white, the plate is unquestionably under-exposed. But, assuming that it has been properly exposed, they will in time dull over; until, looking at the plate as it lies in the dish, the darkest parts of the subject can only just be seen as distinctly lighter in tone than the rest of the plate. The photographer then knows that development is nearing completion. If stopped at this stage, the negative may be a "perfect" one, in the Hurter and Driffeld sense, but not necessarily so for the purpose for which it is required. Some printing processes require a soft negative, some a medium, some a distinctly hard negative. The difference is solely brought about by the extent to which development is carried, and the photographer has now to decide how far he is to continue the operation. To do this by the eye he has three guides: the appearance of the plate looking down on its surface; the appearance on the back; and the appearance looking through it at the light. The first we have alluded to, and theoretically this should be the most reliable, because it is not influenced, as are the other two, by the thickness of the coating on the plate. Actually all three are observed; modern plates are all machine made, and there is comparatively little variation in the coating. Looking through the plate at the light, the image should look decidedly stronger than is desired in the fixed negative, though how much stronger, it is hard to judge. If the plate is a very thickly coated one, and the exposure is correct, but full, it is quite possible that little or nothing will be seen on looking through it, the film to the weak red light seeming quite opaque. The appearance at the back is then the only guide. In a landscape, the outline of the sky should be plainly seen on the glass of the plate, though

the sky ought not to appear as very greatly darker in tint than the rest, or the plate is either very thinly coated or is over-developed. Using plates of the same brand, it is not at all difficult to determine, approximately, when to stop development in this way, though no such uniformity is likely to be secured as when time development pure and simple is employed.

The Watkins method of time development is the easiest that a beginner can adopt; and as used with the Watkins exposure meter, it will be found to give the highest percentage of successful results. Watkins has worked out a series of factors for different developing solutions, the factor being the multiple of the time of appearance of the image, required for complete development. To use this method, then, the developer is poured on to the plate, and the time noted. As soon as the high lights are distinctly visible, the time is again noted. Multiplying the period that has elapsed by the factor for the particular developer in use, we get the time required for complete development. The advantages of the method are undeniable. The plate may be kept covered during the whole time of development, except while looking for the first appearance of the image. As soon as this has been noted, a card may be put across the dish, and the total time worked out while the plate is in darkness. There is no uncertainty as to the extent to carry the operation, and so long as the exposures are reasonably correct, as they should be if the Watkins meter is used, the method gives remarkably uniform negatives. With under- or over-exposures, it is not reliable. An under-exposed plate takes longer for the image to appear, and therefore by the Watkins method it takes longer to develop; an over-exposed plate is the reverse. The tendency, therefore, is for the under-exposed plate to be over-developed, and the over-exposed under-developed. Neither course is desirable, and tends to exaggerate the defects caused by under- or over-exposure alone. If several plates are developed at once by the Watkins plan, and the image on some appears sooner and on some later than on others, if the time of one of the correctly exposed plates is noted and used as the basis for developing all of them, the results on the over- and under-exposed plates will be better than if they had been developed for the times indicated by the appearance of their own images.

The factor for each developer is not a hard and fast figure, but, necessarily, depends upon the purpose to which the negative is to be put. Thus if we find when using Watkins' own figures, that they give negatives harder or softer than we require, we can decrease the factor in the former case or increase it in the latter, until it yields the kind of negatives wanted. The following are a few of the factors given by Watkins himself, in his book, "The Watkins Manual," which should be consulted for further details of his system.

Grains of pyro per ounce.							Factor.
Pyro-soda (without bromide)	1	...	...	...	...	...	18
"	"	"	2	...	...	...	12
"	"	"	3	...	...	...	10
"	"	"	4	...	...	...	8
"	"	"	5	...	...	...	6½
Adurol	...	...	...	...	...	...	5
Pyrocatechin (Kachin)	...	...	...	...	...	...	10
Hydrokinone (with the usual amount of bromide)	...	...	...	...	...	...	5
Eikonogen	...	...	...	...	...	...	9
Metol	...	...	...	...	...	...	30
Glycin	...	...	...	...	...	...	7
Amidol (2 grains)	...	...	...	...	...	...	18
Rodinal	...	...	...	...	...	...	40
Ortol	...	...	...	...	...	...	10

Pyro-ammonia cannot be used with this method, as the results are quite unreliable. The disadvantages of pyro-ammonia, however, should prevent its employment quite apart from this. It requires much skill in its use, and on no account should be employed by a beginner. Pyro-soda is perhaps the most universally popular, as it is most certainly the cheapest; but metol-hydrokinone has many admirers. In the case of combination developers, the factor can be obtained by taking the average of the factors for the two components in the proportions in which they are used. Thus, to arrive at the factor for a developer containing seven parts of hydrokinone to three of metol, we add together seven times the factor for hydrokinone and three times the factor for metol, and divide the result by 7 + 3.

$$(7 \times 5) + (3 \times 30) = 35 + 90 = 125$$

$$125 \div 10 = 12\frac{1}{2}, \text{ the factor required.}$$



IN AN OLD CHURCH  
BY HENRY W. BENNETT





Those developers which have a small factor, such as hydro-kinone or glycin, have that factor very greatly modified if bromide is added to the developer; but with those which have a high factor, metol, etc., the presence of bromide has little or no effect upon it. It has already been pointed out, that in any case bromide should not be added to a developer, as its action, as far as it is traceable, is distinctly injurious. Although a few plate makers still give bromide in their formulæ, it is hardly necessary; and there is certainly no need for it with any of the plates made by the better makers, most of whom do not specify any bromide.

The third method of development is by time, pure and simple. The developer is applied to the plates for a given time dependent upon its temperature, after which they are fixed and washed. There is no need in this case for the plates to be exposed to the dark-room light at all, except to make sure that they are covered with the developer. Any light-fog should therefore be impossible. There is no temptation for the photographer to try and make all his negatives of uniform density, the besetting sin of those who judge development by the eye. Such a course leads to the under-development of over-exposed plates and the over-development of those that are under-exposed; and is responsible for the belief that over-exposure gives thinness and under-exposure excessive density; both views are quite erroneous. If an under-exposed, a correctly exposed, and an over-exposed plate are developed in the same dish for the same time, that time being what is required to make a perfect negative of the correctly exposed plate, it will be found that at the same time the best that is possible has also been made of the other two. We have not ruined the under-exposed plate past recall by over-development, as is so often the case, and if the under-exposure has not been too great it is quite possible that we may be able to intensify the negative so that it may give a passable print. In the same way, judicious reduction will do the best with the over-exposed plate.

The Kodak developing machine was the first commercial apparatus to employ this principle. It is found in the hands of those who have never developed a film in their lives to give results which are as good as the most skilled developer could

make. So certain is the evidence afforded, that the Kodak Company itself uses the machine entirely for the development of roll films, and finds that the percentage of good negatives obtained is quite as high as when the films were developed by their skilled operators in the old method. This is all the greater testimony, since the films dealt with are those of customers many of whom have little or no idea of correct exposure. In the case of this machine, there are the added advantages that it dispenses with any necessity for a dark room, minimizes the risk of finger marks and scratches on the film, and enables a long length to be developed in a compact and easy manner. Great as are these advantages, they are comparatively unimportant beside the fact that it secures uniform development, and ensures the process being carried exactly to the proper stage. The Kodak Company supply developing powders (pyro-soda) for use with the machine, and get over the difficulty of bringing the temperature of the developer up or down to a standard, by a table showing how long the development should take for the different temperatures likely to be met with. This simple method has now been extended to plates and cut films.

Time development of this kind applied to plates, means that the photographer must first find out for himself, as such particulars are at present given by none of the plate makers, the time which the developer he selects requires to turn a properly exposed plate into the kind of negative he wants. Either he must do this for the different temperatures at which he may develop, or he must always work at the same temperature. The former plan is more reliable in practice, but the latter is simpler. It is accompanied by the drawback that if the standard temperature is very different from that of the room in which development is being carried out, the developer soon alters in temperature and the result is not what was anticipated. The Watkins system, with correctly exposed plates as a guide, is actually one of time development and nothing more, the time of appearance of the image acting as a thermometer, and the factor enabling us to put its reading into practice. Taking its merits and its defects into consideration, it is at present undoubtedly the readiest method of obtaining the best possible negative on plates or cut films, as

are the Kodak appliances unquestionably when roll film has to be developed.

So far nothing has been said of the different substances used for development; but it will have been inferred already by the reader, that the nature of the developer is comparatively unimportant. Formulæ for developers are given wholesale in the instruction books, and every box of plates has with it the formulæ which the maker recommends. These are not of necessity any better than any of the others that are at the service of the photographer; but in most cases the makers' formula has this one advantage—it indicates the most vigorous developer that can be applied to the plate without fogging it. Ready-made developers, speaking generally, are a mistake. They are usually purchased by the rawest beginners, and as the ready maker has probably some experience of this class, he takes care that his developer shall contain such a proportion of bromide as shall serve to counteract as far as possible all the beginner's propensity to fog his plates. He is not to be blamed for supplying an article which gives the greatest satisfaction to the greatest number of those who buy it, but his article is to be avoided unless he can be induced to state definitely and truthfully that it is free from restrainer of any kind.

It is a great mistake to wet a negative with water before putting it in the developer, as this has a great tendency to form air-bells, which may not be noticed in time to prevent them from leaving a mark. To avoid these, if the plate must be wetted, it should be placed under a strong flow of water from the tap for a minute or two. The force of the water acts as a guarantee against the adhesion of any air-bells; and there are circumstances in which the preliminary wetting of the plate may prove advantageous, as for example, when a large plate has to be developed with a very small quantity of solution. The quantity of liquid required to develop a plate is governed more by the nature of the dish than by the chemical requirements of the film. A dish with an irregular bottom, or one which bends in the hand, takes much more liquid than a rigid dish with a smooth bottom, little larger than the plate itself. An ounce for each quarter-plate may be taken as approximately correct.

Even in so simple an operation as the pouring on of the developer, there is plenty of room to make mistakes. The developer should not be allowed to stand in the measure for more than a minute or two before it is wanted, as with some waters a scum is formed on the top, which, when poured on to the plate, adheres to the film in parts and is some little time before it washes off. It will not be noticed at the time, but afterwards it will be found to have held back development a little, and so to have marked the negative in a way which is incurable except by the most elaborate retouching. The liquid should not be splashed over the surface of the film, but holding the dish in the left hand and the graduated measure in the right, the side of the dish furthest from the body being higher than the other, the broad edge of the measure, not the lip, is put over the edge of the dish, at the left-hand corner, and then the measure is slid along to the other edge of the dish, raising it so that by the time it gets there it is empty. At the same time the dish has been brought level. The two actions are difficult to describe, but ridiculously easy to perform, and the result is that a smooth even wave of developer passes over the whole plate, pushing off any dust that may be on it, making no splash, and leaving no air-bells behind it. This may be tried in daylight once or twice first; and then its effectiveness will be seen.

No plate, however the length of development is determined, ought to be exposed to the light of the dark room all the time. A cover for the dish may be extemporized from a piece of card, or a larger dish may be used, or a cover may be made and kept for the purpose. A flat board with a narrow ledge round it within which the cover fits, and a fillet about a quarter of an inch in depth and an inch wide running across the middle of its under side, makes it very easy to rock the dish without having to hold it in the hand to do so.

As the addition of bromide to a developer is a thing to be deprecated, and as the action of development leads to the formation of bromide in the solution, the prolonged use of the developer is not to be recommended at any time. In certain cases, such as that of bromide paper, where the developer is one with a high development factor, and therefore very little affected by small quantities of bromide, and

where the developer is plentiful and strong while the film itself is thin and not so rich in silver as a plate, it is found economical and harmless to use the same developer over and over again; until, in fact, we are warned by the colour of the prints, to change it for fresh. But in negative work, it is a poor economy, both because of the uncertain composition of the solution and because of the greatly increased risks of staining the film.

After development and before fixing, the negative should be slightly washed. If development has been determined by the eye, the backing will have been removed from a backed plate already. Some workers wash it off before starting to develop, and thereby introduce the risk of air-bells on the surface of the film, to which reference has already been made. In time development, whether by the Watkins method or pure and simple, the backing may be left to come off, or at least to soften in the development and fixing. A common plan for those who do not use time development, is to wait until the image is well out on the plate, and then to remove the backing under the tap, replacing the plate in the solution to finish developing. No harm is done by the intermediate washing. To get rid of the backing the plate should be held, back downwards, with a gentle stream from the tap running into the centre of the film. A nail brush or a rag may be used to rub the underneath side, to dislodge any backing that may remain, which will then be carried off by the water. If the plate is held back upwards, the water carries the backing on to the film. Though many photographers take a negative straight out of the developer, and put it into the hypo, there is always a risk of marks and stains when so doing; some developers being particularly prone to cause them. It is well known that a developer coming into contact with a solution which contains a silver salt is liable to give rise to metallic marks in the film and to the once common, but now almost unknown defect, dichroic fog. The film of a plate put straight into hypo while full of developer gives precisely the conditions required for the production of such fog. Hence arises the necessity for a preliminary wash, which need only be a rinse under the tap for half a minute, but should not be omitted.

Only two forms of fixing bath have any wide popularity,

the plain hypo solution and acid hypo. For negatives, a solution of four ounces of hypo in a pint of water answers every purpose. It ought to be made up some time before use, to get to the temperature of the rest of the solution, as when hypo dissolves, the solution becomes for the time being very cold. Hypo is decomposed by almost all acids, with the formation of sulphur. Sulphurous acid is an exception; and as sulphurous acid has powerful anti-staining properties, many like to have it present in the fixing bath. Such a bath is known as an acid-fixer. The simplest way to make it would be to add the sulphurous acid direct, but the acid is not a very pleasant compound to have about. As a substitute, therefore, it has been customary to recommend making a solution of sulphurous acid by adding sulphuric acid to a solution of sodium sulphite, and adding this. The sulphite and the sulphuric acid must not be added separately to the hypo, or the acid will at once decompose it. They must first be mixed. For this purpose the following formula will be found effective :—

Sodium sulphite (crystals)...	...	...	...	...	...	1 lb.
Sulphuric acid	...	...	...	...	...	2 ozs.
Water	...	...	...	...	...	80 ozs.

One ounce of this solution is added for every two ounces of hypo in the bath. A simpler plan is to add two drams of potassium metabisulphite to the fixer, to each pound of hypo. As the metabisulphite is a strongly acid salt, in fact, sulphurous acid can be recognized in it by the smell alone, this requires the addition of no sulphuric acid as the sulphite does. In making up the solution of sulphite and sulphuric acid just described, it is important not to increase the quantity of the acid, as free sulphuric acid in the fixing bath would be most injurious.

Whether plain hypo or an acid fixer should be used for negatives is largely a matter of opinion. There ought to be no difference in the cleanliness of the negatives; but those who are at all troubled with stains or scum marks will find the acid-hypo, if not a complete preventive, at least a palliative. It is much more expensive than the plain hypo. It does not discolour in use; but this is not an unmixed good, as it may lead

to the fixing bath being kept and used after it is actually too exhausted to ensure complete fixation. This leads us to consider the manner of its action on a plate.

If we take a negative, and, watching it carefully, remove it from the hypo as soon as the white appearance at the back has gone, wash it, dry it, and place it in a strong light, as would be the case if we were going to print from it, the film will in time turn brown, probably only in patches, and the negative will be ruined. If we had left the negative in the hypo for twice as long, this would not have occurred. The function of the hypo is to dissolve the silver bromide and iodide left in the film and unused in the formation of the image. Hypo acts upon these silver salts immediately, forming salts known as silver thiosulphates. These salts are not readily soluble in water, but are soluble in a solution of hypo. The sign that they have been formed is the disappearance of the creamy bromide and iodide in the film, best seen at the back of the plate; but this disappearance is only a sign that the first stage of the fixing is complete. The thiosulphate is formed, but it is still in the film, and has got to be removed, and its removal must be effected by the solution of hypo itself. For this reason, therefore, the common rule is to leave a plate in the fixing bath as long as is required to get rid of the creamy appearance, and as long again. It is a safe rule, and, in the absence of any other indication to guide us, is the best we can do. But it is purely empirical.

We have already seen that acids, except sulphurous acid, decompose hypo. The same decomposition is caused by alum, but more slowly. This decomposition is a very dangerous, one to the stability of the image in both negatives and prints, and is a thing to be guarded against by all who wish their photographs to last longer than a few months. For this reason, then, alum and hypo, except when their mutual action is employed deliberately for toning, as will be described later, must be kept strictly separate. In hot climates and under trying conditions generally, gelatine plates and films may frill and blister. The remedy usually suggested is an alum bath, and alum certainly hardens the gelatine and renders it less susceptible to such defects; but carelessly used, the alum may cause troubles worse than it prevents. Stains and blotches,



which may only appear some time after the negative is finished, form one of its manifestations. A worse, and totally incurable defect, is a patch of a light colour, best seen from the glass side, looking for all the world as if the plate were insufficiently fixed, but resisting the most prolonged action of hypo. Both are caused by putting a film containing alum into a solution of hypo, or *vice versa*. No harm results if the alum is washed out before the plate is put in the hypo, or if the hypo is removed before the alum bath is applied.

In temperate climates, if there is much trouble from frilling or blistering, it is far better not to attempt to correct it by means of alum or other hardening agents, but to discover the cause and remove it. A great difference between the temperature of the different solutions in which the plate is put will cause it. A caution has already been given against the cold water pipe to the dark room being led for any distance side by side with a hot water pipe. The writer knew of a case where this occurred and gave rise to persistent frilling, although the temperature of the water was never high enough to be noticed. In another instance, the relief pipe of a hot water heating apparatus discharged into a cold water tank from which the dark-room supply was drawn, and caused countless failures, until they were finally traced to their source. Another factor which may tend to produce frilling, is the employment of a developer containing caustic alkali, or even a great quantity of carbonate. Hydrokinone requires caustic soda or potash if it is to be used successfully, and these have a great softening effect on the film. So has ammonia. Careless handling of the edges of the plate during development may lead to frilling, and if a large plate has been unskilfully cut up that, too, may bring it about.

After fixing, it only remains to get rid of the hypo in the film for the negative to be finished. This is done by washing. Important as is thorough washing, thorough fixing is still more so, and repeated experiments have shown that a plate that is completely fixed will carry a good deal of hypo in its film without being seriously affected thereby. At the same time, every negative should be thoroughly washed, both to ensure its permanence and to allow of the application to it of other processes, such as intensification or reduction, with either of

which the presence of even a trace of hypo would be most detrimental. The importance of the washing process has led to the most exaggerated and mistaken ideas of the time which should be devoted to it, and of the method of carrying it out. It has also led to the introduction of chemical "hypo-eliminators" intended to decompose the last traces of hypo in the film and so render them harmless. The worst of it is, that the hypo itself is harmless until decomposed; and, in some cases, at any rate, the product of the decomposition of the hypo is certainly more deleterious than the unaltered salt itself. The best hypo-eliminator is water, and it can do its work completely in half an hour.

Let us suppose for a moment that we have a negative which we wish to wash as quickly as possible, but wish also to be confident that the washing has been thorough. On taking it from the hypo, it is rinsed under the tap and placed in a dish of water. At the end of two minutes it is taken out and stood up to drain, while the dish is rinsed out and filled with clean water. The drained plate is put into it for another two minutes, again put up to drain and the dish rinsed and refilled. At the end of half an hour the negative will have had about ten changes, and, as has been shown by the work of MM. Lumiere and Seyewetz, is as completely freed from hypo as is reasonably possible—quite as completely as is demanded to ensure permanence.

The use of "hypo-eliminators," as they are called, seems to be very tempting to some, on account of the supposed saving of trouble and of washing water. There is no doubt, however, that if the washing is carried out in dishes, as directed above, it will be no more trouble, and certainly will use no more water, than any process involving the application of chemicals to destroy the hypo. Because whatever is used we must get rid of the products of the destroying action by washing. A saturated solution of alum applied for an hour or two is said to get rid of the hypo; but as the action of the alum is practically that which the photographer fears if hypo is left in the film, the remedy is worse than the disease. Sodium hypochlorite, potassium persulphate, and hydrogen peroxide have all been recommended, but are of very doubtful efficacy. Lately the use of water just tinged pink with potassium permanganate

has been suggested. This is employed instead of plain water for washing. The hypo destroys the pink colour, and so is known to be eliminated when the characteristic tint of the permanganate solution remains after the liquid has been in contact with the plate for a minute or two. The solution must not be strongly coloured, or the negative may be stained. If it is stained, it is best to finish the washing and then to immerse the negative in a two per cent. solution of oxalic acid until all the stain has gone, and then to wash it again to remove the acid.

Though the advice is often given to wash in running water a negative that is wanted in a hurry, it is very doubtful whether the method described in a preceding paragraph is not more effective, in the same time, than placing the negative under the tap would be. It is not so much the constant changing of the water as the thorough draining in between each change which is so effective in getting rid of the hypo. Careful experiments have shown that popular ideas as to the efficacy of rinsing are mistaken. We fill a glass with a solution of some salt or other, empty it out, rinse it a few times in clean water, and assume that by so doing we have got rid of the saline matter. But it is by no means the case; and the solution will be found to cling to the glass, and by delicate chemical tests to be present in quite appreciable quantity after the rinsing. If this is so with the smooth polished surface of a glass, how much more is it to be expected in the case of the spongy absorbent film of gelatine? If we could squeegee it between each rinse we could accelerate washing, but the film is too tender for that.

Cut films are not easily washed in the same apparatus that is used for plates, as, unless they are exceptionally stiff, they will not remain in the grooves like a glass plate. Two, back to back, may be placed in the grooves if they are fairly stiff, and have a piece of glass between them. Or they may be washed in a dish like prints. They can also be washed by suspension in a tank. A long length of roll film may have one or two split shot (which are supplied at any fishing tackle warehouse) nipped at intervals of a few inches along the edge. Along the opposite edge are placed small corks, the cork being slit with a sharp knife, and the extreme edge of the film slipped

in. Such an arrangement will float vertically in a large vessel of water; the domestic bath answers excellently. If there is a depth of a foot or so below the film, and it has been rinsed once or twice before immersion, and is rinsed once or twice afterwards, two changes of the water in the bath at intervals of an hour will wash the films effectively. Another plan is to fasten the film with drawing pins to the surface of a board, and float that on the water, film downwards. As there is a gelatine coating on both sides of non-curling "roll" film, the film should not be fastened flat to the board, but bowed so that the water has access to the back also. The image-bearing film must be outwards of course. Films that have been cut up can be washed by inserting one edge in a slit in a cork, and floating them in a vessel of water.

If we examine the surface of a negative after it comes from the washing water, we are almost certain to find it covered with a whitish deposit, or with a scum—the former when the washing water is hard, the latter when it is soft. It will not do any great harm if it is left on, but it is easily removed by holding the plate, film upwards, under the tap, and rubbing the surface gently with a mop of cotton wool. This certainly improves the appearance of the finished negative. It may then be dried. The grooved racks which are sold for drying negatives are very convenient, but on no account must a plate be put in each pair of grooves. The grooves, as a rule, are far too close together for this to be done. An inch or more at the very least should separate the plates, if they are half plates or smaller, while if they are larger this distance should be increased. Drying must not take too long, nor must it be irregular. The wet film is an ideal culture ground for bacilli and mould, and defects in negatives have been directly traced to such causes. The sooner the plate is dry, therefore, the better. Before standing the plates in the rack, the glass side should be wiped dry with a clean cloth. Drying is hastened by taking up from time to time with a strip of blotting paper the drop of water that collects at the bottom corner. It might be worth mentioning for those who suffer from the insects, that "black beetles" regard the damp gelatine film of a negative as a particular delicacy.

The rate at which the film dries has a distinct effect upon

the density of the image. Consequently, if the plate is allowed to dry all round the edges, but the drying of the centre is prolonged, as would be the case if it were stood up with a number of others too close together in a rack, there would be a difference in the density of the centre and edges, separated very likely by a distinct line, and the negative would be ruined ; for there is no remedy for this, even re-wetting and drying failing to remove the mark.

Heat cannot be used in the ordinary way to accelerate drying, or the film would melt. If a developer containing a caustic alkali has been employed, the film may have been made so tender that even the ordinary heat of an English summer day may cause it to run ; but with sodium carbonate this is not likely to occur with any plate, and when pyro has been used, that seems to exercise a tanning action on the film which enables it to resist quite a considerable degree of heat. There is a good deal of difference between different makes of plates in this respect, as will be seen by any one who tries with hot water to clean the films off plates that have been spoilt from any cause. Some yield at once to hot water, while others, after soaking for some time in cold, will stand a stream of hot water which the hand could hardly bear. It is possible to make the film on a negative so insoluble as to resist the action of boiling water. If we place the finished, washed plate in a mixture of formalin one part, water four parts, for five minutes, we can put it into boiling water without injury. This has been suggested as a means of drying a negative very quickly. It is allowed to remain in the hot water for thirty seconds or so, and is then taken out and stood up in a current of air, where it will dry in two or three minutes. This gives the surface a curious glaze, and makes it so repellent and horny, that other operations, such as intensification, are almost impossible. With some plates this process makes the film so powerfully contractile, that, as the plate dries, it pulls right off the glass, and even in extreme cases, may pull the very surface of the glass away with it, as has occurred to the writer more than once. The method, therefore, is not one to be used without first making sure that the particular brand of plate to which it is to be applied will stand it. Another and very common method of accelerating drying is to put the negative,

after draining it, drying the glass side, and wiping the film surface dry with a fluffless rag, in a dish of methylated spirit. In this it is left for three or four minutes, and it is then placed in a current of air. It will be dry in something less than a quarter of an hour. Two cautions are necessary, however. One is that the method is not applicable to celluloid films, as the spirit attacks the celluloid; the other, that the negative is not dry when the surface seems dry, but must be left for at least as long again before printing, or there will be a great risk of the paper sticking to it. Negatives dried by any of these plans are not so clean looking as those which have been allowed to dry spontaneously.

Some workers when they get to this stage varnish their negatives. The very great majority do not. There is no reason why an amateur photographer, who is not going to print hundreds of copies from each, should do so. On the other hand, there are distinct reasons why he should not. In the first place it is an extra process, a messy process, and a risky process. It is easy to the old collodion worker to pour the varnish all over the plate, to drain the excess off into another bottle to be filtered before putting it back, to rock the plate to secure an even coating, and to hold it to the fire and dry it. But the modern dry-plate worker finds the result of the first operation is to send a stream of varnish up his arm, of the second to make a pool of it on the floor, and of the third to cement a number of dust particles to the surface of the negative, and possibly to set the whole of the varnish alight. True, there are varnishes which do not require heat, and can be applied with a brush; but while to some extent a protection, it is doubtful whether it is really enough to justify their application. The careful, methodical worker will probably use such; the photographer, who drives right ahead towards the print as his goal, will probably not. Any varnish, once applied, makes it much more difficult to carry out any after process which depends upon the wetting of the film, as the varnish must first be removed, and the repellent action towards water which it gives to the surface of the gelatine destroyed. Celluloid films can be varnished very simply, by immersing them in a dish of the varnish, and hanging them up by one corner to drain and dry.

## CHAPTER XII

### INTENSIFICATION AND REDUCTION

Intensification—Different processes required by different forms of thinness—Fog—Different reduction methods—Wellington's silver process—Mercury-ammonia—Mercury-ferrous-oxalate—Mercuric iodide—Monckhoven's intensifier—Sanzol—Ammonium persulphate—Ferricyanide and hypo—Namias' permanganate reducer—All such processes are only makeshifts.

THE finished negative may or may not be precisely what we require. If it is not, there are a number of processes at our command by which it can be modified. Some of these are chemical, and are applied usually, though not necessarily, to the whole negative; others are mechanical, and lend themselves particularly to local application. If the negative is too thin to print by the process we propose to adopt, it can be intensified; if it is too dense, it can be reduced. There are several reliable methods at our command in either case. No methods have been the subject of more complete misunderstanding than those of intensification and reduction. It is customary to say that if the negative is too thin it can be intensified, to give one or two methods of intensification, and there to leave it. Reduction is treated in the same way. The fact is that thinness may be due to one of several causes, and each particular kind of thinness must be dealt with in a particular way if it is to be remedied. Some methods of intensification applied to some thin negatives might make the last state of those negatives worse than the first, although in other cases the method might be most valuable. Before anything is done, therefore, either in the way of intensification or of reduction, it is most important to diagnose correctly the shortcoming of the negative.

Taking first the case of negatives that are too thin to give a good print, there are three distinct causes for such thinness, and these demand three distinctly different remedies.



THE NEW SONG

BY F. T. HOLDING





The first cause is under development. The negative has been correctly exposed, but was taken out of the developer too soon. If such a negative is placed face downwards on a sheet of white paper—its edges should be quite clean—there should be some signs of an image in the deepest shadows, and there should be distinct difference of gradation right from the shadows to the highest lights, although these differences are not great enough to give as vigorous a print as can be desired. It may have been over-exposed and under-developed, a very common defect, since it follows inevitably, if the Watkins method of timing development is applied to an over-exposed plate; and most workers, who do not adopt time development, under-develop over-exposed plates from inability, from excessive density, to see how development is progressing, or from a desire to avoid halation. Whether the plate is correctly or is over-exposed, the thinness is due to insufficient development, and the remedy is the same. What is wanted is intensification as far as possible in proportion to the amount of deposit already in the film. The best intensification for such negatives is by Wellington's silver method, but the ordinary mercuric chloride, followed by ammonia or by ferrous oxalate, will be found to answer. In the case of over-exposed plates the mercuric chloride and ammonia is better than the others, but the difference is not very marked.

Thinness may be due to under-exposure. It is often said that under-exposure causes harshness or excessive contrast in a negative, but this is a complete mistake. The harshness is due to over-development, that operation having been carried on too long, with the mistaken notion that perhaps it might bring detail out in the shadows. It never does; the result being merely to make it more difficult than it otherwise would be, to botch up some decently printable negative on the under-exposed plate. Those who doubt this can soon set their minds at rest on the subject by trying the experiment of exposing three plates on the same subject, giving one a correct exposure, and the other two what is a very decided under-exposure, but giving the same to both. One of the under-exposed plates and the correctly exposed plate are developed side by side for the same length of time, the time being that required to give the negative desired on the plate that was

correctly exposed. The remaining plate may be developed as far as possible, in the hope of bringing out detail. Of the two developed together, the correctly exposed plate in every respect will have more deposit and more contrast than the under-exposed plate, showing that under-exposure does not lead to harshness or to excessive contrast, but the reverse. The other plate will doubtless be very harsh; and it will be difficult, if not impossible, to make as good a negative from it as from the under-exposed plate which was developed with the correctly exposed one. Thinness, therefore, may be due to under-exposure. In such a case the best treatment is intensification with mercuric iodide. If mercuric chloride is used, printing density can be obtained, but the print will have all the characteristics of a print from an under-exposed negative; if mercuric iodide is used, and to some extent if the Wellington silver intensifier is used, the signs of under-exposure are less noticeable.

The third cause of thinness is extreme flatness in the subject. The silver intensifier will be found much the best for this. This cause of thinness is the least likely to arise, as in the very great majority of the subjects with which photographers, especially amateur photographers, are likely to deal, the subjects are such as to yield negatives of ample contrast on the plates on the market.

There is little profit in trying to intensify plates that are noticeably fogged. The fog being of the same composition as the image, it is intensified at the same time, and before the action has been carried far enough to improve the negative materially, the fog has intensified to such an extent as to make it unprintable. Some photographers claim to be able to improve negatives which are both thin and foggy, by reducing them first, to remove the fog, and then intensifying to obtain contrast. On paper this looks very satisfactory; but although the author has tried it repeatedly on negatives which looked most favourable for the experiment, it has never resulted in a negative that was in a noticeable degree an improvement on the original. There is a method—Monckhoven's—which improves such negatives a little, as it has a slight reducing action on the thin parts as well as an intensifying one elsewhere, and this offers the best chance, though a feeble one at best, of making a negative that

is both thin and foggy into one that will give a fairly good print.

Reduction is the reverse of intensification, and resembles it in this respect, that it is necessary to diagnose the cause of the over density which we desire to reduce, before we can decide which reduction method to apply. Over density may be due to over development, or it may be due to fog, in which case a reducer is needed which shall take the same quantity of the deposit off shadows and high lights alike. As this latter form of reduction does not have any great effect on the contrast obtained finally in the print, and only lessens the time which the negative takes to print, it is very seldom that its use is justifiable. It is risky, because if reduction is carried on beyond the stage at which all the fog is removed, and it is not always easy to tell when this stage has been reached, it begins to destroy the gradation on the negative, and no after process can remedy this. Its action, in short, is to make a negative obtained with correct exposure resemble one obtained with under-exposure. Reduction of this type may be applied in the form of a momentary treatment to remove surface stains and clear up a negative generally; but it must be momentary, and must err on the side of insufficiency to make sure that it is not overdone. It is sometimes applied with advantage to lantern-slides to clear them; but the conditions then are altogether different.

There are two reducers, either of which may be applied to remedy over-development. They are efficacious whether exposure has been correct or insufficient, although, of course, in the latter case nothing will turn the bad negative into a good one. Ammonium persulphate is one, and sanzol (a cobaltamine salt) the other. There are a number of reducers of the other type, of which the ferricyanide and hypo and the potassium permanganate are the best known.

The negative to be reduced or intensified must in every case, except one, be thoroughly fixed and well washed. The only exception is that of the ferricyanide and hypo reducer, which may be applied to the plate immediately it comes out of the hypo, if for any reason this seems to be desirable. All negatives take these processes more easily if they are applied before drying. On the other hand, the application of the

solution has a softening action on the gelatine, and may lead to frilling ; drying between washing and the after processes helps very greatly to prevent this. If the negative has been varnished, the varnish must be removed by means of a suitable solvent. Shellac varnishes, such as those which require heat for their application, are made with alcohol and can be removed by means of methylated spirit. The negative is placed in the spirit for a minute or two and gently rubbed with cotton-wool. It is then taken out, drained, and put in fresh spirit, being rubbed with a clean piece of wool. After a minute or two, it is again drained and placed in a third bath in the same way. It is then rinsed under the tap and allowed to soak for half an hour or so in clean water. The spirit, after use, may be employed in lamps ; but holds too much solid matter for most other purposes. If the varnish has been a celluloid one, such as are most of the cold varnishes, acetone or amyl acetate must be used in the same way to remove it. Acetone is preferable to amyl acetate, on account of the strong smell of the latter.

Nothing would be gained by giving particulars of other intensifiers and reducers, which are numerous enough, as their action is not markedly different from those dealt with in this chapter, which should be more than sufficient for all the possible requirements of the photographer. He will do better still if he determines to do without them entirely, relying in every case upon correct exposure and correctly timed development to give him the negative which he requires. No reduced or intensified negative is so good as one produced by the operation of development alone. They are all only means for making the best of a bad job, and although they will work wonders in the way of improvement, the result will never be perfect. All said and done, they only act as effective remedies at all in the case of errors in development. As for plates which have been over or under exposed, they are best reduced—with a hammer.

## CHAPTER XIII

### THE HAND-CAMERA

Detective cameras—Distinctive features of hand-camera work—Focussing devices—Depth of focus—Infinity—Magnifiers—Finders—Shutters—Efficiency in shutters—Control of speed—Levels—Plate changing mechanism—Dark slides—Films—Daylight loading—The Kodak—Holding the camera—Reflector cameras—Estimating distance—Pictorial photography and the hand-camera—The exposure problem—Boats—Street scenes—"Press-the-button" photographers.

**H**AND-CAMERA work has been aptly called "spur-of-the-moment photography," and in this descriptive title lies the whole of the difference of principle between the hand- and the stand-camera. It is a difference akin to that between the deliberate firing of the recumbent rifleman and the adventitious sport of the man who carries a gun with him as he walks about the fields. Although most of the processes are the same, and, to a certain extent, the apparatus is interchangeable, yet there is a wide difference between the types of camera best fitted for such different applications, and quite as wide a difference between the mental qualities and the manual skill which hand- and stand-camera work respectively requires.

The hand-camera was called the "detective camera" at first, and even now legends of its use, manifestly suggested by the title, creep into the newspaper from time to time. It was, to an elaboration of one of these, no doubt, that we owe the story of a murderer who was detected from the picture of the very murder itself by a Kinematograph, which "happened to be working at the time." The suggestion implied in the title has not been borne out by the history of the hand-camera during the last twenty years; it has hardly ever been used for "detective" work, and on the rare occasions when such photographic evidence is offered, the judges seem fully aware of the ease which it may be fabricated. At first the hand-camera was despised. It was regarded as a toy. "Only a

*hand-camera*” was a common phrase. At photographic exhibitions, if a class for hand-camera work was arranged, it seemed tacitly understood that it should be judged by a lower standard than the rest of the work. Some of those who had achieved a reputation with the stand-camera “would not be seen with a hand-camera.” That is all a thing of the past. Only the most insignificant exhibitions now have hand-camera classes, the rest draw no distinction between the two kinds of work, and on the walls of the best of the photographic exhibitions the product of the hand-camera hangs side by side with that of its rival, fully holds its own, and only reveals the method by which it has been obtained by the presence of qualities impossible with the other form of apparatus.

This great change has been largely brought about by the increase in the speed of plates and by improvements in lenses, and, to a less extent, in the form of the hand-camera itself, which have combined to give the photographer, whose tastes lie in the direction of work of that kind, a tool which instead of being a useless toy is an instrument of precision. Not only is the hand-camera more accurate and more adaptable than of yore, it is far more compact and portable. A good many years ago, when it was the author’s task to reply to the questions of photographers on matters of practice and to help them with advice, a letter was received which contained the curious inquiry: “Can you tell me how large is a hand-camera?” The reason of the request was never discovered, and there seemed at first some difficulty in answering it. The reply finally sent was to the effect that “a hand-camera is the size of a small box,” and as no further communication was received, presumably it gave satisfaction. A hand-camera can now be bought the size of a very small box indeed, and excellent work is being done with at least one type of apparatus, which can be carried in the waistcoat-pocket.

The distinctive features of the hand-camera are those which allow the user to dispense with the focussing screen at the back, so that the plate may be put into position ready for exposure, and the extent of picture that is to be taken can be settled and the focussing effected afterwards so that exposure can be made at any instant. Otherwise its parts are the same as those of the stand-camera, but often modified largely in

form. Thus, the hand-camera is often arranged to hold a dozen or more plates with a mechanism for bringing each one into position as required, or it may take roll film, which can be wound off as each piece is exposed. The most important feature of the hand-camera is the lens; and it is in hand-camera work more than in any other that a costly and high quality lens repays the money laid out upon it. As has been pointed out already, this does not mean that the work will of necessity appear any better. Under favourable conditions very good work may be done with an ordinary rectilinear, work which it may be quite impossible to distinguish from that done with an anastigmat costing perhaps ten times as much. But that is only when all the conditions are favourable, and in nine cases out of ten they would not be so, and the anastigmat would show its great superiority. It could more often be used at a large aperture, which would mean that the plates were less frequently under-exposed and would allow work to be done in a light which with a slower lens would make hand-camera photography impossible.

The focussing arrangements of hand-cameras are of very different kinds; but the commonest work by means of a scale of feet or yards, and an index which is set to the distance on the scale which corresponds to the effect required. Such scales may work either by altering the distance between the lens and plate, by altering the lens itself, or occasionally by adding to the original lens a supplementary one. The distance between the lens and plate may be changed by racking the front of the camera in and out, or by rotating the lens in a jacket provided with a thread of a great pitch. The result in either case is the same. A modification of the Cooke lens allows us to alter the distance between its component lenses, and in this way to alter the focus of the combination, so that with a fixed distance between the mount of the lens and the plate, near or distant objects can be focussed by changing the focal length of the lens. The third system, that of supplementary lenses, has a similar result, though it is obtained in a different manner.

In the simplest form of hand-camera there is no focussing arrangement at all, the type being known as "fixed focus." It removes one of the difficulties of the hand-camera user, but it limits him enormously. It is not a good quality of some



particular form of lens or camera, but merely the absence of the power of adjustment. Any hand-camera can be converted into a fixed focus one, with a hammer and a nail, or can be used as a fixed focus instrument by the still simpler expedient of not focussing. The only thing that need puzzle the user is the position in which the focussing arrangement should be left untouched. A quarter-plate hand-camera is generally provided with a lens of about 5 inches focus, and for fixed focus work the stop  $F/11$  will be found most suitable. Under these conditions, if the camera is set so that an object 18 feet away is as sharply focussed as possible, or if the scale is put to 18 feet and left there, everything at a greater distance than 9 feet will be fairly sharp. A fixed focus camera taking larger than quarter-plate is not practicable, and except that it forms a fairly convenient means of practising some of the simpler forms of hand-camera work, the fixed focus type is not to be recommended. This does not apply to certain instruments made to take very small plates and working with high quality lenses of very short focus, the negatives being subsequently enlarged.

Cameras focussing by means of a scale demand for their use some knowledge of that quality of lenses known as "depth of focus," and this depends upon the size of what is termed the "circle of confusion." If we take an object at such a distance that its image when sharply focussed is simply a minute point, and then start to throw the image out of focus, examining it all the time both with a magnifier and with the naked eye, we shall see that whereas with the magnifier a very slight movement of the focussing screen suffices to change it from a point to a blurry disc, this change is not so perceptible to the naked eye. In fact, it is generally accepted that the point may have a diameter of a hundredth of an inch before it ceases to appear as a point; or, at least, if its diameter were no larger the photograph would be accepted as sharp. Under these conditions, it would be said that the "circle of confusion" would have a diameter of a hundredth of an inch. For scientific purposes, or if the photograph is to be enlarged and then judged critically for sharpness, the degree of blurriness expressed by this phrase would be too great, and it might be necessary to assume a circle of confusion with a diameter of one two-hundredth or even one

five-hundredth of an inch. For ordinary hand-camera work, however, one-hundredth of an inch is the generally accepted standard. The term "depth of focus" is not strictly accurate. It should be "depth of field ;" but usage sanctions its employment, and the latter phrase would not be understood by most photographers. "Depth of focus," then, means the difference between the distance from the camera of various objects in the picture, all of which can be in focus at the same time. Manifestly the wider these limits the better, if their width is not purchased at too great a cost in other directions.

Unfortunately, it very often may be. "Depth of focus," as we have already seen, is not a quality which exists in some forms of lens and not in others, but depends essentially on the focus of the lens and its aperture. The only way in which two lenses of the same focus and aperture may appear to differ in depth is, that if one has very poor definition at all times, the image does not seem to get blurry so soon, because at no time has the user a critically sharp picture with which to compare it.

At whatever point of the scale the camera may be set, there is always a certain degree of latitude on both sides, within which objects are sharp. Thus with a 5-inch lens at F/8, if we focus on an object at 12 feet distance, or set the scale to 12 feet, everything distant from 8 to 22 feet will be sharp. Perhaps we ought not to say "will be sharp," because this applies only to the theoretically perfect lens, with an object in the centre of the field. It would be more correct to say, that if any object within those limits is not sharp it will not be due to want of "depth of focus," but to other causes. For successful hand-camera work it is most important that the photographer should have some idea at least of the limits of this depth of focus. He cannot know absolutely at any time, unless he is using an accurately made reflector camera ; but he can form an approximate idea, after using the camera a little while and noting the results he obtains.

One of the first things which will attract attention is, that a far greater degree of blur is permissible in distant than in near objects ; in fact, it is often a great advantage to have the distance out of focus. The centre of interest in a picture is never further away than what is known as the "middle

distance," and is generally decidedly in front of that plane. Hence a certain degree of diffusion helps to keep the background subordinate, and does not worry the eyes. The same diffusion in a near object would be most objectionable, and would lead to a complete loss of texture, which would attract attention at once.

In making a scale for a camera, the first point to determine is the "Infinity" point. This should not be the position at which a very distant object is as sharp as possible, because such a position is rarely if ever wanted. As there is always a certain degree of latitude in focussing, and objects both nearer to and further from the camera than the distance focussed will be sharp, it is clear that as we cannot have objects further away than "infinity," if we focus "infinity" we lose such latitude as might be regarded as lying beyond that point. Accordingly, instead of focussing for infinity we focus on a point at such a distance from the camera, that objects at an infinite distance are just within the limits of sharpness set by the circle of confusion that we have adopted. This distance is called the hyperfocal distance, and may be obtained by calculation for any lens if we know its focus and the stop to be used. A knowledge of the hyperfocal distance has another use also. If we focus on an object at the hyperfocal distance we know that everything beyond will be sharp, and may also count upon everything nearer being sharp also, to a distance equal to half the hyperfocal distance. For example, a  $5\frac{1}{2}$ -inch lens used at F/8 has a hyperfocal distance of 31 feet 6 inches. That is to say, if we focus with it as sharply as possible an object  $31\frac{1}{2}$  feet away, everything will be sharp that is 15 feet 9 inches or more away from the camera.

The hyperfocal distance is found by squaring the focus of the lens in inches, multiplying the result by one hundred, and dividing by the F. number of the stop used. Thus a 10-inch lens at F/8 has a hyperfocal distance of

$$10 \times 10 \times 100 \div 8 = 1250 \text{ inches} = 104 \text{ feet } 2 \text{ inches.}$$

It is a good plan to calculate out in this way the hyperfocal distance for each of the stops likely to be used in the hand-camera. A little table of depth of focus can then be drawn up, which, if it cannot be referred to at the moment of use, will at



THE CHURCH OF ENGLAND  
BY WALTER BENJAMIN



least give the photographer some idea of what, with a good lens, he ought to expect. Thus to find the limits of depth for any distance upon which the lens is focussed, the hyperfocal distance in inches is multiplied by the distance focussed for in inches. The result so obtained is divided by the hyperfocal distance, plus the distance focussed for, to obtain the nearest point that should be sharp, and by the hyperfocal distance, minus the distance focussed for, to obtain the farthest point that should be sharp.

As an example, to make this quite clear, the 10-inch lens at F/8 just referred to may be taken. Its hyperfocal distance we have just seen to be 1250 inches, it is desired to know how near and how far objects may be and still be sharp, when the lens with that stop is focussed on an object 20 feet (240 inches) away. These two distances are calculated thus—

$$1250 \times 240 = 300,000$$

$$1250 + 240 = 1490$$

$$1250 - 240 = 1010$$

$$300,000 \div 1490 = 201 = 16 \text{ feet } 9 \text{ inches, approximately}$$

$$300,000 \div 1010 = 297 = 24 \text{ feet } 9 \text{ inches, approximately.}$$

Everything, then, from 16 feet 9 inches to 24 feet 9 inches from the camera, as far as depth of focus is concerned, would be sharp. There is no need to multiply examples.

Most cameras provided with a focussing scale have an infinity mark which is placed at or about hyperfocal distance, and this is most convenient in use. In making a scale, however, a true infinity mark is useful temporarily. Thus, if we focus an object sharply at the nearest distance the scale is to indicate, and mark the position on the scale accordingly, and then focus an object at an "infinite" distance and again mark the scale, we can interpolate other distances on the scale without again focussing. Halfway between the two marks already made will be the point at which an object twice as far as the first is in focus. Halfway between that point and infinity gives us the point for an object twice as far again, and so on. Thus the 4-foot mark is halfway between the 2-foot and the infinity mark, 8-foot is halfway between 4 and infinity, and 16-foot halfway between 8 and infinity, and so on. The results are not absolutely accurate, but are quite as near as can ever be

wanted. For ordinary hand-camera work, the most convenient distances to be given on the scale are 6, 9, 12, 18, and 24 feet, and "infinity," which, as above mentioned, for actual use should be at the hyperfocal distance.

When "magnifiers" or supplementary lenses are used for focussing they are usually uncorrected lenses, but of such low power that their lack of achromatism has no perceptibly injurious effect upon the definition. They are usually provided in sets of three, and the adjustments are settled by the maker of the camera. They ought to be put as closely as possible to the original lens. If this lens is focussed for infinity, it is a very easy matter to select magnifiers for any required distance, the magnifier then being simply a positive lens of focus the same length as the distance of the object to be sharp. Thus, if any lens is focussed for infinity, and a lens of 6-foot focus is brought close up to it, objects 6 feet from the camera will then be in focus.

The question is sometimes asked whether magnifiers alter the exposure necessary. Theoretically they do, since they alter the principal focus of the lens of which they form a part; but as they are only used to counteract the necessity for altering the distance between lens and screen, they do not. In other words, the only condition under which a magnifier would alter the exposure is the condition which the magnifier is used to prevent. If we could focus a near object sharply without a magnifier, and then add a magnifier and refocus, the exposures required in the two cases would be different. But it is just this refocussing that the magnifier avoids; and, therefore, the lessened exposure brought about by the use of the magnifier counterbalances the increase brought about by the conditions which make the magnifier a necessity.

Next in importance to the focussing arrangements of a hand-camera come the finders. The functions of a finder are generally misunderstood. Many photographers, on discovery that the image in the finder does not exactly correspond with the image on the plate, blame the camera maker for sending out an inaccurate instrument; when, as a matter of fact, he is not to blame at all. No finder can be absolutely and invariably correct, except in the reflector type of camera, which

is not in the strictest sense fitted with a finder at all. Finders as ordinarily fitted are indeed rarely as accurate as they might be ; and the hand-camera user who wishes to place any dependence upon them at all should examine them, and, if possible, put them as right as he can. The finders of a camera should include the same angle of view as the camera does, and when directed at distant objects, that part of the subject which appears in the centre of the plate should appear in the centre of the finder. This is the best that can be done ; but with near objects such a finder at once becomes inaccurate, because the position of its lens differs, and must differ, from the position of the camera lens. If the camera has a rising front—and every hand-camera beyond the very cheapest ought to have a rising front—the inaccuracy of the finder is increased, whether it rises with the front or not. In fact, the difference between the two methods is so slight that it does not make any appreciable improvement in a finder's accuracy for it to rise with the front, and whether it does or not is best settled by whether the one position or the other is the more convenient. If the finder includes a larger angle than the camera lens, it may be reduced to the correct size by blocking out on the surface of the finder with Brunswick black and a small brush all those parts of the subject which do not fall on the plate. A type of finder which has its admirers, although it is not at all popular amongst the generality of hand-camera workers, consists of a light metal frame provided with cross-wires, and a piece of metal with a small eyehole in it. If the opening in the frame is the size of the plate, and the distance of the eyehole from the frame is equal to the focus of the lens, the two may be fitted on the top of the camera so that, approximately, the eye placed at the eyehole sees the same quantity of the subject, surrounded by the frame, as falls on the plate. If the frame is fastened on the front, so as to rise and fall with it, such a finder gives a truer indication of the picture than any other, except always the reflector camera. It is, in fact, as accurate in this respect as the finder of a twin-lens camera, though it does not give the power of seeing to focus that the latter type does. This finder only has one drawback—it limits the possible positions in which the camera may be held to those in which the eye can be applied to the eyehole, and these, as a rule, are not the



positions for the steadiest holding. On the other hand, it is the only type in which the camera gives conveniently, and almost invariably, the view as the eye sees it—that is to say, from the height of the observer's eye from the ground or thereabouts. It really deserves a much greater popularity than it has had.

Those who use any other type of finder, therefore, must be content to employ the finder as an approximate indicator only, and not expect a degree of accuracy that we have seen to be impossible. An ample margin for contingencies should be left all round the subject, so that we may be certain of getting what is required somewhere on the plate. The print may then be trimmed to give the arrangement which is best. This is particularly the case with "brilliant" finders, some forms of which show a different picture according to the position of the eye with regard to the finder, although all forms do not have this failing. Those who want to work very closely to the edge of the plate must use a reflector camera, which is the nearest approach to the ideal form of hand-camera, though of necessity the heaviest form and the most expensive.

Instantaneous shutters are not limited exclusively to hand-cameras, but are best considered here: as with a hand-camera a shutter is a necessity. There are two principal forms—those which have one or more metal plates which pass across the lens, and those in which the moving part is a flexible blind on rollers. The latter type is at its best in the focal-plane shutter, so called because it lies almost in the focal plane of the lens—that is to say, as close as possible to the plate. This type gives the highest speed of any, and the greatest efficiency. The only other positions occupied by the roller-blind shutter are immediately before and immediately behind the lens. Neither position is a good one, and, except for its cheapness and compactness, the roller-blind shutter would be used at the focal plane only, because it is not remarkably efficient elsewhere, and labours under the disadvantage that its speed is controlled by varying the tension of a spring, a method never very satisfactory. As it is, the roller-blind shutter is for stand-camera work the most popular form of all. The blind requires attention from time to time, as long usage has a tendency to form pinholes in it. It is said that one or two small holes

can be covered with black court-plaster, but a better plan would be to get a new blind as soon as a hole is noticed, since one is sure to be but the precursor of many. The roller-blind shutter is not much used on hand-cameras except in the focal-plane patterns.

Most hand-cameras have metal shutters. The best position for these is between the combinations of a doublet lens, or just in front of a single lens. Such shutters may either open and close from the centre, in which case while opening and closing they act more or less as a stop, or they may have an opening which passes across the lens. Were it not for its bulk the latter form would be the better, since it can be made more efficient than most of the other patterns.

"Efficiency" in a shutter refers to the time the shutter allows the lens to be fully open, as compared with the time during which the shutter is opening and closing, and therefore covering part of the lens. The focal plane shutter allows all the useful light the lens can pass to reach the part of the plate during the whole time it is uncovered. Its efficiency is therefore at a maximum. Roller-blind shutters usually have an opening which is twice the diameter of the lens, or a little more. Assuming, then, that the blind travels at a uniform speed throughout, the lens is fully open for about one-third the time during which it is uncovered at all. Some metal shutters open very quickly, pause, and then close quickly, and these are highly efficient, particularly at the slow speed. Unfortunately for the photographer, these are just the exposures when efficiency is least important; and at the faster speeds the period during which the shutter is fully open does not bear so large a proportion to the total time, and the efficiency fails when it is most wanted. This question of efficiency is a very important one to hand-camera users, where everything is done that tends to increase the quantity of light reaching the plate in a given time.

Closely allied to the question of efficiency is that of control of speed. The only shutter that has a definite and sharply terminated exposure is the focal plane; all others open and close gradually, and any attempt to measure the speed is made difficult by this fact. Shutter regulation is generally carried out either by altering spring tension, by a brake or pneumatically.

The most perfect method, beyond all question, is the last. But a pneumatically regulated shutter has got to be very well made to be reliable, and is therefore expensive. Cheap pneumatic shutters are plentiful, and very good work is done with them. They only work to the time indicated on the scale with the longer exposures; with the short exposures they are often very greatly in error. A brake-regulated shutter is the easiest of all to make, but so far none have been very reliable, and they are going out of use. A very simple method of altering the speed is by increasing or decreasing the tension of a spring. Next to pneumatic regulation, it is the most satisfactory, though it is liable to get incorrect in time as the strength of the spring alters. In some hand-cameras a method of regulating the shutter speed by regulating the size of the opening in a rotating disc has been employed. By thus using the spring always at the same tension great uniformity was attained, but the price paid was the efficiency of the shutter in the shortest exposures, where efficiency was most wanted. Failing a reliable pneumatic regulation, it is better to have a single speed of shutter, say a fifteenth of a second; and on the rare occasions when this would be too long, to use a smaller stop. It is much better to have only one exposure, but to know that it is constant, than to have an elaborately scaled shutter which does not give the exposures for which it is marked, and has not even a constant error.

While the focal-plane shutter has a maximum of efficiency, it is only in a limited sense that this is so. It is usually controlled by altering the tension of the spring, or the width of the opening that travels across the plate, or both. The narrower the width of the opening, the greater is the difference between the time at which different parts of the plate are exposed. When the slit is a wide one the effect of this is not perceptible, but when, as is sometimes the case, the width of the slit bears a very small proportion to that of the plate, the result is distortion, and often very evident distortion. A curious example of this has been shown in some of the illustrated papers, and it puzzled a good many who were not photographers. It represented a racing motor-car, and as the slit in the shutter had clearly been of the narrowest kind, perhaps an eighth of an inch on a half-plate, the driver and upper portion of the car had been exposed

before the slit reached the lower part, which in the mean time had travelled an appreciable distance. Perhaps a dozen or twenty times the total exposure of any one part elapsed between the photographing of the top and the bottom of that car. Nevertheless, for very short exposures the focal plane shutter has manifest advantages.

For stand-camera work a rubber ball and tube are very convenient, as they lessen the risk of shaking the camera when making the exposure. Curiously enough, they increase the risk with a hand-camera, owing to the greater degree of movement necessary to compress the ball. The better hand-cameras have a pneumatic release for use when the camera is on a stand ; but when it is not it is better not to employ it, but merely to press the button or lever. In doing this, to avoid shaking the camera, it is important not to push the release, but to hold the camera in such a way that the rest of the hand pulls against the pressure of the finger.

Most hand-cameras are provided with levels, but they are of very little use. When the camera is held in the hand for the ordinary hand-camera subjects, it is almost impossible to note the level and the finder at the same time ; while if the camera is used for architecture and similar work on a stand, the average hand-camera level is not accurate enough nor sensitive enough to be of much service. There are some people, no doubt, whose sense of the horizontal is so defective that the level as fitted to a hand-camera gives them a valuable indication, but they cannot be very plentiful.

Plate-changing mechanism occupies the premier place in the attention of the hand-camera worker, because the temptation to make exposures is much greater than it is with the stand-camera, and the customary "three double dark slides" prove quite insufficient. Of plate cameras, those are most popular in which the plates are carried vertically in sheaths, with pins at the lower end of each sheath on which it swings into a horizontal position at the bottom of the camera when the top of the sheath is released. If such a camera is to be reliable, it must not only be in good order when bought, but it must be taken great care of. The mechanism is simple and very cheap to make, but it needs careful usage. The sheaths must not get bent, especially with regard to the pins ; the

camera must not be exposed to violent shocks, and the position in which it is held during plate changing is important. As different patterns vary in this respect, it is best to load the sheaths with spoilt negatives first, and to find by trial the angle at which to hold the camera for the changing to be smoothest and most reliable, and then always to hold it at that angle in future when changing a plate.

Plenty of hand-camera workers still use dark slides. They have one great advantage over magazines and magazine cameras, and that is that an accident to the plate-changing mechanism of the latter makes the camera useless; in the former case it is, as a rule, only the one plate in the slide that need suffer if anything goes wrong. If more than one kind of plate is carried, the dark slides allow them to be used in any order that seems to be desirable. Dark slides are bulky compared with magazines; on the other hand, being separate, they stow more easily. A member of the Chinese Legation in London, who was once a popular visitor at many a Photographic Society outing, was famous for the vast number of dark slides which he was able to conceal in different parts of the picturesque Eastern garb which he wore; the exact total was never determined, but he would certainly stand comparison with any magazine camera.

No automatic or magazine changer is absolutely reliable, but some patterns come so near to perfection in that respect that the difference is not worth troubling about. The maximum of certainty is obtained with those patterns in which the plates are carried in sheaths and are raised one at a time by means of a lever, so that the sheath can be caught hold of by the fingers through a leather bag which forms the top of the magazine, and in this way transferred either from the front to the back, or *vice versa*. In doing this the only cautions that need be given are against allowing the bag to rub against the sensitive surface of the plate, and against allowing the plate to slip to any extent out of the sheath and so with its sharp corner to endanger the bag.

Cut films can be carried in any of the changing arrangements provided for plates. In the case of changing boxes, by means of special sheaths it is often possible to accommodate twice as many cut films as plates. There are also special



SANTA MARIA DELLA SALUTE

BY PERCY TEWIS



methods of changing cut films, which cannot be satisfactorily applied to glass plates. One of the most popular and successful of all is the Premo film pack, which has the great advantage of being "daylight loading." A pack of twelve films can be placed in the "Premo adapter" just as it is bought, and exposed straight away without the need for a dark room. When one pack of a dozen films has been used it can be taken out in daylight and another substituted, and so on as required.

In simplicity and reliability, however, all plate-changing mechanism has to take second place to the daylight-loading roll-film cartridge. It was Eastman who was the first to realize the possibilities which lay before a rollable material sensitive enough for hand-camera use. His first roll film was on paper, but this was soon supplanted by one on celluloid, which was gradually improved, until to-day it is little inferior to glass in any respect, and has, of course, advantages of its own in the direction of portability, ease of changing, and absence of risk of breakage. There are now several makers of roll films, all of whom put them up on spools with black paper for daylight loading. The great drawback of celluloid film is its cost, which is about double that of glass plates. Any one who intends to use roll film will find it an advantage to employ a camera into which the spool of film is placed direct, and not to use a separate roll holder to take the place of ordinary dark slides. At first sight the roll holder would seem to be much more convenient, since then the camera is a plate or film camera at will. But the film on a spool for a roll holder has to be wound the reverse way to the film for a roll-film camera, and the result is that not only is the action of the spool in the roll holder not so smooth and easy as in the camera, but there being some hundreds of roll-film cameras to every roll holder, it is far easier to get a supply of fresh film for the former than for the latter. In fact, film for Kodaks is now obtainable almost everywhere in Europe, America, and Australia, and in many out-of-the-way parts in the other continents.

Another advantage of roll film is that by means of the Kodak Developing Machine, or the same Company's Tank Developer, it is easy to develop without a dark room also; in fact, it is possible by this system to dispense entirely with



the dark room and red 'light. The daylight spool can be inserted into the machine in daylight, and wound off under the surface of the developer, the latter being poured away after the lapse of the proper time, and water poured in, to be followed in turn by fixing solution. The method is sound in principle, and is absolutely reliable in practice ; it minimizes risk of damage to the film from finger-marks and from light fog, and ensures that each exposure, correct or otherwise, shall have that degree of development best calculated to make a good negative of it. There being no need, and in fact no opportunity, to examine the appearance of the film during development, there is no temptation to fog an under-exposed film by adding alkali in a futile attempt to bring out detail that is not there ; nor is there a risk of over-developing under-exposures, and under-developing over-exposures, which is the besetting sin of the photographer who relies solely on his eyesight to tell him how far to carry development. Even if a dark room is available, the machine is a convenience. The author uses it in the dark room to develop all his roll-film exposures. The convenience of the machine in such a case is quite as marked. The dark room may be fairly well lit, and the film, after being developed and washed in the machine, is taken out, cut up, and fixed in an ordinary dish. In this way no hypo goes into the machine at all, and the thorough washing out which would have to follow its use for fixing is avoided. The apparatus only needs a good rinse, and is ready for use to develop a second roll while the first is fixing.

Although the roll-film cartridge should be perfectly safe in daylight, it is foolish to charge the camera in any stronger light than is necessary. Nothing is to be gained by so doing, while there is always the chance that the roll of film may be allowed to uncoil for a moment sufficiently far to let light in and fog it. It is best therefore, whenever possible, to load the camera indoors, and if not, at least not in direct sunshine. Some of the very compact cameras close up so closely to the film, that there is a risk when winding off after exposure that the film is rubbed against the bellows and marked. To avoid this, the winding off should be done before closing the camera. It is important, too, when using roll film, especially with the modern high-class lenses which have a flat field and a large

aperture, to be sure that the surface of the film is as flat as possible, or parts of the picture might be out of focus. To guard against this, it is necessary before closing up the camera to make sure that the black paper has been put quite squarely into position, and is running true. This risk of a want of flatness is not very great in small sizes, up to and including quarter-plate. It should not give rise to trouble with 5 by 4, especially when the film is 4 inches wide, but beyond this size the smoothness of the film becomes very necessary if the lens is to be used at a large aperture, and for half-plate and larger, were such sizes much used with large apertures, there is no doubt it would cause a good deal of trouble; but then other conditions arise, and roll film for large sizes is not likely ever to be very popular. With the rigid glass plate, the surface of which is generally quite as flat as the field of any lens, no trouble on this score is to be anticipated; but with cut films it must always be regarded as a possible danger. Some cameras have had a sheet of glass in front of the film, against which it is pressed for exposure, but this is not a very practical remedy. The great use of roll film is in small sizes, and in small sizes want of flatness is not likely to be troublesome.

The commonest defect of all in hand-camera work is under-exposure. This is due to a great extent to the fact that the user has not learnt how to hold the camera still, or is afraid that if he does not give a very short exposure there will be signs of movement due to his own lack of steadiness. The length of exposure possible depends upon the personal factor (individuals differ very largely in this respect), and upon the constraint or otherwise of the attitude in which the camera, is held. The usual plan is to grasp the camera firmly in the two hands, press it against the "lower chest," bend over it to see the image in the finder, and press the button. It is the steadiest method of all, undoubtedly, but has its limitations. The lungs should be deflated and the breath held when the exposure is being made, if possible; but when one cannot be certain to a few seconds when the conditions will be just right for exposing, this is risky, as the moment for pressing the button may find the photographer gasping for breath, and in the worst possible condition for exposing rather than the best.

The old hand will never lose an opportunity of securing additional support, by leaning against a tree, a wall, or anything that will help to steady the body. It is much better in such circumstances to support the body than to support the camera, unless the latter can be placed on the support free entirely from contact with the person of its user. Some workers seem to prefer to hold the camera under the right arm while exposing, and get along very well in such a position ; but it has always seemed to the author that the attitude is one of constraint, and if the camera has to be held like that for a minute or two, awaiting a favourable opportunity for making the exposure, there is great risk of movement. Any attitude of tension is to be avoided. A skilful worker has thus summed up the rules for holding the camera :—

1. Hold it in as comfortable a position as possible.
2. Avoid all unnecessary tension on the muscles of the body and legs.
3. Take advantage of any available support for the body.
4. Whenever possible deflate the lungs and hold the breath before exposing.

The actual maximum exposure possible while the camera is held in the hand, as already pointed out, depends on a personal equation. But a quarter of a second should always be possible. The most shaky hand-camera user the author has ever encountered gave an eighth of a second quite easily without signs of movement ; the author himself has little trouble with exposures of a second, but this is unusual in his experience. Whatever it be, it is always much longer than the exposure to which most people set their shutters. But in hand-camera work there is not only the movement of the user to consider, but the movement of the subject, and this often imposes very strict limitations on the photographer.

The reflector camera has already been spoken of as the nearest approach to the ideal hand-camera, but there are reflectors and reflectors. With the enormous advantage that the subject can be seen and focussed on a full-size finder up to the instant of exposure, there is the drawback that the camera is of necessity heavy and bulky, while the design absolutely demands the finest workmanship. Good finish is always

acceptable, but in many patterns it is not indispensable; but a badly finished reflector is worse than useless. It is a snare. The design necessitates a double motion to make the exposure; the mirror must first be lifted out of the way, and then the shutter proper released. Usually this is all done by pressing a single button, but the double motion is there just the same, and with it is the risk of shaking the camera just when steadiness is most important. It is only when all these moving parts are accurately made and well finished that the action is so smooth as to be without effect on definition. There is also the accuracy of the register between the plate and the full-sized finder to be considered. The user relies implicitly on this. He must, for it is to be able to do so that he selects the reflector pattern. If the two are not strictly in accordance, therefore, the more accurately he focusses, the less sharp will be his picture. The reflector camera is generally employed with lenses of the very largest aperture, because the power of focussing accurately is then of the greatest use. Lenses, therefore, which work at  $F/5$  or  $F/4$ —one enthusiastic hand-camera worker we know employs an  $F/2$  lens—are not at all uncommon. Such lenses of modern types are capable of covering a very much larger plate than the one on which they are used—covering, that is to say, as far as the cone of rays is concerned; a smaller stop would be required to get definition, but the light is there when the full opening is used. The result of this is that the bellows of a reflector camera are very strongly lit, and they reflect that light on to the plate. This has given much trouble to users of the instrument, and there is no practical cure for it although it can be and is reduced to a minimum by well blacking the interior with a dead black. It could only be prevented entirely by enlarging the body of the camera, and this is already quite as bulky as it should be.

With the exception of cameras of this type and of twin-lens cameras, which are not much used now, and seem likely to disappear entirely, all hand-cameras demand that their user shall be a judge of distance. Even those of fixed focus require this, if the wasting of plates on impossible subjects is to be avoided. To estimate distances rapidly is a thing that can soon be learnt by any one who makes a serious effort to do so; but the mere using of a hand-camera is not sufficient, and it may

take years and grosses of plates if the thing is not set about systematically. Yet too many photographers as soon as they get a camera start to try to get results on their plates at once, instead of using a few dozen in learning to master it. An afternoon devoted to judging distance will work wonders. There is no need at first to have the camera. The simplest plan is to go for a walk with a friend and get him to set problems of distances very promptly, and to demand an instant answer. Walking in a wood let him stop and point to a tree near at hand. Estimate its distance as quickly as possible, state it and then measure it off to see how near the estimated is to the actual. It is good practice with trees, it is much better with persons, horses and carts and such objects; but to be valuable the estimating must be done on a system and not by guesswork, and must be checked with a measure.

The system most workers adopt is one of "lengths." Here we have the standard always with us. A glance on the ground should suffice with a little practice to tell us how many times we could lie down head to feet in a straight line from where we stand to the object. Unless the photographer is distinctly diminutive double that number will give us the distance in yards accurately enough for our purpose. It is easier to do this quickly than to estimate in yards offhand. Distances of more than 12 yards need not be attempted. There are two other exercises, which the hand-camera user will find valuable. One is to select an object, and settle in the mind on a distance, which also should be less than 12 yards. Let him walk briskly towards the object, stop at what is estimated is the pre-determined distance, and then check the estimate by measuring. The same method is adopted, by walking neither exactly towards nor away from the object, but on a diagonal line. When walking away from it, as a rule, it is possible to determine the distance by merely counting the paces.

It is not easy to determine the distance of a person moving towards or from the camera, while all the time watching the image in the finder, and in such cases the following plan will be found distinctly helpful, especially to those who photograph groups, street scenes and single figures. A person of average height, with his hat on, is asked to stand at the distance from

the camera at which most work of this character is likely to be done, 10 or 12 feet for choice, and then getting his image in the centre of the finder, a black line is drawn its exact height, with a fine brush and some Brunswick black. With this line as a guide, it will be found possible to obtain pictures using nothing but the size of the figures as seen in the finder to indicate their distance from the camera.

The original idea of the hand-camera was indicated by its first title, the "detective" camera. It was to be used for the surreptitious photography of individuals. That idea was never realized, though the best use of the camera to-day is for the photography of persons who are unaware at the time they are in the receipt of adventitious immortality. This puts the subject of "the ethics of hand-camera work" upon the carpet. It has been contended that it is not consistent to condemn the practice of photographing people against their will, and at the same time to give instructions how figures and groups can be photographed without consciousness of the presence of a photographer at work. That the two are not mutually antagonistic will be clear to any one upon reflection; but a dissertation on the subject is out of place in a book such as this. Let it suffice, if we say that the hand-camera user who has the instinct of a gentleman will not offend, although he may find what follows of use to him; while the hooligan with or without a camera is a hooligan still, and if our advice helps to make his photographs any better than they would otherwise be, he is probably so much the less objectionable to his victims, although none the less a cad.

The greatest advantage in pictorial photography conferred by the use of hand-camera, is that with it we are able to get figures and groups, the models in which are absolutely unconscious that they are being depicted. Their pose, therefore, good or bad, is at least a natural one, the surroundings may be the real thing, and in perfect keeping, and there is none of that suggestion that the whole arrangement has been made up to be photographed, which in other methods is only avoided with great difficulty. Mr. Craig Annan, and there could hardly be a higher authority on the subject, has said that the pictorial worker should no more have to worry about his tools and methods than the writer needs to think of his pen while using

it; and although photography has not yet reached to that stage, the hand-camera has taken it appreciably nearer.

It is as a travel or holiday companion that the hand-camera finds its most general use; and what could be better in that capacity than a compact, often a pocket, instrument, which with a little skill, will bring back to us at a moment's notice, scenes we may never be able to revisit, and incidents that may never recur? The tourist will want to use his camera not only for figures and groups, but for architecture, shipping, street scenes, landscape, and all the miscellaneous purposes to which any kind of camera can be put. Architecture is perhaps that to which it is least fitted, yet it can be used to give successful results. The great virtue of an architectural subject to a hand-camera worker is that it will keep still just as long as he cares to take in photographing it.

It is in applying it to architecture that the photographer first learns the importance of the rising front. In all probability he will find, if his camera has not got a rising front, that he gets a great deal more of the ground on his plate than he wants, while the sky-line of the building goes right out of the top of the picture. With a rising front this may be curable, though it does not follow. Many cameras have a maximum rise of one inch on a quarter-plate, and though this is much better than nothing, there are often occasions when more would be a distinct convenience. A few hand-cameras have a swing back, but this is not common, and if neither rising front nor swing back are provided, it is a question of tipping the camera, or of leaving the subject unphotographed or incomplete. There is quite an unnecessary objection to tipping the camera. The practice is not one to be indulged in when it can be prevented; but if there is no other way of getting what we want upon the plate, there is no conceivable reason why the camera should not be tipped. Of course negatives so made cannot be printed by contact, or they will show vertical lines converging at the top of the picture, but by properly swinging the plate and the easel when enlarging or making lantern slides this can be corrected with surprisingly little trouble.

The problem of exposure which confronts every camera user is complicated in hand-camera work by the fact that not only must the exposure be the correct one as required by the

plate, but it must be brief enough for the negative to show no signs of movement, either of the camera or the subject. Tables are given in some of the books showing how short the exposure must be to secure sharpness with different classes of subjects—express trains so much, jumping horses so much, etc., etc. Such tables are worse than useless, as they are misleading. If they do give the exposure which will prevent movement from showing, which as a rule they do not, it is so short as to be impracticable with most cameras, and far shorter than should be necessary in most cases. In addition to this the figures are or should be given for a specific size of the image on the plate and for motion at some given angle to the axis of the camera ; conditions which the photographer finds it difficult to observe. The best rule with rapidly moving objects is to ascertain the shortest possible exposure that will give a correctly exposed plate with the largest lens aperture, and to give that exposure. If the negative is a good one, well and good ; if it is not, the photographer has the satisfaction, such as it is, of knowing that he did his best. In all rapidly moving objects, the camera should be as near their path as possible, so as to get an almost front view. This reduces any blurring due to movement to a great extent, and apart from that, is nearly always a much more agreeable arrangement, than when the moving object is taken broadside on. It is possible in this way to get jumping horses, express trains and similar subjects quite sharp, to all appearances, with the ordinary hand-camera shutter, graduated to one-hundredth of a second and actually working, perhaps, at a fortieth. But the moving objects should be as small on the plate as is possible ; as the smaller they are the smaller is the apparent blurring caused by movement.

Exposures made from boats and other moving supports, require to be short to prevent movement of the camera from showing. On the other hand, they are very rarely made on rapidly moving objects near at hand, so that the exposure may be longer than in the previously considered case. We are also working, practically, with a fixed focus camera, for we can set it to infinity and leave it there, since we are hardly likely to have any part of the subject near enough for special focussing to be necessary. There is another advantage in such subjects, and that is that there is very seldom need for a short exposure



on account of the plate, the subjects usually being well lit, or at least without foreground shadows.

In photographing from a steamer there is often more trouble from the vibration caused by the engines than from the progression of the vessel. To minimize this, the hand-camera should be held in the hand rather than planted on the taffrail, the body then deadens the shock. As a general rule, it will be found that a twenty-fifth or thirty-second of a second is ample for all exposures made from a moving ship with a hand-camera with a 5-inch or 6-inch lens. Exposures from small boats are in a different category, and must be determined by the particular conditions prevailing. If any sea is on, the movement of the boat is much more rapid, while at the same time the surface of the water is much nearer, is on a bigger scale on the plate, and, therefore, any movement is magnified.

It is in street scenes and groups that the trouble of harmonizing the demands of the plate for a long exposure and of the subject for a short one is likely to be greatest. Here we have moving objects comparatively near the camera, and deep shadows at no great distance. It is in work of this character that the advantages of a high-class modern type lens and of a reflector camera shine forth; but a great deal can be done with quite inexpensive apparatus if the conditions are not unfavourable. Assuming, as before, that the camera is a quarter-plate one, with a lens of about 5 inches focus and working at  $F/8$ , a fiftieth of a second will be found to be what such subjects require, if they are to be taken haphazard and are to show no movement with figures walking 10 or 12 yards from the camera. In very many cases this would mean that the plate was hopelessly under-exposed. But there is no need to work haphazard, and much longer exposures can be given if the subject is studied a little. With such movements as that of a man's legs when he is walking, and this is the most troublesome movement of all to the hand-camera user, there is a stage when they are moving much faster than the average movement of the man, and another when they are almost motionless. It is this second stage which impresses itself most strongly on the eye, and painters, therefore, when drawing a man walking, draw him in one of these positions when his movement is least perceptible. Such poses are now the accepted conventional methods of representing

figures walking, and fortunately for the hand-camera user they are the easiest with which he can deal. He should learn, therefore, to recognize them, and to time his exposure so that if there is a walking figure in the picture on a large scale, it is photographed when its movement is at a minimum. It is the neglect of such opportunities, coupled with the use of a very short exposure, made necessary by such neglect, that we owe the snap-shots of street scenes that are so commonly seen, the figures in which are almost comically unnatural in their attitudes. There may be a scientific use for such photographs, but pictorially, they are to be condemned. Under the conditions just named, instead of the fiftieth of a second, which is the minimum for haphazard exposures, a sixteenth of a second will be ample if the moment of exposure is selected judiciously. Vehicles in motion in street scenes are to be avoided unless they are quite at a distance, as otherwise the exposure has to be cut down to such a point as to mean certain under-exposure for the plate.

There are many subjects with which the focal plane shutter alone can deal satisfactorily. These include such photographic *tours de force* as motor-cars and express trains broadside on and in full flight, divers in mid air, skipping scenes with every strand in the whirling rope distinctly visible. For work of this character not only is an extremely rapid shutter necessary, but the lighting must be exceptionally good, the lens used at a large opening and, as a rule, the camera must be of the reflector type. They are curious rather than beautiful; and, as in the case of wave subjects, pictorial effect is lost entirely by the absence of all suggestion of movement. A train just starting from a station, with the column of steam and smoke shot upwards by its efforts, taken with an exposure of, say a thirty-second of a second, looks far more as if it were moving than the same train crisply defined in every part though travelling at, perhaps, twenty times the speed and "snapped" in the thousandth of a second.

The hand-camera, so far, has been considered throughout as if the exposures with it were always controllable and known; but this is only the case under exceptional circumstances. There are many, probably the majority, which have shutters of one fixed speed. It must not be supposed that they dispense with the necessity for taking any account of exposures. Far

from it. Unless the user of such a camera takes a little trouble to ascertain what are the requirements of his plate on the one hand, and of his subjects on the other, he will find that his waste of plates is enormous, and that a successful result is only an occasional accident. The lesson he must learn is, what is and what is not, possible with his camera. The shutters of such instruments generally give exposures from one-twentieth to one-fiftieth of a second. This, as can be seen from what has already been said, is, perhaps, the best average speed to possess, and if the lens is one which is reasonably rapid, say  $F/8$ , a great deal of good work can be done with such a tool. Single speed shutters are fitted, as a rule, on cameras with a single lens which seldom work at a larger opening than  $F/11$ , and this lessens the possibilities somewhat. Street scenes are only practicable, then, if the street is fairly open and the light good. Given these conditions, the results with a cheap camera of this type may be as good as, or even better than, those obtained with a more costly apparatus, if this latter is in the hands of one who is not able to take full advantage of its good points. Landscapes generally, except woodland scenery under trees and shut in, façades of buildings, shipping, figures in the open, are all dealt with very easily with a camera with a single lens and single-speed shutter. But it cannot be used successfully when the light is poor, such as on most winter days in this country—except for snow scenes—or when the sun is low on the horizon, or for figure subjects with heavy shadows such as are to be met with in the narrow picturesque streets of South Europe, or for figures under cover. The great thing with such a camera is to study its limitations, and to be prepared for disappointment if they are overstepped.

There are many people who carry a camera but have never done any of the photographic work themselves. Nothing can be said against such a practice except that it is not photography, and is very wasteful of money. Because, even if the work is distasteful and irksome, and, therefore, delegated to some one else, it is not possible to secure a reasonable percentage of good results, unless the user, or perhaps we ought to say the wearer, of the camera has been through the mill of development and printing, and has got an understanding of what he is doing when he "presses the button," an understanding which he can

acquire in no other way. If hand-camera work is to be anything more than a series of bitter disappointments, broken only by unseemly joy over the one poor plate that breaks the otherwise even monotony of the ninety-nine that are so negative as not to be negatives at all, a little time must be spent in learning to use the camera properly, and development and printing must be practised even if they are afterwards to be abandoned.

There is a large and growing class, however, who regard hand-camera work as something more than irresponsible snapshotting; who expect to get good negatives from the great majority of the plates which they expose; who no more regard it as mere "button pressing" than successful shooting is mere trigger pulling. To them, the hand-camera is not a degenerate stand camera become a toy, but the highest stage which the evolution of photographic apparatus has reached, an instrument of precision, the results with which are as certainly successful as with any other well-made apparatus in the hands of fallible humanity.

## CHAPTER XIV

### THE PRINT

P. O. P.—Sensitiveness—Most suitable negatives—Vignetting—Washing and toning—Separate or combined baths—Self-toning papers—Double tones—Developing partially printed P.O.P.—Platinum toning—Fixing—Washers—Squeegeeing—Mounting—Dry mounting—Masking—Wasted advice.

**T**HE negative is only a means to an end, that end in almost every case is the print. There must be just one small reservation, because in certain branches of scientific photography the need for extreme accuracy in the dimensions of the photograph compels the use of the negative as the final result, the expansion and contraction of a paper print with varying degrees of humidity of the atmosphere putting its use quite out of the question.

Amateur photographers, with this trifling exception, regard the print as the final result, a statement which holds good, whether the print is a contact one on a slow paper, a direct enlargement on bromide paper, or a print on glass in the shape of a lantern slide. For the majority, too, a print is a print on some more or less shiny surfaced "silver" paper, the universally used "Printing Out Paper," or P.O.P. P.O.P. is a comparatively recent introduction. Like "gaslight" paper, manufacturers knew how to make it long before they put it on the market in any quantity, and it was due to the enterprise of Ilford, Ltd., that the demand for it was created, at the expense of the trade in albumenized paper, which was virtually killed in the process.

In "P.O.P." the sensitive silver salt is applied to the paper either in gelatine or in collodion. The latter is more popular abroad than in Great Britain. In order that P.O.P. may be sufficiently sensitive to be usable at all, and give a rich image by

printing out, it is not sufficient that it should contain silver chloride only. This is an insoluble salt, and although it does not keep in gelatine as well as does silver bromide, still it is fairly stable. But, unfortunately for the P.O.P. process, soluble salts of silver of a much less permanent character have to be present in the coating, with the result that all forms of P.O.P. gradually, but inevitably, discolour and spoil, even if kept in the dark and with every possible protection. We are speaking now of the keeping properties of the paper in its sensitive condition, not of the permanence of the prints, which will be considered later. The presence of these silver compounds makes it important that P.O.P. should be used while it is still comparatively fresh; and as its deterioration is accelerated by heat, by impure air, and by emanations from common cardboard and other materials of a like kind, it is important that it should be well packed and stored in a cool place, free from gas fumes and the products of combustion generally. A clean piece of P.O.P. shut up for a day or two in a printed book will show distinctly the words with which its surface has been in contact.

The different grades and colours of the paper suit it for different purposes. The mauve or rose tinted glossy papers are liked by many for such portrait work as appeals to the philistine Briton. A slightly higher taste prefers the white; but it does not need a very great degree of culture for all glossy surfaces of the P.O.P. type to be distasteful, and a matt paper, white for choice, to be preferred. There are different degrees of "matt" paper on the market, and generally speaking, the smoother paper is suitable for the smaller sizes. The custom of supplying the paper in pieces cut to the size of the negative rather than in full size sheets, which is now very wide spread, is economical, even from the point of view of those who use only a part of their negative, as it enables the paper to be packed flat in compact envelopes, and saves risk of damage from finger marks when the paper is being cut up; for P.O.P. is very easily injured. The surface is readily absorbent, and a warm finger pressed on it, or the slightest dampness, may make a mark which will be visible on the finished print.

The sensitiveness of P.O.P. is such that it can be freely handled in an ordinary room lit with daylight; but, of course,

even then it must not be exposed too long or there will be a risk of degradation of the whites. There is a method of developing a print on P.O.P., which has only had a short exposure to light, by means of which a strong rich print can be obtained very quickly. As this method brings out very slight traces of light action, traces which in the ordinary way would be quite invisible, it follows that paper that is to be developed must on no account be exposed to daylight with the freedom that may be used if the paper is to be printed out. P.O.P. is coated in yellow light, and if the prints are to be developed the packet should be opened and the printing frame filled and emptied in yellow light also.

It is generally supposed that a very soft negative is required for P.O.P., but this may easily mislead. Soft it must certainly be compared with the negative that is to give a print in carbon or in platinum, but one distinctly harder than will give the best bromide enlargement or print on "gaslight" paper is needed. Much can be done by printing in a light to suit the negative. Thus a strong negative is best printed in a strong light—anything short of sunlight, as this tends to lessen contrast in the print. A weak negative in the same way gives a stronger print if the printing is done slowly in a weak light. The printing frames in these two cases need not be separated, but that containing the strong negative exposed to the direct light of the sky, while the frame with the thin one has one or two thicknesses of tissue paper pasted across it to moderate the light. A curious increase in the contrast of the print, which has never been satisfactorily explained, will be found if the printing is conducted with a piece of green glass between the negative and the light. Direct sunshine is to be avoided in all printing operations, as unless the negative is very fogged or over-exposed the printing is unmanageably quick, and every speck or blemish in the glass of the negative, and very little glass is quite free from blemish, is faithfully copied in the print by the parallel rays of sunshine. In diffused light such spots are vignettted as it were, and do not appear.

Mention of vignetting raises the question how far the photographic "vignette" is justifiable, pictorially. It was Dr. Emerson who first showed that it was a mere commercial "dodge," borrowed from another art without borrowing its



HONESTY  
BY JOHN L. ARTHUR III





justification. In a chalk drawing the artist may leave the background untouched, that he may concentrate his attention and work on the head; in photography the printer who vignettes takes trouble to imitate a style the excuse for which is that it saves labour. A delicately lit head vignetted against a background of white paper is repulsive, from the falsification of its tones, and such things are permissible only in commercial work to suit an uncultivated taste, or rather a lack of taste altogether. If "vignetted heads," as they are called in price lists, are not allowable pictorially, there are cases where a vignette effect is not to be condemned. In little prints which are often used to decorate such things as menus, programmes, and initial letters, a skilful vignetting may be more satisfactory than plain masking. But such vignetting is impossible with the "vignetting shapes" of commerce, and demands individual treatment. The size and shape of the vignette must first be settled, and then cut out in a sheet of cardboard, which is fastened over the face of the printing frame, half an inch or so from the negative. It may be that it is possible to print the vignette straight away with this device, but it will often be found impracticable without pasting a piece of tissue paper over the card to diffuse the light. For the same purpose the outline of the card is not cut with a smooth edge, but it is jagged with teeth like a saw. When there are light parts on the negative which lie beyond the boundaries of the vignette, it may be found that these will show on the print, from the diffused light getting round the edges of the opening in the card. In such a case, after fixing the card in position, cotton wool may be pushed through the opening so as to block up the space between the negative and the card, while by teasing out its edges anything like a hard line can be prevented.

The gelatine film of a negative has a strong affinity for moisture. If printing is conducted in a damp atmosphere, therefore, there is a very great risk of the negative absorbing moisture through the paper on which the print is being made. As in the case of P.O.P., this paper contains soluble salts of silver; some of these are transferred to the negative with the moisture, and under the influence of the light they rapidly turn into black spots, which, as they consist of metallic silver, as does the picture in the negative itself, are very difficult of

*removal without the image on the negative also being affected.* In bad cases, such as may happen when a shower of rain comes on while printing frames are out, the paper may stick to the negative. Leaving the paper in the frame over night, in damp weather, is a very fertile source of these spots, as also is printing before the negative is quite dry. There is no remedy that is invariably efficacious, but the best is the following:—

If the paper has stuck to the negative, as much of the paper as can be removed while it is dry is pulled off, and then the negative is placed for an hour or so in a freshly mixed hypo bath of three or four ounces to the pint. At the end of this time, a little gentle rubbing with the finger will remove anything adhering to the film, and if the photographer has been very fortunate, he may find that the negative is not marked in any way. If it is spotted at all, it must then be washed for a few minutes, and placed in a combined toning and fixing bath, which will remove the spots in an hour or two, if they are to be removed at all. If the negative is only spotted, the preliminary hypo bath may be omitted. If the combined bath does not remove the spots in a couple of hours the case is hopeless.

Varnishing a negative lessens very much the risk of it getting spotted by being printed in a damp condition; but contrary to the belief of many photographers, it does not remove the risk entirely, and if a varnished negative does get spotted, there is much less likelihood of removing the spots. The best preventive is to make sure that the film of the negative is dry before it is printed, to see that the pad at the back of the printing frame is dry also, and not to leave the print in the frame all night. By interposing a piece of sheet rubber between the back of the print and the back of the frame, as is invariably done when printing in platinum, an additional precaution against damp is taken.

As there are many different brands of P.O.P. on the market, which differ amongst themselves in the composition of the sensitive coating, and in the details of the subsequent treatment, there would be little or no advantage in describing a method which would be applicable to all, yet probably not that which is best suited to any one of them. Every packet of P.O.P. contains a description of the treatment which the maker regards as most suitable for his paper, and this, unless

the photographer thinks he knows better, is what should be followed.

Albumenized paper is practically obsolete. Gelatino-chloride paper, such as is the great majority of P.O.P. on the market, must only be dealt with at ordinary temperatures. If the solutions are at all warm, or if the prints are transferred from one bath to another at a distinctly different temperature, there is a great risk of the film blistering; while in hot weather, or even with the heat of the fingers, if the print has been long wet, the film may melt. With collodion P.O.P. there is not this risk, as the film is quite insoluble in water, hot or cold.

The depth to which printing must be carried varies very greatly with different brands of paper, and varies also with the treatment to which the paper is subsequently to be exposed, in the shape of toning. So great is this variation that, beyond pointing out that as a rule the print looks a little colder in shade and darker in tone when dry than when wet, no generalities can be of much use.

Very few of those who take up printing on P.O.P. realize at first the importance of thoroughly washing the prints before attempting to tone them. The soluble silver salts which the film on the paper contains must be removed, if waste of the gold in the toning bath is to be prevented, and the toning is to be even and successful. It is not sufficient in this preliminary washing, or indeed in any operation to which the prints are to be subjected, to let them lie in the dish in a mass. They must be separated and kept moving. The simplest and easiest method is to place them one by one in the dish of water, letting each one get limp before putting the next on the top of it. The pile of prints is then turned over, and taking the print first immersed, it is held up a moment to drain and then placed in a dish of clean water. Each print is transferred in the same way, and then the pile is again turned over, and the operation repeated. Five or six changes of water should be given, until there is not the least cloudiness in the drainings from the prints. If soft water is used the drainings should be allowed to drop into a glass containing some water, to which has been added a pinch of common salt, and there should be no cloudiness where the water from the print meets the salt solution.

Gold toning may be carried out in three distinct methods. A toning bath may be applied to the print, which is afterwards washed and fixed in a separate solution. Or a bath which both tones and fixes the print may be used. Or the paper may contain the materials for toning the picture, and need only immersion in plain water, or at least in some solution which does not contain gold, to yield a toned print.

The first of these three methods is, beyond question, the best. Not only is the range of possible tones much wider, but the action is better understood, and the results, if it has been properly carried out, are more likely to be permanent. The combined toning and fixing bath is convenient; but it labours under the disadvantage that it will tone when the gold is exhausted, so that it is not easy to know whether the print is or is not being toned with gold; and in the latter case there are considerable doubts as to the permanence of the final result. The range of tones in the "self-toning" papers is limited. They are very simple in their use, and appeal to many who do not care to be troubled to make up different solutions.

The commonest defect in gold toned P.O.P. prints, is that which is known as "double toning." That many people are quite blind to it is clear from the fact that in the show cases of professional photographers glaring examples of double toning are rife. The fault is due to the complete toning of the lighter parts of the print before the bath has had any appreciable action on the deeper shadows. While the high lights, therefore, are bluish in shade, the shadows are warm, often quite red. The cause lies in the use of a toning bath too strong altogether, and therefore too rapid in its action, or one which contains too large a proportion of sulphocyanide. Another possible cause of double toning is the use of a toning bath exhausted of its gold either by excessive use or from the presence of some impurity which has precipitated all the gold in the form of a black sediment. Double toning is rarely to be met with in prints toned in baths which do not contain sulphocyanide, but there is no need to avoid that salt on account of it if it is used in a proportion suitable to the rest of the bath. It is said that combined toning and fixing baths never produce double tones. They may, however, tone a print before the

fixing action is complete ; and thus lead to the finished print being imperfectly fixed. The only guarantee against this is the use of a separate fixing bath afterwards, which sacrifices all the supposed advantages of the combined bath.

Self-toning papers vary in the treatment prescribed for them even more than the others. Some of them tone in plain water, others need sulphocyanide or other baths. They all have a strong tendency to give very warm colours, whatever the treatment adopted. A print on a self-toning paper can have its colour much improved by the simple device of passing a hot laundry iron over the finished dry print.

It is possible to curtail the exposure required to obtain a printed out print on P.O.P. to one-hundredth of the total time, or even less, by developing the print. There are two methods of doing this. In one the developer used is an acid one, and the dry print is placed direct into it, developed to the required extent, and then toned and fixed. In the other the print is immersed in a "bromizing" solution ; this is nothing more than a 10 per cent. solution of potassium bromide, and after five or ten minutes is washed and developed.

The chief trouble about the first of these development processes, is that there is a great likelihood that the print will be stained ; in fact the back of the print is almost inevitably discoloured, and the action often shows right through. An acid developer that is suitable is the following :—

Hydrokinone	...	...	...	...	...	...	16 grs.
Citric acid	...	...	...	...	...	...	40 grs.
Sodium acetate	...	...	...	...	...	...	1 oz.
Water	...	...	...	...	...	...	20 ozs.

The second method was introduced by the Paget Prize Plate Company, and is a perfectly practical process. The partially printed photographs, on which the image may be only barely visible, are immersed in 10 per cent. potassium bromide solution, which converts the soluble salts of silver in the paper into silver bromide, and prevents them from staining it. Then, after washing two or three minutes in running water the prints are placed in the developer, in which they come up to their full vigour in from three to eight minutes, according to

circumstances. The developer is made up of two stock solutions as follows :—

A. Hydrokinone	...	...	...	...	...	2 grs.
Sodium sulphite	...	...	...	...	...	8 grs.
Water to make	...	...	...	...	...	1 oz.
B. Potassium bromide	...	...	...	...	...	55 grs.
Sodium carbonate (crystals)	...	...	...	...	...	44 grs.
Water to make	...	...	...	...	...	1 oz.

The proportions in which these two solutions are used may be varied. When the negative is a very flat one, and as much contrast as possible is wanted in the print, we may use 3 drs. of A diluted to 1 oz. with water and mixed with an ounce of B. If, on the other hand, the negative is hard and we want to lessen contrast, we may use more of A up to as much as 7 drs., diluting it to make 1 oz., and then adding an ounce of B as before. However much or little of A is employed, it must be made up to an ounce with water, the quantity of B being left unaltered. A medium developer would contain  $\frac{1}{2}$  oz. of A. On taking the print out of the developer, it must be washed for a moment and then placed in 10 per cent. bromide again for a minute or two, after which it can be well washed and toned and fixed in exactly the same manner as if it had been printed right out. P.O.P. which is to be developed in this way must be handled in a much weaker light than if it is to be printed out. Any ordinary artificial light may be used, both for filling the frames and for developing the prints, but daylight, unless it is very weak indeed, must be avoided.

Hitherto gold-toning only has been considered ; but the photographer is not limited to salts of gold for the purpose. Very fine tones on P.O.P. can be obtained by toning with platinum, and another fine series by toning first with gold, taking care not to carry the operation too far, and then with platinum. The platinum salt that is most generally used for this purpose is potassium chloroplatinite.

Whether the print be toned with platinum or with gold it is important that it should be washed between toning and fixing. In the case of gold-toning in order to stop the action as soon as the right stage is reached, some workers put the print in a weak solution of common salt, washing it slightly afterwards

before fixing. There is likelihood of discoloration if a print containing in its pores some of the toning solution is put straight into the hypo. It is still more important in the case of platinum toning, since the toning solution is acid, and the introduction of acid into the hypo bath is always detrimental.

After fixing, and it is well to remember that complete fixing is as important as thorough washing, the hypo and the silver it has dissolved from the coating on the paper must be washed out. There are washers innumerable on the market for this purpose, but they vary very much in their efficiency, and if one of them is used reliance should only be placed upon it after it has been tested. For this purpose, after a number of prints have been washed in it for the time which is supposed to be sufficient, the prints should be allowed to drain as thoroughly as possible into clean glasses, and to the drainings of each a little water faintly coloured with potassium permanganate should be added. If the colour is discharged or changed to a pale yellow, the washing has not been thorough. It is necessary to test all the prints of any one bath, as some from the accident of floating loose may be completely washed, while others which have been close together still contain hypo. It is this clinging together which is the great difficulty the designers of print washers have to overcome. In some instruments each print is held apart from its neighbours, and the trouble is overcome though in rather an elaborate manner. In others, reliance is placed upon the inrush of the water to keep the prints apart, and this may or may not be effective, depending upon the extent to which the user carries out the intention of the designer of the washer.

When a few prints only are to be washed, there is nothing quite so efficacious and so economical of water as transferring them one by one from one dish to another, with thorough draining in between, the water in each dish being changed and the dish rinsed out between each transference. Or the prints may be washed individually very quickly. M. M. Lumiere showed, some years ago, that the washing of P.O.P. prints would be made much more speedy and efficacious, if the prints between each change were put in a mass and as much water as possible squeezed out of them. Those who use "hypo-eliminators" for negatives may care to do so also for their



prints, and permanganate used in the way already described is said to be effective. But plain water and frequent changes are best, provided the prints are kept moving separately. The one way in which they cannot be washed is by allowing them to accumulate in a mass and leaving them so.

When the prints are fully washed they have to be dried, and as the surface is one of gelatine, they must not be dried in contact with anything to which they may stick. The best plan after draining them is to spread them face upwards on a clean towel. Blotting-paper is sometimes recommended, but it must be that specially made for photographic purposes, as common blotting-paper contains a great deal of hypo. Moreover the paper soon perishes. No heat should be used for gelatino-chloride P.O.P., unless it has been thoroughly hardened with formaline, and even then it is not advantageous, though permissible if the prints are wanted in a hurry. Collodio-chloride P.O.P. may be dried by heat if it is thought desirable.

A great many photographers are in the habit of squeegeeing their prints face downwards on to some material, but it is certainly better to allow them to dry first, and then to rewet them to squeegee. If this is done there will be no risk of the prints sticking to the surface employed and tearing. The squeegeeing process allows of a great range of surface, from an extremely high gloss to a coarse matt.

The highest gloss of all is obtained by the process mis-called "enamelling." A sheet of plate-glass is well polished with French chalk, coated with enamel collodion, and immersed in a weak warm solution of gelatine. In this the print, which must have been hardened in alum or formalin if it is on gelatino-chloride paper, is brought face downwards on to the collodionized surface, and being removed from the liquid is squeegeed into contact all over and dried. When dry the print can be stripped off without any trouble, and has as brilliantly smooth a surface as that of the glass itself. This method is very little used now, as it is possible to get almost the same effect by simple squeegeeing.

The highest gloss is that given by glass, but there is a greater chance of the print adhering. The glass should have a cream of beeswax and turpentine, or one of the ready-made preparations sold for the purpose, smeared over its



THE ORCHARD

BY CLARENCE WHITE



surface, as much as possible should be wiped off, and then the glass polished with a cloth that is free from fluff. An almost equally good surface can be obtained by using "ferrotype" plates, a kind of japanned iron; pulp boards are sold for the same purpose. Celluloid also answers well. All these, except the glass, may be used without the preliminary waxing, and in the case of celluloid this should not be attempted. With ferrotype or pulp boards, it is well to wax them occasionally, as the washing tends to remove the slight greasiness which is otherwise their natural surface. Instead of wax, some photographers treat the glass with French chalk, but this should only be used for glossy and not for matt surfaces. A little is scattered on the surface, and then polished over and rubbed off by going over the glass with a clean cloth; but the polishing must be done gently or the chalk will be rubbed into it too much. Glass has this advantage over the ferrotype, that it is transparent, and, therefore, by looking at the back, it is possible to see if the squeegeeing has been done effectively, or if there are any air-bells left. A sheet of thin rubber or of American cloth should be placed between the back of the print and the squeegee; a flat squeegee is better than one of the roller pattern for this purpose. By the use of finely ground glass or celluloid, glossy P.O.P. may be given a matt surface of a very agreeable character and quite different from the natural matt of the matt papers.

The one difficulty likely to be encountered in squeegeeing is the sticking of the print to the drying surface, whatever it may be. If the print is not thoroughly dry it is certain to stick, and any attempt to remove it will ruin it irretrievably. If the weather is warm, it is possible that the gelatine surface of the print has begun to decompose, and this will make it stick. Formaline or alum is the preventive in such a case—there is no remedy. If the glass or ferrotype is not properly clean, the print may stick. After each batch of prints has been dried, the squeegeeing surface should be well washed with a soft rag and soap and water, thoroughly rinsed and put up to dry. If the mounting method described in the next paragraph has been used, the glass or what not should be soaked for half an hour in cold water, and then washed with warm water and soap. When one is sure that the prints are

perfectly dry, they may be held an instant before a bright fire or in direct sunshine, and this should be sufficient to bring them off. Otherwise one corner may be raised and the print stripped off, by pulling it gently away from the plate, and not by rolling it back, as a sharp curve would break the surface.

One of the most convenient methods of mounting P.O.P. prints was one which the author saw in use at the Eastman Kodak works in Rochester, U.S.A., some years ago. The prints, as soon as they were dry on the ferrotype sheets, but not before, were brushed all over on the back with a glue made by soaking ordinary white gelatine in water, and then dissolving it by heat and applying it hot. This also was allowed to get thoroughly dry, and then the print was stripped off, and trimmed. If it were not to be mounted, the gelatine coating helped to keep it flat; while if it were to be mounted, all that was necessary was to damp a mount with a sponge, place the dry print upon it in position, and pass the two together through a rolling press—a domestic wringer does quite well. The print comes out mounted flat, and without that loss of gloss which follows most mounting methods when the print itself becomes moist.

Trimming is best deferred until the print is quite finished. There are several reasons for this course. It is convenient to be able to trim deliberately in a good light, trying the effect of different shapes and sizes until one best suited to the subject is reached. This can be done by using two pieces of card cut to the shape of an L, and sliding them over each other on the print so as to enclose a rectangular space. By deferring trimming, the extreme corners of the prints, which must inevitably get handled in the processes, are cut off, and the edges which hardly ever are toned quite evenly with the rest of the print are removed.

Trimming is a process all prints, more or less, must undergo; but it is perhaps most conveniently considered here. Prints must be quite dry before they are trimmed or they are sure to tear. The same result follows when we attempt to trim a print with a blunt knife. All sorts of knives are used for the purpose, but there is nothing better than the ordinary pocket knife, with its point kept as sharp as possible by frequent application of a

little piece of Washita or other suitable oilstone, which can be got at any tool shop. Most photographic hand-books recommend trimming prints on a sheet of glass, and with a glass-cutting shape. The glass is a nice surface to cut on, but it punishes the knife point terribly, and a piece of smooth card is much better, though this too will soon blunt the knife if it is dug down into the card needlessly deep. The card also gives a better grip to the print and prevents the cutting-guide from slipping.

Glass-cutting shapes are a delusion and a snare. It is not long since the author, requiring a whole plate shape, went right through a dealer's large stock without finding a single one which was reasonably accurate, and the fault lies not so much with the maker as with the material, which, except at great expense, does not lend itself to accuracy of this kind. It is much better to cut with a steel straight-edge and to use a draughtsman's triangle of celluloid or wood by which to get the corners true.

At the risk of being accused of teaching one's grandmother to suck eggs, a few words on the use of these instruments may be given. Assuming that we have a print to trim, let us note the stages of the operation. The first thing to do is to settle approximately with a cardboard L the boundaries which the trimmed print is to possess. These are not to be marked on the centre of the print, as we may find it necessary just to include a part we should have marked, but a pencil mark is made where each proposed edge cuts the present edge of the print.




FIG. 15.

The square is then placed, as shown by the dotted lines in Fig. 15, with one of the sides which form the right angle parallel with a prominent horizontal or vertical line in the print, a vertical line for choice in architectural subjects, the horizon in sea scenes. Against this same side is placed

the straight-edge, and then holding the straight-edge firmly, the triangle is slid along it, until the side at right angles to the straight-edge reaches the mark at the edge of the print. The triangle is then held firmly in its turn, and the straight-edge is placed along its other side, when, the triangle being removed, the first cut is made. In this way we can be certain that the edge of the print is parallel with the horizon or with the vertical lines of the buildings, as the case may be. Those who are not accustomed to this kind of work may find it safer, instead of cutting the print at this stage, to rule a line with a sharply pointed pencil. The triangle is then slid along the straight-edge until it reaches the second boundary of the print, the straight-edge is put along its other edge, and the second line ruled or cut, and so on with the other two. It ought to be done with sufficient care that when the fourth side has been done, the angle it makes with the first, tested by applying the triangle, reveals no perceptible inaccuracy whatever.

One method of mounting has already been described. The purity of the mountant employed has a very great influence on the permanence of a print on P.O.P. Ordinary glue, which is most impure, should never be used, but the white gelatine, such as Heinrich's or Nelson's, will answer. Nelson's "X Opaque" or cooking gelatine is suitable for mounting.

A gelatine mountant may be made with spirit, which has this advantage, that it does not interfere so much with the gloss of the surface as a water mountant. Such a preparation is made by soaking an ounce and a half of gelatine in half a pint of water until it is quite soft, and then placing the vessel containing it in hot water until the whole is liquid. A mixture of five ounces of spirit of wine—methylated spirit can be used, but is not so suitable—and an ounce of glycerine is then stirred in. Too much spirit will precipitate the gelatine. This mountant should be put away in wide-mouth corked bottles, and will keep for a long time, keeping all the better if five grains of thymol are dissolved in the spirit. To use it, the bottle is placed in warm water for a few minutes, and then in hot water, and the mountant, which will then be liquid, is brushed over the back of the print.

Another mountant is made by diluting the rubber solution

sold for repairing tyres with benzol or mineral naphtha. About equal parts of each will be found sufficient. This mountant is brushed over the back of the print with a stiff brush, and the print is kept under pressure, after mounting, for several hours. Indiarubber mountant does not interfere with the gloss of a print in the least; but it has the very serious drawback that the rubber perishes after a few months and the print drops off its mount. It sometimes appears to stain the whites of the print, but this will be found to go off after exposure to the air for a little while.

Ordinary starch paste is of all mountants that which is least likely to affect the permanence of the print; but it should be freshly prepared and used cold. An excellent mountant of this character, but prepared by a patented process which gives it a curious consistence, is known as "Higgins'." It will keep very well, and is quite without any injurious action on the print. Ordinary gum or paste should on no account be used.

With a mountant such as "Higgins'," which contains comparatively little water, it is easy to mount P.O.P. prints, keeping their gloss. The mountant is spread over the back of the print, which is put face downwards on a clean piece of newspaper, and is quickly and evenly rubbed into the paper. There is no tool to equal the finger-tips for this purpose, and as soon as the peculiar greasy feel is noticed all over, the print is placed in position on its mount, another clean piece of newspaper is placed on the face of it, and it is well rubbed into contact all over, particular attention being given to the edges. The paper may then be changed for a fresh piece in case any of the mountant has exuded, and the print placed under pressure to dry.

Sheets of a thin waterproof paper can be purchased which may be pasted with starch or mountant on to the back of the prints while they are yet on the glass or ferrotype. The paper should be slightly smaller than the print, so that when both are quite dry and stripped, the trimming brings both to the same size, and the waterproof paper enables the print to be mounted without loss of gloss; but this method is going out of use.

Cut-out mounts, into which the print is simply pushed into



position, are the most popular form to-day ; but are only of use to beginners, or to those whose photographs are simply records, and are not intended to have any pictorial value. This follows of necessity, because the cut-out mount is of a stock size determined by its maker, quite without reference to the particular print it is 'to surround, and its suitability therefore can only be occasional, and a mere matter of chance. For such record prints, however, they are very convenient. The visible portion of the print need not be touched with mountant at all, although a spot should be applied to one of the edges to keep the print from shifting about behind the mount. When a pile of such prints are kept together, loose or bound up into an album, the mount prevents anything from touching the surface of the print, so that they are very suitable where the preservation of the print is a matter of great importance.

The bending or cockling of mounted prints is to some extent inevitable, since we have two distinct substances united together, which substances may expand or contract quite differently under the circumstances to which they are exposed. If a print is mounted on a card and a spoiled print of the same kind, or failing that a piece of paper as like it as possible is mounted in the corresponding position at the back, the pull of one counteracts the pull of the other, and we have the most favourable conditions for flatness. Keeping the mounted prints for some time under pressure helps to preserve their flatness ; and if there is any risk of them sticking, the waxed paper in which plates are often wrapped is a good material to put in between them. The tendency to curl is reduced by taking care that the print and its mount, when brought into contact, are as nearly as possible in a similar hygroscopic condition. Mounting a thoroughly damp limp print on a dry mount makes curling inevitable.

A process of dry mounting has been introduced during the last few years, which is almost perfect in its power of preventing cockling. The print has interposed between it and the mount a thin sheet or skin of the same size, which has been treated with a preparation of shellac or other resins on both sides. The two are pressed closely into contact by a hot iron, or in larger sizes in a steam-heated press, and the heat melting

the coating on the interposed skin binds both print and mount to it. The advantage is twofold. Curling is prevented, since both print and mount are quite dry at the moment of mounting, while the skin insulating the print from the mount by an almost impermeable barrier, any deleterious matter in the card is prevented from reaching the print. .

## CHAPTER XV

### PLATINUM PRINTING

Simplicity of the process—Care of the paper—Damp—Artificial light for printing—Suitable negatives—Development—Warm tones—The acid baths—Development with glycerine—Permanence—Gold intensified platinum prints—Packham's process—Restoring discoloured prints—Printing on fabrics—Defects.

**I**F simplicity in a printing method means the reduction in number of those processes which call for personal skill, and the absence of complications in the few that are left, the platinum process stands pre-eminent. The image is visible during printing nothing like so plainly as in P.O.P., but quite visible enough to act as a guide. In fact, it is no harder to learn by looking at it when a piece of platinum paper is sufficiently printed than it is to do the same with a piece of P.O.P. In each case an allowance has to be made for alteration in subsequent processes, and although the alteration is far more in the case of platinum, this does not make the process harder. Besides, when the paper is taken out of the printing frame, all call for skill or for anything more than ordinary care is at an end. It is put in a developer—a plain solution of one substance in water—it is developed as far as it will go, and is quite unaffected by being left longer in the developer. In fact, anything from thirty seconds to thirty hours makes no difference to the print. When the development is over, it is rinsed first in weak acid, and then in water, and is finished. The charm of a platinum print is unquestioned. Its pure black and white make it suitable for every subject, without exception; its plain, smooth surface, free from the slightest suggestion of a coating or layer, appeals to the most cultivated taste, while the permanence of the print is limited only by the endurance of the very paper on which it is printed.

The greatest hindrance at present to its popularity, and



PLAYTIME  
BY WILL CADBY



especially to its use in tropical countries, is the fact that even in hermetically sealed tins, with a due supply of calcium chloride, the paper will not keep indefinitely, and in a trying climate it spoils in a few weeks. Platinum paper should always be stored in a cool place.

Artificial light has been used for platinum printing, the Platinotype Company having devised a lamp by which magnesium in powder is burnt in oxygen, giving a light powerful enough for the purpose. The arc lamp can be used, and during the last year or two the Cooper-Hewitt mercury vapour lamp has been employed for platinum printing. A row of mercury vapour tubes, shown at one of the exhibitions of the Royal Photographic Society, gave a fully exposed print in eight minutes. A reflector was placed behind the tubes, and the printing frame was 6 inches in front. But daylight is, and will probably continue to be, the light *par excellence* for platinum printing. It should be diffused, and not direct sunlight, and, as in the case of P.O.P. printing, the weaker the negative the weaker the light in which it must be printed, if a strong print is wanted. Green glass has a beneficial influence in this case also.

As platinum paper is distinctly more sensitive than P.O.P., and as the injurious effect of exposing it to light is not seen until the paper is developed, care must be used in filling the frames lest it is exposed to light too long. Damp is still more injurious to it, so the paper in the printing frame is backed up with a piece of thin sheet rubber. Indiarubber is not the only substance that can be used for the purpose. Sheet celluloid, such as can be got by cleaning the coating off a spoilt film negative, answers excellently. Even with this precaution, if the paper is left in the frame too long it will deteriorate, in token of which a print left all night in the printing frame is never so good as one made and developed within an hour or so. It is said that negatives for platinum printing should always be varnished because of the moisture held in the gelatine film; but this is an unnecessary refinement. When the paper is taken from the printing frame, unless it is to be developed at once, it should be put back into the calcium tube.

A printing frame which has its hinges nearer one end than

the other will be found convenient in platinum printing, as more of the print can be seen, and it is easier to determine exactly when printing is done. The change is from a strong yellow to a greyish tint, and in noting how far printing has progressed, the grey should always be compared with the unaltered paper, which may be under the mask or protected by the edge of the frame. The printing is finished when the highest lights in the print are just distinguishable from the unaltered paper; but a few attempts show better than any quantity of verbal description, the appearance of the change and the extent to which it should be allowed to go.

Some workers find it more satisfactory to use an actinometer for printing, and not to open the printing frame at all until the process is finished. The subject of actinometers is dealt with more at length in the next chapter. There is no reason why one should not be used; in fact, anything that tends to prevent the access of light or damp air to the paper is beneficial; but the idea that they are required on account of any difficulty in determining from the appearance of the paper whether or no printing has gone far enough, is erroneous. Prints that are to be of a sepia colour are printed a little deeper than black prints, and those which are to be developed in a hot developer need not be printed quite so far as those to be developed cold.

In platinum printing, as in other purely photographic method, the quality of the print depends primarily upon the quality of the negative. A very thin negative is not at all suitable for the process, although it may give satisfactory prints on "gaslight" papers, or by direct enlargement on bromide paper. At the same time much depends on the character of the subject, and the most beautiful portrait prints are made from negatives which the photographer of landscapes would think were too thin to print at all. The very best prints are always made from those negatives which are the hardest to print—from those, in fact, which must be printed "just right" and no more. These are the thinnest that will give good prints at all. If they have more contrast, they are much easier to print, there is a certain latitude, and a little longer or shorter in the printing frame only makes the print a little lighter or darker without actually spoiling it. But the result is never

quite so good. Very hard negatives—always supposing that they were properly exposed—are best printed on the sepia or the hot-bath papers, but a negative which will give a good carbon print, may be too dense to yield a satisfactory one on any kind of platinum paper.

The definite character of the development of a platinum print has put out of court with it all question of remedying in development errors of exposure. They lead straight and unerringly to failure. The print is therefore placed in the developer until no further action is taking place, any attempt at stopping development prematurely giving an unsatisfactory print. A simple developer may be made out of a stock solution of neutral potassium oxalate.

The instructions supplied with platinum papers usually state that the developer should not be used at a lower temperature than 60° Fahr. ; but this should be regarded as an undesirable minimum, and better prints will be obtained if the developer is always placed in warm water for a little while before use, so as to take the chill off. That treatment which is most congenial to a bottle of Burgundy is quite sufficient for the purpose, when plain black tones are wanted.

The Platinotyp Co. supply to order "hot-bath" paper, the predecessor in the time of the present "cold-bath" paper. This is developed on a hot saturated solution of potassium oxalate ; the temperature may vary from 100° to 180° Fahr., but 140 Fahr. is a suitable mean. Some workers prefer the hot-bath paper on the ground that it gives richer blacks ; but it is doubtful how far this is borne out in practice. Plenty of photographers develop the cold-bath paper in a hot developer.

There are two methods in use for heating the developer for platinum prints. It may be poured into a glass flask, and held over a spirit-lamp either with the bare fingers or, if it is to be made very hot, by wrapping a few thicknesses of paper round the neck of the flask ; or it may be heated while in the dish in which development is performed. For individual prints, the first-named plan is convenient, the hot developer being poured over the face of the print as it lies in a dry dish. If plenty of solution is used, there need be no fear of bubbles. The latter is preferable if a number of prints are wanted all of the same



tone. The dish should be one of enamelled iron, and it can be placed on a support, such as a brick at each end, or directly on a gas or oil stove. A better plan is to place on the stove a sheet-iron tray containing sand to a depth of an inch or more, and to bed the enamelled iron dish in this. When the temperature of the developer is correct, the stove may be turned down, and it will be found that the sand helps to keep the heat very constant.

The demand for the temporarily unattainable never ceases. Silver prints gave purple and violet tones, and photographers craved for a pure black. They got the platinum process which gave them what they wanted, and at once demanded warm colours in platinotype. What was asked was granted, and there are two or three ways by which for the black of a print in platinum, a brown may be substituted. Mere alteration of the developer will do much. Using the cold-bath papers of the Platinotype Company, we have a range from the blue-black, obtained by using the "D" salts in a cold solution, or a cold solution of potassium oxalate strongly acidified with oxalic acid, to an orange.

The plain oxalate solution (one in four) diluted with twice its bulk of water, and used at 140° to 160° Fahr., or even hotter, gives a strong brownish black, a very agreeable colour. If a kettle of boiling water is at hand, and we hold the undeveloped print in its steam for half a minute before developing in this same hot solution, the brown is still more pronounced. Generally speaking, the hotter and the weaker the developer, the warmer the colour. One worker of our acquaintance gets a very rich brown by boiling the oxalate bath in a glass flask over a spirit-lamp, and pouring the liquid out of the flask straight over the print as it lies face upwards in a clean, dry dish.

Still warmer colours can be obtained by adding a trace of mercuric chloride to this hot solution, and it is proof of the minute trace of mercury that is sufficient to affect a change in the colour of the paper to point out that a platinum print from a negative that has been intensified with mercury is distinctly warmer in colour than one from an unintensified one, showing, as is indeed known to be the case from other evidence, that the negative had parted with a trace of its mercury, although hundreds, or even thousands, of such prints might be obtained

without any effect being manifest in the negative itself. The proportion of mercuric chloride to be used in the developer varies very much with the fancy of the user.

A developer which gives prints of a warm brown colour on the C.C. paper of the Platinotype Company was described by Mr. C. F. Inston to the Liverpool Amateur Photographic Association in 1902. The following is its composition:—

Neutral potassium oxalate	...	...	...	...	2 ozs.
Mercuric chloride	...	...	...	...	90 grs.
Potassium citrate	...	...	...	...	150 grs.

These are covered with 14 ozs. of cold water, and when dissolved the solution is ready for use. Equal parts of this solution and hot water (not boiling) are mixed together and poured over the dry print as it lies face upwards in a dish.

Nothing is to be gained by multiplying formulæ for these warm tones; what have been given already may be taken as typical. So long as mercury is not present, it may fairly be assumed that, whatever the colour of the image, it consists of metallic platinum, the colour being dependent upon the size of the minute particles of which the image is built up. This may seem strange to those unacquainted with physics; yet it is a common occurrence for one and the same substance to have differing colours at different times, due to this cause alone. So long as the image consists of platinum only, its permanence is indisputable, whatever the colour. Moreover, it is not affected by the acid baths used to get rid of the iron from the paper. But when mercury is present in the developer, the result is by no means such a foregone conclusion. Mr. Chapman Jones, who has made a special study of platinum processes, thinks that in such a case the image is probably contaminated with mercury, although in the sepia paper of the Platinotype Company, in spite of the presence of mercury in the developer, he thinks it is not. Certainly, in the case of prints on cold-bath paper developed with hot solutions containing mercury, such as that given by Mr. Inston, the acid baths must be much weaker and applied for a shorter time, or the warm colour will be removed and a cold print of a washed-out appearance will alone be left.

The Platinotype Company has always deprecated the

attempt to get sepia tones on papers prepared for black tones, and has put a special paper on the market for those who want warm colours. The paper has to be developed with a solution of certain salts which they supply for the purpose, and yields prints of an excellent sepia colour, upon whose permanence reliance may be placed. At the same time, it is probable that a greater number of warm-toned prints to-day are made upon the black papers than upon the sepia, since the greater range of colour, and the fact that black or brown can be obtained on the same paper at will, are advantages not to be despised. This is particularly the case with a stout, rough paper known as "C.C.," which yields very fine black tones and good sepias in the manner already indicated. The black papers, and especially C.C., are also more robust in character than the sepia papers, and certainly possess greater keeping properties.

Great things have been hoped from a glossy paper, known as "Japine," giving prints very similar to carbon prints ; but signs are not wanting that platinum printing is decreasing in popularity with amateur photographers.

In the ordinary way, the print is taken out of the developer and placed direct into a bath of weak hydrochloric acid, 1 oz. of the acid being added to 60 or 80 ozs. of water. Commercial hydrochloric acid has a yellow colour, and is contaminated with iron. As the acid is applied to get the iron out of the print, clearly this is unsuitable. The acid should be water white when looking through a thickness of 3 or 4 inches of it. The print must on no account be placed in water between development and the acid bath, or the iron will be precipitated in the paper and will not be removable. Mercurially developed prints should be placed in one bath of  $\frac{1}{2}$  oz. of hydrochloric acid to 100 ozs. of water, allowed to remain in this for three minutes, transferred to a fresh bath of the same strength for another three minutes, and then washed in plain water. As the only objection to further acid baths is the removal of the brown colour, if it is found that more can be given, they should be used, as they certainly increase the likelihood that the print will be permanent. Ordinary black prints may have a minimum of three baths of the strength just mentioned, transferring them one by one and draining them well before putting them in the fresh acid. More than three

baths are advisable when a number of prints are being dealt with, the instructions of the Platinotype Company stating that the last acid bath, after use, should be quite colourless when seen in a depth of 2 inches. Instead of hydrochloric acid, citric acid may be used,  $\frac{1}{2}$  oz. to the pint of water being a convenient strength, though stronger solutions have been recommended. This substitution makes the process a more convenient one for travellers, as the hydrochloric acid is too corrosive to be carried with ordinary luggage.

After the acid baths the prints have to be washed to free them from acid. In doing this it will be found, if the acid baths have been too strong, or if the prints have been left in the acid too long, that the surface of the paper has become very tender, and the rougher papers may even injure each other by lying on top of one another. If the acid has not been stronger than one in sixty, and the total immersion in acid has not exceeded half an hour, there should be no trouble from this cause. Four or five changes in water, draining between each, are sufficient to remove all traces of the acid, and the prints are finished.

It does not hurt platinum prints to dry them between blotters, as there is no gelatine on the surface to cause them to adhere. In warm weather they are best blotted off and dried as soon as possible. The author had some prints entirely ruined by being put away in summer time for about a week while still damp. They were blotted off as thoroughly as possible, a few pieces of blotting paper were arranged top and bottom, and the prints in a pile between them. The whole was put away under pressure for a few days, at the end of which time a fungoid growth, or mildew, which could in no way be removed without spoiling the print, had badly marked nearly every one—quite ruining them. In a dry print it is impossible to suppose that there would be any risk of this.

If a developer diluted with water were applied to a platinum print with the idea of developing it in parts or by degrees, stopping the action in one place and continuing it in another, failure would result; because the water would dissolve and remove the platinum salt before the iron salt which had altered under the light's action could decompose it. But if the developer could be diluted with some inert substance which

would make its action gradual and under control, but which itself would be incapable of dissolving the soluble salts in the paper, we should have what we require. Such a substance is glycerine; and by the use of it in combination with the ordinary developer, the photographer has a very great power of control over his platinum prints—a power which he can get in no other way. To use the method the usual cold developer is mixed with glycerine in two or three different proportions. Thus we may have three vessels—saucers are handy for the purpose—containing respectively  $\frac{1}{2}$  dram, 1 dram, and 4 drams of the developer, to each of which 4 drams of glycerine has been added and well mixed up. The print is placed face downwards on a piece of glass, while a little glycerine is well rubbed into the back with the fingers; it is then turned over and glycerine rubbed into the front in the same way. This should be done in bright artificial light, as it is very necessary to see what is happening, though the paper is as sensitive to daylight under its glycerine coating as it is at any time. The surplus glycerine being swept off the print on to the glass with the fingers, these may be washed and wiped and development taken in hand. With a brush charged with the most dilute of the developer-glycerine mixtures, those parts of the picture which are to appear in the finished print are covered, and then using one or other of the mixtures as may seem to be required different parts are brought out or held back at the will of the photographer. Where the action is progressing too rapidly the developer is wiped off and glycerine applied; where it is not going on fast enough the stronger solution is used. In this way it is sometimes possible to get effects which are only to be obtained otherwise by gum printing or by bleaching. But the comparative rapidity with which the action takes place makes a great demand upon the user's skill and decision. Anything once brought out is irrevocable, and it is not easy to stop the action at once in any particular part, nor is it possible to follow fine lines or to adhere closely to outlines, as the action always tends to spread.

When carrying out any modifications of this kind—and by no means is the observation limited to the platinum process—it will be found a very great help to have a copy to which to work. This can be made by taking a plain, straightforward



MISS MINNIE ASHLEY  
BY MRS. KASEBIER



print from the negative and drawing on it with chalk, obliterating what is not wanted, and lightening other parts, until the best effect is obtained. The chalk can be wiped off with a cloth that is slightly damp, and no attempt should be made with the developing process until the general effect obtained with the chalk is seen to be what is wanted. When this is the case, the copy may be fixed up behind the sheet of glass on which the print is being developed, and the pattern so supplied followed with the glycerine treatment. The process is seen at its best in irregular vignettes, where it is used to suppress parts which otherwise would interfere with the composition. It is said that there is sometimes trouble from uneven tones in the lighter parts—that is to say, those which are light, not from the opacity of the negative there, but from the process being employed to prevent them from fully developing. These are warmer in tint than the shadows; but using a strong solution of oxalate (one in four), slightly acidified with oxalic acid, the author has not met with any trouble on this score.

Stieglitz and Keiley exhibited some every effective platinum prints in two colours a few years ago, and published a pamphlet giving a description of the method employed. There was nothing of a very startling character in the process, which was merely the use of a developer containing mercury for the warm tones—the flesh tints, as a matter of fact—and a normal developer for the rest; but the skill with which it had been used drew attention to it. No one seems to have succeeded since to the same extent; but the method affords scope for those who have sufficient taste and skill; the former requisite is particularly essential, as it is easy to produce the most absurd discords by the method. If any attempt at brushwork is made, on no account must the brushes used for the developer containing mercury be employed afterwards for the normal solution. The slightest trace of mercury is sufficient to change the tone, as we have seen, and it is quite impossible to wash a brush free from such slight traces.

Prints on any part of which mercury has been used must be washed in the very dilute acid only, or the print will suffer. Any print developed with glycerine on being put into the acid bath should at once have its surface gently rubbed with cotton wool, to remove the glycerine and developer as quickly as



possible. If this is not done, development may go on too far, and the print be spoilt.

The unalterability of platinum not only gives the process its distinctive note, its permanence, but it makes it particularly hard to modify the platinum image by those methods to which a silver picture is so easily susceptible. There is no known method of reducing a platinum print satisfactorily ; but there are several by which other substances can be attached to or deposited on the platinum, either to alter its colour or to intensify the image. The best and most economical method of dealing with a print that is too weak is to tear it up and make another.

A weak print may be used as the basis for a strong one of a very cold tone, if this is desired, by employing Dollond's process. The finished print is soaked in water until it is limp, blotted surface dry and placed on a sheet of glass, or on the bottom of a dish, and a little glycerine is spread all over its face. Then some of the ordinary stock solution of gold chloride (one grain to one dram) is taken and spread over the face of the print with a soft brush, mixing it well in with the glycerine. The print soon commences to tone and to increase in vigour, and the brush should be kept going over the surface as long as the toning is continued. When it has gone far enough the print should be washed for two or three minutes, placed for a minute in an ordinary metol developer, such as is used for negative work, and then again washed for half an hour or so to remove all traces of the developer. The developer has no visible action, the toning being complete when the gold is washed off, but is used to decompose any gold solution that may be left in the pores of the paper, and without such treatment might cause discolouration of the print afterwards.

A curious method of toning platinum prints is due to Mr. J. Packham. If a finished and washed platinotype is immersed in a solution of the vegetable dye, catechu, the paper is not dyed, but the image gradually becomes brown. It was subsequently shown by Mr. Chapman Jones that the action depends on slight traces of the iron salt still remaining in the image after all the acid washings to get rid of it, and not on any action between the dye and the platinum itself. This is immaterial to the user of the process, and the method gives a

fairly permanent result. Catechu, or cutch, is the dye used for ships' sails, and gives them that rich brown colour which is so effective pictorially. Incidentally it helps to preserve the sail. Two drams of dyer's catechu or cutch in powder is boiled in 5 ozs. of water for five minutes, allowed to cool, and has added to it 1 oz. of alcohol. This forms the stock solution, and keeps indefinitely. Half a dram of this liquid is added to a pint of water, the solution is heated to 130° to 150° Fahr., and the print is immersed. Toning starts at once, and can be stopped at any moment that seems desirable, the operation having gone as far as it will go in about ten minutes. Toning may be done with a cold solution, but this takes much longer, up to four and twenty hours.

There are a whole string of processes for altering the colour of platinum prints by depositing silver on the platinum image, or by toning it with uranium and then either leaving it with the colour imparted by that operation, or by turning it some other colour by reacting on the silver or on the uranium compound. There are several reasons why such methods are little known and seldom used. They all, without exception, damage the permanence of the print. Not that the original platinum image is made less permanent by them, but the applied substances are liable to change. The only methods which give a reasonable promise of unalterability are the gold toning just described, and a process of intensification by depositing more platinum on the platinum image, which has no advantage to recommend it. Then in most cases the colours obtained are too positive—violent greens, crude blues, and assertive reds are seldom effective as the single tint of a monochrome ; and when the colours do not have this most undesirable characteristic, they are such as are more conveniently obtained in other ways. A platinum print, it may safely be said without fear of an accusation of unreasonable dogmatism, should be black or brown black ; and for these tones it has no rival in pure photography.

After all that has been said about the permanence of platinum prints, it may seem to be a contradiction to talk of their fading, and to give a remedy for it. Strictly speaking, platinum prints do not fade ; and if the whole of the processes have been properly carried out—surely not much to expect—they will not alter in any way. The last traces of the iron

cannot be eliminated without risk to the print, it is true ; but if any that is reasonably removable is left in, the print may gradually discolour, turning very much the same colour as a faded silver print. A bad quality, impure mount may help to bring about such a state of things. But this is not true fading, and anything that will remove the iron will at once restore the print to its original condition. Mr. Chapman Jones has recommended a solution of hydrochloric acid, one part of acid to twenty of water, to which has been added a few drops of a solution of sodium hypochlorite. Enough of this should be poured in to give the mixture a distinct smell of chlorine. Those who do not know what the smell of chlorine is like need not regard this as an insuperable difficulty. They can add the hypochlorite until they can smell something else besides the hydrochloric acid, and that will be chlorine. They will thus learn what chlorine does smell like, an increase of knowledge not accompanied by that increase of pleasure which is generally supposed to repay intellectual acquisitions. The print is placed in this liquid until it has reassumed its original condition, after which it is washed and dried.

The platinum process is most readily adapted to printing on fabric, and a number of different textile materials used to be made by the Platinotype Company, the list including linen, sateen, and nainsook, a kind of fine muslin. The chemical treatment is the same to all intents and purposes as that of the paper ; but fabrics require careful handling in the printing frame. In an article by Mr. Coulthurst on the use of these fabrics, he pointed out that they should be backed up while in the printing frame with several thicknesses of dry blotting paper. When examining the print to see how printing is progressing, great care must be taken to see that the linen falls back flat on the negative without any creases, which come very easily. For this reason some workers prefer to time the printing by an actinometer entirely. The finished print on material of this kind is dried between blotters and is then ironed out flat. In printing on fabric in sizes larger than whole plate, he recommends fastening the fabric to a piece of thick paper or thin card at the four corners, as this helps to prevent creases, and forms a convenient support for the material during development.

What has already been said should be sufficient to show that the claim of simplicity for the platinum process is not without an ample basis. There is little likelihood of trouble that cannot be traced immediately to careless manipulation. The only defects which need reference here are solarization or bronzing in the deepest shadows, mealiness or granularity in the prints, and weakness and washing away of the image. Solarization is not due to any imperfection in manipulation, but to the use of a negative that is too strong in contrast for the paper employed. In this respect the Kodak platinum paper is very notable, as with it solarization seems almost impossible. If the whole of the film is stripped from the borders of the negative so as to leave clear glass, the severest test that could be supplied, the print on Kodak paper will be found to have a deep rich black border without any tendency to bronze, unless the negative is very opaque. Mealy or granular prints may be due to weak developer or to the use of a suitable developer at too low a temperature, or to the paper being stale ; but the commonest cause is damp. If the damp has reached the paper after it was taken from the calcium tube, precautions should at once be used to prevent further prints being spoilt in the same way. These would take the form of drying the negatives and pads thoroughly before the fire, and taking care that the paper was put back into the calcium tube after printing, until it was to be developed. If the damp has reached the paper while in the storage tube, little can be done. It is said that by drying the paper in an oven that is not too hot, and then printing it and developing with a normal developer to each ounce of which half a dram of a ten per cent. solution of potassium bromide has been added, much better results can be obtained. Or ten minims of the hypochlorite and acid liquid referred to on p. 204 may be added to each ounce of developer. A little carbonate of soda added to the developer is useful if the paper is stale ; but all these are only devices to make the best of a bad job, and good prints can only be obtained by the use of paper in the best condition, kept perfectly dry until development, and developed in the normal manner.

## CHAPTER XVI

### THE CARBON PROCESS

Tissue—The necessity for transferring—Ready sensitized tissue—Its storage—Measuring the printing—Actinometers—Sensitizing tissue—Bennett's formula—Drying tissue—The safe edge—Development—Single transfer—Stripping negatives—Double transfer—Double printing—Spotting—Carbon transparencies—Bichromate poisoning—Ozotype—Gum-bichromate—Mr. Mummery's method—Multiple gum—Single coatings—Gum ozotype.

NOTHING could have been farther from the thought of Mungo Ponton, ninety years ago, when he noted that gelatine containing bichromate, after exposure to light, lost its power of dissolving in warm water, than that he was making one of the most fundamental discoveries of photography. Yet such it was ; and the carbon process is only one of many which are based upon it. It can hardly have looked very promising ; there was no visible change of colour, or, at least, what there was can only have been very slight ; it did not seem to lead to anything of importance ; the sensitiveness was not great ; it was a mere curiosity. It was left for Poitevin, Swan, and Woodbury to show bichromated gelatine as the most Protean of the genii who obey the possessor of the ruby lamp. We are concerned for the moment with the "carbon" process only, a process in which carbon does not necessarily play any part at all. Whoever dubbed it must have been content, like David Copperfield, Senior, to see the nests and take the rooks on trust. He perceived that *if* carbon were used as a pigment, the process was a permanent one, and it was the "carbon" process for ever after.

The process in outline is simple enough, nor is it complicated in practice. If gelatine, potassium bichromate, and some colouring matter are thoroughly incorporated, and a thin coating of the mixture is applied to paper, we get, when it

is dry, a sensitive preparation upon which we can print. For the moment, we will suppose it to be printed with the back, or plain-paper side, towards the negative, so that the light has to strike through the paper to reach the coating. The precise nature of the colouring matter, so long as it is unaffected by the bichromate and is permanent, does not matter much. Such paper is known as carbon tissue. After exposure, no image is visible; but on soaking the tissue in cold water for a little while, and then placing it in warm water, signs of a picture may make their appearance, the gelatine and pigment washing away where the light has not yet acted. In a short time we shall find that no more of the gelatine will wash away, and, if the exposure has been correct, that the paper bears a passable print from the negative. It will have two serious defects, however—owing to the print having been made through the paper, it will be grainy and coarse; and for the same reason it will be the wrong way round, or reversed as regards right and left. The process thus outlined is nevertheless quite practical for large sizes, and a few years ago some very good carbon prints made in this way were shown by Valentine Blanchard. Latterly, this form of the process has been revived by the Rotary Photographic Company, who use thin sheet celluloid as the base, instead of paper, and so evade the difficulty of the grain. In printing through the paper there is also trouble from the length of exposure required, and from the discolouration of the paper with the bichromate. Why, it may be asked by some one not familiar with carbon printing—why not print direct on to the coated surface of the paper? The answer to this question brings in the whole difficulty which confronted the original inventors.

The mixture of gelatine and pigment is necessarily an opaque, or at least a deeply coloured one. When it is exposed under a negative, with its outer surface next the film, the light strikes that surface first, makes it insoluble, and this insolubility only extends a little way down into the film of gelatine. Let us suppose that Fig. 16 represents in a much magnified form a cross-section of a piece of sensitive carbon tissue. The paper support is shown at A, and the gelatine and pigment at G. The light coming through the negative reaches the top surface of G, and the depth below that surface to which

its action extends is governed by the different densities of the negative and by the exposure. Let us suppose the shading represents the part of the film G, which, after sufficient exposure, is rendered insoluble ; H would be a high light in the print, and S a shadow. Now, if such a piece of tissue were put into warm water, it will at once be evident that when the still soluble gelatine, the lighter shaded part, had dissolved, there would be nothing to hold the insoluble film on to the paper, and it would float off and wash away.

Accordingly, in the earlier stages of the process, a sheet of paper was cemented on to the top of the printed tissue by



FIG. 16.



FIG. 17.

means of indiarubber solution, and then, when it was all put into warm water, the original paper support could be pulled away, as at P in Fig. 17, and the gelatine picture adhering to the fresh paper support T was not only not in danger of being washed away, but was in a better position for the warm water, which then had direct access to the soluble part of the film, to dissolve what was not wanted. It was this process of transferring which made carbon printing a practical success. Such a discovery would make the reputation of an inventor, but it is only an incident in the long series that the world owes to Sir Joseph Wilson Swan. Still, as the first of that series—it was made in 1864—it may perhaps have prominence beside bromide paper and the incandescent electric lamp.

Swan having shown the way, J. R. Johnson followed four years later with a remarkable simplification, which left the process where it stands to-day. By applying paper coated with gelatine to the printed carbon tissue while it was still in cold water, after it had begun to soften and swell, but before it had absorbed all the water it could hold, Johnson found that it went on absorbing, and in doing so cemented itself to the coated paper so that no indiarubber solution or other compound was required.

The transferred print, like the print made through the paper



DAISIES  
BY CARINE CADBY





support, is reversed as regards right and left. In many cases this does not matter, but in some it is important; and Swan got over the difficulty by transferring first to one paper for development, and then again transferring the print to a "final support." In 1874, Sawyer introduced his "Flexible Temporary Support," and the carbon process was in every respect what we see it to-day.

No amateur photographer thinks of preparing his own carbon tissue; he can get it in some fifty or sixty different shades, from at least four different makers in this country, and amongst them he must be hard to please who cannot be suited. One great feature of carbon work is that almost any pigment which is not affected by the bichromate may be used. The result of this is that there is no colour whatever in which a carbon print cannot be made, if it is desired. The most popular colours—and, on the whole, the most universally suitable—are engraving black, warm black, standard brown, red chalk, and standard purple. The last named is a colour based on that of a toned-albumenized print, and is not so pleasant as the others. There are a number of other colours—shades of brown mostly—each of which has its admirers, while dark blue and sea green are appreciated by those who do not mind their assertiveness. A special form is known as "transparency tissue." It is supposed to contain Indian ink as a pigment. Not that we would suggest that this is not so, but merely that the manufacturers do not commit themselves as to the ingredients used. The transparency tissue, as its name implies, is most suitable for transparencies on glass; but it may also be used for paper prints of a rich brown-black colour, and is distinguished for the extreme fineness of the pigment it contains, and for a larger proportion of pigment to gelatine than is usual in the case of tissues made primarily for prints on paper.

Any one working the carbon process for the first time will probably buy the tissue sensitized ready for use; but sensitizing at home is so much more economical in the long run, is very little trouble, and gives quite as good results, that as soon as the process has been mastered, the tissue is sure to be purchased in its insensitive condition. When buying it sensitive, it is usual to find out the day of the week on which sensitive tissue is coated, so that it can be bought quite fresh. It is

actually sensitive tissue that is coated, and not a mere sensitizing of already coated tissue, the bichromate being added to the mixture that is applied to the paper.

One of the greatest hindrances to the popularity of the carbon process is the fact that sensitive tissue will not keep. It begins to deteriorate from the very first day, and if kept without special precautions is useless in a week or so. If kept flat, under pressure, so as to exclude the air as much as possible, it keeps longer; and in a calcium tube it will keep for months. But it is never so good as when it is used within a day or two of being made or sensitized; and herein lies the advantage of home-sensitized tissue.

The tissue, sensitive or not, looks like some curious form of plaster. It is not easy to distinguish the colour of the pigment used, as, in its thick coating, it looks almost black, unless a very marked colour is employed. For this reason, and to avoid mistakes, the colour of each piece should be written lightly in pencil on the plain paper back. The tissue is sold in rolls or in cut pieces. Sensitive tissue is best bought cut to size, as this reduces the risk of injury by handling; but it is more economical to buy insensitive tissue by the roll or half-roll, and to cut off pieces of any size or shape that happens to be required. In an ordinarily dry drawer or cupboard insensitive tissue keeps as good as ever for unlimited time. The packet of cut sensitive pieces should be kept in a cool place, away from gas or other injurious fumes to which it is almost as susceptible as a dry plate. Heat and damp together are particularly inimical to it. The surface of the sensitive tissue should be handled as little as possible, and if it is very dry when it is received, it must be unrolled or unbent carefully, to avoid breaking the gelatine surface.

In addition to the carbon tissue, "single transfer paper" will be required; and this also can be bought either in cut pieces or in the band. The cut pieces are always a little larger than the size of the prints for which they are to be used: thus, 5 by 4 is supplied for quarter-plates, 9 by 7 for whole plates, and so on. As the surface of the final print will be the same as that of the transfer paper used, this is made in a number of different grades to suit different tastes; but the smoothest is that with which it is best to start operations, as

the rough papers, though not inherently difficult to use, at least call for a little more care and knowledge. Except the tissue, the transfer paper, and some potash alum, the carbon process calls for no materials that the photographer has not got at hand. One or two small pieces of apparatus are necessary.

The process of printing, not being accompanied by any visible change, can only be ascertained instrumentally. This is accomplished by means of an actinometer or print meter, an instrument which can be obtained in several patterns, but all based on the use of a piece of silver paper exposed side by side with the printing frame in which the carbon tissue is printing, the exposure being timed by the visible alteration in the silver paper. The simplest form of actinometer is a little piece of P.O.P. put underneath a negative of about the same density as that which is being printed in carbon. When the silver paper is about as dark as it ought to appear when finished—those who have read the chapter on P.O.P. will know that this is not the same thing as saying when the P.O.P. is properly printed out—the carbon print is about done. As P.O.P. varies very considerably in the speed with which it prints—as carbon tissue does likewise—and as it is no easy matter to decide correctly that two negatives are of the same printing density, it will be seen that this is an extremely rough and ready guide. Still, it is a guide, and many workers who produce very fine carbon prints use nothing more elaborate.

Johnson's actinometer is the simplest of special appliances. It is a cubical box which holds a roll of sensitive paper, whose free end is led underneath a piece of glass coated with a brown paint, which is quite opaque, but has a clear hole in the middle. The paper gradually darkens to the tint of the patch of paint surrounding it. When this is reached, the instrument is said to register "one tint," and the paper is pulled on a little so as to expose a fresh piece. This actinometer suffers from the disadvantage that it requires constant watching. If a carbon print is to be exposed for five tints, the paper must be pulled forward each time when it has properly darkened; and if from any oversight this is not done once, and the printing is allowed to go on beyond the tint on the actinometer, it is only by guesswork that we can decide to what extent that has taken place.

Mr. J. R. Sawyer therefore introduced a modification of the Johnson actinometer, which has a scale of graduated "densities" and takes a strip of paper, beside which runs the tint to be matched. There is thus no need to move the sensitive paper at all while making the carbon print: all that is necessary is to decide which of the densities represents the depth to which the printing should go, and to expose until the paper under that particular density has darkened to the standard tint. Wynne's print meter is another extremely neat little instrument of the same kind. Burton's actinometer is a further elaboration. It has a row of little negatives with densities in front of them, and a strip of paper beneath, printing being continued until the selected negative has yielded a print of the correct depth.

An actinometer of the Sawyer type is easily constructed, the densities being made by allowing pieces of thin paper, such as cigarette paper, to overlap one another, one density being formed of one thickness, two of two thicknesses, and so on. It is perhaps as well to point out that it must not be supposed that in such an instrument if one thickness of the paper requires a certain exposure, two thicknesses require double, and three thicknesses treble. The relationship is by no means so simple; but if no attempt is made to employ the relationship of one of the densities to that of another, a thing that should not be done in any actinometer, the indications are reliable enough. Whatever form of instrument be used, two cautions must be given if it is to be employed successfully. The angle which the front of the actinometer makes to the incident light should be the same as that of the negative in the printing frame, and the same make of sensitive paper should always be used in it. The actinometer is placed as near to the printing frame as possible. If several printing frames are being put out at the same time, one actinometer will do for all of them, if they are all started together; each frame is then taken in as the tint thought to be correct for that particular negative is reached.

If carbon printing is regularly practised, it is a good plan to mark on the edge of each negative the number of tints or actinometer densities which are the correct exposure for it; and, when different colours of tissue are used, to mark the tissue,

because the speed of tissue varies with its colour. This is only to be expected, since the picture is formed in the tissue by the depth to which the light penetrates into it and makes the film insoluble; and the more opaque the coating, the longer does it take for the enfeebled light which can get through the film to make it insoluble to the depth that is required. Therefore, the more opaque the colour, and the more nonactinic its tint, the longer is the exposure it requires.

There is also a considerable difference in the speed of the different makes of carbon tissue, and different methods of sensitizing have a great influence upon speed. The fastest is undoubtedly the ready sensitized tissue of the Autotype Company, and this also has the greatest tendency to give very clean whites. In fact, this is so marked, that in their handbook of the process the company recommend that the tissue be not used until a day or two after it has been sensitized, as in this way softer and better pictures are obtained. There is no particular advantage or otherwise in this sensitiveness, and sensitized at home the tissues of the company do not show any superior rapidity to those of other makes.

Sensitizing carbon tissue presents no difficulty whatever; and it should certainly be done by any one who thinks of using the process for his work generally. It is only in this way that it is possible to take full advantage of the range of colour which carbon affords. The insensitive tissue can be bought in pieces or in the roll, and a small stock of the different tints that are preferred may be kept. The night before any prints are to be made, one or two pieces of each colour wanted are taken and sensitized for use on the morrow. The tissue is thus printed while it is at its very best. If it is bought sensitive, the least that can be purchased is generally a dozen pieces, and these must be used up very quickly or they are wasted.

Until two or three years ago, the only sensitizing liquid used for carbon work was a plain solution of potassium bichromate, to which some people added a trace of liquor ammonia or of potassium carbonate. In October, 1903, Mr. H. W. Bennett described an improved sensitizing bath which he had worked out, from a suggestion made by Professor Namias, which had certain very marked good qualities. The orthodox

sensitizing bath to which we have referred was generally one of 5 per cent. strength—

Potassium bichromate	...	...	...	...	...	1 oz.
Water to	...	...	...	...	...	20 ozs.

Five drops of strong liquor ammonia were sometimes added, and it was usual in hot weather to reduce the quantity of bichromate to one-half or even one-quarter of that given above. This sensitizing bath keeps quite indefinitely, as indeed do those which are to be described. As the quantity is reduced by being absorbed by the tissue, fresh may be added so as to keep the bulk about the same. A Winchester quart (80 ozs.) is a convenient quantity to make up for sensitizing tissue up to 15 by 12 inches in size, but the greater the depth of solution in the dish, the easier does the operation become.

The sensitizing bath recommended by Mr. Bennett is made by dissolving an ounce of potassium bichromate in a pint of water, and a quarter of an ounce of citric acid in about the same quantity, and mixing the solutions. Strong ammonia is then added, two or three drops at a time, stirring after each addition, until the colour of the liquid changes from the deep orange red of the bichromate to a lemon yellow. As soon as this stage is reached no more ammonia is added, but the bulk of the liquid is brought up to 50 ozs. by the addition of water, and the sensitizing solution is ready for use. With some makes of carbon tissue, one-third this quantity of ammonia was found to be sufficient. This quantity is ascertained by taking one-third of the total bulk of bichromate and citric acid solution, adding ammonia until it changes colour, and then mixing it with the remaining two-thirds to which no ammonia has been added. It is not possible to give the quantity of ammonia, as this depends upon the nature of the sample of bichromate used and upon the strength of the ammonia solution, which latter is variable, the solution becoming weaker every time the bottle is opened. The only way is to judge by the change of colour, as has been described; but this is very marked, and involves no difficulty at all in practice.

Variations in the strength of the sensitizing bath and in the length of time the tissue is immersed in it, give corresponding variations in the character of the prints. The stronger the

solution, the softer will be the contrasts in the print ; to obtain uniform prints from the same negative, not only should the sensitizing bath always be the same strength, but the tissue should always be immersed in it for the same time. The bath made up according to Mr. Bennett's formula, and used for two minutes, will be found to give a very satisfactory tissue. The Autotype Company recommend a bath which is practically a 5 per cent. solution of bichromate, applied for three and a half minutes, a time which is easily checked by means of one of the little "egg boilers." As potassium bichromate is largely used for manufacturing purposes there are several qualities on the market, some of which are anything but pure. It should be in clear ruby red crystals, with little or no orange-coloured dust adherent. The powdered bichromate, sometimes sold, should be avoided ; both because its appearance gives no evidence of its purity, and it is exceedingly hard to dissolve, caking together and taking a long time.

A squeegee, a dish, a sheet of glass a little larger than the tissue, and a few dark-room pins are needed for sensitizing. A piece of the tissue, which should always be cut a little bigger than the finished print, to allow an edge for handling, is taken in both hands, and bent into a convex shape, with the coated surface outwards and downwards. Held like this the convex part is pushed under the sensitizing liquid in the dish, and then the hands being separated and lowered the rest of the sheet is submerged, starting from the centre and finishing at the edges, when it should all be underneath the surface ; the time is then noted. In this way any air-bells are pushed to the ends and broken. If any air-bells are seen on the back they may be broken by touching them with the fingers, and the tissue is then turned over and the face attended to in the same way. A broad camel-hair brush is a convenience at this stage, and by brushing it gently once or twice in both directions across the face of the tissue all risk of air-bells is prevented. At the end of the time, the tissue is picked up by two corners, allowed to drain for a few seconds, and then placed face downwards on the sheet of glass and gently squeegeed from one end to the other to get rid of surplus bichromate solution. This is the only purpose of the squeegeeing, and it must be done without any vigour or the tissue will



be injured. The sheet of tissue may then be pinned up by two of its corners to dry.

All these operations can be done in broad daylight, as carbon tissue is only sensitive when in its dry state. Tissue sensitized on a plain bichromate bath must be dried where there is no risk of it being injured by gas fumes, which render the outer surface insoluble, and so prevent clean high lights from being obtained. If the citric acid and ammonia sensitizing solution is used, the tissue is far less likely to suffer, and may be dried in any ordinary room from which daylight is excluded.

If, after sensitizing, the tissue is squeegeed down on to one of the opaque pulp boards which are supplied for squeegeeing P.O.P., or on to a ferrotype sheet, it may be dried without removal from the ferrotype or pulp. This has several advantages. The opaque substance screens the face of the tissue from the light, and as the bichromate stains the paper back a very non-actinic colour, the tissue may be dried without injury from daylight in an ordinary room. It would be possible by placing it in a direct and strong light to spoil it in the process ; but by avoiding any deliberately unnecessary exposure, the proceeding is quite free from risk. As the front surface of the tissue is that which forms the delicate high lights of the picture, and as anything which affects it is therefore more injurious than if it affected the back where it washed away, an absolute protection against fumes is afforded by drying the tissue in this manner. Finally the tissue leaves the ferrotype with a very glossy surface, which allows of the most perfect contact between tissue and negative during printing. Against this must be set the fact that drying in this manner takes longer, and requires a number of pulp boards or ferrotype, which must be perfectly clean.

On no account must the tissue be printed until it is perfectly dry, as if it sticks to the negative, as it will do if it is at all moist, the negative is ruined, while if any bichromate is absorbed by the negative, it is equally fatal, and a mark will be made which by no ingenuity can be removed. As there is no occasion to examine the progress of printing, the frame may have a solid back, or we may even dispense with the frame altogether. For large negatives the author uses a



THE QUAY  
BY T. J. BROGDEN



drawing-board, on whose smooth surface the sheet of tissue is placed, covered by the negative, and the two pressed into contact by means of a sheet of stout plate-glass, which is prevented from sliding about by means of a few dark-room pins as described later on.

If an ordinary frame is used with a negative the full size of it, the precaution now to be described is not so necessary; but with a drawing-board what is called a "safe edge" is important. If a clear shadow on the negative comes right at the edge of the picture, the tissue underneath may be rendered insoluble so completely that it will not adhere to the transfer paper in development, but will form a kind of pocket or frill, underneath which the water will get, and may detach still more of the film from what should be its support. For this reason it is customary to provide all negatives that are to be printed in carbon with a black opaque border, preferably on the glass side. It need not be more than an eighth of an inch wide, and can be made with a brush and a little Brunswick black; but the usual method is to use the narrow strips of black paper sold for binding lantern-slides; they may be cut down the middle, as they are wider than is needed. By applying the "safe edge" to the glass side its border is vignettted a little into the picture, and there is no sharp edge of insoluble machine standing up on the paper. The "safe edge" ensures the extreme edge of the print being composed of soluble gelatine, which on development forms a kind of buffer, and prevents the film from washing up. For a similar reason, as the edges of a piece of tissue are invariably the parts which are first attacked by that gradual insolubility which constitutes its deterioration, it is decidedly convenient to sensitize pieces slightly larger than the negative to be used, and to trim a quarter of an inch off the tissue on all four sides, before exposing. If small sizes are worked, a better plan is to sensitize pieces a little more than twice or four times the size required, and to cut these pieces out of the middle.

The tissue, after being sensitized, is of course kept in the dark until it is required for use, and after it is taken out of the printing frame, it is similarly preserved from light. If it is put into a calcium tube, it may be kept for a long time between printing and development without alteration of any kind,

provided the drying action of the calcium is efficiently performed. But if there is any moisture whatever present in the tissue, it is subject to a curious phenomenon, first discovered by Sir William Abney, and known as "the continuing action of light." The action started by light under the negative proceeds in darkness, very much in the same way as if the tissue were still being printed. The result is, that a print half done, if put away for some time before it is developed, may be found to yield as vigorous a picture as it would have done had the printing been complete and development followed on at once. Where carbon printing is constantly being carried on, it has been found possible to take advantage of this continuing action to shorten the time of printing when the light is poor, but when using the process in a small way and at intervals, as an amateur does, this is too risky to be worth attempting; since the rapidity of the action varies with the temperature and with the degree of moisture present. When development has to be postponed, this phenomenon may give rise to trouble; and it is particularly prone to lie in wait for the skilful carbon printer who has accepted the invitation of the secretary of his Photographic Society to "come down some evening and give us a demonstration." He is in the habit of printing and developing in close succession, and either forgets all about the continuing action, or at least greatly underestimates it, and in the interval between printing in the daytime and development before the Society at night, the tissue has actually overprinted. It is a curious fact, and shows how persistent is the tendency to underrate this action, that the author, who has seen many such demonstrations, has hardly seen one in which the prints were not distinctly darker than was intended from this cause, and has certainly never come across a single case in which they were too light from excessive allowance having been made for the continuing action.

Up to the stage that we are now considering, the single transfer and the double transfer carbon processes are identical; but we are now at the point at which they differ, though only slightly. The reversal as regards right and left, which is the one drawback of single transfer, for many subjects is quite unimportant. In pictorial work generally its influence has never been carefully studied, and many photographers would say that provided the picture did not purport to represent any known

subject with which it could be compared, and its reversal thus detected, it did not matter which way round it was. This does not apply of course to the case of portraits, in which this is very important, much more so than many think. If the wedding-ring is shown on the wrong hand, the observant eye of a lady detects it instantly, though without so self-evident a clue she might see the portraits of all her friends reversed right for left, and never detect that there was anything wrong at all: showing that her observation was superficial and limited, as indeed is that of most people. Any one who cares to take the trouble to study a face, as a painter has to do who would portray it properly, knows that the two sides of it are never alike. "Nature knows no equality," said an orator, "and the only equality possible artificially is in the voting power of St. Paul and Judas Iscariot in the ideal democracy." Without following him into politics, we may note that his sweeping generalization is true enough of the two so-called symmetrical halves in which the human being can be regarded; although the extent of the difference varies very much. Still there always is a difference, especially noticeable in the face, and a very little observation will show it. In landscape, too, the effect may be decidedly different in two pictures, identical in all respects except as regards this reversal of right for left; and the subject is one which might well receive the attention of a critic of analytical turn of mind. It would necessitate the careful study of a large number of pictures if any generalization of value is to be drawn up; for there has already been far too much verbiage on subjects of this kind that seems only to have been evolved from its writers' inner consciousness, and not based upon any thoughtful analysis of examples, which alone could give a result of any value.

While the single transfer process, if the print is made from a glass or film negative in the ordinary way, gives a reversed picture, there are several ways of preventing this from being a reversal of the original subject, without having recourse to double transfer. If the negative is on a film, printing may be carried on with equal ease, and with almost equally good definition from either side. All we have to do is to print in carbon from the opposite side of the film to that ordinarily placed next the sensitive material. If the negative is on glass,

it may be stripped therefrom, or "filmed" as it is called, and printed from the reverse side in the same way. If the negative is to be specially made for single transfer carbon, the plate may be put into the dark slide the wrong way round, with its glass side towards the lens; but this is rather a brutal proceeding. The exposure is increased, there is danger that the spring of the dark slide may injure the surface of the film, and a backed plate cannot be used, though this is only troublesome if the plate is already backed, as halation is not likely to arise, for obvious reasons. Then, again, the thickness of the glass is not precisely known, yet it must be allowed for in focussing—a thing generally done in a happy-go-lucky way by reversing the focusing screen. Last, but not least, any imperfection on the surface or in the body of the glass of the plate prints itself on the negative with the approximately parallel rays from the lens, though it might never show when printing in the ordinary




FIG. 18.—A REVERSING PRISM.

manner in diffused light. A fairly good string of objections, surely! A much better plan is to employ a right-angled prism in front of the lens, which reflects the image, and in doing so reverses it. This is the method employed by process workers to obtain reversed negatives. If the prism is too costly, a piece of plate-glass, silvered on the surface, which can

be got from a good optician comparatively cheaply, may be substituted with a fairly good result.

Single transfer paper of the thin smooth character generally used requires no preliminary soaking, but if a rough or thick paper is employed, it must be soaked for some time before use. Very rough papers should have at least an hour in cold water, or, if this is not possible, they should be put for ten minutes or so in warm water and then be transferred to cold. The whole secret of successful transferring lies in the selection of the proper moment at which to bring tissue and transfer paper into contact. Unless the tissue is quite dry when transferring is begun this moment cannot be ascertained properly. The print should feel quite stiff, or, at least, it should not be limp. A sheet of glass, or a board covered with a smooth piece of zinc, and a flat, not a roller, squeegee are the most suitable

implements. The transfer paper, a little larger than the tissue, is placed, face upwards, on the bottom of a dish of clean water, and the piece of printed tissue is immersed in the same dish, and looked to that no air bells remain on it back or front. It will curl up with the coated side inwards for a moment, but very soon it will be noticed that the tissue starts uncurling. This is the sign that it is in the right state for transferring, and it must be at once arranged, face downwards, in position on the transfer paper, the two withdrawn from the water together, and laid on the glass or zinc. The squeegee is then applied vigorously, but not violently, in all directions, to bring the two surfaces without loss of time into close contact. If the operation has been carried out properly the tissue will go on absorbing water, will suck up all the thin film existing between its surface and that of the transfer paper, and will adhere closely to it. The operation need not be performed in a hurry, but it must not be carried out too deliberately, or the favourable moment will have gone by ; and when once the tissue has fairly flattened itself in the water, it has absorbed as much as it will, and no degree of squeegeeing or of pressure will make it adhere. After squeegeeing, the two papers may be left for fifteen or twenty minutes on the squeegeeing board, or between blotters, or hung up, while preparations are made to develop the print.

Warm water is the only developing agent required by the carbon process, and the wonderful way in which under its influence the repellent black mass, which is all that is visible at first, gradually reveals a picture in all the gradations of light and shade, has a curious fascination for those for whom familiarity has not made the phenomenon seem a matter of course. There is no need to use a thermometer, as slight differences of temperature in the water do not make any very great difference in the result, but it is well not to have the water too hot to start with. It should feel agreeably warm to the hands and nothing more, and if this is examined with a thermometer it will be found to be from 105° to 115° Fahr., according to the callousness of the photographer. Before being at the trouble to develop a print it is well to make sure the tissue is in good order. In fact, if the tissue has been kept for more than a day or two after sensitizing it is a wise precaution to see that it is soluble, before being at the trouble to print on it. This is done



by taking a small strip, allowing it to soak in cold water for a minute or so, and then holding it so that half of it is immersed in the warm water. The gelatine and pigment will wash away leaving the paper support quite white, if the tissue is in good order.

The print adhering to its transfer paper is slid into the warm water, tissue uppermost, and left there for a minute or so. Before that time has elapsed, coloured gelatine will be seen to be oozing out at the edges all round, and this is generally taken as a sign that the paper may be stripped off. It is well not to hurry it, as nothing is gained by so doing, beyond the risk of pulling some of the image off with the paper, and so spoiling the picture. When there is no doubt about the dissolving action being general, one corner of the paper is raised and it is skinned off with a smooth unbroken pull, leaving a dirty-looking dark coloured mass on the transfer paper. The warm water may be gently splashed over this with the hand, or the print may be left undisturbed for a few minutes. In either case signs of the picture will soon appear, and it will become more and more visible by the washing away of the soluble pigment and gelatine. If the print is allowed to lie on the surface of the water, face downwards, it will gradually develop spontaneously; but if this method is adopted it is most important that there should be a good depth of water beneath it—enough at any rate to remove all risk of the face of the print coming into contact with the bottom of the dish, which would almost certainly injure it. Most carbon workers prefer to support the print, face upwards, on a sheet of glass and pour warm water over the face of it, there being a widespread belief in the power of modifying the tones of a carbon print by so doing. A stream of warm water is directed on to those parts which are to be lightened, avoiding the rest of the print. There is a slight power to be obtained in this way, but it is much overestimated as a rule, and if there is to be local alteration of this kind, the only method that is really satisfactory is by work on the negative, such as is discussed in Chapter XX.

It is not possible to stop developing a carbon print just when the vigour of the result seems to make it desirable, and the operation must be continued until most of the gelatine, which is still soluble at the temperature of the water that is

being used, has been removed. If this is not done, there is great risk of the surface being covered with greasy-looking mottling. At the same time, it is possible to control the strength of the image that shall be left, by the temperature of the developing water. With equal printing, the hotter the water the lighter and softer the resulting print. Over-printed tissue is therefore all the better for being developed in hotter water than usual, while under printing may be compensated to a certain extent by cooler water. It may happen that the development has gone far enough to prevent mottling, but the print is a little muddy in appearance. By drawing a tuft of cotton-wool over its surface while still under the water, a certain quantity of pigment and gelatine will be removed, as will be seen by looking at the wool, and the print will be cleared up a little. The same result can be obtained by the use of a camel-hair brush.

Any manipulation at this stage must be done with the utmost gentleness if the print is not to be ruined, and it should only be tried as a last resource, and on a print otherwise valueless. The thin film of gelatine on the transfer paper, especially in the highest lights where it is of microscopic thickness only, is most delicate, and the slightest roughness will remove it and leave an unsightly mark. If the temperature of the water is too high there will be great risk of blisters on the prints. A safe rule is never to use water which is too hot for the hands. The developing water soon gets dirty, from the dissolved pigment, but this does no harm to the prints.

The carbon print when developed is virtually finished. Its appearance is almost that which it will have at the end of the process, and if it were hung up just as it is and dried, it would be permanent. It is customary to give the prints an alum bath after developing, as this has two advantages—it hardens the film, preventing accidental injury while drying, and it removes the slight yellow tint due to the bichromate, which is still to be noticed in the developed picture. A five-per-cent. solution of alum, best made by dissolving a couple of ounces of potash alum, the alum of the oilshops, in a few ounces of boiling water and diluting it to make a quart, is all that is necessary, and the developed print, having been placed for a few moments in cold water, is put into the cold solution of

alum, in which it may be left for anything up to an hour or more. The exact time is not important, provided the colour is completely discharged, which should be ascertained by holding the print up to the light and looking through it. It is then washed for a few minutes to get rid of most of the alum, and is hung up to dry. —

Besides the very great range of colours which the carbon process enables us to use, there is almost as wide a range of paper textures. The tissue manufacturers supply a number of different transfer papers, both smooth and rough, of varied tints, and with varied grain. The Autotype Company in particular have a great variety of these papers, and it is well worth the time of the enthusiastic carbon printer to find out precisely what transfer papers the company are in a position to supply at any particular time, over and above the ordinary kinds which figure regularly in its price list. But when all the commercial papers have been obtained, we are only on the fringe of the possibilities of carbon.

It is quite an easy matter to prepare any paper not absolutely rotten in texture, so that a carbon print may be developed on it. All that has to be done is to give it a sizing of gelatine of such a character that it shall not dissolve off in the warm water.

The simplest method of preparing transfer paper is that given in the "Autotype A.B.C." Two solutions must be prepared, one of an ounce of Nelson's No. 1 gelatine in a pint of cold water, dissolving by heat after allowing the gelatine to soften, and the other of twenty grains of chrome alum in two ounces of hot water. Both the solutions are made hot, and, the gelatine being stirred, the chrome alum is added a few drops at a time. The selected paper is immersed for a minute in the warm mixture, taking care to break air-bells which form, and is then hung up to dry. Or the gelatine solution may be spread over its surface with a brush or sponge, taking care to rub it well in, especially if the paper is a rough one. Another sizing solution which has been recommended for the purpose is made by boiling for half an hour or so, three ounces of shellac and an ounce of borax in a pint and a half of water. Shellac is not soluble in water, but will dissolve slowly in a hot solution of borax, and so will form a water-varnish, in which the paper



PRIAR ROSE.

BY J. CRUWYS RICHARD.



may be immersed and then hung up to dry. If a piece of some particular paper is wanted in a hurry for a single transfer, it may be dipped in one of the ordinary cold or celluloid negative varnishes and dried.

Tinted papers, if not too dark, form very effective supports for prints on carbon tissue, ~~and~~ their use has hardly been as extended as the facilities which they afford for certain effects might lead one to expect. Even brown paper, at times, gives very pleasant results, though the power which the crayon worker possesses of picking out his highest lights in white is one the carbon worker does not enjoy, and one whose absence limits the applicability of the deeper shades of paper.

Double transfer is not very extensively used by amateur photographers, but is more the process for the professional portraitist of the better class. The method does not differ very greatly from single transfer. The tissue, after being printed, is transferred, not to a final support, but to a temporary one on which the print is developed. The most convenient medium is Sawyer's "Flexible Temporary Support," a coated paper whose surface has to be waxed before use. It is best to buy the waxing solution ready made, but it may be prepared by dissolving six drams of yellow resin and two drams of pure beeswax in a pint of turpentine. A day before the flexible support is to be used, a little of the waxing solution is poured on to it and rubbed all over with a piece of flannel. With a fresh piece the support is given a final polish, taking care that it is not left in a streaky condition, and the support is then pinned up to allow the turpentine to evaporate. Or the waxing solution may, instead, be applied to the ground surface of a piece of fine matt opal glass. The opal or the flexible support is used exactly as the single transfer paper, and the print developed on it, washed, and alumed. The flexible support requires a longer soaking in alum to remove the bichromate stain than does the opal, but otherwise the treatment is identical. The prints may then be dried, or may be brought while still wet into contact with the paper upon which finally they are to rest.

The final support in double-transfer work, should have a thicker coating of gelatine than in single transfer, and is therefore best bought ready coated. It should be cut up into pieces

a little larger than the pictures on the opal or flexible support, but smaller than the support itself, and soaked for half an hour in a solution of half an ounce of alum in twenty-five ounces of water. It is then transferred to a dish of cold water, from which it is taken for use. A dish of water which is just warm is wanted for the transferring process, and the print on its temporary support of opal or paper is placed for a minute or so in this, the final support is immersed in it also, brought with its coated side in contact with the print, and the two are brought out together, laid on a flat surface, and gently squeezed. If opal is used, it is well to put it away under gentle pressure for twelve hours, with some blotting-paper lying on the print, but if a paper support is employed it may just be hung up to dry. After twelve hours, the opal is allowed to finish drying in a vertical position or in a rack, and when dry the finished prints should fall off it without stripping. If not, and one is quite sure they are dry, they may be coaxed off by raising one corner with a pin. There should be no trouble at all in stripping prints from flexible support; the opal gets better with repeated use, if it is waxed but is not washed between each. The flexible support may also be used over and over again, and if for any reason a print on it is spoilt, it is good economy to transfer it to a final support all the same, as this is the best way to clean the temporary support ready to use again.

Prints on flexible support, when transferred, have a fine glossy surface almost equal to that on glossy P.O.P. If the matt opal is used, the surface is not so shiny. In either case, if there is any dulness of the surface it may be removed by gently rubbing it with a piece of flannel moistened with methylated spirit or with benzol.

The subject of printing in clouds is dealt with elsewhere, but there is a method of doing so which is only applicable to the carbon process, and therefore is more conveniently considered here. In this method, the landscape is first printed, transferred, and developed. The clouds are printed to the requisite depth, the tissue being marked so that the position of the clouds and skyline on it may be known thereafter. This may be done in pencil on the back. The landscape print, having been alumed, washed, and dried, is allowed to soak in

water exactly as if it were a fresh piece of transfer paper, and the cloud tissue is squeezed down upon it in the position desired. Pencil-marks on the margin of the landscape print make this process easier. The clouds are stripped and developed in the usual way, and when the cloud-picture has been brought to the right depth, a fine brush with stiff hairs—a sable does very well—is employed to remove the image of the clouds from those parts where it unduly overlaps the landscape print. With care this can be done to conceal all junctions whatever, so that the clouds and landscape show no trace of their separate origin, provided of course, always, that they do not give the secret away by their incompatibility.

The spotting of a carbon print is best done by taking a little strip of the tissue while it is still soluble, dissolving it in hot water, and putting it aside in a tall vessel to settle. If it is left a week or two all the better. The water is then poured off as closely as possible, leaving a little pigment at the bottom, which may be mixed up with a little gum and employed with the certainty that in colour it is a perfect match with prints on the same tissue as that which yielded it.

There is only one other modification of the carbon process that need concern us here, and that is the development of carbon prints on plain glass for transparencies. This has a twofold application. The transparencies may be used for ordinary purposes of decoration or for lantern slides, or may be backed up with suitable material and framed just as if they were paper pictures, and they may also be used as the means of duplicating negatives either the same size as the original or larger. It is, unfortunately, only too obvious to those who attempt it, that in making a positive from a negative on an ordinary gelatine plate, whether by contact or in the camera, and then making a fresh negative from that positive by a repetition of the process, there is a very serious falling off in quality. This is always seen to take the form of a falsification of the intermediate tones of the picture, and theory shows us that it is inherent in the dry-plate process. This falsification does not take place in carbon printing, and we may therefore make a positive transparency on glass by means of carbon, and from that make any number of carbon negatives, which, with proper precautions, may all be identical in character, and, what



is more important still, may be faithful transcripts of the original negative. Such negatives will be practically the same size as the original, though, in consequence of the expansion of the tissue, they will not be quite accurate in this respect. If we want an enlarged negative, we are bound to use a dry plate, but we may at least use the carbon method either to make a transparency by contact from which to enlarge, or to make a contact negative from the enlarged transparency, and in so doing we get rid of half the inherent falsification which we should get by employing the dry plate both for transparency and negative. Valuable negatives, which cannot be replaced, or at least which can only be replaced with great difficulty or expense, should always have a carbon transparency made from them before they are printed in any other way or exposed to risk of damage. It costs little, it is very little trouble, and is a guarantee that if anything should happen to the negative it can be duplicated.

The process of making glass transparencies in carbon is very similar to that of making prints, but certain precautions have to be taken which are not necessary when the prints are being made on paper. The glass must have a preliminary coating of gelatine, to ensure the adhesion of the film. After thorough cleaning with soap and water, followed by rinsing, the glasses should be immersed in a solution made by dissolving six drams of Nelson's No. 1 gelatine in a pint of warm water, and adding enough bichromate to give the solution a sherry colour (Autotype formula). This should be filtered while warm through a tuft of cotton-wool, and if, on taking a plate out of it, the solution seems to run off it as if the surface were greasy, the plate must be rubbed with a clean flannel dipped in the gelatine until it is seen that its surface is thoroughly wetted. The glasses are then placed in a rack to drain and dry in daylight, so that the bichromate may make the thin gelatine coating upon them insoluble. The author has succeeded in making some very good carbon transparencies by coating the clean dry glass with ordinary celluloid negative varnish as a substratum instead of gelatine. The varnish seemed to hold the tissue equally well, and, contrary to expectation, did not show any sign of stripping off the glass when this was placed in warm water to develop the picture.

If the exposed tissue is collodionized before applying it to the glass, it is a little extra trouble, but this is always repaid in quality. To do this, the piece of tissue must be at least a quarter of an inch larger on all sides than the negative, and after printing this edge is turned up, and the tissue fastened to a flat piece of wood with four pins, one corner of the tissue overhanging the wood. Some enamel collodion is poured into the flat dish thus formed, and after tilting it so that it will flow all over, is poured out again and the tissue stood up to dry, which it will do in a few minutes. This must be done in very weak daylight or by artificial light, not too near a naked flame, as the ether in collodion is very inflammable. When the coating is dry, the print is immersed in water and transferred to the glass just as to a piece of transfer paper. The squeegeeing must on no account be violent or the transparency may be marked. Undue pressure in the printing-frame may also cause marks, especially if the tissue when in the printing-frame is at all limp. If the carbon transparencies are to be used for enlarging, these marks are comparatively unimportant, as even in very bad cases they may be quite invisible on the enlargement, but when the transparencies are to be viewed direct, they must be avoided.

A good many amateur photographers seem to shun the carbon process because of a mistaken impression as to its difficulty. This is due in a great measure to the unfamiliarity of the processes by which a carbon print is made, differing so very greatly from those of other printing methods. When they do not allow themselves to be daunted by imaginary obstacles and plunge boldly in, they are surprised at the ease with which carbon prints can be made, and particularly at the absence of mysterious defects. There is very little that can go wrong in a carbon print, and if anything does help to make it what it should not be, the cause is generally easily detected, and precaution taken against it in the future. The sensitizing bath must not be too strong, nor must it be too warm. In very hot weather it may be necessary to put a lump of ice in it to prevent the soft gelatine of which the coating on the tissue is composed, from actually dissolving in the solution. Such a precaution is very rarely needed. The point where there is most often error is in selecting the wrong moment for

taking tissue and transfer paper together out of the bath for squeegeeing into contact. We had written that "is where there is most risk of error," but really there is none. The tissue curls up, and then commences to uncurl, and the first unmistakable sign of that uncurling is the indication that the moment has arrived. If the tissue neither curls nor uncurls, it is too damp altogether to use, and should have been dried more thoroughly. If it has become insoluble in warm water, it will not adhere at all; but then, as if it did it could not be developed, this is hardly a defect, but a virtue, saving transfer paper, tissue, and temper. If it has not been properly squeegeed, the finished print may show tiny bright specks on its surface, where little air-bells have prevented perfect contact between the tissue and its final support. Before immersing transfer paper in the water, it will be found helpful to scribble in pencil on the back, to show that it is the back. Otherwise on coming to use it when wet, it may not be possible to tell back from front.

One word of caution may be added before we leave the subject of carbon, and that is with reference to what is called the bichromate disease. Bichromate, although it is not scheduled in Parliament as a poison, is so regardless of that august body as to be fatal to any person who attempts to use it as food, even in very small quantities. Still, in this respect it is no worse than most of the chemicals used in photography. It is, however, particularly injurious if it can find a cut by which it may enter the system, and those who are constantly using it are liable to skin trouble of a serious kind in consequence of its absorption by the pores. Used in a small way, as is the case with amateur carbon workers, it is quite harmless, provided there are no cuts on the hands, and provided also that a reasonable degree of cleanliness is maintained, the nails being brushed with soap and water after the fingers have been immersed in bichromate solutions for any time.

One of the most curious characteristics of the carbon process is the property which a printed piece of tissue possesses of transferring its image to an unexposed piece of tissue, with which it has been kept in contact for a little time. This property was the basis of two processes entitled "Mariotype," from M. Marion, who introduced them over thirty years ago; they have long since been obsolete. Although differing very

widely from Mariotype, Mr. Manly's "Ozotype" seems to take advantage of some similar phenomena; but although its practice is simple enough, opinions are divided as to the nature of the chemical change underlying ozotype.

In ozotype, well-sized paper, is sensitized by the application of a solution containing both potassium bichromate and a manganous salt, and when dry this paper is printed under a negative in the usual way, the result being a visible but faint image. As soon as possible after printing the paper is washed in several changes, or in running water, until its imprinted edges are quite white, when it may be allowed to dry. In this condition it may be kept for a long time, many months in fact, although it gradually alters. The final stages of making the print can therefore be deferred at will. They consist of the immersion of a piece of insensitive carbon tissue in a solution which contains copper sulphate, hydrokinone, and acetic acid, and when the tissue is limp, the immersion of the print also, which is placed with its face in contact with the tissue, the two being then withdrawn, and squeezed into contact. After the lapse of a certain time, during which the image on the print is acting on the pigmented gelatine of the tissue, the two are placed in warm water, the backing paper is stripped off, and the "carbon" image developed on the surface of the original print.

As the process is a patented one, there is no need to go into its manipulations at any length. It is claimed for it that while there is all the range of colour and surface and the permanence of a carbon print, ozotype has the additional advantages of a visible image as a guide in printing, of no second transfer to avoid reversal as regards right and left, and of no need of a safe edge. On the other hand, the process is distinctly more complicated, and there seems to be no doubt that in the great majority of cases there is a decided loss of definition, although this is not of necessity a drawback. In spite of its ingenuity, it has never become a popular process in any sense of the word, though its inventor, Mr. Thomas Manly, has striven hard to make it so.

The most notable modification of "carbon," and one which, as an amateur's method, is certainly growing in popularity, is gum-bichromate, called affectionately by its adherents and

derisively by its opponents "bi-gum." It is supposed by some to be incapable of rendering detail, by others to be inseparable from a coarse granularity, which has been compared to cocoanut matting ; but these characteristics are by no means inherent in it, however they may be in the results of some of those who use it. The pictures of some of its most skilful practitioners, such as Mr. Cruwys Richards, M. Demachy, and Mr. Mummery, to name but three, reveal none of this texture, and in their way are often indistinguishable from platinotypes, except by the power of control over the result which the producer has been able to exercise. Perhaps we cannot do better than let Mr. Mummery, who has identified himself with the process as its most successful British exponent, tell of it in his own words :—

"Of all the printing methods at the disposal of photographers," he wrote to the author recently, "that known as gum bichromate is essentially the process of the amateur ; of the individual who works for the love of the work. Its capacity for responding to the personal feelings of the worker, and its flexibility in his hands, are at once the charm and the difficulty of the process. The charm is felt as the worker is led to a new and extended view of photography and its possibilities as a pictorial art ; and although the chemical reactions are just as uncompromising as in any other process, if a little less certain, and all the old methods of printing by combination, masking, shading, etc., may be employed, yet there comes a point when the gum worker makes a new departure of his own.

"In most of our processes, when the print is ready for development or toning, its fate as a picture is already decided—the previous labours have been satisfactorily performed or they have failed, the developer merely confirms this ; but in the case of gum printing the development becomes the opening of fresh opportunities for direct selection and modification. It is at this period that the personal factor becomes paramount, and the print, now visible and right-handed, may be considered in its artistic aspects, and treatment adopted to suit the requirements of each particular case.

"It may be thought the labouring of this point in the

practice of the process is unnecessary, but in reality the preparation for this after treatment is the key to success, and must be borne in mind from the beginning. The mere manufacture of a print in gum without taking advantage of its special characteristics, in most cases, will only yield a result which can be better and more easily obtained by other processes, and will cause disappointment to the producer. The personal control to be exercised is purely a matter of taste, and cannot be described by formula, but must be left to be dealt with as the cases arise ; and the necessities and aims of each worker, if seriously followed, may be trusted to develop a suitable technique. All the formulæ and methods described are open to wide modifications, and should be considered as standards from which departures may be made.

"Bichromate salts in the presence of a colloid substance (gum, gelatine, etc.) are sensitive to light. Not only is a visible image formed, but the parts more or less affected by light are rendered more or less insoluble in water ; and beyond this, again, the film will absorb water, and swell in an inverse proportion to its exposure. This swelling and the formation of a raised and sunk image is an excellent guide to the condition at the time of development. In the early days of photography much effort was directed to the working out of a satisfactory printing process on these lines, and Mr. Pouncy, of Dorchester, discovered that by the use of gum as the colloid, mixing it with pigment, he could obtain a satisfactory image on paper. He published the particulars in 1858, under the name of 'Pouncy's Carbon Process.' His method, however, was obscured by the further perfection of what is now known as the carbon process, and it was not until 1894 that it was seriously revived and further developed by the application of after work ; and, later, by the use of multiple printing.

"The practice may be divided broadly into two methods, commonly known as 'multiple printing,' where the picture is built up by two or more coatings and exposures ; and 'single printing,' where the full effect is attained by one coating. Each has its own special qualities. The single printing yields freshness, brilliancy, and spontaneity ; multiple coating, the opportunity for correction of the values—greater finish, the use of various colours, and ease of manipulation in large sizes. The

procedure in both methods is very similar, but to prevent confusion, it may be convenient first to describe multiple printing, and afterwards to point out the difference in the single method. The materials and apparatus are few and simple, and the description will be limited to those not usually found in the photographer's outfit.

"A very wide choice is open in the selection of a paper. Almost any surface, weight, colour, and quality are available, so long as the sample is well sized; but if an absorbent paper is employed it may be necessary to give it one or two coats of size, in order that the pigment may be retained upon the surface without sinking into the texture and degrading the high lights. With a hard sized paper this is not likely to occur unless the solution of gum is very weak or in bad condition. Either of the following preparations may be brushed over the surface to size it if required:—

3% to 5% of gelatine in water, with five drops of formaline to the ounce, or  $\frac{1}{2}$  oz. of Bermuda arrowroot to 16 ozs. of water mixed cold, boiled until it thickens, and allowed to cool before use.

"Such papers as Whatman's, the old water-colour paper, and the Arts Company's hand-made and machine-made drawing papers, Joynson, Michallet, and many cartridge and letter papers are not likely to require any additional sizing. Another point to be kept in view is the capacity of the paper for returning to its original dimensions after prolonged wetting, as failure to do this will affect the registration in after coatings.

"For the gum solution ordinary gum arabic in tears and free from adulterants is quite as good as the selected colourless gums. The solution may be prepared by placing, say, 2 ozs. of gum in the centre of a piece of clean linen, with the margins tied up in the form of a bag. The whole is suspended in 6 ozs. of cold water, contained in a wide-mouthed bottle. The gum will dissolve out in about two days, when the bag containing the refuse may be thrown away, and the gum is ready for use. The solution should be kept well corked: it will gradually become acid; but this is no defect so long as it does not proceed so far as to render the solution thin and watery. The proportions given yield a 33 per cent. solution, which is about the weakest gum it is desirable to employ. It will be found



SNOW  
IN THE TIME BY





easier to lay evenly than a more viscid solution, but will require at least two coatings to get transparency in the shadows. The strength may be increased to anything up to 50 per cent., and richer darks will result ; but the beginner, at least, may find a difficulty in laying the coating as thin as it is desirable.

"The bichromate solution may be simply a saturated solution of potassium bichromate. The amount of the salt in the coating affects the rapidity of printing very materially ; the solution should, therefore, be kept in a warm place and fully saturated. Ammonium bichromate may be used if preferred. It is more soluble and quicker in printing, but harder and more refractory in development ; it is, however, useful if a fractional method of development is adopted.

"The pigments employed may be obtained from an artist's colourman, in the form of powder colours or moist colours in tubes or pans. The former can be bought by the ounce, and will require a short grinding with the gum to obtain an intimate mixture ; they are thus more troublesome to mix, but are more easily measured, than moist colours. Such colours as lamp and ivory black, light red, burnt sienna, the browns, and many others are suitable ; but the browns will work more readily if compounded of black and red or burnt sienna. For moist colours Schoenfield's *Tempera* colours and the *Syntonos* colours are less costly than ordinary colours, and will work excellently.

"An ordinary camel or bear hair mop is required for laying on the coating, one in which the quill holder is about  $\frac{3}{4}$  inch in diameter will be found a suitable size ; and a 4-inch hoghair grainer's softener will serve for smoothing the coating and removing inequalities, also some small camel hair and sable brushes for working upon the face of the print. Other accessories are : a small drawing board upon which to coat the paper, drawing pins, a piece of ground glass as a grinding slab, and a small glass muller, dishes, graduates, saucers, a palette knife or thin cheese knife, an actinometer for printing, and some muslin for filtering.




FIG. 19.

"To prepare the mixture for coating, we may take, say, 54 grains of ivory black in powder, 1 oz. of the 33 per cent. gum solution, and 1 oz. of bichromate solution. This will give an extremely thin coating of a warm black. Should lamp-black be substituted, 18 grains would give an equivalent depth of colour, but in the case of colours of lighter hue more pigment would be required. Placing the powder colour upon the glass slab, a portion of the gum is poured on to it, and with the knife the whole is mixed to a paste, and is then ground with the muller for two or three minutes to secure an intimate mixture. Having done this we can lift the mixture from the slab to a saucer by means of the knife, and, adding the remainder of the gum, stir the whole well with the mop brush (which should have been soaked to swell the hair). The bichromate solution is added, and the mixture is again stirred, and is then transferred to a measuring glass. From this it may be filtered through one or two thicknesses of muslin into a second glass, and poured into a clean saucer. It should now be limpid, free from dust, and ready for use. If moist-tube colours are used, the grinding and filtering are not necessary.


"To coat the paper, a sheet of absorbent paper (newspaper will answer the purpose) is placed on the drawing board, and upon this again the paper to be coated is placed, the whole being secured with four pins at the corners. Then, taking the mop brush, and stirring the mixture well, wiping out the surplus liquid against the edge of the saucer, we can proceed to paint over the paper with long horizontal strokes, dipping as required, and using as little of the mixture as possible. As soon as the horizontal strokes are completed, we can go over the surface with a series of vertical strokes, without adding any more of the mixture. Then, taking the softener and holding it quite vertically, with only the ends of the hairs touching the surface, a series of horizontal and vertical strokes must be given until the coating lies quite even. The small ridges left by the hairs will disappear as the coating dries. The whole operation should be done in from 40 to 50 seconds, as the coating rapidly hardens, and must not be dragged. It is essential to keep the mixture in the saucer well stirred, and to take up as little as possible upon the brush.

"The coating will harden in about half an hour ; it should

then be thoroughly dried in a very warm room, or over the plate rack of a kitchener when the fire is low, and if placed forthwith in a calcium tube will remain unhurt for some weeks, although it is always better if used fresh. The surface of the coated paper should be slightly glossy, and, if unexposed and fresh, should lose the whole of its coating if soaked in water for thirty minutes. The brushes must be carefully washed after coating, as if allowed to harden they will be spoiled. The paper is not sensitive to light till dry. After printing, developing, and drying, additional coatings may be laid over the image in a similar manner, and local coatings may be applied to small spaces only if such are required.

"The negative best suited to the process is one which is thin, clean, justly exposed, and without violent contrasts. The printing may be performed in an ordinary pressure frame; but for multiple printing some contrivance must be devised for replacing the negative and print in exact register for further printing. This may be achieved by printing upon a drawing

board, upon which the paper is laid face upwards, and upon this the negative film downwards, an ink line being drawn on the paper round the edge of the negative with



PLAN.



DETAIL SECTION.

FIG. 1

a ruling pen. Or a simpler method may be adopted, by screwing wooden fillets to the face of the board along two adjoining edges at right angles to each—say, at the top and left-hand edges. The paper is then pushed up into contact with the top fillet, and slid along until it touches the fillet on the left; the negative is then treated in a similar manner, and a piece of plate glass laid over the whole will keep all in position. By this arrangement the paper and negative may be removed and replaced in exact register as often as required; and if two

strips of card, cut with parallel sides, are introduced between the edges of the negative and the fillets, as shown in Fig. 20, the print will be brought away from the edge of the paper, which is desirable, as the edges are usually somewhat imperfectly coated.

"The exposure for paper prepared as described will be considerably less than for P.O.P.; and, as a rough guide, a piece of P.O.P. may be exposed under the negative until it looks correct in the frame. The exposure given to this, measured by tints upon the actinometer, will give an approximate exposure for a spray development.

"A thick coating, or a coating with more pigment in its composition, will require longer exposure. The visible image being too feeble and indistinct to act as a guide to exposure, the actinometer must be relied upon, and the utmost care taken to avoid over-exposure, which gives a dull and lifeless image. Printing must not in any case be done in direct sunlight, and when exposure is completed the paper must be kept perfectly dry until development.

"There are a variety of methods available for development, each yielding its own particular effect. The simplest is perhaps an automatic development, followed by after work, which may be practised as follows:—

"The print is placed face upwards in a dish of cold water until it is seen that no air-bells adhere; it is then turned gently over, face downwards, when, if the paper is in good condition, and the exposure has been well timed, the superfluous gum and pigment will gradually fall away, leaving the picture visible. It may now be taken from the water and placed face upwards upon a sheet of glass; and the pigment further washed away from large areas by pouring water very gently upon the glass margin, directing its flow over the portions of the print it is desired to lighten. By the use of a small sponge charged with water, and held in the hand just above the surface, drop by drop may be squeezed out over isolated portions and development so continued, keeping a cushion of water upon the surface of the print to soften the effect of the drops. When the most obvious local modifications have been made by these means, the print may be returned to the water until the general development has proceeded far enough.



A ROAD IN THE FENS, LOOKING SOUTH.



"If the paper is not fresh, or is over-exposed, the print may refuse to develop as far as required ; in this case resort may be had to water at a higher temperature, or even in refractory cases to the addition to each pint of hot water of a small piece of caustic soda of the size of a pea, but this should not be necessary. When the print has washed away to its proper strength it may be taken from the water, laid upon a sheet of glass, and stood up vertically to dry. This it will do without much loss of brilliancy if the exposure has been correct, and as the gum tends to get dry and firm, high lights, which show the white of the paper, may be picked out with a sable brush, and the drying completed in the dark. When dry, the print may be moistened in water and worked upon to any extent with brushes and stumps, modifying not only small details, but broad areas if required. This method requires much delicacy, and perhaps is better suited to single than multiple printing ; the gauge of correct exposure is, that the print dries without running and without losing brilliancy.

"A simpler and less perfect method of development is by a fine rose connected by a rubber tube to a water tap, the spray being directed over the face of the print. Here a longer exposure will be necessary, and the print should only be just wetted before commencing to spray.

"A method of giving either a delicate or drastic development at will is by the use of an ordinary spray diffuser, as used for fixing drawings. It is inserted in a cork and used with a bottle of cold water, the print being arranged on a sheet of glass in a vertical position. The spray, consisting of fine particles of water, is blown upon the face of the print,

and varies in strength with the power employed and the distance of the nozzle from the surface. In small sizes the spray may be




FIG. 22.



operated by the mouth, but more convenience is obtained by the use of 'Fletcher's Bellows' (No. 3 being a suitable size); this is connected to the spray by a  $\frac{1}{4}$ -inch rubber tube, and worked by the foot. The exposure here must be nicely adjusted to the spray, and will be slightly longer than for the automatic method described; the print should not soak for more than one quarter to a half minute before being subjected to the spray. If under-exposed the pigment will be washed away, and if over-exposed further soaking must be resorted to; in either case the result is defective.

"Development by the direct application of brushes or cotton wool whilst the print is in the water is possible, but is open to the objection that the exposure required for such rough handling is necessarily long, and the quality of the print suffers thereby.

"The print should always be stood up to dry vertically upon a sheet of glass, and not laid flat; and the perfection of richness is obtained when the print is in such a condition that it will only just dry without further running. This condition is purely a matter of correct exposure.

"After any of these methods of development the print may be dried in the dark and afterwards wetted and again worked upon, and specks of dust may be lifted from the print during development by means of a fine-pointed sable brush.

"When the first coating and printing has been completed the print may again be coated, and the whole process gone through as before for the purpose of strengthening the picture generally or in parts, obtaining greater or less contrast, or giving transparency, etc. The illustrations show the appearance of a picture as developed by the spray diffuser after the first and second printings respectively, and although they hardly show the extent to which modification has been effected, they at least indicate how the image is built up, and how the effects of solidity and distance may be obtained.

"The yellow bichromate stain, if present, may be removed at any time by soaking the print in a 5 per cent. solution of potash alum or sodium bisulphite, and afterwards rinsing it; but this treatment is best left until the final printing is completed, as it will cause a slight contraction of the paper.

"It will be seen that in multiple printing there is





opportunity for many modifications. For instance, with a dense negative a thin coating may be first applied and exposed very fully to obtain the image from the densest parts of the negative, and afterwards a thicker and darker coating with shorter exposure may be given for rendering the thinner portions. Or it may be desirable to give a coating with little or no pigment, to give a richness to the print; or, again, the field is open for printing in two or more colours and for many other variations which will suggest themselves to the worker.

"The description I have just given will apply also to single coating, but as the final strength is to be obtained in one operation the following modifications are desirable: The solution of gum should be 45 to 50 per cent., preferably the latter, and with this 60 to 66 grains of ivory black, or 20 to 23 grains of lamp-black to the ounce of gum solution should be added. The additional thickness of the gum will render the coating somewhat difficult, and care must be taken to lay it as thinly and quickly as possible. The exposure with the thicker coating may be somewhat longer.

"In development, although it is possible to use the spray, the automatic method followed by after work is par excellence that for single coating. To obtain the richest and most perfect single prints the paper must be quite fresh, say not more than two or three days old. The negative must hold the correct range of tones for the paper, and the exposure must be quite correct."

Thus far Mr. Mummery, and there is little or nothing to add to his account of a process at which he has shown himself an adept. The growth in the popularity of "bi-gum" has led to ready-coated papers being put on the market. The treatment of these differs to some extent from that of home-coated papers, as their coating is necessarily harder; and caustic soda is generally recommended to help development. The kindred processes of oil printing and of bromoil are more conveniently considered with collotype (p. 390). The ozotype process has been modified by the brother of its inventor to apply to gum bichromate.

## CHAPTER XVII

### BROMIDE PAPERS

Machine-printed bromides—Qualities of paper—Exposing—Gauging exposures—Development—Lighting the dark room—Developer formulæ—Washing—Carbograph—Gaslight papers—Toning—Hypo-alum—The Blake-Smith process—Intensifying bromide prints—Ferguson's copper toning—Uranium toning—Blue tones—Ozobrome.

**T**HE printing methods that have been considered so far have all been such that daylight was necessary, or at least was almost a necessity for printing. There remains one and only one which may be carried out by means of ordinary forms of artificial light, and this is merely a modification of the process used in negative making.

It is to Swan that we owe the idea of applying the dry-plate emulsion to paper on which a positive print could be developed; and in his bromide paper patent, he not only contemplated this, but also the use of machinery by which a band of such paper could be impressed with a series of prints from the same negative, developed, washed, and dried. At the time of his patent, long since expired, this was little more than a possibility, as the developers then known, although they could be used to give very fine prints, did not lend themselves to use in a machine, because of the necessity of an acid bath which they entailed. Nowadays, with modern developers many such machines are in successful operation, and editions of thousands of bromide prints have been made in them for book illustrations, while the little photographs which are inserted in packets of cheap cigarettes are printed in this way, not in thousands, but in millions. In these machines the paper is led in a long band under the negative, where it is held for an instant while exposure is made to an electric light, and then passes along through a succession of tanks holding developer, a fixing bath, and water, finally emerging in a state requiring

nothing beyond drying and cutting up. Such machines are in use by Messrs. Wellington and Ward, the Rotary Photographic Company, and others, and have considerable commercial importance; and a simple device on similar lines for making a number of prints quickly has been brought out by Messrs. Marion and Co. But all of these are more for the manufacturer and professional than for the amateur, whose printing apparatus need not exceed the plain printing-frame and the usual dishes and solutions.

There are two distinct classes of such paper, which for convenience are usually known as "Bromide" and "Gaslight" paper respectively; but it must not be supposed that either term is necessarily descriptive and accurate. It is commonly believed that gaslight papers contain not only silver bromide, but silver iodide and chloride also. This is by no means a hard-and-fast rule; but whatever their composition, the terms are convenient and are generally understood. Bromide paper can be made as sensitive as the fastest plate, but nothing would be gained by such rapidity, and much comfort in working would be lost; so that the fastest bromide paper on the market to-day is certainly not more rapid than a very slow plate indeed, while the slowest gaslight paper is a long way behind even that standard of sensitiveness. Gaslight papers, as their name implies, are sufficiently insensitive to be worked in gaslight. It should never be forgotten, though, that their insensitiveness is not absolute, but only a question of degree, and that if they can be developed by gaslight, they can also be printed by it, and therefore fogged by it. A simple plan to prevent any risk of this sort, is to erect a screen—a drawing-board will do—between the light and the dishes in which the print is developed, filling the frames and developing and fixing the prints in the shadow of the board.

In printing on bromide paper by contact, and still more when printing in the same way on an ordinary dry plate, the photographer is surprised at the extreme shortness of the exposure. He is accustomed to exposures in the camera of a second or so to daylight, and knows that with artificial light these have to be enormously prolonged; he may lose sight for the moment of the difference between letting the light enter his camera by a small hole at the lens, and be spread over an area many times the size of that hole, and the same light

striking straight through a negative to the plate. Over-exposure is, therefore, the tendency at first. If an average negative is put in a printing frame, a rapid plate put behind it, and the frame held up to a gas-burner at a distance of say 2 feet, it will not be possible to turn that burner up and down quick enough to avoid over-exposure, and the frame would have to be moved a good deal further away. Bromide paper is nothing like so fast as the plate, but at 3 feet from an ordinary gas-burner the exposure is only a matter of a few seconds. Gaslight paper at the same place might want anything up to an hour or more, and is therefore printed at a much shorter distance.

As on bromide paper there is no image visible until it is developed, there is no need for the printing frame to have a hinged back, while as the exposure is so short, one frame is all that is necessary. With gaslight papers exposures run to minutes, and it is often possible and indeed convenient to have a number of frames exposing at once. While we cannot see the progress of printing, we are able to gauge it with great accuracy, because, doing it by a constant artificial light, we need only take care that the frame is the same distance from the light every time, and is exposed for the same number of seconds. The gas-flame is the usual light, and if always turned up just short of the point at which it "roars" it is reasonably constant, although occasionally it may vary enough to upset one's calculations. No attempt should ever be made to vary exposure by varying the height to which the gas or lamp is turned up, as it is quite impossible to regulate this properly, and to repeat any given exposure obtained in this way. The light should be burning at its best always, and exposure determined by the distance of the frame.

Those who do much bromide printing by gaslight will find it worth while fixing what is termed a Methven screen on the gas-flame. This is a piece of metal—thin sheet-iron will do—3 or 4 inches each way, in whose centre is cut a square hole, with a side, in this case, half an inch long. This is fixed half an inch in front of the flame, so that, viewing the light from any part of the printing frame, nothing but an even yellow flame can be seen through the hole. In this way we cut off much of the irregularity in the power of the gaslight due to uneven pressure, and exposures are much more uniform.

With such a screen it is even comparatively unimportant whether the gas is turned fully on or not, provided the jet is always big enough for the aperture in the screen to be opposite a plain bright flame all over. Gas pressure is most likely to be a source of error in foggy weather and on Sunday evenings, when, as a rule, it is much lower than at ordinary times. The screen may be used with equal advantage on a "paraffin" lamp.

Incandescent gas is much more powerful than is needed for bromide work, but is an excellent light for gaslight printing ; but then, as all available light is required, it is not advisable to reduce its power by the use of the screen. This paper is also printed very conveniently by the use of magnesium ribbon, the exposure being regulated by measuring the length of ribbon to be burnt. A small spirit-lamp is useful for lighting the ribbon, which should be held in pliers to prevent burning the fingers.

The distance from the light at which the printing frame should be placed is very important. The exposure increases with the square of the distance, so that at 2 feet we have to give four times as long as at one foot, at 3 feet nine times, at 4 feet sixteen times, and so on. The most convenient distance for bromide paper is generally 2 or 3 feet, and an appliance may be made to carry the printing frame at that fixed distance from the light. The writer uses a hook on the edge of a shelf, the frame having an eye screwed to it so that it can be hung on the hook, which is 22 inches from the gas-jet. If no special arrangement is provided to carry the frame, this latter may have a wooden arm of suitable length screwed to it and projecting in front. The end of the arm is then placed against a prearranged portion of the lamp or gas bracket, and the distance of the frame is then always the same. Or a piece of string may have one end tied to the bracket, the other end being held in the hand which holds the frame. Gaslight papers are generally printed much nearer to the light, to reduce the time of exposure. For quarter-plates or thereabouts, 6 inches is a convenient distance ; but the larger the negative the greater the distance to which it must be removed, if uneven exposure is to be prevented. As a guide, we may point out that little irregularity from this cause will be noticed if the frame is always separated from the light by a distance at least as great as the diagonal of the plate.

The thinner the negative the feebler should be the light in



which it is printed, which is best accomplished by moving the frame further away. Green glass placed over the printing frame has much the same effect in increasing contrasts as it has in printing-out processes. If the glass of the negative is imperfect or marked in any way, it may be that printing at some distance from a comparatively small source of light these blemishes will appear on the print. A sheet of ground glass or tissue paper prevents this by diffusing the light, but upsets calculations about exposure. It is better, then, to hold the negative, moving it about and turning it round, but always at the same distance from the light.

The character of negative required by bromide and gaslight papers varies. Speaking generally, a stronger negative is wanted by bromide than by gaslight paper, which latter seems to work best with a negative that is too thin for any other printing process whatever. But different makes differ in their characteristics in this respect, and some of the papers are specially made for printing from hard or from soft negatives. The faster the bromide paper the harder may be the negative used successfully with it; but this, too, is only a vague generalization, and must not be pushed too far. There is no such vast difference between the speed of the different so-called "bromide" papers as there is between plates. The Kodak Company make two speeds—one about four times as fast as the other, and most well-known makes are approximately the speed of one or other of these two brands. The fast papers include Wellington, Morgan and Kidd, Ilford "Rapid," and the "Rotograph;" while the best-known slower ones are Marion's, the "Barnet," Ilford "Slow," and the Paget paper. The "gaslight" papers are, of course, far below the slowest of these in speed.

There is a little appliance made by Marion and Co. which is very convenient for bromide printing, and is shown in the illustration (Fig. 22). Its purpose can be seen at a glance. A negative being inserted in it, with a piece of bromide paper behind, the back—it is like a printing frame exactly—is fastened in. The wooden shutters being withdrawn, the frame is exposed at the proper distance from the light, and the shutters pushed in in succession. If a plate is to be tested for negative work, the exposures need never differ by less than double or one-half that of the next each way. That is to say,

if four seconds' exposure is correct, neither three nor six can be noticeably incorrect; and, in fact, it is hardly possible to detect the difference in exposure represented by three and four seconds, or by four and six seconds, and the difference between three and six will only just be noticeable. Photographers who have never given much thought to this subject almost invariably vastly overrate the effect of such differences, and we have even heard two skilful workers discussing whether a certain subject should have eight or ten seconds; whereas if they had given two similar plates those two exposures and developed them together, it is certain that they could not pick out which had the longer exposure from the prints, and very doubtful if they could do so from the negatives. If they did, it would be by taking into consideration appearances that were quite without any printing value. Accordingly, in negative work, we double or halve exposures at the least. If two seconds is insufficient, we know that four cannot possibly be too much; and if thirty seconds is more than is needed, we may be equally confident that fifteen is not too little. In printing on bromide paper this is not the case, and exposure must be more accurately timed, as slight deposit, which on a negative would be quite invisible viewed by transmitted light, is enough on a print to degrade the whites and make it look—as, indeed, it would be—overprinted. In using Marion's "speed-testing frame," therefore, with bromide paper, we use shorter intervals than half or double. As it is not simple to determine the exact geometrical mean between the exposures, it is best to let every other exposure be double, and to close the shutter for the intervening ones halfway between the two. Thus, if we suspected that sixteen seconds was the correct exposure, we might shut the six shutters thus—




FIG. 22.—MARION'S PRINT-TESTING FRAME.

No. 1	...	...	...	...	...	6 seconds.
No. 2	...	...	...	...	...	8 "
No. 3	...	...	...	...	...	12 "
No. 4	...	...	...	...	...	16 "
No. 5	...	...	...	...	...	24 "
No. 6	...	...	...	...	...	32 "

On development of the print so exposed, we might find that an examination of it was sufficient to show that twelve seconds was a little short and sixteen a little too long, and give fourteen accordingly.

There is no need to use the "speed-testing frame" for every negative by any means ; but it is useful in taking up a new make of bromide paper, or in dealing with a negative that is much out of the common in point of density, or when bromide printing has been put on one side for some time, and is unfamiliar. It is, of course, equally useful with "gaslight" papers, and, in fact, is a little appliance which will save its cost in no time. It is impossible to urge too strongly, if there is any doubt at all about exposure, the economy of deliberately using a piece of paper for such a series of trials. The wastefulness of making a print which, if wrong, only gives a very vague clue as to the correct exposure, and may have to be repeated five or six times before getting it right, is only apparent when this has actually been done.

Bromide paper can be developed in a bright yellow light ; but as there is yellow and yellow, and as some of the yellow glass on the market lets pass a great deal of light to which rapid bromide paper is sensitive, a trial should be made before placing implicit reliance upon the dark-room window. It is sufficient if a piece of bromide paper is placed in a dish where development is usually carried out, and half of it shaded by a card, which ought not to be quite in contact with it, as the card itself may affect the paper if it is not quite pure. After leaving the paper exposed like this to the yellow light for two minutes, it should be developed, keeping the dish covered all the time, and should show no difference between the exposed and unexposed portions. A light that is safe for plates is *a fortiori* absolutely safe for bromide papers, and may be used by those who do not mind its obscurity. But the comfort of working in a profusion of safe yellow light has only to be experienced to be adopted.

The development of these papers calls for little comment. It is usual to soak the bromide paper in water first, as this makes it possible to develop with a smaller quantity of solution, and as the developers used for bromide paper generally act very quickly, it reduces the chances of uneven development ; but it is not otherwise a necessity. Gaslight papers give the





best print when the development is very rapid, and it is therefore customary to place them in the developer while still dry. The developer employed for these papers is, for the same reason, much stronger than that which can be used successfully with bromide papers. With both papers the development must be complete and definite if the print is to be a good one; any attempt to curtail development to keep the print light, or to push it on to remedy under-printing, or to restrain it with bromide to counteract excessive exposure, results in loss of quality.

The developed image in a print has not only to be of the right depth or vigour, as it has to be in a negative, but another condition is imposed which does not obtain in negative-making—the image must be of a pure black colour. This is not the case if the developer has been unduly diluted, while the presence of more than a trace of bromide causes the picture to be a most unpleasant greenish tint. For this reason the same developer must not be used over and over again too often, since the result of its action on the paper is to produce bromide in the solution. At the same time, as it is convenient to use plenty of solution in order to be able to cover the paper quickly, and as the coating of emulsion on bromide paper is much thinner than on a plate, the developer is not so quickly exhausted, and may be used until there is any sign of the production of a poor colour.

If the development of a properly exposed print is watched, it will be noticed that after the image has reached the proper degree of vigour the action of the developer seems almost to cease. If the print is then torn in half, and one half fixed, while development of the other half is continued for nearly as long again, and it is then fixed also, we shall see, on comparing the two, that there is very little difference between them. That portion which was developed for the longer time will be very slightly darker, and possibly discoloured a trifle in the high lights, but although developed for twice as long, it will not be twice as vigorous. The action, in short, has proceeded to a certain point and then virtually ceased, and experience will soon teach the bromide printer, if he will not learn it by precept, that it is only when the paper is correctly exposed and development is carried to that stage, that he can expect to get the best the process will yield. This is particularly the case with prints that are subsequently to be toned. With gaslight papers the stoppage of development is less marked, and the

discoloration of the whites by prolonged action is more noticeable, but it occurs all the same, and complete development is just as necessary if a good rich print is to be obtained. Much of the disfavour with which the bromide process was once regarded was due to the production of poor prints from insufficient development.

Formulae for the development of bromide and gaslight papers are legion. Every packet sold contains particulars of the solution which the maker finds best suited to his own papers. In the early days of bromide printing ferrous oxalate used to be employed for the purpose, but it was necessary to wash the prints in dilute acid immediately after development, to get rid of the iron salts, and then to wash out the acid before they could be fixed; so the ferrous oxalate developer was soon supplanted by others which did not entail so much trouble, although, as far as the quality of the print is concerned, it has never had a superior. 'Amidol' is that which is now the most popular.

Both bromide and gaslight papers should be rinsed after developing and before fixing. Some makers advise the contrary, in order to safeguard their papers from suspicion owing to the washing being carried on too long; but it is well neither to omit it altogether and so to carry developer into the fixing-bath, nor to take very long about it, especially in the case of gaslight papers, and so involve a risk of discoloration of the whites. A mere 'rinse of three or four seconds' duration will remove a good deal of developer.

The hypo bath may be a plain one of two ounces to the pint, but an acid fixing bath is very much to be preferred, as it is all-important to keep the prints a good colour, and the acid bath helps to ensure this. Methods of preparing it have already been described (page 134); the simplest and most satisfactory is to add two drams of potassium metabisulphite to each pound of hypo. The prints are plunged beneath the surface of the fixing solution, and should be left there for a quarter of an hour. Almost immediately they are immersed, a kind of clearing or brightening of the picture will take place, but this is no indication that it is fixed, and there is nothing to tell when fixing is complete. The only plan is to take care that the fixing bath is a new one, is of the proper strength, and is allowed to act for a sufficient time. It is very important that the prints should be kept well below the surface of the bath while fixing, and also well under water until most of the

hypo has been washed out. If this point is neglected, the action of air and of the hypo together will lead to an irregular reduction of the image and to stains, which are quite without a remedy and spoil the print entirely. As the prints have a tendency to float up, some means should be taken to prevent this. A very simple plan is to immerse them face downwards both in the hypo and in the washing water, and to place a vulcanite dish on the top of them, in which water is poured until it floats so deeply as to keep them well below the surface.

The washing of prints on bromide or gaslight papers is carried out in the same way as that of negatives or of prints on P.O.P. It is important to get rid of the hypo, if the print is to be permanent, but if this is done there is every probability that the result will be much more lasting than in the case of a print on P.O.P. The image in a bromide print consists of metallic silver enclosed in gelatine, while in a P.O.P. print the image is formed of a mixture of compounds of which little definite is known, except that they are very readily attacked by sulphur, which may get to them from traces of hypo, from an impure atmosphere, or from attachment of the print to an impure mount. The author has a bromide print which was made in 1887, and has been hanging up, framed, without any special care ever since, and is to all intents absolutely unaltered.

An ingenious modification of the bromide process is that introduced by the Rotary Photographic Company, and known as "Carbograph." The emulsion contains pigment as well as silver bromide, being in fact a kind of cross between carbon tissue and bromide paper. Enlargements can be made direct upon this, with artificial light, just as on ordinary bromide papers. After development, which must be carried out by time, as on the dark surface of the Carbograph little of the image is visible, the print is placed in a solution which contains potassium bichromate and alum. It is then squeegeed on to transfer paper and developed like a carbon print, the silver image which was first developed being left in or taken out with a suitable reducer at the discretion of the photographer. As a means of making carbon enlargements direct, there would seem to be great possibilities before this process, which gives a wide range of colours, and a guarantee of permanence, as in ordinary carbon work.



Gaslight papers possess the peculiarity that by giving them prolonged exposures and then developing in suitably restrained solutions, the colour of the prints may be modified from black through a series of sepias and browns right up to bright red, and when they were first introduced much stress was laid upon this feature. It is difficult to say precisely why so little is heard of it now, but the fact remains that it has almost entirely gone out of use. Probably the uncertainty of the tone and the necessity for considerable skill in determining when to stop development, and in making a number of prints of the same colour has had much to do with it.

If development to obtain warm colours has to a great extent gone out of fashion, there has been an enormous increase in the popularity of certain toning methods; to such an extent, indeed, that at some exhibitions toned bromide prints or enlargements have formed 80 per cent. of the total number. While there are many ways of changing the colour of a print, in many cases it is only a change for the worse, but the brown tone obtained by the conversion of the silver image into one of silver sulphide is often a great improvement, and it is this toning method which enjoys the greatest favour. Moreover, if the conversion is a complete one, as it may be under proper conditions, there is no reason to suppose that the toned print is any less permanent than a black one, which is certainly not the case when other toning processes (notably those in which uranium is employed) are adopted. The change of the silver into silver sulphide may either be direct or indirect. Both methods are in everyday use; the former is generally known as the hypo-alum process, the latter as the Blake-Smith, from the name of the gentleman who first studied it and introduced several new methods of carrying it out.

A most ingenious process by Mr. T. Manly, the inventor of Ozotype, combines the advantages of bromide and carbon printing, and is known as "Ozobrome." A bromide print or enlargement is soaked for a few minutes in clean cold water, and a sheet of carbon tissue is meanwhile soaked in a patented solution called the pigmenting solution, and supplied by the Ozotype Company. The solution contains, in addition to certain hardening agents, potassium bichromate, potassium bromide, and potassium ferricyanide. The tissue, having absorbed what it will of this solution, is squeezed down upon the bromide print

and left in contact with it for half an hour, more or less. Under these circumstances a curious change takes place. The potassium bromide and ferricyanide attack the image of the bromide print and cause it almost to disappear, just as a mixture of those salts in solution does when applied to the bromide print in the process of sulphur toning. The bye-product of this reaction acts in turn on the bichromate, this in turn rendering the tissue insoluble just where it is in contact with most silver on the bromide print. So that in its effect on the carbon tissue, contact with a bromide print, under these conditions, is equivalent to printing under a negative.

The print on carbon tissue so obtained is developed with warm water in the usual way. It may be left on the bromide print and the two placed together in the warm water, the paper backing of the tissue pulled off and the picture developed on the bromide print itself. A better plan is to separate tissue and bromide print under the surface of cold water, to squeegee the tissue on to a piece of transfer paper and then to develop it, and to wash the bromide print thoroughly in water. It may then have its image brought back to full strength by the application of any ordinary developer for bromide work, and is ready for a repetition of the operation. The only limit to the number of carbon prints that can in this way be obtained from a single bromide—or gaslight print, for that does equally well—is the capacity of the paper to stand the repeated wetting and pulling about. If the Ozobrome is developed on the bromide print, the image beneath may be left as it is, or redeveloped to enforce the print above it, or turned into silver sulphide, as in the Blake-Smith process. Or all traces of it may be removed by means of the ferricyanide and hypo reducer.

Ozobrome presents great advantages to the exhibiting photographer. He can make his large carbon prints by its means, direct in the enlarging lantern, without the intervention of a transparency and enlarged negative. There is much gain in truth of tone in so doing. There is no reversal as in single transfer carbon, the bromide print and the Ozobrome from it being both the same way round. The process calls neither for daylight for printing, nor a dark room for developing; and should prove a serious rival of all other methods for producing the best amateur work.

## CHAPTER XVIII

### ENLARGING, REDUCING, SLIDE MAKING

Enlarging—Illumination of the negative—Diffusers and condensers—The optical arrangements—Daylight—Curing distortion—Exposing on bromide paper—On dry plates—Developing—Slide making—By contact—A lantern-slide printing frame—Slide cameras—Development—For warm tones—Intensifying slides—Clouds—Dodging slides—Mounting and spotting—Masking—The lantern screen—Small displays.

THE growth in popularity of the hand-camera has caused a corresponding increase in favour of methods of getting a large print from a small negative. There are two systems by which this can be accomplished, each having its good and bad features, and each its devotees. One is by enlarging direct upon bromide paper—a method which dispenses with all intermediate stages and by bringing the final large print closer in its connection with the original negative, is capable of as great a degree of accuracy in rendering its tones as in any contact printing method. The other is by making an enlarged negative—a process which is inevitably accompanied by loss of truth of tone, but has the great merit of allowing the final print to be made by contact and consequently by platinum, carbon, gum, or any other method affected by the photographer.

All enlarging is re-photographing, and requires a lens and a camera. True we may enlarge with a lantern in a darkened room, but this is not dispensing with a camera, since the room itself becomes the camera in such a case. And we can substitute a pinhole for the lens, if we have a reasonable anticipation of living to the end of the exposure. The essential fact to grasp is, that it is actually a repetition of the original operation. The subject is the small negative, the lens the lens of the enlarging lantern or camera, the bromide paper corresponds to the plate, and the space between the lens and paper is the camera. The

first important proceeding is to arrange for the illumination of the negative.

This can be done either by diffused light, or by means of a condenser, and the distinction between the two should be clearly understood. If we place a negative as at N (Fig. 23), with a lens at L, and paper at P, and illuminate that negative by a light, I, with the idea of obtaining an enlarged image on P, we shall




FIG. 23.

find that the only part of the negative which is properly lit is that which lies in a direct line between the lamp—that is to say, the centre. The rays from the lamp, as shown in Figure 23, proceed in straight lines in all directions, only a few reaching the lens and thence the paper P. But by placing a lens, C, between the negative and the light, as shown in Fig. 24, the rays may so far have their direction altered that they now




FIG. 24.

all practically meet at L, and the image formed on the paper P shows the whole negative evenly illuminated. Such a lens, C, is called a condenser, and is used in all optical lanterns for projecting slides, the arrangement of which, substituting the slide for the negative N, is precisely that shown in Fig. 24. A condenser is also used in most enlarging lanterns. It must not be supposed that there is any essential optical difference between a condenser and any other lens. The so-called

condensing is precisely the same action as that of any other lens placed in the same position, and is due to the fact that the condenser is forming an image at  $L$  of the light at  $I$ . To make this clearer, any one with a condenser can hold a sheet of paper at its focus at  $L$ , and will see not merely a spot of light, but an actual inverted image of the flame and of the brightly lit parts of the lamp. Consequently,  $I$  and  $L$  are conjugate foci, and the nearer we push the lamp  $I$  to the condenser, the further off will be the point  $L$ , at which the rays of light are brought by it to a focus.

Another fact may be gathered from the preceding paragraph. If the concentrated spot of light at  $L$  is an image of the light itself at  $I$ , the nearer the light is brought to the condenser the larger will be its image at  $L$ , just as the nearer the lens of the camera is to an object the larger is the picture on the screen. Also the larger the light itself is the larger will be its image, if the distances  $IC$  and  $CL$  remain the same. Therefore, if the light is too near the condenser, or if the source of light is too large, it may make a bigger image at  $L$  than the lens itself that is placed there, and all the light will not get through the lens. On the other hand, if the source of light is very small, or its distance from  $C$  is increased, the image at  $L$  may be such a spot of light that it only occupies a small piece in the centre of the lens. It does not often happen that it occupies the whole of the lens at  $L$  when we are enlarging with a condenser, and this has an important bearing on the subject of exposure.

A small stop, we know, improves definition, because, to a certain extent, only the centre of the lens is then used to form the image. If the condenser forms at  $L$  such a small image of the light that it only occupies the centre of the lens, the margins of the lens are not used, and it is possible to insert a smaller stop in the lens at  $L$  without cutting off any of the light that is passed by the lens. Therefore under such circumstances, the insertion of a smaller stop does not necessarily increase the exposure, as it does in ordinary camera work. It may not increase it at all; but if it does, the rule as to the exposure doubling with each stop in succession as we pass from one to the next size smaller, does not hold good. When enlarging with a condenser, therefore, the exposure must be ascertained for the particular stop that is being used, there being no

reliable method of ascertaining the alteration in illumination brought about by a change in the size of the stop.

Further consideration of the diagram (Fig. 24) will explain also how it comes about that the smaller the source of light the finer the definition in the enlargement, until when we come to work with the spot of light of an electric arc lamp we are practically using a small stop in the lens, although actually it may be fully open. The definition, when enlarging with an arc light, is at times so fine as to be troublesome, every speck and blemish in the glass of the negative appearing faithfully and enlarged on the screen.

The adjustment of an enlarging lantern is performed in three stages. First, the lantern is set up with the negative in position and focussed on the screen. The distance of the screen decides the degree of enlargement. When this has been done, the distance of the light from the condenser has to be adjusted, so that the latter brings the image of the light upon the lens L. This cannot be done before, because until we have got the picture the right size and focussed we do not know the final position of L. The negative is therefore taken out of the lantern, and the light adjusted, until a perfectly evenly illuminated disc is seen on the screen at P. This is an indication that the light is in the right position, and the negative may be put back. It is best, then, to focus it again, as it was difficult to do so before the light was right, and the slight further focussing is not likely to disturb the illumination. We are then in a position to expose.

So much for enlarging with a condenser. If we return now to Fig. 23, it will be obvious that if the negative were no larger than that small portion of it which lay in the direct line between the lens L and lamp I, it would be illuminated evenly without a condenser; or, what comes to the same thing, the whole negative N would be evenly illuminated if the source of light were sufficiently large. It is not practicable to get a direct source of light of such a size, but it is easy to get it indirectly. Instead of the condenser C, we may substitute a screen of ground glass, G (Fig. 25). This scatters or diffuses the light passing through it, so that some light from every part of its surface will reach the lens L, although, as it scatters the light indifferently in all directions, only a comparatively small proportion

of that which falls on the ground glass will reach the lens, and not all, as was the case with the condenser. Hence the exposure with such a diffuser will be much longer than with a condenser; still, every part of the negative will be lit, and not merely that which lies in the line between the lens and the light. Instead of the ground glass, a smooth reflector of white




FIG. 25.

paper or card may be used, as shown in plan at R (Fig. 26), the result being much the same, except that the reflector is even less efficient, as far as the strength of the light is concerned, than is the diffuser. With these diffusers, as it is no longer a case of a condenser forming a brightly lit spot in the centre of the lens, the negative behaves exactly as if it were a landscape




FIG. 26.

or portrait that was being photographed, and as the lens L is stopped down, the exposures are increased in the same way as in ordinary photography. With diffusers, therefore, there is no need to ascertain the exposure by trial with the stop actually used for making the enlargement; we may, if we will, use any other stop for the trial, and calculate from it to the exposure

with the stop finally selected. This detailed consideration of the conditions which prevail when enlarging has to be done is necessitated by the fact that the subject receives very little attention as a rule, and even in the treatises put forward professing to deal with enlarging, there have been statements which were altogether inaccurate in these matters.

A condenser is only used when enlarging by means of artificial light. The apparatus generally employed for such a purpose is a lantern, which only differs from the ordinary lantern for showing slides, in the arrangements for holding the negative, and in the greater care that is given to prevent stray light from getting out of the lantern. This ought not to be a difference, as it is quite as important to keep the room dark when showing slides as it is when enlarging. But when enlarging is in hand, the paper is fogged if there is too much stray light, and the photographer knows that all is not as it should be; whereas in showing slides he does not, as a rule, appreciate the value of comparative darkness. Few lantern exhibitions are as they should be in this respect. The general arrangement of an enlarging lantern is shown in Fig. 27, which is one made by Hume of Edinburgh, and can be used with any illuminant that may be selected. In the form illustrated, it is employed with incandescent gas and a Welsbach mantle. Those who have not got a supply of gas can employ a similar light in which the mantle is made incandescent by means of a spirit flame, as in the well-known "sol lamp." Acetylene may be employed, or an oil lamp, or an oxyhydrogen jet, while those who have a supply of current may use the Nernst electric lamp or the arc light. The author prefers a mantle made incandescent with gas or spirit, as it is easy to put up and use, the light does not alter when the lamp is run for some time, and the exposures are neither unmanageably short nor inconveniently long. By placing the enlarging lantern on a table and putting an easel for the bromide paper on the same table,




FIG. 27.



there is not so much risk of movement as when the two stand on separate supports.

The cost of a condenser for larger plates than 5 by 4 is out of proportion to the advantages conferred by its use, while its weight makes it unwieldy, and its thickness very liable to breakage. For larger sizes, therefore, it is usual to employ a diffuser. When the light is artificial, one thickness of ground glass is not sufficient, while a white reflecting surface, although giving a beautifully even illumination, entails so great a loss of light that it is not practicable, except with daylight. There is an exception to this—the form shown in plan in Fig. 28. Two incandescent gas burners are placed at A A,




FIG. 28.

and the curved metal reflector, which is whitened inside, illumines the negative evenly and well. This arrangement is commercially obtainable, enclosed in a light-tight lantern, for use in a darkened room. With ground glass, it is usual to employ two pieces, and,




FIG. 29.

in order to allow them to diffuse the light properly, to separate them from each other and from the negative by a space of at least an inch. It is important also that they shall be larger than the negative they are to illuminate, or its edges will not be properly lit. Fig. 29 shows in plan a simple method of

enlarging with a camera the size of the enlargement, which dispenses with the need for a dark room. It is not so often used for enlarging, but it is a very common arrangement for reducing and making lantern slides, an operation which differs in no way from enlarging, except in the relative sizes of original and copy. L is an ordinary oil lamp or incandescent gas burner ; G G are pieces of ground glass ; N the negative, placed over an aperture in a piece of card or wood, M, in order to prevent light getting round its edges. There is no need, with such an arrangement, to cover in the space between the negative and the camera. If the arrangement is tipped up, so that there is uninterrupted sky behind the negative as seen from the lens, there is no need for the ground glass, and daylight can be used. As in such a case a small stop is often employed in the lens, it is important to make quite sure that the view of the sky is uninterrupted, as buildings, chimneys, and even a strongly marked cloud form, may show in the result. But clouds are not likely to be troublesome.

Many photographers like to use daylight for their enlarging. The simplest method is by means of a fixed focus enlarging camera, which is merely a box or bellows, at one end of which the negative is placed, and at the other end a holder for the bromide paper. Between the two, in such a position that it forms a sharp image on the paper, is fixed a single lens. In the simpler forms, the whole arrangement is carried into the dark room to insert the bromide paper, and then carried out and placed on end so that the negative is exposed to the uninterrupted light of the sky. More elaborate patterns have a dark slide in which the paper can be carried. The best method, however, is to have an opening into the dark room (Fig. 30), which can be closed with the negative itself, or with a frame holding it, and provided outside with a white reflector. The ordinary camera with which the negative was taken may be placed, with its focussing screen removed, on a bench against the negative, and the focussing cloth used to block out any light between the junction of the camera back and negative holder. The enlarged picture is then focussed on the easel. There is no need to get a special lens for enlarging. Any lens that sufficed to take the original negative may be used to enlarge from it up to any size that may be required.

It will be seen that the choice of arrangements is a large one, and must be decided by the conditions and by the character of the work to be done. Fixed focus enlargers and apparatus of the camera type suffer from one limitation, which for some work quite puts them out of court—there is no opportunity of modifying the resulting enlargement by shading or dodging during exposure. With an enlarging lantern, or with such a system as that represented in Fig. 30, this is easily done, the photographer standing beside the enlarged image on the easel, and shading it with as much ease as if he were contact




FIG. 30.

printing, or even more. The different means of effecting such alterations are dealt with in Chapter XX. There is one alteration which may be mentioned more appropriately here: it is the curing of distortion due to the camera used in the first case not having been level. The result is that perpendicular lines in the original, in the photograph converge towards the top. If such a negative be placed in the enlarging lantern, and the easel on which the image is focussed is swung so that it is no longer vertical, but that part of it which is receiving the part of the image where the vertical lines are closer together is tilted away from the lens, that part of the picture will be rendered on a bigger scale, and if it is done sufficiently, the lines will be made parallel again, and on a superficial examination there will

be no distortion noticeable. The method has two inconveniences: a very small stop must be used in enlarging, to bring all parts of the image to a sharp focus on such a surface, and it also introduces foreshortening, or perhaps, to avoid accusations of inaccuracy, it would be best to call it "forelengthening." These are both surmounted by inclining both negative and screen, as shown in Fig. 31. The exact inclination of each can be calculated, but for all ordinary purposes it will be found that a result which is practically free from distortion can be obtained by tilting both till the convergence disappears, while the degree of tilt given to the easel is a little larger than that given to the negative. Enlarging lanterns, unfortunately, do not allow of




FIG. 31.

the negative being swung, but it is easy to swing it when the arrangement shown in Fig. 30 is being used. There is then no need to tilt either negative or easel, as, by placing the negative on its side, the camera may be twisted slightly round on the table, the easel being moved and twisted also, until the vertical lines in the subject are all strictly horizontal in the enlargement. A similar method has been used, or suggested, for curing the distortion, cushion or barrel shaped, due to the use of a single lens, by making an enlargement—which, to use an Irishism, may be the same size, or even smaller—with the same lens with the stop in the same position, as regards the original negative, as it was when that was taken. The second bending of the lines is in the reverse direction, and therefore tends to correct the first.

The bromide paper usually employed for enlargements is fastened on the easel with pins, or may be held under a sheet

of glass. A piece of white paper is fastened on the easel for focussing purposes, or in some enlarging arrangements the easel carries a ground glass focussing screen, focussing then being done from the back as in an ordinary camera. A third method combines the two, a hole an inch or two in diameter being cut in the easel, and glazed with a piece of ground glass, on which fine focussing may be done with a magnifier. This is a refinement which is not required unless the illumination is very poor indeed. All the needful arrangements can be made very easily on the white paper. When this has been done, the lens is covered, not with an ordinary opaque cap, but with one glazed with yellow glass, so that the adjustment of the bromide paper in the exact position required is facilitated.

By substituting a plate for the bromide paper, and a positive transparency for the negative, an enlarged negative can be made. The plate should be a slow one and backed. The positive must not be one of the same character as a good lantern slide. In lantern slides, the highest lights should be almost transparent, or the slide will not look bright and effective on the screen. Such a positive makes a very poor enlarged negative, as it is not possible to keep the detail in the shadows; in fact, theory confirms what practice has long shown to be the case, that while it is possible from a good print to obtain a fair quality negative, it is not possible to make a good negative from a good lantern slide, and the better the slide, the less suitable for the purpose will it be. The positive for enlarged negative making requires a longer exposure than does the same plate when a slide is to be the result, the positive being kept thin and possessing a distinct and printable image in its highest lights. In developing enlarged negatives, those who are only accustomed to deal with small ones are sure to have a tendency to over-develop. The wider separation of the high lights and shadows, due to their size, makes the negative seem much thinner than it actually is. Time development in this is as useful as in other cases. As large plates are expensive, bromide paper has been used successfully for making enlarged negatives, as has also negative paper. A negative on bromide paper must not resemble a good enlargement, but should look like an enlargement that was both over-exposed and over-developed. Some

workers make such an enlargement direct from the negative, and then print an enlarged negative from it, by contact ; but the usual practice is to make a small transparency, and to make the enlargement from that. If enlarging is only done occasionally, it will be found economical to use the first plate or the first sheet of paper in making a graduated series of exposure tests. In making an enlarged negative the exposure of each strip should be double that of the preceding one, but in making enlargements on bromide paper there should be at least one intermediate exposure, as was explained in the chapter on bromide printing. In most packets of large size bromide paper a small piece is included for the trial exposure. This is of little use, as it is not often possible to get a really reliable guide to exposure from a piece less than half the size of the entire sheet. The small piece cannot take into consideration any widely separated tones ; and if a guide is wanted at all, it is wanted to give information accurate enough to save wasting a whole sheet of paper. A sheet or half a sheet used deliberately on a test should give precisely the information required, whereas a sheet exposed in the ordinary way, if found to be incorrectly exposed, only gives a rough suggestion of what the correct exposure might be, and it may take three or four more pieces, used in the same way, to get the best result.

## 11

It has been said that the greatest test of technical excellence in a negative is making a lantern slide from it, and the observation is very true. Prints can be dodged to an unlimited extent, minute pinholes in the negative are lost in a rough surface print, even large holes can be stopped out entirely with a little skill, so as to pass quite unnoticed ; but spotting on a lantern slide is almost impossible. The searching magnification it gets on the sheet, the complete absence of anything to correspond to the texture of the surface of a paper print, the difficulty, or rather, the impossibility, of making a complete match in tone and outline between pigment applied with a brush and the delicate shades of the developed image, all combine to demand that the slide to a great extent shall be an "unfaked" copy

of a flawless original negative. But if the test is a severe one, the result, when successful, more than justifies it. The "optical lantern"—for it is "magic" no longer—properly worked, remains the best method of showing the beauties of a photographic picture. Comparatively few pictorial workers adopt it, but this is only to be expected. Comparatively few pictorial workers are sufficiently capable technicians for their work to stand such a test, but that men like Stieglitz and F. H. Evans are slide makers is sufficient to show that there is nothing inherent in the process which unfits it as a means of pictorial expression. Those whose ideas of a "picture" are limited to something that might pass as the work of an artist in some other medium—a mezzotint or a monochrome painting, for example—condemn the lantern slide as inartistic. The association of the magic lantern with Sunday-school treats and tea-fights makes those who are keenly sensitive to ridicule avoid anything leading to its use; but the time will come, we are assured, when the fact that pictorial photographers wilfully threw aside one of their most powerful mediums of expression, and one that is peculiarly photographic, will excite the surprise and condemnation of their successors. In the meanwhile, those societies which are cultivating slide work should be encouraged, and the amateur photographer, who has passed the novitiate of negative making, should not regard his progress as complete until it has likewise led him into slide making.

Lantern-slide making, in its simplest form, is merely a printing upon glass instead of paper. Lantern plates are coated with an emulsion of bromide paper character, or thereabouts, and being exposed underneath a negative are developed much as a negative is developed, and yield a black image. A slower form of lantern plate is capable of being exposed for many times the normal exposure for black tones, and then so developed as to give warm colours. This process is akin to that which has been suggested for "gaslight" paper; but most of the lantern plates to which it is applicable, while slower than black-tone plates, are still too fast to be worked in gaslight, and a yellow light must be used for them. Gaslight lantern plates are also made.

Slide making by contact is a very easy operation. In the yellow light the lantern plate is placed behind the negative in

a printing frame, and it is exposed, developed, and fixed. A special form of frame is made for the purpose, and is convenient, but is not a necessity. There is a standard size for lantern plates, so that they may fit the lantern carrier. This in the United Kingdom is  $3\frac{1}{4}$  inches square. In the United States the size is  $3\frac{1}{4}$  inches in height, and 4 inches in width; so that American slides will fit British carriers of the "push-through" type where width is immaterial, but not other patterns. In consequence of the limitation of size, the largest possible picture on a lantern plate, with due allowance for margin, is 3 inches each way, or a trifle less, and a square shape is very seldom satisfactory. We therefore have to confront the difficulty in making slides by contact, that either the negative must be specially taken, occupying a small portion of a quarter-plate—not much more than half—or we can only get a part of the complete subject on the slide. Alas! that it should be so; but in the great majority of slides it is only too apparent that the latter course has been adopted, and the vital parts of the picture are either partly off the slide, or what is even worse, are just squeezed on; so that the one thought in the spectator's brain is the close shave they had to get on at all. The slide printing frame is an appliance to help in the selection of the particular part of the negative that is to be got on the slide. It is a frame provided with a flat surface, which may be of wood or of glass with a mask of the required size. If of wood, it has a square opening in its centre about  $3\frac{1}{4}$  inches each way. On this surface the negative is put, film upwards, and is shifted about until the part which is to appear on the slide is seen centrally in the opening, when the back of the frame is fastened on, and holds the negative firmly in position. In the back is an opening a shade larger than a lantern plate, and provided with a door. The lantern plate can then be dropped into this opening so that its film comes against the film of the negative, and the door being closed it is ready for exposure. The greatest advantage of this apparatus is that it removes all risk of sliding the lantern plate on the negative, which would damage one or both if there should be the slightest particle of grit between the two. Otherwise, an ordinary printing-frame, a size larger than the negative, to allow of adjustment, may be used with a piece of clean glass in it, upon which to



place the negative. For slides on collodion emulsion plates, which a very few enthusiasts still use in the belief that they yield finer lantern slides than are possible on commercial gelatine plates—a belief which is, perhaps, due to the fact that the slides on lantern plates they have seen have not been nearly as good as the process will yield—the slide printing-frame is a necessity, on account of the extreme tenderness of the collodion film.

The other method of exposure has already been referred to; it is effected by means of the camera, exactly as in enlarging, except that the image is smaller rather than larger than the original. The best slides are necessarily made in this manner, and it enables any part of the negative, or the whole of it, to be reproduced on to the lantern plate of the size required to occupy it properly. It is not easy to explain why it should be so, but this method can undoubtedly be made to yield finer definition in the slide than any method of contact printing. All risk of injuring the surface of either negative or plate is avoided, and converging vertical lines can be corrected just as they can in enlarging. The only requisites are means for evenly illuminating the negative, such as have been dealt with in the earlier portion of this chapter, and a carrier to fit into the dark slide to hold a plate  $3\frac{1}{4}$  inches square. Fixed focus lantern-slide cameras are made on similar lines to the fixed enlargers. They can be used with daylight in the same way, or by placing a couple of sheets of ground glass, an inch apart, an inch behind the negative; it may then be lit by a lamp, by incandescent gas, or by magnesium ribbon. Exposures are shorter than when enlarging, as the light is not spread over so large an area.

The development of lantern plates, except when black tones are to be obtained, is not so easy as the development of negatives. More light can be employed, but there is much difficulty in determining when to stop development, on account of the colour of the deposit, which is light, and not so very different from that of the unaltered sensitive salt. There is not the extensive range of developers that are applicable for negative making, as some of these give colours which in a lantern slide are not attractive; but there are still very many that can be used, pyro and hydrokinone being the most popular.

To obtain warmer tones, the developer is restrained by adding bromide, and the exposure increased. Most of the text-books put great stress on the control of the colour by increasing the exposure to some definite extent; but this is putting the cart before the horse. The governing factor in the question of colour is the time of development, and this in its turn is influenced by the composition of the developer. To get uniform colour we must therefore employ the same developer each time, and must so regulate the exposure that the development to the proper density is carried out always in the same time. It will be seen that this removes the great difficulty of correct density. The developer is applied for the required time, and the slide is then washed and fixed. If it is too dense, a fresh plate is exposed for a little shorter time; if too thin, the next exposure is longer, the time of development being kept the same.

Lantern plates may be fixed in the ordinary or in the acid-hypo bath, as preferred, and are washed and dried exactly as is done with negatives. Just before placing a finished slide in the rack to dry, it should be held under the tap and rubbed very gently with a tuft of cotton wool. The slightest abrasion of the surface may show when it is on the sheet, so it must be done carefully, and the slide must be dried where there is no fear of dust getting at it, as this when magnified in the lantern is much more apparent than when printed from a negative. Slides on lantern plates may be reduced or intensified in exactly the same manner as negatives. The Wellington intensifier is said not to affect the colour of the slide, but it is doubtful how far this would hold good with very warm tones. All other intensifiers alter the colour, and have a tendency to choke up the shadows; they are best avoided, and if a slide is too thin a fresh one should be made. A slight reduction improves many slides, if it is not allowed to go very far. It just clears up the high lights, and generally makes the slide look cleaner. If carried a shade beyond what is required for such a purpose, the slide is ruined irretrievably, so that it is better not to tamper with a good slide by reducing it in the hope of making it better still. The ferricyanide hypo reducer is the best for the purpose, sufficient of a 10 per cent. solution of ferricyanide being added to some of the fixing bath to give it a pale yellow colour.

Slides having a warm tone obtained by development may have this modified by applying to the finished slide either a combined toning and fixing bath or a plain sulpho-cyanide and gold bath, such as is used for P.O.P. In this way some very fine purple colours are obtained, and many of the better commercial lantern slides are made by this or by a similar method. As gold toning tends to make a warm colour colder, it is useless to apply such baths to a black-toned slide; but most of the methods already referred to for toning bromide prints are equally applicable to lantern slides, though the colours are not always the same. The sulphur toning mentioned on page 253 gives a very good colour to a black slide, but all toning methods tend to make the slide heavy and opaque, and the colour is never quite as good and transparent as it is in the best slides obtained by development pure and simple.

It is not easy to introduce clouds into a lantern slide, and in most cases the fact of their introduction is apparent and therefore to be condemned. The method usually adopted is to print the clouds on a separate plate, develop it with the first side by side, so as to obtain identical colour, and then to bind up the two together, film to film. Manifestly, this cannot be done when there is a risk of a cloud form showing across some part of the picture on the other glass, and this limits the possibilities. A lantern plate may be fixed up on the enlarging easel, and a small image of the cloud projected on it through the landscape slide—which in this case must be made first—which is placed in contact with it, film to film. The landscape then acts as a mask, and spaces on it where the clouds might print through, and are not wanted, may be blocked up with pigment on the glass side of the landscape. This is a perfect method in theory, but in practice it is hampered by the difficulty of getting clouds and landscape into absolute register and keeping them there. If this is not done, the result can only be described as painful to the producer and ludicrous to the spectators. Still, it is possible, and when done is effective enough.

A supplementary picture on the cover glass has been used as a means of toning down parts, which were too light in the original slide, without affecting the rest. A thin negative image is obtained on a lantern plate by making a contact print with the slide itself as the negative. This is developed, and

the parts which are not wanted are reduced away entirely, after which the two are bound up together in register, the negative image on one toning down excessively bright lights in the other as required. In binding up such slides it is better to put the mask outside, the two films being just moistened at the four corners with a touch of gum; they are put together and carefully adjusted in the usual way. Toned slides are generally improved by being varnished before they are bound up; ordinary negative varnish answers excellently for the purpose.

While the opportunities of "dodging" a slide are not by any means so extensive or so varied as with a print, a great deal more can be done than many slide-makers seem to realize. Shading during exposure is possible whenever the photographer can see between the lens and the lantern plate, but when a slide-making camera is used this is impracticable. Then the finished slide can be locally reduced by means of a physical reducer, such as Baskett's "Globe polish" (see p. 294). Mr. Wild, who has been very successful as a slide-maker, states that with a piece of flannel moistened with "Baskett" fairly large areas may be rubbed down evenly and quickly. If care is used, there is little risk of scratching, and with practice light and atmosphere may be rubbed into an evenly tinted sky, or one or two well-placed touches may give life and texture to a flat expanse of water. For smaller areas the flannel may be folded two or three times, and used edgewise. For still smaller portions a piece of soft cork cut to a convenient shape may be used, and for smaller still, a wooden match, which should be cut to a blunt chisel edge, and the sharp edges rubbed off with a piece of fine glass paper. Another method of reduction, a chemical one this time, is by the use of—

Saturated solution of iodine in alcohol	...	...	1 part
Saturated solution of potassium cyanide in water	...	...	2 parts
Water	...	...	Quantity sufficient

This, be it observed, is very poisonous. "By reason of its clean working," says Mr. Wild, "it can be used, if necessary, with a brush on the dry film, and so affords an easy means of completely taking out any portion, leaving a sharp clean edge." He also states that it does not alter the colour even of

warm-toned slides, and may be used, if desired, for general reduction.

The finished slide has got to be mounted with a cover glass to protect its film before it is ready to be shown in the lantern. In public that is, for in private no slide ought to be mounted until it has been seen in the lantern and thought worthy. Black-toned slides may be judged, after a fashion, by looking through them at a sheet of white paper, but any other colour—never. The appearance in the hand is no guide to the appearance on the sheet. Photographers starting out to make lantern slides for the first time have been known to purchase cover glasses as well as lantern plates; it certainly saves the trouble of cleaning the film off the defective slides, but is not otherwise economical; and he is an exceptionally skilful worker or else an easily satisfied one who can get six slides worth mounting out of a box of twelve plates. This is not to say that the process is exceptionally difficult, quite the contrary; but rather that when all the arrangements are made, it is such a little trouble to make a second or third slide, and costs so little for material, that the photographer is certainly justified in doing so, if he thinks he can get in any way an improved result. The first stage in mounting is masking. Masks can be purchased, neatly cut out of thin black paper, and if a sufficiently large assortment of sizes is obtained there is little difficulty in getting one to fit each slide. If there should be any, a strip of black binding paper will put things right. It may be taken as a general rule, to which exceptions must be extremely rare, that the best mask is one with a rectangular opening and perfectly straight sides. Circles, domes, cushions, ovals, squares with or without rounded corners are unsuitable. In arranging a picture on the ground glass, we instinctively do so with reference to the boundaries of the glass itself, or without reference to any particular form. Hence to show such a picture subsequently, in a shape which is either actively unsuitable or at least noticeable, is to weaken the effect of the picture by diverting attention to its shape. A circle or oval is sometimes permissible, if the picture has been expressly arranged to suit it, but not otherwise. The other shapes are too assertive to be used at any time. Many workers mask each slide by means of four strips applied separately, but it is not easy to get true right angles in



GRANNIE'S STOCKING  
BY ARCHIBALD COCHRAN



this way. After masking, the slide should be thoroughly dried, and the cover glass also, unless it is of bare glass, and the two are then brought together and bound with the gummed silk or paper strips sold for the purpose, attaching two strips to opposite ends of the slide and then the other two when those first applied are dry. Silk strips last longer than paper, but are not so easily applied. It only remains to attach two circular spots of white paper to the glass at the top corners facing the eye, when the view seen on looking through the slide is the right way round and the right side up. These are a guide to the lanternist, and enable him to put the slide into the lantern in the one position which, out of the eight possible, is the only one which will bring the picture in the proper aspect on the screen.

Lantern slides are generally accepted as the means by which photographs can best be shown to large audiences, but it is a great mistake to limit them in this manner. The error is due to the attempt to use too large a screen, which entails the necessity of employing an unnecessarily powerful light. For ordinary displays at home, a screen 4 feet each way, if good, is all that is wanted, and portable screens, rolling up into a very small space, can be used. Generally speaking, a "sheet" will not do, as it is not opaque enough and is very wasteful of light. The most convenient portable screen is one shown in Fig. 32. The two uprights




FIG. 32.

are hinged where they join the box and fold down and form its lid. The box contains the screen which is wound on a spring roller, and is set up in a moment by lifting the bar attached to one end of the screen and catching its ends in the notches in the uprights, as shown. A better screen still for home use is made by getting a frame-maker to construct a picture frame of plain dark moulding, such as is used in house decorating



rather than for picture framing, and also to make a board which shall fit in behind the moulding in place of a picture. The front surface of the board must be planed quite smooth, and should receive two or three coats of white paint. The paint surface is not a good one to receive the slides, but is the best basis for a smooth layer of white paper which is pasted down on it before the board is put into the frame. When this gets soiled it is very little trouble to replace it with fresh. Such a screen, 4 feet each way, can be hung on the wall for use, like a picture, but its lower edge should not be more than 2 feet from the floor. With a good lantern lens and a suitable condenser, lantern slides may be projected on to such a screen with ordinary incandescent gas, with perfect success and no sense of a deficiency of illumination. But to do this, the room must be perfectly dark, the lantern should be efficiently light-tight, and there should be no white disc thrown on the screen ; it should never be seen unless either it bears a picture or is dark. The pleasure of a little lantern exhibition on these lines must be experienced to be appreciated. There is no "crick" in the neck from gazing upwards at gigantic pictures on a colossal screen ; no heat or smell from limelight in a lantern that is on the point of bursting into flames ; no sense of the ridiculous or even of the horrible from the magnification of little things to many times life-size. One's friends may sit comfortably round and view at their ease, pictures neither out of scale nor dazzlingly bright and hard. There is no doubt the lantern is the way to show photographs, and those who fail to appreciate this should see a lantern show well done, on the lines indicated.

## CHAPTER XIX

### ORTHOCHROMATIC AND THREE-COLOUR PHOTOGRAPHY

Insensitiveness to yellow and red not altogether an evil—Colour contrast—Pure and impure colours—Two chief classes of orthochromatic plates—Light filters—Adapting them to plates—Dyed films—Measuring the effect of light filters—Colour photography—The Lipmann process—What are not colour photographs—Colour vision—The Young-Helmholtz theory—Three-colour work—Direct processes—The Autochrome—The preparation of the starch grain—Development and reversal—Copying autochromes—Uto paper.

**I**N an earlier chapter the use of orthochromatic plates has been referred to, but nothing was said as to the details of their manipulation. It was at a very early stage in the history of photography that the inconveniences of the irregular sensitiveness to different colours of all photographic preparations were experienced; but nothing of importance was done to remedy it, until Dr. H. W. Vogel found that the addition of certain dyes to the sensitive silver salts made them far more sensitive than they were otherwise, to yellow and red. It is on this basis that all modern commercial orthochromatic plates are prepared, although Sir William Abney succeeded, many years ago, in preparing an undyed collodion plate sensitive to the extreme red.

If the insensitiveness of plates to yellow and red is sometimes troublesome, it is far more often a very good feature of which the photographer takes full advantage, by using light of those colours in his dark room; and we must not forget that when we have the perfect orthochromatic plate, the plate which will give us true rendering of all colours in monochrome without any light filter, we shall have a plate that must be manipulated in perfect darkness. And that will not be its only doubtful virtue. Colour contrasts will disappear entirely in our photographs, and the photographer will have to pay much more

attention to a subject which at present he can largely ignore. An example will serve to make this point clearer.

Let us imagine we have a draught-board, whose squares, instead of being white and black, are respectively blue and red, of exactly the same intensity. To the eye such squares would be almost, if not quite, as visible as if they were black and white, though we should be unable to say which was intended to represent the lighter series of squares. With a perfect orthochromatic plate the photograph of such a board would show no signs of its divisions into squares at all, but, as both colours were of equal intensity, the board would appear of a smooth, even tint all over. This is an extreme case, and one which could only be brought about deliberately and with much trouble ; but it will serve to show one of the directions in which the perfect orthochromatic plate might not be all that was wanted. •

The ordinary or non-orthochromatized plate is extremely sensitive to blue and violet light, so much so that any object of a very intense blue colour photographs almost like white. Violet also, so long as it is true violet and free from red, photographs far lighter than it appears to the eye. Green, on the other hand, appears much too dark in a photograph, while pure yellow, and still more pure red, appear practically as dark as absolute black. To take a very common example, an orange placed on the customary greyish-black focussing cloth, and photographed on an ordinary plate, appears in the print almost as dark as the cloth itself, yet to the eye the fruit stands out as a brilliant high light. This is an exceptional instance, the skin of the orange being of a particularly pure colour. The great majority of the colours in nature are far from pure, but, when analyzed, show themselves to be subtle compounds made up of many tints, some of them quite unsuspected. Then, again, most natural objects have a surface which reflects a great deal of white light, foliage being a case in point ; and this white light will affect the plate, even if the object from which it is reflected is of a colour to which the plate is insensitive. These and other considerations prevent the non-orthochromatic nature of the undyed plate from being the unmitigated nuisance which, under less favourable circumstances, it would be. Still, at times it may yield a result that is absurdly false. Highly coloured

flowers and insects are often impossible of transcript without orthochromatic plates, as, of course, are paintings and many artificial productions.

The insensitiveness of the plate to red is not usually very important, as pure red is so uncommon as to be met with scarcely at all; in addition, red is not a colour of great luminosity. With yellow it is different. Yellow, to the eye, is the brightest of all the spectrum colours, and a comparatively pure yellow is not an uncommon colour. Green provides still more of a case in point. Green is often almost as bright to the eye as yellow, while in outdoor nature green vastly predominates. Moreover, the ordinary plate is even less sensitive to green than it is to yellow, so much so that it has been suggested that green instead of yellow or red glass should be used for the illumination of the dark room.

Plates orthochromatized to get over these drawbacks are now issued by almost every maker, and although these plates differ amongst themselves, they may be divided broadly into two classes: those that are treated so as to be more sensitive than otherwise to green and yellow, but still not so as to be very sensitive to red; the other those which are sensitive to red also. Plates of the former class can be used in dark rooms lit by red light, with but very little more precaution against fog than would be required with extra-rapid non-orthochromatic plates; those of the latter class must either be worked by specially prepared glasses in the lamp, which generally allow so little light to pass that the only thing to be seen in the dark room is the lamp itself, or must be worked in total darkness. A "safe light" for red sensitive plates has been termed a "modified darkness," while an American writer, with picturesque exaggeration, said his lamp gave so little light that when he shut his eyes the room brightened up considerably. Red sensitive plates have done much to make time development a necessity.

Whatever the method of orthochromatizing may be, it always, so far, has failed to make a plate so sensitive to yellow and green as it is to blue and violet, and as both yellow and green to the eye appear the more luminous, something more must be done if the orthochromatic plate is to show a result noticeably more truthful than can be got with an ordinary plate. This something is the use of a colour screen or light filter, a

transparent coloured glass or filter which, by stopping some of the light to which the plate is unduly sensitive, but allowing all to which it is insufficiently sensitive to pass, goes some way to correct the error in colour rendering, still present with the orthochromatic plate.

By the use of a suitable light filter a very fair rendering of green and yellow objects can be obtained on an ordinary plate, but the exposure is increased to such an extent as to deprive the method of any particular value. Mr. Arthur Payne published two illustrations to show this some years ago. Both were taken on an ordinary plate, one without a screen, the other with a yellow colour screen, which increased the exposure from half a second to an hour. The result was a very fair rendering of the subject. Had an orthochromatic plate of the same general speed been employed, the half-second exposure without a screen would probably have been a little but not much better than on the ordinary plate; but a light filter could have been made which would have given as good a result, if not one actually better than that obtained with the hour's exposure, but calling for an exposure of not more than five or six seconds. In other words, at least as good a result can be got on an orthochromatic plate with a screen increasing the exposure ten times as can be got on an ordinary plate with a screen calling for seven thousand times the exposure; both plates without a screen being of about the same rapidity.

A colour screen of necessity lengthens the exposure, but how much it does so depends on its depth of colour and suitability to the plate, and the former depends upon the degree of correction which the photographer requires. This is determined by the extent to which it is possible to allow the exposure to be increased. With the hand-camera a four-times screen is as much as circumstances will permit, and even then it is often impossible to use it to get a fully exposed plate. For landscape and similar work on a tripod a ten-times screen is perhaps the best, although a four or six times will often do all that is wanted. When we come to picture copying, or to the photography of coloured objects, where truthfulness of colour rendering is of the utmost importance, a red sensitive plate and a screen which increases the exposure forty times may be required. But the best all-round screen is, no doubt,

one of from four to six times, as this in most cases will do all that is wanted without making the exposure unmanageable.

In order to get the greatest colour correction with a minimum increase in the exposure, it is important that the colour of the screen shall be adapted to the plate with which it is to be used. This is being recognized now by the makers of the plates, who supply screens suitable to their own goods. For many subjects a piece of thin, clear gelatine, stained with suitable dyes, will answer every purpose, and such screens are to be obtained very cheaply, sometimes free of charge, from the plate-makers. They interfere slightly with the definition of the picture, especially if carelessly used; but if properly employed there is no reason why the definition should appear any worse than without them, unless careful comparative tests are being made. Such screens are best placed at or near the stop of the lens. If this is not possible they may be put close to the lens and behind it, a better position than outside the lens or in front of it, though not quite so accessible. A little cardboard fitting, like the lid of a pill-box, with a circular hole in it, is easily made and carefully blacked all over, and then forms an excellent holder for the screen, which may be lightly attached to it by means of sealing-wax. This is better than gum, as the moisture in the gum may make the gelatine warp. A lens fitted with a slot for a Waterhouse diaphragm may have such a diaphragm carefully cut out of two pieces of thin card and blackened, and the gelatine may be placed between them. Other ways of mounting such films will occur to the reader.


A properly mounted screen enclosed between glass to protect it from injury should always be used by the photographer who takes up orthochromatic work seriously; though the gelatine film may serve to induce him to do so, and suffice for preliminary attempts. The most expensive screens are made of "optically worked" glass, by which is meant glass which has been ground quite flat with as much care as is given to the grinding of the curved surfaces of a lens. It is a needless luxury, and carefully selected "patent plate" glass is all that is needed, and all that is usually supplied. A very popular form of light filter in America is a glass trough or cell in which coloured liquid is enclosed, the solutions used

containing picric acid, naphthol yellow, potassium chromate, etc. These screens have never been very popular on this side of the Atlantic ; possibly because no great effort has ever been made to push them. Liquid screens are often used in three-colour work, however.

Without a screen there is not any very great difference noticeable between the results on ordinary and on orthochromatic plates. Many workers like to use them for landscapes, in the belief that even without the light filter clouds are rendered better ; but the difference is not very marked, though it is certainly perceptible. As soon as a screen, even a very pale yellow one, is employed, the improvement in the cloud rendering is very noticeable. White clouds against a blue sky are almost impossible on an ordinary plate, the blue of the sky coming out in the print almost as white as the clouds themselves, and it is in this and in the delicate green foliage tints that the combination is most likely to be of service to the amateur.

For a long while, orthochromatic plates were sold, but except some yellow glass screens nothing for use with them was commercially obtainable. Glass is not at all suitable as a material for colour screens, though it is an excellent protector for them. All so-called yellow glass is really brown, as becomes evident when a piece is placed on a sheet of white paper. The brown is due to an admixture of black with the yellow, and while the yellow alone affects the proportion of the different colours reaching the plate, and so is effective enough as a light filter, the black, if not otherwise objectionable, at least means that light generally is cut off, and that in consequence the screen lengthens the exposure more than it need. Practically all colour screens to-day therefore, except liquid ones, are made of dyed films, which may be mounted between glasses for protection.

The author uses for most commercial yellow-sensitive plates, adjusted screens of a yellow or green shade, made on lines suggested by Mr. McIntosh, who has given much time to this subject. The method is a very simple one. The first necessity is some good glass evenly coated with gelatine, and this is supplied to hand in an unexposed lantern plate or two, which may be fixed out in clean hypo and well washed. By



COMING TO THE COAST  
VALLEY OF THE





examining the reflection of the glass side of a straight object, such as the sash bar of a window, moving the glass about, it can soon be seen if it is reasonably flat. When a flat piece or two has been obtained, it is allowed to soak in a solution made by dissolving two grains of naphthol yellow and four grains of naphthol green in half a pint of water. The naphthol yellow may be used by itself if preferred, but the author's preference is certainly for the combination—for landscape work at any rate. Sheets of thin, clear gelatine are obtainable, and if preferred these may be cut up, soaked in the dye, and squeezed on to glass to dry. When dry they may be mounted between two thin pieces of patent plate glass by means of Canada Balsam, or celluloid roll film, fixed out and washed, may be treated similarly. The lantern plate screen must have its film protected in the same way.

Much has been written on the preparation of suitable colour screens, and it has been thought best to give an outline of a practical method ; but it must be pointed out that their manufacture is not to be taken in hand, if a screen can be bought from a reliable maker. Messrs. Sanger Shepherd and Co. have specialized in this direction, and supply colour screens increasing the exposure to any required extent, and suited for any particular plate ; and it is much better to get such a screen made and tested by methods which are beyond the reach of most amateurs, than to employ a home-made article, which may give excellent results, but perhaps at a totally unnecessary prolongation of the exposure.

As far as the use of orthochromatic plates is concerned, there is little special to them to note. They must not be exposed to the dark-room lamp unduly, of course, because even if not "red-sensitive" they are far more sensitive to it than ordinary plates. When using a screen, and especially in landscape work, particular care must be given to expose them fully, or much of the advantage of the screen will be lost.

There are many ways of ascertaining how much any particular screen increases the exposure. One of the easiest is to make a standard black and white subject, which may be a large tuft of cotton-wool on a focussing cloth, and to expose two plates in strips upon that, first without and then with a screen. If the two plates are developed side by side for the same time,

it will be seen that on both plates there are portions which exactly correspond, and the relative exposures of these portions will give the relative exposures with and without the screen respectively.

The increased exposure which a colour screen entails is not a fixed quantity, but depends on the character of the light. Such an experiment as that described in the last paragraph, if performed in bright daylight, will give the effect of the screen on ordinary daylight exposures, but will not be correct for exposures made towards sunset, or by lamp-light, for example, when the light is much yellower. In such a case the screen no longer increases the exposure so much, and if very pale in colour it is conceivable that it would not increase it appreciably at all. But this is an extreme case, and enough will have been said, if the reader remembers, that as the light yellows, the ordinary or unscreened plate will want a longer exposure proportionally than the orthochromatic plate with a screen. The number of times a screen increases the exposure, as marked on commercial screens, or given in catalogues, refers to its effect in ordinary daylight work. Too deep a screen, or one made for one plate and used for another, may overcorrect the shortcomings of a plate. In landscape this generally manifests itself by excessively light foliage, especially in the case of grass and other bright greens in the foreground. It also tends to destroy ærial perspective, by cutting out the light bluish haze upon which much of that depends. Landscape negatives on orthochromatic plates should not be developed until they appear quite as vigorous as on ordinary plates. One result of colour correct photography is to reduce contrasts caused by minor differences of colour, and a perfect negative on an orthochromatic plate should look distinctly less harsh than a perfect negative on an ordinary plate. It has been said that most orthochromatic plates cannot be developed with pyro-ammonia without fogging. There is no doubt a greater tendency to fog with this developer than ordinary plates manifest, and pyro-ammonia is not a very satisfactory developer at any time; but at one time or another we have developed orthochromatic plates of a great many different makes with it, and have not had any trouble. Orthochromatic plates and a pale yellow screen, if used for portraiture, have been said to dispense with a good deal

of the need for retouching: much of this being due to the exaggeration by the ordinary plate of any slight yellow freckles or reddish spots on the skin. Theoretically this ought to be the case; but the fact remains, that comparatively few orthochromatic plates are used in the studio, and we never heard of a portrait photographer who habitually employed them and a colour screen; as even a very pale yellow would tend to make exposures too long.

### COLOUR PHOTOGRAPHY

We might almost as well have written the heading "Three-colour Photography," for the three-colour process in one or other of its modifications is the only method of colour photography that need concern the photographer. The Lippmann process of colour photography is not a three-colour method, it is true, but then it began as a laboratory experiment requiring great nicety and skill, and has ended there. And it forms the only exception.

The popular impression that the gaudy-coloured picture postcards and local views now seen about in such numbers are true photographs in colours is about as accurate as such impressions usually are. Thank heaven! photography is not responsible in any way for their colouring. The three-colour process has enough chromatic sins upon its conscience truly, but for the aniline sunsets and beetle-green grasses of the shop "photographs in colours"—for that is how the unscrupulous tradesman too often describes them—it has not to answer. Many three-colour photographs are quite as wrong, but they are more naïvely wrong, and show some sort of consciousness of their error, which the flaunting varnished collotype on a gaudy lithograph background never approaches. The three-colour process or processes are the lineal descendants of orthochromatic photography. Before it was discovered how a plate could be made sensitive to the red—an essential, of course, of any true colour process—the method by which with such sensitiveness three-colour photography might be possible was not only worked out, but published by du Hauron. All three-colour photography is based on the Young-Helmholtz theory

of colour vision, and though anything like an adequate account of either would be out of place in a work of this kind, we may glance at both in outline.

According to this theory, our consciousness of all colour is the result of the excitation of one or more of "three colour sensations" of which the human eye is capable. There are three "somethings" in the eye of every one not colour-blind, and by the extent to which each of those is simultaneously stimulated, so does the person have that form of consciousness which we associate with the word "colour." Prof. Clerk Maxwell investigated this further, and was able to define the three sensations as being those excited by a particular shade of blue, of green, and of red respectively. Thus we may say that when we look at pure blue light of the particular shade in question, only one of the three sensations is aroused, and so on with the others. All hues and shades of all colours of which we are conscious are the result of the excitation of these three sensations in different proportions. Thus when we see a yellow object, that object is exciting the green and the red sensation in our eyes, and the combination of these two in proper proportion, gives rise to the compound sensation we term yellow. By far the greater number of colours we see around us involve all three sensations. When all three are excited in a proper proportion, we get the balanced result we term white. White is just as true a colour as the most pronounced cardinal or mauve or emerald, though not a primary colour. If we could analyze any given coloured object so as to find out the extent to which it excited each of these three sensations, and if we could then find three pigments which each excited one of the sensations and one only, and if we could then superpose the effect of those three pigments in those proportions on the eye, we should experience the same colour as when we looked at the object itself. It was this which du Haeron attempted.

Three-colour photography requires three distinct negatives of the scene to be obtained. These are taken through colour screens similar in construction but not in hue to those used in orthochromatic work. The aim of each screen is to let through only that light from each part of the subject which excites one of the three sensations. These three negatives are then printed

in colours, so that the effect of each colour is to excite the primary colour sensation exactly as that sensation would have been excited by the original object. When the three are seen simultaneously, the result should be a true rendering of all the colours of the original. The three negatives so obtained, be it understood, have no colour in themselves ; they are only *records* of the extent to which the subject excited the three colour sensations in the eyes of the beholder.

Comparatively simple as such a process sounds in theory, there are many difficulties in practice which experimenters are labouring to overcome. The obtaining of the three negatives is the first step ; when they have once been obtained with reasonable accuracy, there are several methods of utilizing them to give rise to a coloured picture. We may print them by the carbon process on three films and superpose them ; we may multiple-print them in gum in three colours, by which the weirdest effects may be got. By a modification of the carbon process involving the use of dye solutions, we may get all three pictures on one film ; or we may throw on a single disc on a sheet the images of three lantern-slides by means of a triple lantern with a coloured glass in each lantern. The details of these various methods must be sought in works on three-colour photography, which already has a literature of its own. They are being worked by enthusiastic and painstaking amateurs, and the number, though small, is a growing one.

The advent of a direct process, by which the most perfect transparencies in colour can be obtained on a single plate by a single exposure, has extended the circle of colour photographers immensely.

It is now almost as easy to get a photograph in colours as it is to get a negative in black and white. The photograph is only a glass transparency, it is true, but it is wonderfully faithful, while its production is simplicity itself. Moreover, it has directed photographers' attention to the colour problem in a way nothing else has ever done. The "Autochrome" plate of Messrs. Lumière was the first screen-plate method to make its appearance ; and its enthusiastic welcome by photographers at once set rival inventors hard at work. So great was the step taken by the "Autochrome" plate, that it seems that a comparatively short stride further must give the direct paper print in colours also.

The method by which the "Autochrome" plate accomplishes its object is not new, and the outline of the manufacture of the plate itself was published some years ago ; but no one, except its inventors, appears to have realized the capabilities of the process, and it is more than doubtful whether any one but the brothers Lumiere could have worked it out so perfectly as has been done. It was only in the summer of 1907, when the plates were first commercially obtainable, that the photographic world awoke to the full extent of the work that had been accomplished.

That work is, briefly, this. A plate has been made, on a commercial scale, that can be exposed in the camera, a suitable yellow screen being put on the lens, and will then give a transparency reproducing all the colours of the original subject, with a marvellous fidelity, and with only quite simple manipulations, akin to ordinary development. No three colour process up to the present has been able to rival the "Autochrome" in its power of colour-rendering. The finest shades, the subtlest tints are reproduced as easily and as faithfully as the crudest primaries. There are a few exceptions to this accuracy in certain yellows and reds, but even the worst of these equal if they do not surpass the best reproductions of other processes. Greatest test of all, the "Autochrome" will render black, white, and grey without a tinge of colour of any kind, and will do all this without any delicate adjustments of screen and plate, or screen and dyes, on the part of the photographer. That has all been done for him by the plate makers ; he has only to expose and develop the single plate to get the coloured result.

The means by which this is accomplished are very interesting. The material employed is potato-starch. It is a well-known peculiarity of starch granules that when obtained from the same source they are all of the same shape, and, to a very large extent, of the same size. In the case of potato-starch the shape is almost circular, and it is possible to get the granules approximately one two-thousandth part of an inch in diameter. Three separate portions of such starch are dyed with suitably selected dyes, red, green, and blue violet respectively, and these three coloured powders are then mixed in such proportions that they yield a powder which has no residual colour at all. That

is to say, the three intense colours are so mingled in the eye that the mixture of powders looks merely a grey neutral tint. A glass plate being coated with some suitable adhesive, this powder is then dusted over it until it is covered with a single layer of the dyed starch grains, as close together as possible, but not overlapping. The precise method of doing this on a commercial scale has not been published by Messrs. Lumiere. As the grains are round, there will be interstices between them, through which white light could pass, and these must be filled up. At first this was done by finely powdered carbon in some way, but this has now been abandoned and the plate is rolled under considerable pressure, which flattens out the individual grains of starch, so that there are no longer clear spaces between them. At this stage the coating is not very transparent, but by applying a varnish to it, of the same refractive index as the starch itself, this defect is overcome. Seen under a powerful microscope the coating now resembles a stained glass window, the panes being all very much of the same size and shape, polygonal, and intensely coloured red, green, and violet, the distribution of the colours being quite irregular. Looked at without a microscope a foot or two from the eye no colour is to be seen at all, the coating appearing a perfectly uniform olive grey. At a certain angle it is seen marked with parallel bands, caused by the rolling. At this stage the "screen plate," as we may call it, is completed.

The manufacture of the screen plate is not a photographic operation, and can be carried out in ordinary daylight. The strictly photographic side now commences. The glass, coated as just described, is treated much as ordinary glass is treated in plate making. That is to say, it is coated on the starch-grain side with a panchromatic or red sensitive emulsion. There is no doubt that this emulsion, although resembling in many ways the red sensitive orthochromatic gelatine emulsions with which we were already familiar, is still decidedly different. It has to be extremely fine in its grain, and very thin, in order that the photographic image which is formed on it, may be as close as possible to the tiny granules of starch, themselves not more than the two-thousandth of an inch in diameter. When the plate has been coated in this way its manufacture is complete. It is put on the market as the "Autochrome" plate.



Its use is very simple. It is exposed in the camera, not with the coating turned towards the lens, as in ordinary photography, but with the glass side towards the lens, so that the light has to pass through the glass, and through the starch grain layer before it reaches the sensitive coating. A special yellow colour screen is supplied, and this is put on the lens to counteract the inevitable super-sensitiveness of any photographic emulsion to blue and violet. The exposure may be calculated with the meter in the usual way, the rapidity of the plate under these conditions, with the colour screen, being about 2 Watkins, or F/14 Wynne. It is then developed by time, as the emulsion is red sensitive, in pyro-ammonia, and instead of being fixed in hypo, is immersed in a solution of potassium permanganate acidified with sulphuric acid. This dissolves out the silver negative image, which has just been developed, leaving a positive image in silver bromide as a result. This bromide image in its turn is converted into a silver one by being treated with an amidol developer in daylight, and the positive image so obtained, after being intensified, is the final result.

The result, as already pointed out, is a transparency which reproduces with the most remarkable fidelity all the colours of the subject that was photographed. The whole of the operations in its production, from the time of commencing development, take less than half an hour, the extreme thinness of the coating on the plates making the action of each solution very rapid, and enabling the film to be perfectly washed in about five minutes and dried as quickly.

It is not difficult to understand how such a result has been attained. For simplicity's sake, we will take the case of an object which is a bright yellow colour, and follow out the reproduction of such a colour by means of the "Autochrome." The yellow rays entering the lens fall upon the starch grain layer of the plate in the camera, through which they have to pass to reach the sensitive film. Yellow light is freely transmitted by those grains which are dyed red, and also by those which are dyed green, but it is stopped completely by those grains which are dyed violet. The result on development is that on that part of the plate where the image of the yellow object fell, behind every little particle of red and of green

starch, we develop up a little black speck of silver, as the light has been able to reach the film there and affect it. But behind the violet particles we can develop no image, as the violet dye has stopped the yellow light effectively. These little developed specks block up and obscure the starch particles against which they lie, and if we fixed the plate at this stage we should find that, as the green and red particles of starch were blocked up by the developed image, the bright yellow object was represented on the plate as of a deep violet colour, since it was only the violet particles which had no developed image stopping them up. In other words we should have a *negative* image, one in which not only the light and shade but the very colour itself was reversed, violet being the complementary of yellow. It is an interesting experiment to stop one plate at this stage, just to see how faithfully each colour is represented by its complementary.

This colour negative, in actual practice, is never seen, however. The plate after development is put into the acidified permanganate, which dissolves out the silver image just developed. Accordingly, behind the green and red particles of starch there is no longer an obscuring particle of silver after this treatment, and they transmit light freely. But as the plate has never been fixed, there is a semi-opaque particle of unaltered silver bromide partly obscuring the violet particle. So that after this treatment with permanganate, the yellow object is represented by a mixture of green and red, together with a little violet, since the silver bromide is not quite opaque. The combined effect of green and red light on the eye is yellow, and the combined effect of green, red, and violet is white, so that at this stage the yellow object appears yellow, but diluted or weakened with a certain amount of white. By treating the plate with a developer again, in daylight, the silver bromide, partly obscuring the violet, is turned into metallic silver, which obscures it much more effectively, and this obscuring is made complete by the intensification process. The yellow object is then seen as of its true colour; and in the same way, all the most complex shades of a natural subject are faithfully reproduced.

The new process is not only a vast improvement on all that went before it in simplicity and ease of manipulation; it is

also greatly superior to its predecessors in the fidelity with which it reproduces the more subtle tones. While still-life subjects have been the favourites with three colour workers in the past, on account of the ease with which they can be reproduced time and again until a satisfactory result has been obtained, and on account of the vividness of their colouring, the "Autochrome" plate from the very first has dealt with landscapes and portraits, and has shown itself able to render the most delicate gradations of tint. A moss grown wall, the tones of weathered stone and brickwork, warm and cold greys and drabs, are reproduced as faithfully as vivid green or violet. In fact, except for instantaneous work, there seems to be nothing that the ordinary camera can deal with in monochrome that the "Autochrome" cannot render in colour.

Although the final result in an "Autochrome" plate is a finished transparency on the very plate that was exposed in the camera, it is not possible to suppose that the process will stop there. By fastening up such a transparency and illuminating it from behind, it can be copied in the camera on another "Autochrome" plate. If, instead of making the finished transparency originally, we fix it out without reversal, so as to get a colour negative, and re-photograph that in the same way, but omitting to reverse the second "Autochrome" also, we get a negative in colour of a negative in colour, that is to say the final result is again a positive, so that we can reproduce the original subject in any number of copies *via* either a colour positive or a colour negative. Instead of re-photographing in the camera, copies can be made by contact. The exposure must be made to daylight through the yellow screen supplied with the plate.

The introduction of a plate giving a colour transparency so simply, has given importance to another method of colour reproduction, which although in a very crude state at present, is at least very promising. By coating paper with certain fugitive dyes, it has been found possible to furnish it with a greyish black layer which gradually bleaches to a colour which is a rough approximation to that of the light to which it is exposed. Thus such a paper—"Uto" paper is its commercial name—exposed under a strongly coloured transparency, reproduces those colours to some extent. At present the

reproduction of "Autochrome" transparencies on paper of this kind has not been very successful ; but it is quite on the cards that it may be accomplished, and that very shortly. Another method, which should be quite feasible, is to make three separate negatives, for any of the three colour processes, from a single "Autochrome" plate, by exposing through three different colour screens, so as to isolate the three separate images of which the "Autochrome" picture is made up.

It is too soon to do more than speculate on these things. The plate has revealed to photographers at large immense possibilities. It has turned their attention towards colour photography so definitely that rapid progress in one or other of the directions hinted at is inevitable. It remains to be seen which of the many possible roads will lead furthest.

## CHAPTER XX

### DODGING AND "FAKING"

Selective focussing—Physical reduction—Baskett's reducer—The use of matt varnish—Work on the negative—Sensational effects—Printing in clouds—Work on enlarged negatives—A printing board—The Cherrill frame—Spotting—Sunning down—Softening definition—Modifications when enlarging—Combination printing—Retouching—Vignetting by reduction—Guide prints—The misuse of dodging.

**T**HE enthusiasm of the photographer who has managed to acquire sufficient mastery over negative making and printing to attempt to use them to make pictures finds itself suddenly damped down by the limitations of the camera. That beautiful rolling moorland, broken by the play of light on the heather, and those immense masses of cumulus, are an uninterrupted grey patch in the print, uninteresting in itself and crowned by an even less interesting white expanse to represent the sky. The quaint old gables and chimneys of the Tudor mansion are delightful to the eye which can take them in and ignore the iron railing which divides the park from the lawns; but the uncompromising camera deals out impartial emphasis to Elizabethan walls and Victorian railing alike. The painter may show us a landscape with every plane subtly distinguished by the increasing veil of sunlit air through which we see it, but the photographer can only do likewise, by pure photography, when the photograph happens to be taken at a time when Nature has exaggerated her effect and so forced it upon the notice of the dry plate. For a little while in the career of most photographers, especially for those whose aims are to put their cameras to picture-making purposes, there is a feeling of disappointment, and sometimes almost of despair, when they begin to learn of the limitations of the process by practical experience.

There is no reason to despair. Far from it. The photographer who has learned to make good negatives, and good straightforward prints from them, has only mastered the A B C of his art. The hardest to learn, and the dullest lesson, no doubt, because everything beyond is brightened by the possibilities which unfold—possibilities no longer limited by the absolute literal truthfulness to outline, nor by the almost invariable untruthfulness to tone of the photograph. Both can be overcome, and the final result can be made as individual and personal as a painting or an etching.

Many photographers will ask why we should interfere with the product of the straightforward use of the camera at all, but the reply to such a question will be found in the chapter on pictorial work, and in the mind of the photographer himself. If he is content with what his camera gives him, let him stop at that, and look upon what we are now going to consider as not meant for him at all.

The first departure from the most purely mechanical employment of photography lies in what is termed differential or selective focussing. Half the changes which we want to bring about in our photographs are due to the uncompromising character of the purely photographic rendering, which gives important and unimportant details with equal impressiveness and force, and one of the methods by which this is remedied is by focussing sharply on the principal object in the picture, and letting the parts on which we wish to put less emphasis be blurred or indistinct. If it could always be done, it would be a most powerful weapon in the photographer's armoury; but, unfortunately, it is very rarely possible to use this as we would.

No local control whatever should be attempted during the development of the negative. So sweeping an assertion is not based on theoretical or dogmatic grounds, but simply on the facts that the development is done in an extremely poor light for seeing anything; it is done under circumstances which make it quite impossible for the photographer to gauge the extent and nature of the alterations he is effecting, and the changes he may bring about, good or bad, are irrevocable. His aim, therefore, should be to produce a negative which, while not embodying any changes due to the photographer, is of such a character as to lend itself to after treatment. Such

a negative must be one which is not on any account over-developed, or there will be difficulty in dealing with it, because the easiest methods are by adding to its densities locally, rather than by reducing them.

Chemical methods of intensification or reduction are only satisfactory when applied uniformly to the whole negative. If the plate has certain parts which may with advantage print a little lighter, it is sometimes possible to effect this easily by rubbing down. A little plug of cotton wool, or a fine handkerchief, may be stretched over the finger, and this being moistened with methylated spirit, and squeezed almost dry, will be found to rub away the image gradually. If too much spirit is used, the rubber will not bite; if too little, it will endanger the film. It is quite easy to determine the right degree of moisture, and to control the action. The rubbing should be done with as varied a motion as possible, to avoid lines or streaks, and as the rubber blackens with the silver removed from the negative it may be changed. The action is much quicker if, instead of rubbing with plain spirit, the Baskett reducer is used. This is made by mixing 2 ozs. of terebene, and 2 ozs. of salad oil with the contents of a twopenny tin of "Globe polish." The mixture is well stirred up and strained through two or three thicknesses of fine cambric, to remove any coarse particles, and will be found a wonderfully effective reducer. After reducing the film, the negative must be wiped as clean as possible, and given a rub over with a piece of cotton wool moistened with benzine to remove any remaining traces of the mixture.

But the most frequently used means of "dodging" or "faking" are additive, as they are not only more easily applied, but can be modified, removed, and reapplied as often as we like, without affecting the negative permanently in any way, which is a very great advantage. We may cover the glass side of the plate with matt varnish, which gives it a sort of ground-glass appearance. The varnish is applied by pouring a pool into the centre of the plate, tilting it so that it flows into each corner in succession, and then tipping the surplus varnish off, and standing the negative up to dry. If there are any parts of the negative which would be all the better for lightening a little, we can do this very simply by scratching off the varnish opposite to them with a knife. If the varnish

is plain matt varnish, this will make a distinct difference ; but if a trace of a yellow dye has been added to it to tint it, the difference will be very much more marked. This may be done when it is necessary, but the plain varnish is to be preferred as far as possible, as it is more controllable.

The rough surface provided by the varnish will be found to take the pencil very readily. We can make lighter any shadows in the print which are too dark by cross-hatching with a soft pencil on the varnish, or we can apply lead to it with a stump. In this way, and by removing the varnish in parts, great modifications can be introduced into the print which it will yield.

Another plan, which is perhaps preferable to the varnish, is to stretch *papier mineral* on the glass side of the negative. This is a very fine, textureless paper, which can be obtained from the better class of photographic dealers for a few pence per sheet. A piece is cut the size of the negative, immersed in clean water in a dish, and then placed for a moment between blotters to take off the surface moisture. With a small brush, or with one of the sponge-tipped gum-bottles now so common, a narrow edging of gum is given to the glass side of the negative, which is then laid down on the damp *papier mineral*, and picked up, bringing the paper with it. The edges may be gently pressed into contact, but there is no need to attempt to get the paper quite flat. If it is stood up for a few minutes, it will dry, and on drying will be found to be stretched quite smooth and creaseless. With a sharp knife we can then cut away such parts of the paper as we wish, and we shall find that its removal makes a greater difference than the removal of colourless matt varnish. As it is not always possible to cut away what we want, without interfering with the rest, we can get a similar effect by painting the paper, where we wish to make it more transparent, with a mixture of one part of Canada balsam and six parts of turpentine. We may also work on the paper with stump and pencil, or tint parts of it with water colour to make them print lighter. In using a pencil on the *papier mineral*, we must be careful not to be too violent, as the paper is very easily torn, and a tear may mean that all the labour we have put on it is wasted, and that we must clean off the paper and start afresh. Negatives that have been treated



with the paper must be stored very carefully also, or the paper will get injured.

Considerable modification can be carried out in this way. Such work is least likely to fail if it is used, not so much for the introduction of sensational effects, as for the concentration of the interest on some feature that is already in the negative. It is surprising how much can be done in this way to improve upon the plain photograph, without at the same time depriving it of its photographic character, or leaving in the final print any suggestion of the interference of the photographer with another method. By going over all the most distant parts with stump or crayon, they can be lightened in tone until they suggest their distance far more faithfully than is usually possible with the plain, undoctored photograph. Patches which are broken up too much with scattered lights and shadows can have the most intrusive lights toned down by the balsam treatment, and the deepest shadows strengthened with pencil touches, and in this way we can give that emphasis to the centre of interest which we desire.

The process is one which is easily abused, as our exhibitions are constantly showing. Pictures are to be seen in which the photographer has got a dull, flat negative, and by the insertion of high lights and deep shadows—where by no possibility they could be found with any natural illumination whatever—has obtained a theatrical and stagey effect, which may catch the untrained eye, and, to those who are not accustomed to study pictures, may seem for the moment very successful. But such pictures, as soon as the trick is seen through, cease to appeal to the spectator. They are the laughing-stock of the painter, and are only examples of what to avoid. We must remember that when we enter upon this ground, where painters have long been in possession, the knowledge which is indispensable to the painter is equally so to the photographer. The latter may not need the manual dexterity of the user of the brush, but he must at least have his feeling for the beautiful, his knowledge of composition, of values, of chiaroscuro, of those things, in fact, which every painter studies at the time he is acquiring his technique, but which it is safe to say no photographer thinks of when he is learning how to expose and develop.

The method of working upon a negative which has just been

described entails printing in a very diffused light if the handwork is not to be apparent. In a strong light we shall reproduce in a print all the lines of which the cross-hatching is built up, and where the pencil and brush marks have a distinct edge this will be visible. By printing in a diffused light these edges and lines disappear, and the final result need not suggest the methods by which it has been attained. Negatives which have been treated in this way can only be used for contact printing, as when an attempt is made to enlarge from them the lens of the enlarging arrangement shows up the handwork. Other methods are therefore used when enlarged work is being done.

The modification that is most often carried out in contact printing is the printing in of clouds, an operation which calls for a good deal of skill if it is to be done properly. The landscape negative, it is very likely, is not dense enough in its sky portion for this to print out quite white. It may therefore be strengthened with matt varnish or paper and blacklead. If clouds are only to be slightly indicated, many workers can do this with a stump on the glass side of the negative. The method which some adopt, of making a silver print, cutting the sky portion out as accurately as possible with knife or scissors, allowing it to darken, and fastening it to the glass side to strengthen the sky, is one which generally results in the making of a harsh line on the print, however careful the worker. Blocking the sky out by painting on the film of the negative with Indian ink, or other opaque pigment, is equally objectionable. Such methods reveal themselves at once, by the different character of the definition along a line made with a brush and black paint, from that which has been given by the lens itself, and are all inferior in their results to the strengthening obtained by the use of a stump on paper or matt varnish. This can often be helped by shading with a black cloth during printing. The landscape portion of the silver print from which the sky mask was cut away may be used as a mask to protect the print while printing in the clouds; but, as a rule, it is easier to do this with a black cloth, as it minimizes the risk of a hard line showing on the print. All such combination printing, however, is crude, and in most cases unsatisfactory. It is preferable, whenever possible, to secure the clouds on

the same plate, which is easily done with an orthochromatic plate and a suitable screen. Such a method is a guarantee against false lighting, and such mistakes as have been seen at our exhibitions before now, when the landscape has been lit, clearly, with the sun on one side and the clouds with it on the other.

The great opportunity for dodging a result comes when the original negative is to be made the basis of an enlarged one, because whereas by working with a pencil or stump, which is much the easiest way of modifying a negative, we can only cause it to print lighter in those parts to which we apply the blacklead, by working first on the transparency in the same way, we can darken portions which we wish to make darker, and then, working on the enlarged negative, we can lighten other parts by the same process. There is also a great advantage in working on a transparency that we are dealing with a positive and not a negative, and are therefore in a position to gauge the exact effect of every alteration we make. The transparency in such a case is best made the full size of the enlarged negative. It may then be covered with *papier mineral*, or tracing paper, or even tissue paper can be used; and work on this is done by applying lead or weak washes of Indian ink to those parts which are to be darker in the final print. Figures or objects which are not wanted can be got rid of with surprising ease in this process by using a little care. To do this we reduce any lights on the figures, as nearly as we can, to the same depth as the surrounding parts, ignoring those parts of the intruding object which are darker than their surroundings. Then, when the contact negative is made from this transparency, we can cover it with paper, and deal with the darker parts, which are now lighter than their surroundings, and are toned down accordingly. When this has been done we shall find that, without calling for any excessive degree of manual dexterity, the object which we wished to remove has vanished.

The two prints which face this page form an excellent example of the extent to which this treatment may be carried when there is any occasion for it. They are by Mr. C. J. Harrison, who writes of them as follows:—

“The original negative was not one of my own, but I am not sure that the offending branches might not have been



TWO PRINTS FROM THE SAME NEGATIVE

BY C. J. JACKSON



removed or avoided during exposure. However, they were not avoided, as the print shows, and it fell to my lot to make the best of this negative. The lower print shows how far I succeeded. Here all the dark branches that fell across the light brickwork were removed with pencil and brushwork on the film side of the negative, making no particular attempts to indicate the bricks, merely getting the retouched portions near the same density, and only trying to introduce the more striking marking, for a brick or so misplaced would hardly be likely to be noticed. The branches which cross the sky part were blocked out solid, as the sky was perfectly opaque. Then, as the finished prints were to be done on bromide paper, I did not trouble to rub down the light branches on the right, but touched them out of the print itself with Indian ink. Only a very close examination would show that these intervening branches had ever existed."

Whenever a transparency is to be worked up, it will be found a great help to take a plain print and sketch on this with crayon until approximately the effect desired is secured, and then to reproduce as far as possible the same effect on the transparency. Some workers employ a more rigid support for their handwork than paper. A sheet of matt celluloid may be used. Mr. Harrison uses thin transparent sheets of gelatine, and these, being cut to the size of the negative or transparency, may be attached to it with gummed paper, or even registered to it without.

For printing in large sizes for exhibition and similar purposes, we can dispense entirely with a printing-frame, and use a drawing-board instead. This allows us much more freedom. The paper, whatever it is, may be of a larger size than the negative, and fastened to the board with four drawing-pins. Then, if we arrange the negative in position on it, we can insert two pins along one long edge of the negative as far apart as convenient, and one pin in the centre of an edge at right angles to the first. Then, if the negative is always pushed up to these three points when printing, it should always be in exactly the same place. The writer uses fine needles for this purpose, which are pushed into the board with a small pair of pliers. In this way the negative can be removed and the entire print

looked at, and the negative replaced in exactly the same position, provided it is pushed up to all three needles. If the paper is fastened to the board in this way, it is quite possible that the weight of the negative itself will be sufficient to keep it in contact; but if not, a piece of plate glass may be laid on the top of it, or a drawing-pin or two used to keep it pressed down. If drawing-pins are employed, we must see that they do not pull the negative away from the guide-pins. If plate glass is used, these pins must be below the top surface of the negative, or the plate glass must be pushed up to them as well as the negative. These and other points will suggest themselves to the user of a drawing-board instead of a printing-frame.

A very ingenious printing-frame for use in this way has recently been invented by Mr. Nelson K. Cherrill. It is arranged so that any number of masks or negatives can be brought as often as required into absolute register on the one piece of paper, so that a print can be continuously modified while it is being made. Thus we can print it a little, interpose a mask to prevent the sky, let us say, from printing, while the rest is carried deeper. We can then take the mask away and print the whole negative a little more, or inset a fresh mask. After each of such alterations we can look at the entire print and see exactly how we are progressing.

Amongst the minor devices, which may well be considered at this point, are spotting and sunning down. However careful a photographer may be, he will occasionally get negatives which have some slight defects, either in the form of transparent or of opaque spots. To prevent these from showing in the prints, the negative must be "spotted." This is done with a fine brush and a little opaque water colour. Indian ink does very well, but special colours are supplied for the purpose. It is a mistake to have the brush too fine; if it is a good one it will come to a point, which will allow very difficult work to be done, even if the brush itself is comparatively large. A very little of the paint should be used, the most important condition being that the brush is almost dry. Assuring ourselves of this by trial on a piece of white paper, each transparent spot is just touched with the tip of the brush, so as to make it print out white. When the print is made, a little colour is mixed up, so

as to match its tone, and then this is used very dilute, and again with a brush that is almost dry, to touch out the spots. It is quite surprising to those who have never tried it before to find the ease with which the most disconcerting spots can be taken out. But the brush must always be in such a condition that it will only make five or six spots before it becomes too dry to mark the print at all. As a rule, it is not possible to get the colour dilute enough by rubbing the brush on the pigment; but a little being obtained in this way, a drop of water is put on a piece of paper, and the brush is worked up with that until it is seen just to tint the paper sufficiently for use.

Sunning down is a method not used as much as it might be. If we take a print just as it comes from the printing-frame, and expose it all over for a very short time to the light, we shall find, of course, that the highest lights will discolour more noticeably than the shadows, and that the result will be a print that is not so hard as it was before. If the sunning down is carried too far, the print will seem degraded and unpleasant; but there is no need to go as far as this. Moreover, if we will, we can localize the sunning down. A piece of tracing paper may be stretched on a sheet of glass, or a piece of ground glass may be used, if preferred; and putting this on the print in a light which has no effect on the sensitive paper, we can go over the outlines in pencil, and then apply blacklead or other medium to those parts which we do not wish to sun down, leaving the rest clear. The glass being held in position on the print, it is exposed to daylight until the necessary action has taken place. In spite of its name, sunning down is not a practice to be carried on in the sun, but in a diffused light, so that it may be well under control.

If the negative is one in which the definition is too keen throughout, there are various ways in which it can be softened. Very large negatives may be printed through the glass, or if the reversal which this brings about is objectionable, a thick piece of glass may be interposed between the film and the paper. A stout sheet of matt celluloid is more useful for this purpose, as the diffusion obtained with it is not so marked, but is often quite sufficient. A sheet or two of tracing cloth or of bolting silk may sometimes be used to advantage for a similar



purpose, but the commonest method of getting rid of wiry definition is by the use of a rougher printing surface.

When enlarging direct on to bromide paper, there is not so much opportunity to modify the result as when enlarged negatives are to be printed by contact ; but a great deal is possible, nevertheless. The use of a lantern for the purpose allows the photographer to intervene between the lens and the bromide paper. In this way, by the use of a card, he can shade parts of his subject, while letting the rest have further exposure. A sheet of glass, with a piece of card stuck in the middle of it, may be used if the part to be shielded is surrounded by parts which are to be exposed, or the card may be fastened to the end of a wire. Whatever screening is attempted, the screen should be kept moving all the time to avoid harsh lines.

Focussing when enlarging allows of a certain alteration being brought about, if the original is too hard ; but "bolting cloth," or "bolting silk" as it is sometimes called, is still more convenient. This is a very fine fabric of regular texture, which can be obtained from the Kodak Company, to whom we owe its use in photography. It is best to stretch it on a piece of glass, or on a wooden frame, for use. If the bolting cloth is placed on the surface of the bromide paper during exposure, it will break up the image into little dots, almost like a half-tone picture, such as most of the illustrations in this book will be seen to be on close examination. Such an arrangement has its use in making the blackest parts of the enlargement less black, while the highest lights are hardly affected. It does not make much difference to the definition, but softens contrasts a little. But if the bolting cloth is slightly separated from the surface of the paper, it not only softens contrasts somewhat, but also softens the definition to an extent which depends upon its distance from the paper. Within certain limits, it may be said that the further it is off, the more blurry is the definition, until we reach a point where its effect begins to fall off again. If we move it still further away, it has no effect on the definition at all. Bolting cloth calls for a distinct increase in the exposure that must be given to the paper—generally from 25 to 50 per cent., but this depends on its distance from the paper. The easiest way of regulating the distance is to have a few pieces of glass of different thicknesses, and to interpose one or other

of these between the bolting cloth and the bromide paper. The latter must be perfectly flat upon the easel, or it will not be equidistant from the cloth all over, and the definition will vary accordingly.

There are other methods of bringing about alterations during enlarging, only one of which need be mentioned here. If we have a negative which will give an excellent enlargement in every respect but one, viz. that it is a little too harsh in its contrasts, it is often possible to soften it by giving nearly all the exposure necessary, and then holding a piece of card in front of the bromide paper. The front of the lens of the enlarger is then breathed on, and the disappearance of the moisture caused by the breath is watched on the card. When it has nearly (but not quite) gone, the last few seconds of the exposure are given, with the result that the enlargement is distinctly softer in its contrasts, without being blurred in definition.

Combination printing from two or more negatives is not difficult to any one who is able to apply to it the methods which are now being dealt with. It is easiest perhaps with the lantern, enlarging on bromide paper. To do this an enlargement is made from one of the negatives, shading with card those parts which are not required. The enlargement is then developed and washed, but not fixed: is blotted off with clean blotting paper until quite surface dry, and is then again put on the easel. The parts already developed are masked with black paper, any fine edges being protected by painting them over on the wet enlargement with photopake, and a second exposure is given. The photopake is then washed off, and the paper again developed. If the first exposure was correct, and the paper developed right out, the second development will have little or no effect upon it. Mr. Baskett has described a somewhat similar plan by which clouds can be printed in and other combination work carried out. The developed print is fastened on the easel with glycerine, and the clouds are developed up during the exposure by applying developer mixed with glycerine to those parts which need it.

Another form taken by combination printing is the preparation of an enlarged negative, which embodies parts of two

or more, and from which combination prints can be taken by straightforward printing. This is a method often used for the introduction of clouds into an enlarged negative. Having made an enlarged transparency of the landscape portion, the sky of which is practically clear glass, any light parts elsewhere on the transparency are painted over on the glass side with opaque water colour. Then, after focussing the cloud negative on the enlarging easel, the plate on which it is to be enlarged has the landscape transparency placed on it film to film, and, using the transparency as a mask, the exposure is made and the cloud-enlarged transparency is developed. Landscape and cloud transparencies when finished are bound up carefully together in register, the glass side of each is cleaned, and a negative is made from them either with further enlargement or same size in the camera. Other combinations can be carried out in the same way.

Little has been said about the process known as "retouching," because it is hardly an amateur's method, since it is occasioned more from the desire of the sitter to obtain a smooth and flattering portrait than from any recognition of its photographic necessity by the photographer. It is certainly best left alone, at least so far as the form in which it is usually known is concerned; but there are times when a little hand-work of the same kind will save a lot of after trouble with the prints. The first necessity is the application of something which shall give a tooth for the pencil. A special kind of varnish is sold for the purpose, known as retouching medium. A drop of this is applied by the finger to the part of the negative, on the gelatine side, which is to be retouched, and rubbed over until it feels "tacky," when it is put aside to dry. In the mean time some arrangement must be fixed up by which the negative can be supported at a convenient angle with the light behind it. A large printing-frame, with a piece of glass in it, will often serve, and on the glass may be put a piece of card to support the negative on its top edge. A good quality H pencil is the best to use, and this should be most carefully sharpened to a very long fine point. The tip should be an inch or more from the commencement of the taper. Fine emery paper is useful to give the last touch to the lead point. When the medium is quite dry and hard, we may





VIGNETTE  
BY H. WILD

place the negative on its support, and then proceed to work upon it.

The method of retouching must be left to the taste of the worker. The easiest plan the writer has always found is to make short, fine lines side by side. In fact, it resolves itself into delicate, but not "niggly" shading. There should be no attempt to get a lot of lead on in any one place by using a soft pencil or exerting any pressure, as this will result either in removing the medium or in breaking the point. Stippling a series of dots will often serve, while Mr. Harrison, who has been already quoted in this chapter, advocates working with a fine circular movement of the pencil, taking it off as little as possible, making a continual series of minute rings, keeping the pencil on the negative and always on the move, running lightly from one little defect to another, filling in thin places, blending all the harsh lights and darks, until the effect desired has been obtained. It is a good plan to start retouching by taking a negative of, say, some foliage which is a little inclined to appear spotty, and endeavouring, by the use of the pencil, to make the more transparent parts of the negative print lighter, so that the spottiness is less pronounced. Not only is it excellent practice, but such an application of retouching is more likely to be useful to the amateur photographer than is its employment in portraiture, which calls for other skill and knowledge than the mere ability to darken a light patch to the depth of its surroundings.

The vignette by Mr. H. Wild, which faces this page, has been obtained by a process which allows of the very easy removal of those parts of the picture which are not required, when that picture is on bromide or gaslight paper. Here also it is well to make a guide print first, and to try the effect of different alterations upon it with chalk, before actually setting to work on the final print. When the effect that is wanted has been obtained on the guide print, we may keep this before us while we modify the final picture. The method consists of the application of a reducer, which is made by mixing one part of a saturated solution of iodine in alcohol with two parts of a saturated solution of potassium cyanide (extremely poisonous) in water, and diluting this with water to suit the particular purpose in hand. "Some cotton-wool," says Mr. Wild, describing

his method, "a sheet of glass rather larger than any print to be treated, some small camel-hair brushes in quills (as cheap as they can be got, as they do not last long), and, if running water be available, a large dish of water in the sink—if not, two large dishes on the bench, with the water frequently changed will do—and three or four small saucers such as are used by architects for mixing water-colours, complete the equipment.

"In two of these saucers about three drops of iodine solution and six drops of cyanide are put. To one we add about half a drachm of water, and to the other about a drachm to a drachm and a half. The chalked print is pinned up where it can be seen, and, placing the dry print to be treated on the glass, a brush is dipped in the stronger solution, and all that is not required is roughly wiped out. It must not be taken out too closely, as at this stage a hard line will be left, which must subsequently be softened, so enough should be left to work upon. All parts that are to be taken out cleanly, such as chimneys on a house, boughs of a tree, or any other parts that are to be cleared away altogether, should be done at this stage, before the print is wetted.

"Having done this, the print should be rinsed well (for preference under the tap) at the same time lightly wiping the surface with a wad of wet cotton-wool. This should be left in one of the dishes of water just at hand, as it is wanted frequently, and sometimes in a great hurry. The wool is squeezed as dry as possible, and the surface moisture wiped off the print as it lies on the glass. We now proceed to soften and break up the hard edges, and to shade off where required. I find the best way to do this is as follows: the wool, full of water, is put on one corner of the glass, where it can be seized in a moment. A brush is dipped in the weaker solution, and wiped over the darker edges, and the solution so applied almost immediately wiped off with the wet wool. The wool is squeezed out, taking off surface moisture, and, if necessary, I go over it again, and continue this until I get the effect wanted. For the lighter parts it is advisable to weaken the solution still more. The weaker the solution the easier it is to get delicate gradations. When we have nearly finished, we shall probably find that some little dark bits, not noticeable before, will now look as if they

should be reduced in strength, or removed altogether. The print is rinsed, the surface wiped, and blotted with clean blotting paper. Then, with a small brush, or, for very small spots, a match sharpened to a point, we can take up a very little of the stronger solution and carefully paint over the parts to be treated. Only one bit is attempted at a time, and the wet wool is kept ready to wipe off with, while the effect is still a little darker than is wanted finally. A good washing completes the process, and it will be seen that the purely technical part is reasonably simple."

A method of obtaining very similar results on platinum prints by the use of glycerine was dealt with in Chapter XV. The guide print, upon the usefulness of which Mr. Wild lays stress, is even more valuable in this case, because of the fact that we are working from white to black, and not *vice versa*; it is, therefore, very helpful to know exactly what it is we want to bring out in each part. There is no satisfactory method of reducing the platinum of the platinotype print in the same way that the iodine and cyanide solution will reduce a bromide print. Other reducers, moreover, are not applicable to a bromide print for the same purpose, because in removing the parts which are not wanted they give rise to a distinct change of colour on the vignetted edges.

In leaving the subject of "dodging" or "faking," let us add a word of caution about its misuse. There is nothing to which the purist can take exception in any of the processes employed to alter the strictly photographic result, provided always that the purist is not able to detect that they have been employed. If their use is apparent, then it is to be deprecated, not because it is not pure photography, whatever that may be, but because the art of the photographer has not been successful in concealing his art. Few indeed are the photographs that cannot be improved by judicious handling, but when that handling asserts itself as handling, it is no longer an improvement.



## CHAPTER XXI

### LANDSCAPE PHOTOGRAPHY

Pure landscape characteristically British—Size of camera—The lens—Films and plates—A view meter—Exposure meters—What not to take—The disappointment of panoramic views—Where to find subjects—Woodland scenes and tree studies—The fashion in subjects—Shipping and marine—Wave studies—The rendering of movement—The hilly road—Snow and frost pictures.

**W**HAT finer amusement can be desired by the lover of nature, with all the British fondness for fresh air and outdoor life, than to wander through the fields and woods, drinking in their charms of sight and sound and smell, with just that pretext for his stroll afforded by the camera. The fisherman claims that his sport brings him closer into contact with Nature than can be got by any other means whatever ; but the landscape photographer may fairly challenge comparison with him. Whether he go abroad in the fresh summer morning, before the mists have cleared in the valleys and the flowers of the day have opened, or whether his shadow stretches far behind him as he turns to watch the glorious colouring of the setting sun, he is in touch with Nature, can note and study all her changing moods, and can endeavour to get, and may often succeed in getting, pictures which will recall to him, and perhaps to others, some of the delights he experienced in the making of them.

No class of subject, therefore, appeals to the amateur photographer in this country like landscape, and, to judge from the exhibitions, landscape without figures. This last is the result of the difficulty of introducing figures which shall seem spontaneous and natural—figures picturesquely clad, and at the same time free from any suggestion of the theatrical “countryman or milkmaid.” The pure landscape—such as Mr. Job’s “On the Arun,” or Mrs. Dumas’ “St. Martin’s Summer,” to

name only two examples—is the most characteristic product of British pictorial photography; and to obtain pictures of this type is the whole circuit and extent of the ambition of many a photographer.

The technicalities of the production of a good photograph of an outdoor subject are comparatively simple. Most of such work lies within the range of the user of a hand-camera, although, if he is wise, he will provide himself with a light tripod, as a support of some kind allows more careful selection and arrangement of nearly every subject, while under trees and in woods the exposure will often make it not a convenience but a necessity. "What should be the size of a camera for landscape work?" is not an unusual question. The reply has to be guarded. What weight of apparatus is the photographer willing to carry about the country? Two of the author's friends tramp the fields and lanes together, carrying respectively a  $12 \times 10$  and a  $15 \times 12$  outfit, each with one double slide, generally containing films or negative paper. With them may occasionally be seen just as great an enthusiast with a quarter-plate instrument and pockets full of dark slides. To judge from the photographers to be met with engaged in the work, half-plate is perhaps the most popular size of all, and one of the cheap 'stand-camera' outfits, with a rapid rectilinear lens and a roller-blind shutter, will do all that is wanted in most cases.

The lens used on landscape work pure and simple is oftenest a rectilinear; but, as Captain Cuttle said on a memorable occasion, "Lord, it might be anything for the matter o' that." We should certainly not have had the modern triumphs of the optician had the needs of the landscape photographer alone been in view. No lens could be so bad as to be incapable of use in that work, and a pinhole, except for the length of exposure it entails, gives a quality of definition which many would like to be able to get with a lens. The single lens is often referred to as a "landscape" lens, because its one ineradicable defect—the curvature of lines that are straight in the original when they fall near the edge of the plate—is then immaterial; but the term is somewhat of a misnomer. A single lens is at least as suitable for portrait work, and, if of good quality and not used at too wide an angle, may also be

employed in architecture. On the other hand, any lens will do for landscape photography, and will do well, the principal thing of importance being its focal length. Too wide an angle is a defect, because the illumination in all wide-angle lenses falls off rapidly towards the edge of the plate, and therefore they are to be avoided when the subject does not demand them. In landscape it very seldom does. Moreover, the wide-angle lens tends to dwarf distance, and this in most landscapes is exactly the opposite of what the photographer wants. A convenient focus will probably be found to be about the length of the longest side of the plate, if the lens is a doublet. This will allow the back half of the lens to be used with most landscape cameras. In this way an image on about twice as large a scale as with the complete lens is obtained. If a single lens only is to be used, it may well be of longer focus than the doublet—say, half as much again. The caskets of spectacle and other lenses are very suitable, as with three or four lenses ten or a dozen combinations can be secured, giving a range of focus which will suit almost every imaginable requirement.

It is in outdoor photography especially that the advantages of films are so apparent. Their lightness allows more to be carried than could be done with plates, while they are unbreakable, and, greatest merit of all, are daylight loading. Until a few years ago it was a reproach against roll film that it was not orthochromatic, but that has now been removed. In very large sizes cut film takes the place of roll; or negative paper may be used with considerable saving in weight and little loss of efficiency. Even ordinary bromide paper has been used for negative making; but the coating of emulsion on it is purposely kept very thin, and therefore it does not have that long range which is such a characteristic of a plate or film made for negative work. Orthochromatic plates will be found to offer great advantage over ordinary, particularly if used with a screen. Indeed, in no work is their superiority so manifest as when they enable us to get clouds and landscape on the same plate, and when they differentiate between the light spring green of the new foliage and the deeper shades of the evergreen, which the ordinary plate renders practically alike and both far too dark. Backed plates are, of course, used invariably by all except those who are willing to sacrifice a certain

degree of quality to obtain a little diminution in trouble or expense. Very rapid plates are not so much a necessity in landscape work as in much other photography, but at times they are a boon. Particularly is this the case in windy weather, or when there is much light foliage in the foreground, stirred by the least breath of air. Those are the times when the shutter is most useful, not only for the short exposure obtainable in no other way, but for the liberty to watch the subject and to expose exactly at the right moment, without taking the eyes off it.

Those who use the hand-or-stand type of camera can carry it open and employ it as a view meter; but when the ordinary landscape pattern is adopted, particularly if it is half-plate size or larger, it is often inconvenient to carry it in any way except in its case. Instead of unpacking and setting it up every time there is any idea of taking a photograph, we can then add a simple form of view meter to our outfit, which will save a lot of trouble in this direction, by allowing us to settle upon the subject before the camera is taken out at all. The best form of meter is one which can be constructed at home in a very few minutes, out of a piece of card and thread. The card, which is best blackened, should have an opening cut in it the same shape as the plate, and with its two sides in the same proportion. By drawing the pencil round a plate put on a piece of paper, the proportion is easily obtained. We draw the diagonal of the plate very carefully on the paper, and then any rectangle we construct in the angle at one end of the diagonal will have its sides proportional to those of the plate, if its diagonal coincides with that of the plate. A convenient size of opening for a view meter to use with a half plate is one  $3\frac{1}{4} \times 2\frac{3}{8}$ , or with a whole plate  $3\frac{1}{4} \times 2\frac{1}{4}$  inches. The width of margin all round the opening should be at least half an inch. The thread is fastened to the centre of one side of the card, and is marked at distances which bear the same proportion to the side of the opening as the focus of each lens available bears to the corresponding side of the plate. By holding this card up as far from the eye as is indicated by the mark on the thread and closing the other eye, we shall see in the opening exactly the subject that we shall get on the plate, using the lens whose focus corresponds to the mark

Where there are several lenses we can try the card at different distances from the eye, and in that way decide whether the subject is suitable or not, and, if so, what lens will be required. Such an instrument can be slipped into the pocket and saves a lot of packing up and unpacking.

The exposure meter is never of more service than in landscape photography, since there is so great a variety in the character of the subject and the strength of the light that reaches it. On the same afternoon we may have a cloud effect or distant view fully exposed with a hundredth of a second, a group of cattle requiring perhaps a tenth, a mass of undergrowth and moss-covered trunks with thick overhanging branches calling for two or three seconds, all with the same stop. Thanks to the orthochromatic plate and yellow screen it is now possible in many landscapes to secure the clouds on the same plate as the rest of the picture.

The earliest lesson the landscape photographer has to learn is that of what not to take. We have all suffered under the well-meaning friend who has guided us up to some place where there is "Such a lovely view; just the thing for your camera," and in common politeness we have enthused, and put up the tripod and made an exposure on it; but with what a result! The expanse of country which looked so fair and wide and luxurious as it spread out before us for miles, dotted with homesteads and woods, with the silver ribbon of the river winding through it, now bending round the hills we know, which from our present position hardly seem to rise above the general level, now flowing by the little church and beneath the old stone bridge, the whole panorama stretching out clear and unmistakable right up to the purple hills in the distance, is this the photograph of them? That white streak, can that be the river? And that dull grey patch cut off from the top of the print by a blank stretch of white. Do not say that that is photography's version of the delectable mountains and of the masses of cumulus that flecked and dappled them as the clouds floated by the sun. The church we find after much careful scrutiny; but the fields beside the river and the woods that crown the little hill are indistinguishable in tone from each other or from the houses. That is the camera version of the scene. The charm of colour we did not expect to get; but

the photographer who is making his first attempt at such a view may be forgiven if he expected a little more than this.

He forgot that his impression was not obtained by looking at some little bit of it through his view meter, but that he was conscious of the expanse around him, and that he turned his eyes from side to side, deriving a broad and general impression which the camera cannot render at all. The details stand out largely because of their colour, the blue haze through which the more distant objects are seen does not hide them from the eye to the extent that it cuts them off from the lens, and we are conscious of foreground objects with decided outlines and casting bold shadows, even if they are not included in our view for the moment. All these, of course, are absent in the photograph, which may just serve to remind us of the extent of the prospect, but can never convey a faithful impression of it to any one else.

The camera craves for some object near at hand with decided outlines, with bright lights and deep shadows, something on which the eye may fasten as the subject or dominant point in the picture ; and this is just what is sure to be wanting in the panoramic view. The impression of space or extent is there to the eye, but it can only be conveyed in the photograph by having some object in the foreground beyond which the space is suggested. In plain language, there must be a mark from which the eye can measure, though the distance may be indicated by nothing more than the difference of tone.

For particular purposes views of wide expanses may be taken, but they are hardly to be regarded as examples of landscape photography in the ordinary acceptation of the term. It is often useful to have such a view, including a much wider angle than any ordinary lens would give, and for this purpose panoramic cameras have been devised, some forms giving the entire circuit round their standpoint. If one of these is not at hand, the ordinary camera may be used to take a succession of pictures, which are subsequently to be mounted up side by side. To do this the tripod top must be carefully levelled, and not moved afterwards until the whole series is complete, or the consecutive pictures will not follow on properly. In any case, it is better not to attempt to join them up in contact, but to mount them with a narrow space between each. The eye then

overlooks any slight lack of register, which otherwise would attract attention, to the exclusion of nearly everything else. The Panoram Kodak is a very popular instrument for views of this type, but even with it panoramas are sure to be disappointing, and it finds its best use when employed on subjects which demand a very wide angle, but subjects in which the interest lies essentially in the foreground.

In selecting a place in which to do landscape work, a photographer, if he wishes to do more than get a few pleasant mementoes of his visit—and most of us aim higher, whatever we reach—should be guided by his own liking for some particular type of scenery or some particular effect. One will find that wide stretches of flat country, broken only by dyke and hedge-row, and dotted here and there with church or windmill, seem to his eyes to offer more pictorial possibilities than woodland or hillside; and he will be wise if he tries to do his landscape work in the surroundings he finds so congenial. For years at the big London and other exhibitions pictures of this sort predominated to an extraordinary extent, and the flat country at the estuary of the Thames and the mouths of the Essex streams formed the happy hunting-ground of numberless photographers. Some went because they felt in sympathy with the subjects to be obtained there, but many were undoubtedly led to go in consequence of the work they had seen others do in that neighbourhood. For the typical English landscape of stream and pasture, quaint locks and timber bridges, that Constable loved to paint, many go to Constable's own country, making their headquarters at Dedham, near Colchester, a kind of photographic Mecca. It is a very delightful spot, though terribly hackneyed. The hills and valleys of Derbyshire, of North Yorkshire, and of the Wye and Severn district are more to the taste of some; while for peaceful river scenes, only failing, if at all, from being even too picturesque and sentimental, there is the luxurious Thames. All of which only comes to this—that the landscape photographer will work best in the country he knows best and loves most. Let him therefore be guided by his own inclinations, rather than allow himself to be tempted to pastures new just because he has seen fine work done there by some one else.

Woodland pictures pure and simple are the easiest, as far

as access to the raw material of which they are made is concerned; and for that very reason work in this direction is harder if it is to be fresh and original. The dweller in the country will know his own district well enough to find what he wants. The city man may need some direction, but should not want much. The Londoner is particularly fortunate in the beautiful commons and woods that lie only a few miles from the Metropolis along its southern edge, and in Epping Forest, stretching away for miles to the north-east. There is an immensity of material in the Forest for those who care to find it, though it is quite possible to walk far without seeing anything but brushwood and little unimportant shrubs. Some of the beechwoods there are magnificent, and there are silver birches, too, for those who admire that most graceful of trees.

The photographic possibilities of the silver birch were first forced upon the attention of photographers by the pictures of Mrs. Dumas, of W. Thomas, and of Charles Job (see the plates facing pp. 112 and 256), and when once these workers had shown the way, a host of others followed; and the Essex marshes were succeeded by a "birch-and-bracken" epoch. Later, we had years when ploughing seemed to have monopolized photographers' attention, and anon flocks of sheep, then landscapes seen through doorways, and the like. These are not given as hints for subjects, but rather as examples of the tendency there is towards a fashion or craze for some particular class of picture. It is best to leave such to those who care to make them; it is only one or two pictures by the pioneers that cling in the memory, and the host of imitations pass away and are forgotten. If silver birches, or sheep, or teams ploughing take the fancy, by all means use such material; but let the treatment be personal and individual, and the picture more than a mere echo of another.

Shipping and marine subjects generally, although not perhaps in the strictest sense landscapes, may well be treated here. No one has done more in wave pictures than Mr. Mortimer, and he has kindly allowed us to reproduce one (see the plate facing p. 316). This is a class of work altogether apart, and as practised by Mr. Mortimer in winter on the wild and stormy coast of the Scilly Isles, it is perhaps the most exciting and dangerous form of photographic picture making. A tripod is



of little use, the photographer must carry his camera, both in oilskins, and must use it much as it is employed in ordinary hand-camera work. "The ideal camera for wave photography," says Mr. Mortimer, "would be a box camera of the magazine type, absolutely waterproof, and with no projections whatever beyond, say, the shutter release, focussing screw, and view finder." The lens should be of fairly long focus, about 8-inch for  $5 \times 4$ , or 10-inch for half-plate, and a roller-blind shutter, working in front of the lens, with adjustable speeds up to one-hundredth of a second, and also a focal-plane shutter, would be required. The shutter must be in front of the lens, as otherwise there is nothing to protect the glass from the spray, which would cover it and prevent photography in a very few seconds. An exposure of an eightieth of a second with F/16, with a fairly rapid plate, will be found to be about correct for many wave studies. This is a type of subject wherein there is not merely the exposure required by the plate to be considered, but also the exposure necessitated by the movement of the subject. If the exposure is too long, the flying spray and swirling surf are blurred into indistinctness; while too short an exposure, such as that obtained with a focal-plane shutter working at its fastest, or almost its fastest, say one five-hundredth of a second, gives every detail so hard and sharp that the water seems lifeless or frozen, and all sensation of movement is lost.

The rendering of movement, the photography of objects in motion so that they shall appear in motion, has always been a difficult problem. With fast plates and a fast shutter it is not difficult, if the light is good, to get them so that they shall not show much sign of movement; but, then, that is not at all what is wanted. An express train, flying along at sixty miles an hour, might be photographed so that all its details were sharp and distinct, and the photographer might be very proud of the result. But pictorially there might be nothing to indicate that it was not standing still at the time. The painter gets the effect by showing the wheels as little more than a swirl; but no exposure that the photographer can give could show them anything like the painter's version. All he can do is to take care that the rapidly moving parts are not too crisply rendered, and help the effect as far as he can by the driving back of the



A WIND SEA  
ON R. 1. NORTHWARD



steam in the case of the train, by the cloud of dust from the motor-car, by the attitude or pose of figures riding or driving, and so on. It is one of the hardest pictorial problems to encounter in photography, and may well be put beside the photography of a hilly road. Let the photographer who knows a steep hill in his neighbourhood, if he is fond of grappling with difficulties, sally forth to get a photograph of that hill which shall in any way convey a suggestion of its steepness. The vertical lines of a house contrasting with it may seem an easy solution ; but the house is not always there, and it is not possible always to show its lines so that they sharply contrast with the hill. Carefully posed or happily caught figures may help to give the right impression ; but the almost impossible character of the task will surprise many who will think at first that, if it is a steep hill, it will look a steep hill in the print. It may appear as such to the photographer, because the print recalls the hill to him ; but let him try the effect on some one who does not know it.

Snow and hoar-frost subjects are often very tempting, but their photography has difficulties of its own quite apart from those of cold feet and benumbed fingers. Hoar-frost generally resolves itself into the question of a suitable background to show up the delicate tracery of the rime-encrusted branches ; but in snow scenes the trouble is to get snow that looks like snow. The texture of the snow surface cannot be represented by unsullied white paper ; yet that is all that stands for it in many a snow picture. When we look at a snow-clad field, more especially when the sun is shining—but not then only—we cannot help being struck by the variation in what, without study, we might think was an even stretch of white. We see, plainly visible, a grain or texture over the white surface, and, besides this, a constantly varying tone due to the hummocks and depressions caused by the uneven ground beneath. Over and above this, we have the unevenness due to footprints, cart tracks, and the like, all of which may be valuable helps in picture making, and some at least of their appearance is essential if our snow is to suggest snow in any way. There are two means by which this end can be furthered : one is in the lighting, the other is development. If we stand in the middle of a snow-covered field and look around, we shall find

that in some directions the characteristic surface is much more clearly seen than in others, those directions being governed, of course, by the position of the sun, or the quarter from whence the strongest light falls. As the surface is not so easy to get at any time, we try and arrange our picture so that the lighting is secured that emphasizes it most. Then, again, in development, the snowy surface will probably be the highest light in the picture ; but it must be kept thin enough for its detail to print out. Many a snow scene is spoilt from no other cause than over-development, with the idea of getting plenty of contrast, the result being that printing, if carried on long enough for the snow, has gone much too far for everything else. Those who are keen after pictures of this type will find a word of warning about the time of day may save disappointment after a snowfall. We can hardly start too early in the morning, provided it is daylight at all. The best effects are almost invariably to be secured at sunrise, or shortly after, and by eleven o'clock on a winter's morning much of its beauty may be vanished, the sun covered by the mist which precedes another fall, or else powerful enough to turn what was a glittering lace of hoar-frost into black and dripping branches.

There is no need, nor indeed is there space, to deal one by one with the many classes of subject into which landscape, or rather outdoor, photography might be divided. Each has difficulties of its own, each calls for particular treatment in some way, and each has its own charms and its own followers. It is the widest of all the divisions of photographic work, the most popular, and the most fascinating. Whether we take our cameras to the coast, where sea meets land in daily strife, or whether we wander by brook and meadow, where everything breathes of peace and quiet, we are in touch with Nature, led to study her in one or other of her many moods, and to take from her not merely pleasure and delight in the present and in anticipation, but that freshness and strength which the open-air life and the pure but absorbing mental occupation go hand-in-hand to give.

## CHAPTER XXII

### ARCHITECTURAL PHOTOGRAPHY

Cathedrals and churches—Interiors—The use of the exposure meter—Backed plates and halation—Perspective and point of view—Wide-angle lenses—The level—Most suitable type of camera—Anastigmats—Focussing dark interiors—Supplementary illumination—Living-rooms—Views through windows—Permissions to photograph—Their abuse.

THE photography of architecture may be approached either from the recording or the pictorial point of view; the object of the photographer in the one case being to obtain a delineation of some architectural feature or detail, and in the other to secure some passing phase or effect to convey to others the impression which the work makes upon him. This latter aspect of the subject hardly concerns us at present. The magnificent cathedrals and churches of this country are the inspiration of many a photographer, and few more delightful occupations for those who like camera work can be imagined than a summer day spent

“Where spreading oaks embow’r a Gothic fane,”

following reverently the mind of its designers, and recording the details of shaft and capital, door and buttress, that take the fancy or lend themselves to delineation.


Moreover, for the effect secured the work is easy. The structure stands unmoved, and we can expose just so long as we choose. The lighting, as a rule, is bold and simple, and the difficulty of getting enough contrast in his plates is not likely to trouble even the beginner. It has difficulties of its own, but they are not great. The problem of exposure, approached in the way described in Chapter X., solves itself. The exposure meter in interior work is not to be held in the deepest shadow that can be found in the subject, but in some light which represents fairly the average illumination of the subject, the face of

the meter being turned towards the source of the light. As in this work the time taken for the paper to darken to the full tint is often very considerable, the quarter tint will be found to be sufficient guide ; this, in the Watkins meter, is the lighter of the two tints provided. Even then the time taken may be longer than the photographer cares to spend before commencing to expose. A very simple plan in such a case is to use such a stop that, with the plate employed the time taken for the quarter tint to be reached is the correct time of exposure, and then to start exposing both the plate and actinometer paper together. When the latter has darkened to the tint, the lens is capped. If a smaller stop than the one so indicated is necessary, it is easy to prolong the exposure accordingly ; but this hardly ever happens. With an ordinary (not extra rapid) plate, the Watkins quarter-tint is generally the exposure required with  $F/32$ .

Outdoor work on architectural subjects calls for no special notice.

If there be one purpose for which backed plates are more than ever necessary, it is in interiors. The range of light is so great, and the strongest illumination is often so close to the deepest shadow that, without proper backing, halation is almost sure to be troublesome. Round a brightly lit window, even with a backed plate properly exposed, there will often be noticed signs of halation. It is a mistake to regard these as a defect ; as if such a subject is looked at critically, it will at once be apparent that the effect can be seen with the eye also. In fact, round any very brilliantly lit object there is always a certain glare, and if the true effect is to be secured in the photograph, that glare must be shown.

Without trenching on the subject of pictorial photography, a few hints on the arrangement of architectural subjects may not be amiss. The direct square front view of a building is nearly always unpleasing. The effect given is too much that of a geometrical design or elevation, and an improvement is at once manifested when the building is regarded more at an angle. At the same time, this must not be overdone, for the camera placed opposite one corner—the line from it to the corner exactly bisecting the angle of the corner itself—gives a result even worse than the "straight-on" view. The actual







angle must be decided by circumstances ; but it does not need a very great departure from a front view to obtain the best effect, as a rule. In the same way, the camera should not be set up in the centre of an aisle or colonnade, but a little to one side or the other. In this case it may point straight down the aisle, taking care that the more interesting side is that which is the more fully shown. In subjects such as this we have to be careful to make the picture complete. That is to say, important architectural features must not be shown in a truncated form : a heavy arch should not have its supporting pier or column removed : nor should a prominent column be shown without its base. If the arch must be included, its contour should leave the picture while it still tends upwards, so as to avoid any feeling of want of support or instability. It is as bad, or even worse, to get the principal feature just on the plate, so that the first feeling aroused on sight of the print is what a close thing it was that it was got on the plate at all.

Another point worth mentioning is the avoidance of an unusual standpoint. The architect built for his work to be seen from the height of the eye, say 5 feet from the ground, or thereabouts ; and, as far as we can, if we are to avoid an unnatural appearance in the print, the camera should view it from a similar position. It is often much more convenient to take advantage of some elevated standpoint to get the view we want, but the view suffers. Nothing gives a more unsatisfactory rendering of some architectural feature than the appearance in the print of the upper surfaces of details and mouldings that were manifestly intended to be seen from below. Such a standpoint also leads directly to a very common failing in architectural work, and that is the inclusion of insufficient foreground. This may arise also from the use of the rising front too heedlessly. The sense of space in front of the work that is being photographed is lost when the vertical lines of the building are only allowed to meet the ground close to the bottom of the picture.

These are only general considerations, and must be modified according to circumstances ; those circumstances nearly always resolve themselves into insufficient room to get the camera far enough away from the subject to allow of the use of anything but a wide-angle lens. The wide-angle lens in

architectural interiors comes in for a lot of abuse ; but it is open to question if it is not better to employ it constantly, even when there is just room for one of longer focus to be used. If this course is followed, and the photographer is able to screw his courage up to the sticking-point and trim his prints down ruthlessly, he is less likely to find, when he comes to consider his finished print, that he has cut things too fine, and that in order to be able to use his long-focus lens he has just sacrificed a bit of foreground which is almost a pictorial necessity. If the wide-angle lens is always used as suggested, it must not be made a pretext for getting close up to the subject, as then the perspective will seem forced. It will give us pictures on a smaller scale than the long-focus lens, and that we must put up with, or enlarge, but the power it gives of making the final selection of the subject to be included on the finished print instead of on the focussing screen is a very valuable one.

The level is a necessity in architectural work, and the photographer, who does not want to have distortion caused by tipping the camera, will be wise if he provides himself with something more than one of the little patterns made for attaching to the camera. The best of all is a metal square, with a spirit-level let into one side ; many of the tool shops keep it. One side is placed on the ground glass itself, and the level will at once indicate any departure from the vertical. Failing this, a plumb line, such as can be extemporized from a piece of thread and a bunch of keys, will be found the most convenient.

If much architectural work is to be done, that fact ought to be borne in mind when the camera is being bought. Some workers have expressed a preference for a camera with taper bellows, the back fixed and the front racking out ; but a better form is the rather old-fashioned square type, focussing from the back as well as from the front. Ample swing on the back should be provided, especially if telephotographic lenses are to be used on distant details, and in that case a strong firm tilting table is almost a necessity. A more important feature in the camera used for architecture is the rising front. A very common defect is insufficient rise ; nothing limits the photographer so much. It should be possible to raise the lens until its top edge is in a line with the top of the plate ; more than this may at times be useful. An arrangement for holding the

tripod legs to prevent them slipping on stone floors is also a very comforting one, taking a lot of strain off the temper, and sometimes saving serious damage. When it is not to be had, corks may be fastened on the points of the tripod, or pieces of rubber tube slipped on, or a focussing cloth may be put down to prevent any sliding about. This last device may be employed in English churches, but in Continental cathedrals is too expensive, as, if the photographer is at all squeamish, he may want to burn the cloth after use.

Most that need be said about the lens and its use has already been given, and there is little to add. The best of modern anastigmats is not too good for the purpose, for if ever there is a subject which can take advantage of all its excellencies, it is an architectural one, and an interior at that. 'If only one lens is to be carried, it should be one of decidedly wide angle, since this can be used on all subjects, and when possible the print may be trimmed down, or a portion of the negative enlarged. If this is not the case, and a lens of normal angle is used, the photographer will find that a certain number of subjects which he would be glad to get will have to be omitted. Such a lens as is suggested would be a 4-inch lens on a quarter-plate, 6-inch on half-plate, 8-inch on whole plate. If a second lens is possible, one of a focus half as long again will be useful. The advantage of many of the modern lenses is, that while nominally very rapid medium angle instruments, they are also good wide-angle lenses when used on a larger size of plate. Thus a quarter-plate anastigmat of 5-inch focus in the author's possession, which can be worked at  $F/6.3$ , may be used with excellent results on a half-plate by stopping it down to  $F/22$ , while its back combination, of a little over 9 inches focus, covers a half-plate at full aperture, in that case  $F/12.5$ . There is an impression in many quarters that a single lens, however good, is not suitable for architectural work, on account of its distortion of straight lines. This is largely a question of the lens; with some the distortion is very marked, with others it will hardly be detected, unless a subject is specially arranged to give it, by getting a long straight line close to the margin of the picture, so that the slightest discrepancy between the two can be seen.

Focussing in interior work is sometimes very difficult, on

account of the difficulty of seeing the image. Many get over the focussing difficulty by doing the best they can by their unaided eyesight, and then using a stop so small that everything must be sharp. There are certain lenses which must be focussed with the stop that is to be employed, the stopping down altering their focus, and therefore tending to blur things that were sharp originally; but the real objection to this rather happy-go-lucky sort of treatment is that it makes exposure so much longer than it need be—and exposures in interior work are generally quite long enough as it is. In very many cases where there may be trouble the difficulty is simplified by the fact that the most distant object is a window or other high light, that can easily be seen on the ground glass. In that case we can focus the window as sharply as possible, insert the largest stop likely to be serviceable, and then gradually rack the lens and plate further and further apart, stopping as soon as any departure from absolute sharpness is noticeable in the outline of the window. If the foreground objects cannot be seen on the screen, a candle may be lit and placed against the nearest of them, and it will soon be seen if it is sharp or not. If not, then a smaller stop is inserted, the distant high light is again focussed, and the procedure repeated. Even when there is not a window in the field of view, and the most distant object is dark, it is often possible to employ this method by turning the camera so as to bring one of the windows into the required position, focussing on it, and then turning the camera back. In all such cases we should remember that a little diffusion, which would be quite allowable or even unnoticed in a distant object, would spoil the picture altogether if it were noticeable in the foreground. A couple of short pieces of candle should always be included in the camera-case when interiors are likely to form the subject of the work. Very often they can be placed on the nearest and most distant parts respectively, and then the task is a very easy one. When both of these are inaccessible, and the image cannot clearly be seen on the screen, at the worst we can place a candle at a position behind the nearest object, distant from it approximately one-third of the separation between that nearest point and the most distant one. Focussing then on the candle, and inserting the smallest stop permissible, we can be confident that we have got a fairly good


general focus. Such devices, fortunately, are very seldom needed.

Professional photographers, who have much work to do in dark interiors, often manage to reduce very much the time needed to get a full exposure by using magnesium to help in the illumination of the deepest shadows. It is a very dangerous auxiliary for those whose work is to be seen and judged by other photographers, but in prints for the non-photographic public, whence the professional draws his customers, false lighting or a few extra and unexplained sources of illumination make little or no difference. They merely want to see everything that they know to be there ; and, to do the professional justice, he generally gives them what they want. If magnesium is to be used at all, it should be used very sparingly. Ribbon is more convenient than flash powder, as it is more under control, and, burning slower, may be moved about more. It is out of the question in most sacred buildings, and in others which are of national importance, but in domestic interiors it may serve its turn. It is, of course, kept well out of the field of view, the necessity for that any one can see ; but when it is used in an ordinary room, with mirrors, pictures, brightly polished furniture, and similar things about, the difficulty of avoiding a reflection of the light is much greater than many would imagine. The only way to make quite certain is to have a piece of the ribbon burnt in all the positions it is to occupy, and to watch the screen closely all the time. If the blinds can be drawn down while this is being done, so much the better.

There is an effect which many a photographer tries to secure, only to find that he fails : an interior of a room with, at the same time, a view through the window. If there are two windows to the room, we can darken one by hanging brown paper all over it, and giving nine-tenths or thereabouts of the total exposure by the light of the other, the window that does not figure in the field of view. Capping the lens while the brown paper is removed, the remaining tenth is given when the window is uncovered. The actual relative exposures must be ascertained by trial. If the first is too long, the room will look unnaturally light. As a general rule, it is well for any error made to be on the dark side, as far as the room itself is concerned. By giving the two exposures on two separate plates

and combination printing, a better effect can often be obtained, but it requires more skill, and is considerably more troublesome. Occasionally the effect sought for can be got by working on the negative with cotton-wool and a little Baskett's reducer (*q.v.*).

While, in buildings of any architectural pretension, the photographer, as a rule, has the advantage that the subject of his work has been arranged and lit on purpose to show it to the best effect, this is not invariably the case by any means; and the question of illumination will often be a puzzling one. The morning and evening, when the sun is low, are the best times for the greater number of subjects, and in this country at least there are many interiors in which photography is only possible during the summer months. Spring weather—sunshine and fleeting clouds—while reducing exposures, may give trouble from the necessity of waiting to secure some given effect of sunshine and shade, or to avoid it. There are many comparatively commonplace subjects which are transfigured by a shaft of sunlight; and this is nothing like so difficult to secure as many might think. Perhaps as fine an example of this as has been done by photography is seen in "Wirksworth Church," by Mr. Bland (the reproduction faces this page). The value of the sunlight streaming in by the chancel windows speaks for itself. A totally different lighting proved very useful to the author some years ago, and may be mentioned as one of those unusual accidents which are beneficial rather than otherwise. He had tried to photograph a fine old oak ceiling, black with age and very badly lit, and had got a result with which he had to be satisfied, as, poor though it was, it seemed the best under the circumstances. The merest chance took him there one spring morning after a light snowfall, and the illumination, due to the light reflected from the snow, was so much improved that, at considerable inconvenience, the roof was photographed again. The result was one which could never have been obtained but for the snow, and puzzled considerably a number of photographers who had tried their hands on the same subject. The moral to be drawn is that difficult work of this kind should be seen under as widely different conditions as possible, and the best selected. Of course, the lighting of an interior due to snow outside is hardly likely to give a true effect, unless the presence of the snow is suggested in some way; but in this case



WIRKSWORTH CHURCH

BY W. R. BLANE





it was a simple question of getting a good record photograph of the fine carving.

It is not easy to get a photograph of an ordinary living-room which will look quite natural. Some suggest that all the furniture has been pushed up into one corner for the operation, while others look as if they had been arranged to death. Exclusion should be the guiding principle of any arranging that has to be done, taking away first one thing and then another, until a satisfactory effect is obtained. Pictures are often the source of brilliant reflections where they are not wanted, and these ought to be looked for specially, as otherwise they may only be noticed when the print is made and alteration is impossible; a cork or wedge behind the frame will often alter its angle sufficiently to prevent an unpleasant reflection from the glass. Furniture close to the camera, so that only part of it appears, and that disproportionately large, should always be removed, and as much space as possible allowed between the lens and the nearest object. This is generally the chief trouble in photography at home, because of the size of the room. In such a case the photographer who finds a door behind his camera, so that he may get a few feet further back, is lucky; those few feet often make all the difference.

Permission to photograph in cathedrals is generally obtained by written application to the dean. The actual permit often comes from the chapter clerk or surveyor, but it is to the dean that application should be made. At some of the cathedrals a charge is made, notably at Norwich and Canterbury. At others, members of photographic societies that are affiliated to the Royal Photographic Society are permitted to photograph without special permission, on the production of the "Red Book," which acts as the certificate of membership. It ought not to be necessary to point out that religious buildings of all kinds are erected for other purposes than photography, that it is a concession on the part of those to whom they belong, or in whose charge they are, to allow photography to be carried on within them, and that the character of the building should never be forgotten. With public and private buildings alike, it should not be forgotten that the fact that the conditions under which photography is

allowed are published does not confer a right on the photographer ; and that in availing himself of the permission granted, he should leave nothing undone to prevent the necessity for making them more stringent. A case came before the writer not very long ago, when he found that a building of great beauty and historic interest was closed to photography without special permission, whereas at one time there were no restrictions. The cause on inquiry was found to be that a photographer with more enthusiasm than *savoir faire*, without any inquiry or warning, had blazed off a quantity of flash powder in one of the rooms, filling it with smoke, and setting some of the woodwork on fire.

## CHAPTER XXIII

### PORTRAITURE

The necessities—Neither studio nor “portrait lens” essential—Diffusion of focus—Type of camera—Backgrounds—Niagara Falls as a background—Portraits in ordinary rooms—Position of the sitter—Reducing exposures—Sunshine effects—Under-exposure and over-development—Dress—Outdoor portraits—Groups—The hands—Artificial light—Magnesium—“Smokeless” powders—Retouching—Animal photography.

**I**N portraiture we have at once the easiest and the most difficult of all the applications of the camera. It is the easiest in its technical details, because, as far as these are concerned, the conditions vary so little for different portraits. The illumination is far less variable than it is with landscapes or with architecture, for instance, and it is very much more under control. There is no such immense range of light and shade that the plate has its capacity taxed to the utmost, or even exceeded, in the attempt to register it truthfully. The subject is set us; and, in its simplest form, the problem how to get a passable negative is easy in the extreme. It is only when our ambition carries us to attempt higher flights that we begin to realize the difficulties of portrait work. When we are no longer satisfied with a mere bald record of the sitter's exterior; when we want to get a picture which shall not represent him merely as he happened to look when being photographed, but as we know him to be; when we are no longer content that he shall be shown as a head attached to some clothes, arms, and legs, but that the arms and legs, and even the clothes themselves, shall form part of one complete representation, and help to show us the man as he is—not suggesting even that he is being photographed, but simply suggesting *him*.

The noblest study of mankind is man, says the poet; and later commentators have added that man embraces woman. In

photographic portraiture we have the noblest side of photography, or at least we might hope to make it so. Before attempting any of such higher flights, however, we have got to master the rudiments of the art ; we must learn to walk before we try to fly.

Let not the reader be deterred from attempting portraiture because he does not happen to have a regular studio, or even a portrait lens. For professional photography, for dealing with children, and with nervous sitters who have heard of "the instantaneous process" and insist on that latest product of science being placed at their disposal, such means of cutting down the exposure to the minimum are very useful. But, except for the shortness of exposure they allow, there is nothing to be gained from the use of portrait lenses ; while, as far as studios are concerned, they will give certain lighting effects not easily secured in ordinary rooms, and will allow us to control the lighting readily, but are not otherwise of much service. Certain it is that ordinary living-rooms, if only they are large enough to allow the camera to be placed far enough from the sitter, give a wonderful choice of lighting suitable for different subjects, and give a certain guarantee against unusual lighting, which is the besetting sin of the studio worker. Nor is the light in the ordinary room necessarily so weak as to make exposures difficult ; and under favourable conditions from five to ten seconds should do all we want.

The "portrait lens," so called, was the result of the demand for the shortest possible exposure, when exposures ran to minutes rather than seconds, and much in its design was sacrificed to rapidity. It is still used and popular, and for the purpose of professional work is a valuable help. Its size and weight and cost render it rather a white elephant to amateurs. Only a solidly built studio camera will hold a whole-plate portrait lens, while many a landscape-pattern camera has not a front large enough to take it, even were its build strong enough to carry such a burden. The most serviceable lens the amateur can have is his anastigmat, rapid rectilinear, or similar all-round tool, for full-length figures ; while for large heads, busts, and work on a comparatively large scale, the single half of that instrument, or, better still, a single lens of longer focus, will be found useful.



A DECORATIVE PANEL

BY DAVID BLOUNT



There is one advantage about some forms of portrait lenses that is not to be despised, and it is due to a feature introduced many years ago by the late J. H. Dallmeyer. By unscrewing the cell which holds the back lens a little way, a certain degree of blur or diffusion of focus can be introduced at the will of the photographer. It may be asked, Why is there need for such a device, when the image may simply be thrown out of focus? But the result is not at all the same. When we throw the subject out of focus, the extent of the blur varies according to the position of each part with reference to the camera. When we get the desired blur on the principal object, we may find that a more distant part is so terribly diffused as to be offensive and a nearer part has been brought into critically sharp focus, and is in consequence altogether too prominent. Or this state of things may be reversed, the nearer object being blurred and the distant one sharpened. In either case the result is not what we want, and we shall find, sometimes at least, that by mere focussing with a lens that can give a critically sharp picture, the effect is not to be got. The adjustment on the Dallmeyer and other portrait lenses is of a different nature entirely. It introduces a certain degree of diffusion over the whole picture, over and above any due to selective focussing; and it also gives us the very valuable power of increasing or decreasing the diffusion at will, or of repeating any particular effect exactly. To accomplish this, all we have to do is to take care that the extent to which the lens is unscrewed is the same each time. When large portraits are attempted, and softness of focus is very desirable, the Dallmeyer-Bergheim lens, already referred to, will be found very useful, both for the extent of the diffusion that is possible with it, and for the fact that, being constructed on the telephotographic principle, it can be used at a considerable distance from the sitter without any need for an abnormal camera extension. But portrait lenses of these types are costly, and partake of the nature of luxuries rather than necessities; and a single lens, even an uncorrected single lens, in the hands of one who takes the trouble to master its capabilities, will do wonders. For large work critical definition is rarely wanted at all; the perfect lens sharply focussed gives quite an unnaturally sharp texture to skin and hair and fabric. In such cases the single lens may be opened out to work at



F/11, or even at F/8 or F/6, and will do wonders at that. Those who like a compromise between a portrait lens and a rectilinear, and propose to limit their work to half or whole plate, will find that kind of lens which goes under the name of the Euryscope very suitable, being faster than the rapid rectilinear (F/6 usually), and if slower than the portrait lens, at least flatter in the field. Pinhole portraiture has been performed—performed is emphatically the right word under the circumstances—but is hardly practicable, or rather, is practicable hardly.

If no special form of lens is a necessity, still less is any particular type of camera. The landscape camera, if it will carry the lens, will do all we can want of it; but portrait work with a tripod, if possible, is at least very inconvenient. Far more handy is a simple studio stand, on casters or otherwise, by which the camera can be raised or lowered without moving the feet, and the whole arrangement moved to and fro as desired without having to adjust three legs every time. It need not be an expensive one, provided it will stand firm and has the needful adjustment. A studio shutter, opening inside the camera so as not to be noticeable, and provided with an ample length of rubber tube and a big bulb, is a luxury, but again, is certainly not a necessity; it may prove a nuisance in long exposure, unless kept in very good order, by a trick it will sometimes acquire of gently closing while the bulb is still tightly pressed.

The most obvious necessity of the portrait worker will seem to be a background of some kind; yet even with that he may dispense, and, if he can, his work will be the better for it. Except in large heads, and very few other instances, the complete elimination of surroundings is a mistake. It is generally due to a desire to dodge the difficulties involved in dealing with accessories. The studio background, with its trees, landscape, rustic bridge, or whatever it may happen to be, it is to be hoped, will never find its way into the workroom of the amateur. Such a self-proclaimed sham has only to be seen to be condemned. The background is merely the setting of the figure, and therefore it should either be a natural background of the actual surroundings in which we see him in life—carefully selected, arranged, and lit, it is true, in order to help

towards that effect which it is our object to secure—or else a mere tint which may show up the model without attracting attention to itself, either by what it purports to be, or by what it is not. It comes, then, to this—that our background should be a perfectly plain fabric of suitable tone for our purpose, or that we should use the ordinary surroundings in the room. In other words, the best background of all is none at all.

As it is often impossible to arrange the surroundings in the way desired, or as the portrait may be merely a half or quarter length figure, or perchance the head alone, when any distinct character in the background would be competing for attention with the sitter and out of place, something in the nature of a plain background is at times very useful. This may be extemporized, or made, or bought. A background which did very good service with a clever portrait worker of our acquaintance was a buff-coloured camel-hair travelling-rug, which had one feature we have never seen possessed by any other background whatsoever—it could be rolled or folded or crumpled to any extent and apparently for any length of time; but when pinned up by two corners it hung flat and smooth, without a crease or wrinkle to cast a shadow. Rollable backgrounds with their two sides of different shades are purchasable; but they must be handled very carefully if they are to be kept free from creases. The most lasting background is one made by stretching sheeting on a frame, and giving it two or three coats of colour, which may be distemper—whitening, size, water, and colouring matter—or flatted oil. The latter lasts longer, but the former is so easily renewed that it is generally to be preferred. Flatted oil is the term applied to oil paint which has had the shiny character of its surface destroyed by being treated with a mixture of the colour and turpentine only, the brushmarks being taken out by stippling the surface, before it dries, with a badger softener. Those who do not care to adopt this can employ a makeshift almost as effective, but not so lasting, by applying the colour, in fine powder mixed up with powdered dextrine, to the material which has been damped to receive it. Brown or grey paper sold in rolls about 5 feet wide, under the name of carpet felt, makes an excellent background, which, if not lasting, is at least

very easily renewed. Other materials will suggest themselves from time to time.

It is important that a background, when one is used, shall not assert itself as such. It should either appear as a mere tone in the print, or else as the surface of the wall behind the sitter. Creases and folds in walls are not customary, and we must therefore avoid them in the background which is to represent the wall. If the creases are slight they may be made invisible by throwing the background out of focus, while even bad ones can be hidden if the background can be kept moving during exposure. The fault of the elaborately painted background is not that it represents itself to be what it is not, but rather, that it does not represent itself as what it purports to be. The dull, uniform tint of a flat background may well stand for a wall, as no one can say that it is not, and the effect in every respect is what it would be were it a wall. And in photography the effect is what we strive after. On the other hand, no one with the slightest power of observation or art training can be taken in by the representation of a figure, with most unmistakable indoor illumination on it, standing in front of a painted landscape. At Niagara they will take you standing in front of a background representing the falls, but the effect is only fit for those who appreciate it. That there should be a public for such things—and there is one, and a large one, on both sides of the Atlantic—must excite the astonishment of all except the cynical.

In the use of a background its position with regard both to the model and the light is very important. If it is close up to the sitter, or very near him, he will throw a shadow upon it, which is often very useful pictorially; he may even be in contact with it, and so his pose will get that support which such contact will inevitably suggest. But it must then be a pose with which such support harmonizes. No one sits in an ordinary everyday position touching a wall, or even very near it, but in the smallest room naturally selects a place where there is a certain space for freedom of movement; therefore, if such a pose is adopted, the background must appear to be well away from the figure—an illusion which can be at once destroyed by the appearance on it of the sitter's shadow. The darkest background will show a shadow if it is in a fairly

strong light. The angle it makes with the light is important, because of the means it gives us of controlling the tone of the background. The more it faces the light the lighter will it appear, because it will receive more light than when it stands obliquely with reference to the source of light. This is mentioned here, because it has been stated recently by a writer on portraiture that the reverse is the case; an observation which shows that its author is more familiar with an elementary law concerning the reflection from polished surfaces, than he is by experience with the behaviour of the dull matt surface of a background reflecting diffused light from a limited source.

The principal faults of the ordinary room for portraiture are that it entails a longer exposure than would otherwise be needed, and is often inconveniently small. On the other hand, there is less temptation to produce a portrait of the "being photographed" type, beyond which so few professional photographers seem able to get. We can show our ~~sitter~~ as we see him, amid his everyday surroundings, ~~and in~~ an everyday pose. It is this that we must study to secure, and when the camera is set up and the general arrangement has been settled, a very important part of the task remains. As far as the material before the camera is concerned, all unnecessary objects likely by the contrasts they present to be assertive where assertion is not wanted, must be removed or rearranged. It is not the objects themselves that will give trouble, so much as the way in which they become prominent by contrast with their neighbourhood. So long as the general effect is low in tone, where lowness in tone is wanted, the mere presence of a lot of accessories that are completely in character with the rest of the subject is an advantage rather than the reverse, by filling up an otherwise bare blank space in a suitable manner. This can be helped further by focussing so that emphasis is put where it is needed, and the unnecessary is rendered unobtrusive. There is no objection to subordinate parts appearing out of focus—provided that they are not blurred in that intermediate manner which is so disturbing; that is to say, they must either be sharp enough for us to see what they are, or sufficiently blurred for it not to matter in the slightest what they are. Blurring is only really offensive when it attracts attention, by arousing an inquiry it does not satisfy.

The idea that the sitter must be close to the window is best thrown overboard at once. There is only one reason for it, and that is the shortening of exposure, dearly purchased at the expense of a satisfactory lighting and harmonious result. The nearer to the window the harsher the contrasts, and the more need for that very doubtful auxiliary, the reflector, with the danger of double and unnatural lighting it introduces. Many of the difficulties of home portraiture vanish by the model being placed well within the room. The question of space becomes much less troublesome, there is room to put the background well away from the figure, and, if need be, the camera may be placed so that it sees the sitter from a point much nearer to the source of the illumination. It is the fact that the lines joining the sitter with the light and with the camera respectively, often meet nearly at right angles when the sitter is posed close to a window, that helps to make the reflector so essential; as those lines close together, so does the lighting get flatter and flatter, until, when the camera is directly between the light and the sitter, exactly the opposite defect is introduced.

The time of exposure is reduced by this means to an extent quite remarkable to those who only consider the falling off in the strength of the light caused by distance from the window, and not the increased light in the shadow, which is the governing factor in exposing portraits, as in most other forms of photography. The north light idea is another notion which is best left to studio or regulation portraiture. There is no real reason why a portrait should not be taken in a room into which the sun is shining; in fact, the best portrait of the writer ever taken was made by Coburn, in a room undoubtedly designed as a bedroom, with a south aspect, and the sun shining in, but missing his head by an inch or two—thanks to the lower part of the window being curtained off. In that, the sun only helps the general illumination; but fine portraiture has been done with splashes of sunlight, actually used to help the effect. The north light and the sky light are both legacies from the studio of the painter; necessary to him from the conditions under which he works. Necessary also to the professional photographer, whose customers might regard the sunshine on dress or surroundings as a defect. They have



ZULEIKA

BY WILLIAM CROOK



come to look upon a certain kind of portrait as correct ; and they won't be happy till they get it.

Under-exposure is as utterly ruinous in portraiture as in all else photographic. The directly visible result is in the exaggeration of the difference between the high lights. If there is any part of the subject lighter than the face, as there often is, the under-exposure leads to this being increased by over development, which usually accompanies it, until the face is quite unnaturally dark. This darkness is the cause of much wonderment to the beginner at times ; as he is apt to expect that the face should be white—which it never is. He marvels, therefore, when it is darker than it should be ; that in turn being darker than he thought. He is likely to over-develop, too, especially if he has had any experience with landscape work. A portrait negative should always look much thinner than a landscape ; it has more tendency to strong compact high lights and a broader area of shadows, and it is absolutely necessary that its very highest lights should have printing value. "Stop development when you think it half done" is sound advice to the landscape photographer making his first attempt at portraiture. Only by exposure full enough for the deepest shadows, and density not too great for the highest lights, can we hope to get that truth of tone essential to a good portrait. Have as broad and as deep shadows as may seem fit, let the high light be a mere spot in its concentration and brilliancy, but let it have a value determined by the deposit on the negative, and not merely be the negation of colour.

Dress in portraiture may be as characteristic almost as the face itself ; but its characterization is lost the moment it is worn for the purpose of the photograph, and that only. The work then passes into the domain of a figure study ; where the dress may be assumed along with the expression, to convey some suggestion quite other than a likeness of the sitter. That field is a large one, and is very alluring ; but needs to be trodden very carefully, if the pitfalls of anachronism and incongruity are to be avoided. There is so thorough a suggestion of the presence of the actual model before the camera, that the photographer who tries to deal with subjects of a bygone age, men in armour, Grecian damsels, Roman senators, and even sacred subjects and Biblical scenes, as some rash workers have



done, handicaps himself by the modernity of his process with all the weight of inevitable makebelieve. There is no reason why the model should not wear a fancy dress ; but it should be a fancy dress, and the deliberate introduction of a suggestion of modernity is then an artistic virtue, and not a pictorial crime. Otherwise the dress is best when it is a perfectly natural one. However sumptuous and ornate—and such dresses may be perfectly natural in their place—it must be subordinated to the sitter, or the sitter at once becomes a mere clothes-horse. Perhaps such a result may be sought. There are circumstances under which it would be the most truthful—and cruel—portraiture ; but the result would be hardly likely to be pleasure giving.

A point of much importance is the general tone of the costume. A poor complexion is helped very much by avoiding so light a tone in the clothes that they accentuate it. It may be noted, in passing, that there is always a tendency for flesh tones to come too dark—a tendency that will only be overcome when we have the perfect colour-sensitive plate. Without a screen, orthochromatic plates in portraiture will not be found to give noticeably truer renderings, while a screen is usually out of the question. A good complexion will often stand a very light dress, and treatment altogether in a high key, circumstances must be allowed to decide ; this high key demands more skill as a rule, but the result often more than repays for it.

Portraiture out-of-doors removes at one sweep the bugbear of long exposure, since this, under all ordinary circumstances, comes down to a second or two. The mistake most often made with such work is the attempt, by the use of plain or other backgrounds, and by similar devices, to get what are essentially indoor effects of lighting. It is as wrong to try and get such results out-of-doors as it is to get sham outdoor pictures indoor ; both are worse than crimes, they are blunders, and in art the Talleyrand epigram has real justification. It is possible by putting the sitter in the angle of a wall, cutting off top light with some screen, and generally dodging the illumination, to get something that may pass in a crowd for an indoor effect ; but it will never justify the trouble taken. After all, people have been seen out-of-doors, some even have gone so

far as to spend quite an appreciable part of their lives in the open air, so why should not the fact be boldly faced and made the most of? Those who have attempted genuine outdoor portraiture have accomplished some very delightful pictures; and, compared with many other paths, this one has been curiously untrodden. There should be little or no need for a warning against such offences as evening-dress in a sunshine picture, or slippers in a snow scene, though both have been perpetrated and *shown*. The shadow thrown by a hat need not be unpleasant, it may even form a delightful tone just where it is wanted, and the contraction of the pupils of the eye in the strong outdoor light is not unnatural. The commonest fault is found in the attempt to make the portrait far more than a portrait, to turn it in fact into a landscape and figure. The result is that fear of over-exposure for the landscape leads to under-exposure of the true subject, the sky comes out hard and white, and the face of the model almost black. Even when the exposure has been right, the enormous difference between the face and the sky may prove more than the plate can register properly, and the tones are untrue and have to be modified by some form of "faking." The easiest course is to avoid the inclusion of any sky in the picture at all; by doing this, and by taking great care to subordinate the setting to the subject, although not attempting to suppress or to conceal the fact that it is an outdoor and not an indoor picture, it should not be hard to get successes from the first, which might not be completely satisfying but are at least full of encouragement for the future.

Groups are the hardest subjects with which to deal in portraiture, and a group of more than three or four is seldom anything except a collection of persons standing still to be photographed, and all that we can hope to get is a good record of that occurrence. Occasionally we may meet with exceptions, and a croquet party, a few people waiting for a train, or saying good-bye, or otherwise engaged in some occupation which may be common to all, may inspire the photographer; but this will be seldom. The best he can do is to arrange the group so as to get little absolute uniformity in the pose of its components, and at the same time to see that they form a group and not a series of disconnected units. A natural background is a

necessity in such a case, and may be foliage, or a building, as circumstances permit. The mere recording is easy enough ; it is when the photographer has higher aims that the difficulty of the group appears.

The hands play a part in portraiture, which ought never to be neglected. "Show me the hands in the print, and I will tell you what I think of the photographer," said a colleague to the author, as they were judging an exhibition together. The speaker had achieved more than local fame in figure work himself, and in all his sympathetic treatment of the hands was noticeable. Perhaps no finer example of this could be wanted than the "Aubrey Beardsley," by F. H. Evans (facing this page), where that clever worker has succeeded in conveying as much by the wonderful hand of that eccentric genius as by his no less remarkable physiognomy. Mrs. Kasebier, in reply to a remark upon this same subject, brought out a collection of photographs of hands and nothing else, which was at least proof of the deliberate study of a feature, whose chief interest to many photographers seems to be conveyed by the remark, "How am I to get rid of the hands?" Rather should it be, "How am I to show the hands revealing the personality that lies in them, as it does in the face, at the same time subordinating them to it?"

Portraiture by artificial light is more a professional photographer's stern necessity than the amateur worker's delight. Flashlight work is curious, but seldom pleasing. This is due in large measure to the impossibility of deliberate study of the lighting effect beforehand, and to the improper placing of the flash, which is the inevitable sequel. If a flashlight portrait is to be attempted, the best effect will be found to be given when the flash is arranged as high above the sitter's head as it is in front of him, so that the greatest light falls at an angle of about 45°. This is mere rule-of-thumb, and is open to many exceptions. A diffuser of thin tissue paper or tracing paper is useful, when it does not catch fire, and very careful attention is necessary to prevent the presence of all kinds of unexpected shadows and reflections. Economy in flash powder at the present price of quarter-plates is false economy, only justified when the photographer has to stay in the room for some time afterwards in company with the smoke. All "smokeless" flash powders

the author has seen, and he has seen and tried many, were only smokeless before they were lit.

The most effective use of magnesium in portrait work lies in its employment to obtain firelight and lamp-light effects. The light from a fire is strong enough to the eye, but so slight is its action on a plate that portraiture by it is quite out of the question. But it may be supplemented either by a concealed flash-lamp, or by using flash powder or magnesium ribbon, without any falsity of effect, if the arrangements have been properly made. Flash powders are convenient, but must be handled with great care as they are all essentially explosive, though there is a difference between some and others as far as risk of accidental ignition is concerned. Still the safest plan is to regard all as explosives and handle them accordingly. 'They should never be kept in a stoppered bottle, for instance, where there is a risk of grinding against the glass. Flash-lamps, that is to say lamps constructed to project powdered magnesium—not the same as flash powder, which must never be used in a lamp—are safer, and on the whole are to be preferred. There is less risk of startling the sitter, and it is easier to control the exact moment of ignition. The Platinotype Company makes a lamp for burning magnesium ribbon in oxygen gas, by which a very powerful light can be obtained, and the light being enclosed in a globe, no smoke gets out into the room.

A chapter on portraiture would hardly be complete without some reference to retouching, but most that need be written on this subject will be found dealt with in Chapter XX. Retouching is at the best a painful concession made to his customers by the professional photographer. It is employed, justifiably, to remedy minute defects in the plate, and to counteract its tendency to darken the flesh tints. This it does at great risk of destroying characteristic modelling and texture, and of lessening likeness. If it must be used, it is best done vicariously; since it is in no sense a photographic process, nor is it easy to imagine any one delighting in it as a hobby. In pictorial portraiture it is seldom necessary to render the skin with such microscopic definition that retouching becomes an object at all, and if by any chance this has been done in the negative, the employment of a matt and not a glossy surface printing-paper should remedy matters. If it does not, a sheet

of celluloid, matt on one side, interposed between negative and paper during printing, will remove that intense definition, which, in its way, is almost as bad as over retouching, and may be quite as false.

The photography of the lower animals is not so different in essence from the photography of the highest animal, as to call for much distinctive treatment here. Most that ought to be said is more a matter for the naturalist than the photographer, and Mr. Douglas English, whose delightful work is so well known, has given us in his book, "Photography for Naturalists," such a full and explicit description of his methods and results that those who follow that wide and fascinating branch take his instruction as their guide. Pictorially, animals often form both intelligent and beautiful models. They are free, to a large extent, from that conscious pose which in the human model is often the despair of the photographer; though that they are entirely free from camera consciousness, or at least some notion that they are required to look their best, is not the opinion of many of those who have had much to do with the photography at least of dogs and horses. Mr. Wastell's lion (facing this page) shows camera consciousness of another type; but in that case the photographer has seized the opportunity much as one would expect the lion might do, should it occur. For the rest, he will succeed with animals best, who is enough of a photographer to recognize the importance of tone value as well as outline, and enough of a naturalist to know how to treat his models so as to get their confidence and co-operation. Stirring a lion up with a stick is all very well for a wild beast—the wilder the beast the truer the portrait it may be contended—but domesticated animals may be expected to respond more readily to a gentler and more sympathetic treatment.



A LION  
H. W. L. F. WASHBURN



## CHAPTER XXIV

### PICTORIAL PHOTOGRAPHY

John Richard Green on photography—Distinction between pictorial and technical work—The picturesque in nature—Subject and treatment—Laws of "composition"—Chiaroscuro—Breadth—Composite printing—Clouds—Aerial perspective—Truth of tone—Key—Early pictorial workers—Hill—Rejlander—Mis. Cameron—H. P. Robinson—Davison—Emerson and "Naturalistic Photography"—Present position of pictorial photography—The R.P.S. and the Linked Ring—Position in the United States—The Photo Secession—"Camera Work"—Stieglitz—Position on the Continent—The German workers—M. Demachy on pictorial photography in France.

PROCESSES and methods absorb the lion's share of the photographer's attention, and much that is written about photography deals with them; but, after all, the narrowest technician would admit, in words at least, that these processes are only means to ends. The end in some cases is a faithful record of certain facts; and to many this is the highest ideal before the photographer. To them the camera is a machine for making perspective representations of objects put in front of it, and nothing more. They are quite unable to realize that the nature of that rendering depends very largely upon the user of the camera, or that the rendering by photography may be absolutely false and misleading or astonishingly true, according to his will and his power; and the common explanation of the fact that one man's work is better than that of another is conveyed in some such a phrase as "He must have a very fine camera."

Of course, this is very wide of the mark, as most of us know. A man does not have to use his camera long before he realizes that his own skill plays a very large part in the results obtained with it. This is so, even when the most at which he aims is a technically good, bright print of what was in front of his apparatus. Such a print is generally what the photographer



strives for in his novitiate; and it is an excellent ideal at the start, because its production is evidence that the simpler processes have been mastered. Such a print will not include so wide an angle as to convey a false impression; its definition all over will bear the most critical scrutiny, it will have a good colour, be free from blemishes of any kind, and will take full advantage of the capacity of the printing process to render gradation, its extreme high lights being almost, if not quite, white paper, and its deepest shadows the darkest tone the process will give. When this ideal has been reached, and, unfortunately, many photographers never attain it, easy as it is, many stop. It provides good firm ground for a great deal of useful record work. Botanists can employ their time in depicting flowers and leaves and stalks; naturalists poke their cameras at birds' nests and arrange traps by which wild beasts photograph themselves; architects and engineers portray buildings and structures, while in conjunction with the microscope and other 'scopes, microscopists and other 'ists, obtain delineations that can be studied at leisure. We must not overlook the fact, also, that an immense proportion of the portraiture that is done both by professional and amateur is strictly of this description; and that, were it not, it would fail to satisfy those to whom at present it is a delight. It was John Richard Green who wrote that "in counteracting the tendencies, social and industrial, which every day are sapping the healthier family affections, the sixpenny photograph is doing more for the poor man than all the philanthropists in the world." And the joy which the sixpenny—and the six-guinea, for that matter—photograph confers is one which is based strictly upon the technical fidelity with which it registers the externals of the subject.

While no one who sees many photographs can doubt that this is the case, we are confronted with the fact that the principal photographic exhibitions are conducted on quite different lines. The perfect technical print, as such, is apparently not wanted there at all. The work which is spoken of most highly by the critics may not comply in any way with the ideal just described; and the great photographic public will look, and wonder, and pass on. Here and there it will find a spokesman, who will talk about "the fuzzy school," "the cult of the spoilt print," and similar things, and the man

in the street will agree with him, though perhaps only *sotto voce* ; but the exhibitions go on their way, and the real direction of photography is left in the hands of those to whom many of the "spoilt prints" appeal. The reason for this is that every now and again some of these pictures do strike a sympathetic chord in the heart of the majority, and when they do, their superiority is manifest and unquestionable ; and that being so, the majority seem content to take the rest on trust. The "man in the street" will look at one of these pictures, much like Fernando in the ballad, who "knew 'twas very clever, but didn't understand it."

The broad line of distinction between work of this kind and the good "technical" photograph is, that the former is intended solely to give æsthetic pleasure by conveying some feeling or suggestion from the artist to his public, while the latter is limited strictly to a statement of facts. It is the difference between the click of the telegraph and a sonata, between the price list and the poem. Æsthetic pleasure is the aim of one, instruction the object of the other. It is necessary to point out that between these two lies a vast body of photography which is without aim, produced simply to pass away time with its production. Photography is as good an amusement as any, and better than most ; but the photographer must not confuse the idle snappings of a shutter with work deliberately done with a pictorial motive.

The picture must have in it some of the personality of the artist, and not be a mere transcript of some actual arrangement of things in nature. Natural, in the highest sense, it must be ; but it must be a personal or an individual rendering of nature, and not a diagram. The difference between the actual position and colour of objects as they might be ascertained with a foot-rule and a spectroscope, and the suggestion which the scene makes on any beholder, is infinite. The one has no reference to the spectator whatever ; it exists, not to diverge into metaphysics, irrespective of him entirely. The other must differ with every observer, and the impression can only be conveyed by an artist who can give something more than the bare scientific facts.

The means by which the photographer can do this are the same as those at the command of the painter, subject to the

limitations of his process. The first—the very simplest—is in the choice of his subject. There is a tendency on the part of most photographers to attach too much importance to the sumptuary details of the subject, and still more a tendency on the part of the exhibition-going public to consider those to the exclusion of everything else. “I cannot see why he took that” is an exhibition banality we have all heard, just as we have its reverse, “What a pretty tree!” or, “What a fine sunset!” There are some photographers whose photographic lives are spent in a search after effective subjects — “picturesque” material so arranged by the hand of nature that the photographer can get his camera to some place where his view of it will comply with the various “laws of composition.” The great majority of people who visit photographic exhibitions—that is to say, most photographers and many others—regard “subject” as of the first importance; indeed, it is doubtful whether many of them realize that there can be any other pictorial qualities at all, and would be inclined to assert that a technically perfect rendering of a “fine subject” is the final aim of the picture-maker. If this were so, there would indeed be very little in pictorial photography.

There are many scenes in nature which are very pleasant to look at. The picturesque appeals to us all, and appeals as strongly, or even more strongly, to the artist than to others. But the pleasure which is caused by a photograph of a picturesque spot is quite a distinct and different feeling from that to which a picture gives rise. The picturesque spot may provide painter and photographer with subjects, and may excite and keep up that love of nature without which no artistic work can be done, but the careful, painstaking copy of it is not of necessity a work of art. Reliance upon subjects which are of recognized, not to say hackneyed, sentimental interest—waterfalls, Gothic ruins, rustic bridges, sunsets—is a sign of weakness and mediocrity. The power to see poetry in an everyday event or scene, and to convey to others its impression, is the highest possession of the artist. The fuller his vision, and the more complete his control over his means, the less is he trammelled by the feeling that it is only with certain subjects he is able to deal. This is a truth that comparatively few are able to appreciate in pictorial art, though no one doubts it in literature.



THE WHITE CAT  
BY DOUGLAS ENGLISH



"He touched nothing that he did not adorn," wrote Johnson of a literary artist; while Lamb was able to expose to us his delightful temperament, whether he wrote of the early dramatists or of the discovery of roast pig. So the photographer, who wanders about seeking always for the picturesque, is putting a comparatively unimportant detail in the forefront of his requirements. What he should seek is not the sentimental or the striking, but rather what will allow him to express his own personality. Precisely what this is must of necessity vary with the photographer. What is one man's meat is another man's poison; and one man may find a district teeming with opportunities which to another is altogether barren. The latter is not, of necessity, less of an artist than the former; he may simply be out of sympathy with his particular environment. Subject will never make a work of art, while treatment may glorify the most unpromising of subjects. It is over the recognition of this that five-sixths of the photographic world still boggles, although it bows to the decision of the remaining sixth as far as yielding up to it the control of its exhibitions is concerned.

What, then, is this "treatment"? Its externals are the selection of the subject, and will decide its arrangement on the plate, the tone values of its various parts, then definition, the scale of the finished picture, its key, and finally the little details of the print and its setting, in the shape of frame, mount, etc. Some of these are comparatively unimportant, but it is never wise to ignore them in the hope that the other factors will prove so powerful that the rest can be overlooked.

This is particularly the case with the art of photography, because in certain directions the photographer is so much more limited than the painter that minor matters about which the painter troubles little are almost vital to him who uses the camera. Mounting, framing, and hanging may well be taken as extreme examples of this. There has been a very great improvement in the taste shown in these matters during the last twenty or thirty years, not limited by any means to photography. Except in such places as the Royal Academy, where tradition reigns supreme, it is recognized that the appeal and force of a picture may be increased manyfold by careful study of the conditions under which it is seen, while it may be

almost neutralized by neglect of these conditions. The full force of this was first realized by photographers, and it was their example which was followed by the painters and others, as is shown now by almost every picture exhibition.

We must realize in pictorial photography that we have much more to do than to record a natural and fortuitous grouping of things. The painter decides for himself what he shall put in his picture, and where each part shall go. The photographer has not such a free hand, so that composition in the strictest sense of the word is not open to him, and he has instead selection and arrangement. His picture has got to suggest something far more than a map of the subject before the camera, and to do this the very first opportunity lies in the decision what to include and what to leave out.

There have been a number of well-intentioned books written for the guidance of the photographer on this important subject, some helpful, some the reverse. Most of them, from the "Art Essays" of Burnet downwards, deal with what are called the laws of composition, generalizations drawn from the study of the great masters. The study of these rules is very interesting, and their application to pictures an entertaining pastime, but it is little more. No study of the laws of composition will make an artist, nor is it possible to arrange a picture by carefully selecting and placing each part in accordance with rule. No great picture altogether ignores them, or perhaps it would be truer to say that they will be found to hold good in all great pictures ; but it is impossible to conceive of the artist putting this here because of one rule or that there because of another. His picture was what it was because he felt what was right and did it, and any attempt to follow formal laws would have robbed the whole work of spontaneity.

The photographer in his own sphere must do the same. If he does not feel the weakness of putting the dominating point of interest in the mathematical centre of the picture, he is not likely to improve his result much by remembering that there is a rule against it, and altering things accordingly. The introduction of something to balance something else already there and unsupported will not be a success if it is done because of a deliberate examination to see if the law as to balance has been observed. It must be put in because without it there is a

distinct feeling of something wanting. There is no harm in turning to one of H. P. Robinson's books or to Burnet, afterwards, if the photographer is curious to know what has been said about balance.

Composition is not to be learnt from a set of rules, but from the study of pictures themselves ; and in so doing it is far better to go to the painter than to the photographer. To start with, the painter has been at his art much longer ; pictorial photography has not yet attained to three score years and ten. Then the greatest masters have always been found in painting, because of its greater flexibility, and always will be. Cheap and good reproductions of the world's greatest pictures are so easily obtainable that there is no excuse for ignorance of them. The best, too, are reproductions in monochrome ; and though much of the charm of the original is necessarily lost, they are, if anything, even more valuable to the photographer from the absence of colour to distract his attention. Such a series as that issued by the Autotype Company will provide material for study that is unsurpassed. It may be said, How can such copies in themselves teach the photographer anything ? How is he to get any lesson from them, or to know what to draw from each ? It is not possible to tag on to every picture an artistic moral, nor can art be learnt quite like the kings of Israel and Judah, or the French irregular verbs ; but much can be done by reading judicious and not too didactic criticisms, by the comparison of one work with another, by the study of books written of artists by men who were in sympathy with them. Even then, unless the student has an artistic temperament at first, he will not profit much by such labour. The germ must be there ; but, once there, it is susceptible of infinite cultivation. It has always seemed a strange thing that many photographers attempt to produce pictures by photography, when the slightest self-examination should surely show them that they are without the slightest æsthetic sense. They seem to regard it much as the man who didn't know if he could play the fiddle because he had never tried, but, unlike that cautious individual, they do try, but are unconscious that they fail. An exhibitor, who had distinctly lofty aims in pictorial photography, once casually let fall the observation in the author's



hearing that he had never been in the National Gallery. He was a Londoner. The incompatibility of the possession of the qualities that would go to make him an artist, with the entire absence of so little interest in art as was required to take him to see the national collection, never seemed to strike him.

The photographer does not need to learn the painter's technique, but every other side of the painter's education is essential to him. It is a handicap that his process is so easy, that, unlike the painter, in learning its details he is not at the same time increasing his art knowledge. In painting, these two things can and often do go hand-in-hand; in photography, never. This accounts in great manner for the success which painters meet almost at once if they master the details of photographic technique; they are able to transfer to their new art much of what they learnt in the old. It is a strange comment on pictorial photography, that such a thing as a photographic art school, or even a class where photography is regarded throughout as a means of pictorial expression, has hardly been mooted. Certainly no serious attempt has ever been made to form one.

Composition or selection is the first stage toward the completed picture. To the photographer, it is probable that a picture will be more definitely and consciously suggested by nature, than to the painter, from the difference in their methods. To think out beforehand a landscape subject, and then to seek photographic material for it, though not so improbable as it seems at first thought, is rather putting the cart before the horse. In figure work, the photographer has fewer limitations, and can realize his conceptions with comparative ease, except in the case of the nude, which is not impossible, but almost impossible, photographically.

Chiaroscuro, literally light-dark, the disposition of the principal masses of light and shade in the picture, is, in photography, the result of the selection of the subject. The arrangement of a photograph may be looked at in two lights—as a design in grouping of tones, and as the disposition of the most salient lines. The two are interconnected, but far from being one and the same, the tone scheme being the more important consideration of the two. This is altogether irrespective of the

particular things which happen to be represented in the picture ; so much so, that it may safely be said that we should derive a certain pleasure from looking at the picture even if we do so under circumstances which prevent us altogether from distinguishing what any part of it is intended to represent.

The quality known as "breadth" is one of which critics love to talk, and one which "the man in the street," as he cannot get a simple definition of it, is disposed to look upon as a kind of pictorial Mrs. Harris. In photography it is secured in more ways than one, and it may perhaps be defined negatively by saying that it is the characteristic quality that is *not* present in a sharply rendered, bright, clean photograph, taken in a good light. Its absence in the simple lens picture marks an essential difference between it and the visual impression. There are subjects in Nature, occasionally, which a simple and straightforward photograph will render broadly ; but they are not common. This quality of breadth is not to be obtained by the use of any one photographic trick, though there are several whose assistance may be wanted at different times to secure it. An example may perhaps make this clearer. In one part of our subject we have a mass of foliage, which in the sum total of its tone is what we want in our picture ; yet if we turn the eye directly towards it and study it, or if we photograph it in a straightforward manner, we shall find that that sum total is made up of a number of bright and dark patches intermingled. If these are broadly treated, we are not worried in the picture by their spottiness, and we represent them by a tone which sums up their effect *en masse*. To do so in such a case calls for direct personal interposition in some way or another, the actual method depending on the printing process employed and other circumstances. Sometimes it is possible to do what is necessary by focussing, keeping the important parts sharp, and letting the rest be diffused ; but often this is not practicable, and handwork is a necessity. The appearance of fine definition in a picture is always a mistake. By this is not meant that the picture need be blurred, or even need be anything but critically sharp, but simply that, on looking at it, the thought that it is sharp should not be what it suggests. The actual definition has little to do with this sensation, which is always the outcome of a lack of breadth. A picture may

have remarkable definition all over, and yet not suggest sharpness ; though in consequence of the difficulty of dealing with unnecessary details in a sharp photograph, such a case is not common. Still the feeling that a picture is very sharp is more a matter of subject and treatment generally than of mere definition by itself.

The actual selection of a point of view is not the only control the photographer has over his subject ; he can add to it by making his print from more than one negative, while by handwork in printing and on the negative he can often remove, or at least suppress, unnecessary details. The commonest case of addition is in the printing in of clouds. It is possible to do this effectively, as photographs have shown ; but it is very rarely that the result is completely successful. The more carefully Nature is studied, the more apparent does it become that every light and shadow in the landscape is directly but subtly connected with the forms and tone of the sky above ; and that even if no perceptible seam divides the composite photograph, there is not a complete feeling of unity in the picture. Modern orthochromatic methods enable us to get clouds and landscape on the same plate, and if the cloud forms to which they limit us are not always exactly what we would have them, the gain is greater than the loss, as pictorial workers seem to appreciate more and more as time goes on. There is at least the certainty of a more complete harmony throughout, than when two negatives, taken perhaps under very different conditions, are employed.

Closely allied to the subject of clouds in landscape is that of aerial perspective. Geometrical perspective the photographer may leave to his lens, which will give it with an accuracy which is the ideal of the painter and draughtsman, but aerial perspective is far otherwise. The sense of distance is conveyed to the brain not merely by the scale of different objects, but also by their tone and colour. With the latter the photographer is not so directly concerned as with the former, but the effect of distance on tone is a vital one to him. A dark object appears lighter and lighter as it recedes from the eye, since it is viewed through an increasing depth of illuminated air, and similarly, but to a less extent, a light object is darkened by distance. It is possible to imagine a world of dustless air,



HARVEST MOUSE  
BY DOUGLAS ENGLISH



or even an airless one, wherein aerial perspective was not, and fanciful attempts have been made in pictures to represent such a world, which the moon is supposed to be. A lunar landscape we may conceive as having no aerial perspective. The shadow of a distant mountain is as black as would be the shadow of the camera itself, and the outline of each would be as sharp and cutting. The background of the sky in such would be of inky jet, on which the stars shone out in broad daylight more brilliantly than they can ever be seen from the air-clothed earth. We are more fortunate.

The effect of the atmosphere upon different planes of a picture is twofold. The more distant a dark object the lighter it appears in tone, and the less sharply defined are its boundaries. Under favourable conditions the camera may reproduce both these effects faithfully enough. The most perfect lens will not give as crisp a rendering of a distant object as it will of one that is close at hand, if only the exposure is long enough for the atmosphere to exert its influence on definition, as those who do much telephotography realize to their discomfort. In the same way we may get a print in which, without any conscious effort on our part, the camera has given us the effect of the air on the different planes: one, that is, in which there is the true aerial perspective. This does not always occur, by any means, and the photographer may find that he has got by some device or other to remedy the shortcomings of his process. As a general rule, there is a great loss of atmosphere in a straightforward photograph taken in clear weather. When the sun is low, when there is mist about, and especially when there is rain, the aerial perspective in the print will correspond far more closely to that which we perceive with the eye. The abuse of the orthochromatic plate and colour screen tends to deprive the picture of what is a valuable aid to its appeal. The fondness of photographers for grey day and evening effects is largely due to conscious or unconscious recognition that their process is better able to give good aerial perspective than in bright sunshine. In the latter case it is almost always necessary to employ manipulation of some kind to keep the more distant planes of a tone true to the rest of the picture.

No pictorial worker questions for a moment the importance

of truth of tone, or "tonality," as it is sometimes called; yet the haziest ideas seem to prevail as to the real meaning of the expression. One voluminous writer has laid it down that the aim of the photographer is to secure a rendering in which the lights are as bright and the shadows as dark as they are in Nature; and some vague notion similar to this seems often to be entertained even where the photographer's own work shows that unconsciously he is aiming at something very different. Except in some very few cases of indoor figure and similar work, nothing approaching such a rendering is possible. The photograph is generally on white paper, and its highest light therefore can never be lighter than plain white paper seen in the subdued light of a room, while his deepest shadow cannot be darker than the same paper blackened by the printing process employed carried as far as it will go. Beside a deep foreground shadow out-of-doors such a black is seen to have quite a light tone, while held against the sky, or still more against a splash of sunshine on a whitewashed cottage, the white paper in diffused light appears very dark. How then can we obtain truth of tone in a photograph?

Truth of tone has nothing whatever to do either with the actual lightness of the highest light in the print, or the actual blackness of the deepest shadows. This is a question of key only. By truth of tone we mean rather that between the two extremes, which may be as near together or as far apart as we choose, the other tones shall occupy positions which are relatively correct. This may be obtained by pure photography, provided that the subject is one within the range of the plate, and the exposure given is correct. The technics have already been considered in Chapter X., and what is there written need only be supplemented by pointing out that the tone values in the print will only be correct provided the negative has not been over-developed for the printing process employed. Under development does not affect the values, but only the key. Subject therefore to the orthochromatism of the process, tonality is dependent upon the way in which the exposure has been timed, and development adjusted to the printing process. The quality sought so painfully by the painter, can be attained in photography by comparatively simple means. A far-seeing critic has said its power of

rendering tone values correctly is the greatest and most valuable of the qualities of photography.

The photographer can, to some extent, control the key of his picture in development, by carrying on the process or by cutting it short; the prevailing fault being such over-development as results in false tonality, by the closing together of the high lights. As these are often concentrated in the sky, where colour plays a large part, and where orthochromatism is very important, the defect is exaggerated. The selection of a printing process also allows the key to be controlled, as does the depth to which printing is carried. But all these are only means by which the real determining factor may be influenced a little one way or the other; the nature of the subject, the prevalence of deep shadow relieved only by bright concentrated light, or *vice versa*, deciding the keynote of the whole. This is well seen by comparing two such pictures as "The House on the Wall," by Emmanuel (facing p. 356), and Coulthurst's "Evening on the Marsh" (facing p. 384), which may be taken as representing the two extremes.

It was by the adoption of a low key for grey day effects, and by their fondness for such effects, as well as by the free use of diffusion of focus to secure breadth, that the "impressionist school," as they were not too accurately termed, called down upon their heads the wrath of those who looked upon its definition and detail as the great merit of photography—as indeed it is in record work—and regarded the utilization of anything short of the entire scale of the printing paper as a crime. There still linger technicians who believe, or affect to believe, that a grey day effect is grey because the photographer could not make a negative with more contrast if he would; and that the diffusion of focus in a picture is there because its producer could not afford a better lens, or perhaps did not understand the use of stops. Far be it from us to disturb such a peace-giving creed. It harms no living soul, and must be inexpressibly soothing to its possessors. But they are getting rarer and rarer; and the photographic world has come to accept sharpness or diffusion, vigour or delicacy, brilliancy or softness, as alike legitimate, provided any are employed not haphazard, but to secure the effect that is desired.



How each of the different qualities which have been referred to is to be employed in any finished picture, how far that shall depend upon the mere guidance of the camera and what are called processes of pure photography, and how far upon the direct intervention of the photographer, each must decide for himself. Since, in pictorial photography, there is no direct attempt at imitating some particular scene in Nature, there need be no hesitation about using any or all the means at our command to produce what we want.

Those who think that pictorial photography is a product of the last quarter of a century would do well to study the work of David Octavius Hill, a Scottish painter, who turned to photography in 1842, originally to help him in his painting. He soon became fascinated with his new method. Some of his portraits are not surpassed by anything that has been done since, although Hill had no other process than calotype at his command. A volume of his work is in the possession of the Royal Photographic Society, and his negatives are still in existence, so that it is possible that one day they may be published. After Hill, the history of pictorial photography in England shows a long gap. The wet collodion process was being perfected, and the extraordinary detail and delicacy of the pictures obtained with it, took photographers away on a totally different track. Mid-Victorian tendencies were shown as strongly in photography as anywhere, and able workers lost themselves in morasses of false sentiment, and swamps of elaborate theatrical unrealities. Rejlander, a Swede, who came to England after an adventurous career on the Continent, studied as a sculptor and painter, but, turning photographer, endeavoured to get a living by professional work, and at the same time to practise photography as an art. Rejlander and, later, H. P. Robinson carried combination printing as far as it was possible to do, one of the former's most notable pictures having more than twenty figures, separately arranged and photographed. It is easy to sneer at such things now—we have travelled far since "the Railway Station" and "the Derby Day"—but in their time, and amongst their generation, these men did much to keep up the recognition of photography as an art, whatever may now be thought of the lines on which they worked.

Contemporaneously with them lived a lady, Mrs. Julia



THE HOUSE ON THE WALL

BY CHARLES H. L. EVANUEL



Margaret Cameron, who exercised a considerable influence upon those who came within her circle, and was fortunate enough to include in this category many of the well-known men of the time—amongst others, Herschel and Tennyson. Mrs. Cameron realized what few could then appreciate, the difficulty of dealing with the critically sharp definition of the portrait lens, and it was to meet her requirements that instruments were made with an adjustment by which any required degree of spherical aberration could be introduced at will. Her portrait work is characterized by a breadth and force seen in that of no one else since the time of Hill, and it is only by one or two modern workers, of whom Steichen may be noted in particular, that the succession is maintained.

Mrs. Cameron died in 1879, just as the dry plate was being perfected, and during the next few years there is little to note in pictorial photography, except that the modern amateur movement was gradually gathering force. By 1885 it was in full swing; photography had once more become a craze, and interest was manifested in it by thousands. The Camera Club was founded, and in its early days was a social centre for pictorial workers, although these were only a small minority of its members.

Photography was now to feel the effects of the sweeping change in art which characterized the last quarter of the nineteenth century. In 1888, Dr. P. H. Emerson published "Naturalistic Photography," a work which has been compared to a bombshell dropped into the midst of a tea-party. Manifestations of the change, as far as pictures were concerned, were shown at the exhibition of the Royal Photographic Society in 1900. Davison's "Onion Field" took the photographic world by storm. Photography had taken little count of the trend of art, and when Emerson and Davison drew attention to it with a jerk, old-fashioned toilers at composite photography found the ground moving from under their feet, and their palace of art, a respectable stucco-fronted mansion, collapsing over their heads. The earthquake passed away, but its effects remain to this day. Impressionism was to have its place in photography as in the other graphic arts; and the conventionalities and unreality of thirty years were left behind in three. "Naturalism" was the text preached from by Davison,

Emerson, and others, and their influence was immediately seen in exhibitions, both in subject and in treatment. Davison had gone to the Essex marshes for some of his best-known pictures, and a weekly exodus towards Canvey Island and the Blackwater followed, which must have had its effect upon the dividends of the Great Eastern Railway. It followed that going down into Essex, photographers must need discover Constable's country, and the discovery was not without its result on English photographic landscape. The "Mud Flat School," as it was termed, broadened in its views until its name ceased to be appropriate.

The characteristic of present-day photographic work in this country is its atmosphere, its appreciation of the beauty of cloud form, and the reliance often placed upon the sky to provide the real subject of the picture. These, of course, have always been essential features of British landscape art, and in this photography is at one with painting. But mediocrity seems to be the note to-day, and the centre of interest, as far as pictorial photography is concerned, has shifted across the Atlantic. No one seeing our exhibitions year by year can fail to observe that, while the number of workers of some note has increased, there has been no increase in the interest of the pictures shown.

Some have explained it as a levelling up, others call it stagnation. Certain it is that the leaders of ten or fifteen years ago have been caught up by those who followed them; but it is not so easy to determine whether this is due to the progress of the one or the lack of movement of the other. The great increase in numbers has been brought about by the extraordinary simplicity and ease of modern methods, which have attracted thousands to photography who would never have thought of it otherwise. Here and there amongst the number have been some who realized that the amusement of an idle hour might be made much more, and that in the camera they might have a means of expression, which lack of inclination or lack of training had prevented them from finding in the pencil.

The "Linked Ring"—an association of pictorial photographers, mostly British—although taking its origin in a personal squabble in the Royal Photographic Society, was

inevitable in some form or another ; and, in spite of well-meant, but not far-seeing, efforts to combine the Society and the Ring, will no doubt continue to have a separate existence. The outward manifestation of the Linked Ring is its annual exhibition—"The Photographic Salon"—held for many years in the Dudley Gallery, Piccadilly, but latterly transferred to the Water-colour Society's Gallery in Pall Mall East. The Royal Photographic Society's Exhibition is held in the New Gallery, Regent Street. The two shows are to a certain extent rivals, and are open simultaneously. The older body, however, has to cater for more than pictorial photographers only, and its pictorial section is only a section, though the most important one, of the entire exhibition. Signs are not wanting that the Linked Ring in its present form has outlived its utility, but that there is a field for such a body if it choose to occupy it, no one can doubt. There is much to be done both in Britain and on the Continent to secure the inclusion of pictorial photography in the category of art ; and in this, as might have been expected, the New World has taken the lead.

In the United States the last few years have witnessed a considerable change in the attitude of the art world generally, but of the painter more especially, towards photography. Much of this has been due to the publication there, by Mr. Stieglitz, of a series of quarterly volumes, beside which nothing else can be placed. First as "Camera Notes," the official organ of the New York Camera Club, and then as "Camera Work," an independent publication altogether, this series, by familiarizing the art world with the work of photographers, by means of the most careful facsimiles in photogravure, and by its persistent teaching, has had its effect. The loosely formed union of photographers calling itself the "Photo Secession," as indicating its independence and general attitude, controlled and directed by the same individual, has tended to the same end. Apart altogether from the particular pictorial work which the members of the "Photo Secession" have achieved, we must put the fact that it has come to be regarded by the Painters' Societies and by other bodies of artists as one of themselves ; the Secessionists have had art galleries placed at their disposal in different cities, and have obtained a recognition for their art, which it has certainly not received elsewhere. To no one man can

this be exclusively attributed, but the lion's share of the labour has undoubtedly fallen on Alfred Stieglitz, as organizer, editor, and author, and it is to him that we turn to know how such a result has been achieved. He has been good enough to send us a note, which he entitles, "Some of the Reasons." It is perhaps best printed here exactly as he sends it.

#### "SOME OF THE REASONS

"All movements that have exercised any influence on the moral and artistic advancement of mankind have been actuated by abiding faith and hope in the hearts of the leaders. The mass is always quick to enthusiasm, but, like the Banderlog, just as quick to lose faith and to worship strange gods. Each revolution of thought has been founded by the fanatic, bigoted, and single-minded belief in its principles, which through thick and thin held sway in the minds of the very few.

"This principle has held true in the revolution which has convulsed the American photographic world for the past years. And to-day, when the photographic world has acknowledged, and the art world is in the act of acknowledging, the achievements of American photography, it is interesting to analyze the causes which have led up to these results. In photography, as in every other department of human endeavour, individual ambitions are the prime causes which lead to sporadically successful exploits; but it requires something more than isolated achievements to accomplish the aims of a radical movement. In their clear insight and recognition of this principle lay the power of the leaders of American photography. While ready to acknowledge the successes of the individual, they nevertheless insisted upon a certain subordination of the claims and ambitions of the one, in the interests of the cause which they believed in, fearing lest such limited and circumscribed views of the functions of photography, as would necessarily be held by the isolated worker, would result in making photography narrow and provincial—stifling the universal spirit which is essential to the life of every art. It was because of their adherence to this rule of partial suppression of the individual that the leaders were subjected to the reproach and

misunderstanding of those who would serve only their personal ambitions, and of those who failed to understand, because they lacked the knowledge, or were constitutionally disabled from appreciating, the motives of these leaders.

"It may be that the world's approval of the bull-dog tenacity of those who do not know when they are beaten was an element in the beginning of the success which followed the strict adherence to their rule. A certain respect was ultimately gained among those who began to feel that there must be some kernel of truth in a faith for which men were willing to sacrifice so much, and a reaction from the blind rage of the mob began to set in. Undazzled by growing successes, the American pictorialists, as a body—of course, there were always some stragglers—continued to tread the steep and narrow path which led towards the heights of their ideals, and to-day, while they have reached above the clouds, they distinctly realize that the pinnacle is still far above them.

"Of course, we in America fully acknowledge that in other countries there are enthusiastic workers who have done very much towards enhancing the dignity of pictorial photography, and even bodies of workers who have striven towards a goal ; but it is borne in upon us that their spirit of loyalty and enthusiasm has been directed towards organizations, rather than towards broad and universal ideals. True to the American spirit, of which it has been said that even its transcendentalism and Puritanism have been tempered by practical considerations, there has been an incidental material side to all this, which the American worker fully realizes. Though the individual American photographer was subordinated to the success of the cause, yet, in its success, the individual was enabled to achieve, and did achieve, a far greater distinction than could ever have been his portion if he had been compelled to rely upon his unaided effort ; and thus, while individual effort, ability, and talent have made possible the results of the American School, yet the recognition which is being accorded to photography, as a new and additional means of art expression, could not have been accomplished by the work of any one, no matter how inspired. As an example of this, there can be cited the accomplishments of one American, a painter-photographer, whose work has succeeded in clinching



the conviction, photographic and pictorial, that the claims of photography were entitled to serious consideration. Yet had the movement not prepared the way for an appreciation and active encouragement of his talents, they would have excited but sporadic and passing interest as the clever manifestations of a painter.

"The ultimate results no wise man will attempt to prophesy, but the future can in a measure be anticipated by an analysis of the present and the past ; and, taking the accomplishments of the past few years into consideration, it would be folly to limit the possibilities. But even if its future strides be not as great as those just taken, yet there is already apparent in America one result which is fraught with great promise. Through the medium of carefully selected and restricted exhibitions there is being placed before such members of the younger generation, as are endowed with artistic feelings and desires, the ripest past and present achievements of photography, and the art student of to-day, who will be the painter of to-morrow, is learning, before prejudices and cant have narrowed his artistic soul, that photography not only may be, but actually is, one medium of individual expression.

"ALFRED STIEGLITZ."

Turning from the United States to the Continent, we find the condition of things resembling more that which prevails in Britain. Denmark, Belgium, Holland, Germany, and Austria have their workers, but each labours in his own way, and beyond the ordinary clubs and societies, there is no distinctive organization of pictorial photographers. The Camera Club of Vienna has produced two or three of the front rank, but they have not sufficient followers to be regarded as a school, although the work of Henneberg and the Hoffmeisters is perhaps more distinctive and characteristic than that of any other. In France, MM. Demachy and Puyo are leaders who have a following, though not a large one.

M. Demachy himself, writing to us recently, said that he did not believe that the state of pictorial photography in France was different enough from what it is in England to allow of any striking comparison between the two countries. The only difference was in numbers, the proportion of really talented

photographers being about the same on both sides of the Channel.

"There exists," says M. Demachy, "a much thicker layer in England than in France between the quite upper strata and the lowest. It seems to me that amongst French pictorialists those who have failed to attract the enthusiastic attention they expected at the National or foreign salons have dropped photography altogether; it has been a case of everything or nothing for them. This would explain the absence in our country of the good and honest work—not very original, perhaps, because it is founded on correct composition more than on personal interpretation—that comes after the work of the English leaders, and fills up in your exhibitions the gap that we notice in ours. This peculiar state of affairs is more than elsewhere felt in the arduous recruiting of illustrations for first-class photographic magazines. These are extremely rare in France; I may even say that, outside of a portfolio publication or two, there is only one good illustrated periodical of the sort in the whole country."

British landscape work comes in for praise at the hands of M. Demachy, who points out that, after the best workers have been put on one side, there still remain many landscapes which show undeniable qualities of composition, and, in their authors, positive appreciation of Nature and its different moods. "But I must say," he goes on to observe, "that, in that class of work, the level of the studies or pictures dealing with figures is very much lower than in landscape—as bad as with French workers of the same order. For it is evident that amongst photographers there are many who are capable of recognizing and making use of good composition—ready-made—in Nature, and yet who cannot mould stuffs, folds, and human limbs into a correspondingly harmonious *ensemble*."

"Now, I do not exactly know what is the degree of temperature of the English pictorialist's enthusiasm in his own work and process. I think it must be higher than Frenchmen's, if I take into account the superior amount of work brought out in England, and the greater number of able workers. Here we do not 'take ourselves seriously,' and are heavily handicapped by this fact alone. Look at the beautiful enthusiasm of American workers—violently attacked by half the photographic community, and raised to the skies by the other half—that is

quite invigorating! Here we politely compliment our leaders once a year on their interesting work, in just about the same tone as we would take to thank them for the delightful evening we have passed in their company, and we say the same thing, or nearly so, to the man whose work we do not like in the least—because we feel that, after all, there is no use in getting ourselves excited—*à quoi bon?* This is certainly not productive of emulation. Then there is the influence of artistic Paris—the constant comparison between our small work and the work in the numberless private and public exhibitions in oils, pastels, water-colour and what not—by first-rate artists, whose names will perhaps never be known out of their own set. There is the *camaraderie* with the leaders of both the Salons de Peinture, their frank avowal of discontent at their own superb work, and of their inefficient striving after other and more complete expression. All this may turn a self-proud photographer into a more modest man, and it does, generally; it will also make him more careful in his productions and more severe for his faults, but it will not make him work furiously with the idea of glory ahead. Now, I really believe, if the active body of the Secessionists was brought forcibly to Paris and left there for a year, that after six months they wouldn't 'do a thing.' And it would be a pity, for I admire their work immensely, and I was the first one over here to fight for their cause.

"Yet pictorial photography is not at its last gasp. It is quite alive, and we are trying to keep it so. MM. de Pulligny and Puyo are working at pictorial lenses, Puyo and I at a book on pictorial processes, Fresson has been perfecting a pictorial printing paper, and a number of men are working over photographs in the hope that they will turn out pictorial too. In truth, we have been getting some very promising work from the provinces lately, from Brittany especially, and the prospect is not of an alarming character.

"But there is no getting out of it, pictorial photographers are, and always will be, called photographers, and the name covers such an amount of anti-artistic iniquity that it will be hard, in France, at least, to get rid of the associations that cling to that name, and suggest eternally young ladies with beautiful smooth faces and clean-cut eyes, smiling at you from the polished surface of a bevelled-edged portrait carte.

"You will probably find a certain lack of optimism in my private views on pictorial photography in France. Well, it would have been easy enough to stir up a frothy mixture of jingoism and gum, and serve it hot ; but you know that we Frenchmen have a knack of painting ourselves blacker than we are, for fear of subsequent detection, perhaps, or with the hope that we will be judged more leniently when the time comes.

"R. DEMACHY."

## CHAPTER XXV

### EXHIBITIONS AND SOCIETIES

The display of prints—Albums—Exhibiting—The question of size—Framing—*Passe partout*—Mounting in the American manner—The autumn and winter exhibitions—Copyright—How to register a photograph—Selling the right to reproduce—Prices of pictures—Prints suitable for reproduction—Amateur or professional—Photographic societies—Postal clubs—Journals and text-books—Photographic classes—City and Guilds examinations.

THERE are very few photographers who pursue their hobby for themselves alone, irrespective of the pleasure which they can bestow on their friends by its exercise, and therefore it is only in due course that, after dealing with the production of the photographs, we come to the question of their exhibition, under which heading may fairly be grouped all the different methods by which they are shown to others. If he had to please himself only, the photographer in many cases, we expect, would be satisfied with the negative, and instead of making prints from it would derive meditative gratification from the thought of the mighty pictorial possibilities it contained. But if good intentions form a satisfactory pavement for a well-trodden highway, they are a poor covering for the walls, either of a home or of an exhibition gallery; and the camera worker therefore has to realize his, as far as he can, if his friends are to judge of his work, or are to share in the pleasant memories which his prints revive.

The most popular application of the camera is as a travel companion, and it is in the results which we bring back from a trip to the seaside or to foreign lands that the greatest number of its users find the greatest pleasure. But if these are to be seen under reasonably favourable conditions, it will never do to show them as a tattered envelope full of dog-eared, unmounted silver prints, thumb-marked and pocket worn. Prints

that are worth showing to any one are worth careful trimming and mounting, and if they deal with a journey, or otherwise fall into a natural series, they should be so arranged. The slip-in album that is so popular is a device for sacrificing quality to ease. A packet of cut pieces of P.O.P. can be bought and printed, and the prints slipped into the album without any trimming whatever. Some people who use this device take the trouble to put a drop of gum where it will not show, to hold the print in position; but most photographers seem to prefer not to do so, that the album may have its contents changed as often as they like. The practice is a very slovenly one, and nobody who takes a pride in his work would resort to one of these albums—except to hold a set of prints as an index or catalogue of negatives. For not only do the prints shift about behind the opening, but this shows almost the entire surface of each print, and so allows no selective trimming at all.

The method by which the print is trimmed to shape has been described in Chapter XIV. ; but what are we to say of its application? How many photographers realize the power they possess of improving the arrangement of the picture by the judicious use of the knife, pruning away all that is unnecessary or antagonistic to the composition, and placing the leading features in the most effective position with reference to the borders? This work is done by the painter as he paints, since his method does not compel him to fill a canvas of some predetermined size with all that is before him, on a predetermined scale. He paints what he wants on the scale he wants, and leaves the rest. Not so the photographer. It would be far more troublesome for him to omit what he did not want than to include it, and his chief aim at first therefore is to take care that all he will want for his picture is on his plate; and, if he can, to take care that it is as large as the plate will reasonably admit. But thanks to enlarging processes this latter is not at all a rigid requirement, and a picture of the size of two or three square feet is easily made from a little bit of a plate not much larger than a postage stamp, if the original negative is a good one. The selection of that bit from the entire plate is best made afterwards, when it can be studied leisurely in its monochrome rendering, and the right way up. A mounted

print is best for the purpose, and then with a couple of L-shaped cards we can try the effects of different trimming, until at last we settle on that which gives what we think the best result. And if we value our photographic reputation, that and that only will constitute the print as shown to any one else.

For exhibition at home, the album is the most convenient arrangement. The slip-in album has been denounced, but there are other forms with some of its advantages, without any of its disadvantages. There are albums with plain leaves of any tint we care to select, which leaves are hinged and perforated and held into their covers by ribbons or laces. These allow the prints to be mounted on the loose leaves, and dried under pressure, so as to come out quite flat, and then permit them to be arranged and rearranged in the albums as often as we like. Moreover, if we made a mess of one of the pages, it does not form a blot on the entire book, as it does when the prints are stuck into a made-up album. Such are known as Zahnsdorf Albums, from their designer. For odd prints another popular type may be styled the higgledy-piggledy album. Here we have large cardboard pages, interleaved with sheets of toned paper with cut-out openings of different sizes and shapes. We can fit prints to the openings, and then mount them on the card so that they appear in the proper places behind them.

The "album de luxe," or the highest outcome of the collected photograph, is seen when each print is made on platinum paper with a broad white margin. Quarter-plate negatives may be printed on half-plate, or, better still, on whole plate paper, each being masked so that exactly the portion selected is shown, and on exactly the right part of the paper. To do this a mask is made for each negative of broad strips of black paper, just touched with gum at its extremities. The position of the full-sized piece of paper is marked on this mask in pencil, so that when the negative is placed on a piece of plain glass in the printing-frame, and the mask is put on top of it, we see exactly where to put our paper down. If the sky of the negative is very dense, or if there are very white objects right against the line of the mask, it is best when the print is finished to hold mask and paper firmly with one hand, to open the printing-frame, and slip out the negative with the other,

and then, for a moment, to expose the paper to light behind the mask. A very brief exposure suffices and marks the boundary of the picture all round. Nothing looks so bad in this style of printing as a blank white in the picture, running without an indication of a dividing line into the white margin. When a set of such prints has been made, they may be arranged in order and sent to be bound up into an album, with a neatly written title-page, and then form the finest record of a tour which any photographer could wish to possess. The cost of binding depends, of course, upon the quality of the work put into it, and the style. When done in full morocco and in the best manner, this method of keeping prints is necessarily an expensive one, but the result is certainly unrivalled.

Besides the collection of prints into albums, the photographer will, perhaps, wish to try his skill with individual prints against those of his fellows in a photographic exhibition. Exhibiting is very fine practice, even if it does not lead to a collection of plaques and medals. In fact, it is almost better for the photographer if it does not, as it shows that he is competing amongst his fellows, or, at least, not amongst his inferiors.

Systematic pot-hunting, or the deliberate amassing of medals and awards, is not a particularly edifying pursuit, and is, moreover, decidedly costly. One well-known exhibitor has put his expenditure for carriage, frames, entry fees, etc., at over £100 per annum, and in spite of remarkable successes, the value of the awards he received would be very much less than this. The best advantage is taken when the pictures are sent to one or two exhibitions where they can be carried direct, without any packing, as then the frames will not suffer, and the photographer can himself go and see what his work looks like beside others. If he is so fortunate as to get a competent and candid criticism of it, all the better, but this is not very likely; the review in the local paper is generally far too flattering, and frequently is hopelessly and absurdly inaccurate. An award is, at the best, the expression of the opinion of the judge, or perhaps only marks a compromise reached by a board of judges; but if the award is made by a judge who is known to be a competent critic—not at all the same thing as a successful exhibitor—some value may attach to it. At least



the exhibitor will feel that he has succeeded in getting recognition from one who has some claim to be regarded as an authority.

As soon as an exhibition is determined upon, the photographer is at once confronted with the question of size. Any one who wanders round an exhibition is sure to devote most attention to the large pictures, and will very likely leave the smallest unnoticed; and the exhibitor, therefore, is often tempted to send in large work. As far as the judging is concerned, there is no doubt that small pictures receive quite as much, and as careful, attention as the large ones, and in that respect are just as likely to get awards. But the public demands size, and most exhibitors have a tendency to give it what it wants. Besides, it is easier to make a big print than a little one, especially if there is much dodging or "faking" to be done. The most popular size for exhibited work seems to be  $15 \times 12$ , and at many exhibitions nearly half the pictures are as large as can be got from this size. Such a print or enlargement looks very big at home, when we see it all by itself, but as soon as it is hung amidst its fellows, it will appear curiously smaller, an alteration that should always be allowed for when settling the size.

Except for very small exhibitions, limited usually to work of members of the society holding them, all exhibits must be framed and glazed. There is a fashion in framing, which it is well to study if not to follow; as the framing of the surrounding prints will be found to exercise a very marked effect on the print they are near. For many years fashion ran strongly in the direction of framing close up, that is to say, without any mount showing at all, and this is still very popular. A print to be shown in this way must be distinctly stronger in its contrasts than if it is to be seen on a mount, or it will be weak and poor against the strongly marked lines of the frame. This latter should be of a simple moulding, free from anything like elaborate ornament. The lines should all run parallel with the edges of the print, and the greater part of its width should be one unbroken flat or curved surface. Frames with very deep curves will be found most suitable for strong prints, delicate prints looking better in frames with shallow curves or flats. A gilt slip separating the frame from the print is sometimes

very useful, but the effect should always be tried both with and without it, as in some cases the bright line it makes is objectionable. Shiny frames are almost always unsatisfactory, the best finish being plain, dark wood, stained or not, and then slightly oiled. No photographs are seen at their best in silver or in gilt frames, and since such frames would often strike a jarring note in an exhibition, they should not be used, as they may endanger the acceptance of the photograph, and even if it is hung may lead to it being stuck where it will neither interfere with its neighbours nor catch the public eye. Most of the mouldings which are stocked by the ordinary picture-frame makers are quite unsuitable for photographs for exhibition purposes; but one or two can be picked out at times that will do. Failing that, some of the plain wooden mouldings made for builders' use will be found very good. They may be smoothed down with glass paper, stained and oiled, and will then make excellent frames for the purpose.

It is a mistake to send framed photographs from one's walls to exhibitions. The heavy, bold moulding and strong print which is generally most suitable for an exhibition, is not the best to hang at home by itself; and a still stronger objection is the damage which frames always sustain, however careful the authorities, and however well packed they may be. No frame can go unscathed through a couple of railway journeys, and even if it is not actually chipped or scratched, the joints are sure to be loosened in the process.

There are signs that the photograph framed up close has seen its best days, and the practice of showing prints on a mount is again coming to the fore. The American workers set the example, both by the care and thought they gave to their mounts, and by the reduction of the frame to the merest border. In fact, many of their exhibits are shown in *passee partouts*.

The *passee partout* is not only a very economical method of showing a photograph, it is often extremely effective. The name is given to a card or mount, without any wooden frame, which is attached to the glass by means of strips of paper or linen at the edges. Rings are attached by loops of tape to the back of the card, by which to hang up the print. Materials can be bought for making these *passee partouts*, but there is

no need to limit one's self to these ; and it is better, as far as final effect is concerned, to let the binding of the *passe partout* form part of the scheme of mounting. A stout card should be cut to the size of the glass, and the print with its paper mount may be fastened to this. Strips of the same paper, or of some other suitable tint, are carefully cut with a sharp knife and stuck to the glass, so as to form a margin of equal width all round. The paper may project 2 or 3 inches beyond the glass with advantage. Thin smooth paste is an excellent material for the purpose, and the strips should be allowed to dry, firmly adhering to the glass, before the print is put in position. It is then laid face downwards on the glass, and the paper, being smoothly folded back, is pasted down on the back of the card, the rings are attached by loops of tape glued to the card also, and the back neatly finished off by covering it with a piece of brown paper pasted on. Not only is this method cheap and very effective, but it reduces the size of the case when pictures are to be sent away, and reduces carriage also. It is often possible to send prints so mounted by parcel post.

A card backing was mentioned in the previous paragraph, because the *passe partout* is oftenest used in conjunction with what is called "the American method" of mounting. In this method the print is dried under pressure so as to be quite flat, and is then carefully trimmed to size. It is next touched at its two top corners with some adhesive—seccotine answers very well, or Higgins' mountant can be used—and is stuck on a piece of paper of a suitable tint. This paper is then trimmed down to some pre-arranged size, and it in turn is stuck on another paper by its top corners. This paper is trimmed down and mounted in turn on another, and so on. In this way the print is seen surrounded by a series of tints of different widths. By using one or more pieces of white paper, and trimming these only the slightest bit larger than the piece above them, we can get the effect of a fine white line ; a dark line can be got in a similar way. This method is the most effective that can be devised, but is a snare for those who have not sufficient taste to use it successfully. Even when the different papers employed harmonize well enough, they may be used in such a way as to attract attention from the print to the method of mounting. The best papers to use for this

mounting are made primarily for book covers, but some of the brown and grey papers used for wrapping are very effective.

The photographer who has succeeded in making prints that please himself, and is anxious to try his fortune at exhibitions, has plenty to choose from. Most of them are held during the winter months, the ball being opened by the two London shows, the "Royal" and the "Salon," which run contemporaneously in October of each year, and should certainly be seen and studied by the aspirant. At that time lists of forthcoming exhibitions with open classes are published in the photographic journals, with the names and addresses of the secretaries; and a note to these will bring entry forms and full particulars. In filling up the form, the column "price if for sale" will, perhaps, puzzle most budding exhibitors more than any other. The usual price for an exhibition print, including the frame, varies from one guinea to five, beyond which very few are ever sold. A print  $10 \times 8$  to  $15 \times 12$  by an unknown exhibitor is not extravagantly dear or ridiculously cheap at a couple of guineas. A friend of the writer, who exhibits pretty consistently, multiplies the price of his frame by six, and sells a good many at that price. Those to whom factorial development appeals may like to carry the principle into the sale of their work; if so, they had best ascertain their personal factor by experiment.

Before selling a picture, if it is likely to be a popular one, the question of copyright should be considered, especially as there may be an exhibition rule allowing the reproduction of any exhibit in the catalogue, and the exhibitor may be applied to for permission to reproduce it in newspapers. Photographic copyright is an intricate subject, but its broad principles may be stated briefly. The law confers upon "the author" of a photograph the copyright in it for his natural life, and for seven years after his death; at the end of which period it is open to any one. By copyright is meant the "copying, engraving, reproducing, and multiplying . . . by any means and of any size." The "author" is the person who is in the main responsible for the arrangement and production of the picture, and although in the case of professional photography this may not be too explicit, there is little doubt as to the author in the case of those who practice photography as a hobby. The

presser of the button is the author in the copyright sense of photographs sent away to be developed and printed.

When any one goes to the studio of a professional photographer and pays to be photographed in the usual way, the copyright no longer belongs to the photographer, but to the person who employs him, unless the photographer makes a reduced charge on the understanding that the copyright shall be his, or the customer signs an agreement to that effect. Otherwise, the photographer is the proprietor of the copyright in pictures taken by his employees, but if he did not play a part in their production he is not the author, and the term during which he is protected will depend on the lifetime of the employee who produced the photograph. It will be seen, therefore, that any one can permit the reproduction of portraits taken to his order in the usual course. Moreover, he can stop the exhibition of such portraits by the photographer in his window or showcase.

These rights in a picture are only conferred by law after certain regulations have been complied with ; in other words, the photograph must be "registered" at Stationers' Hall. Registration is a simple enough process, and can be done at a cost of thirteen pence. For the sum of one penny each, forms of registration can be obtained on application to the Registrar of Copyrights, Stationers' Hall, Ludgate Hill, London, E.C. Such a form, which contains full particulars describing how it is to be filled up, has spaces for a description of the picture, the name and place of abode of the author, the name and place of abode of the proprietor of the copyright, the date of any agreement or assignment transferring the copyright, and the names of the parties thereto. These last particulars are left blank if the copyright has not been assigned, and the amateur photographer registering his own work merely has to give a short description of it, such as "Landscape at Buenos Ayres," or "Portrait of Rev. A. B. Smith," fill in his own name (in full), and his address, both as author and proprietor, sign the form, and send it, with a fee of one shilling and a print of the photograph, to Stationers' Hall, where it will be duly registered, and a receipt given to him for the fee. The print may be a silver, or any other one, and should not be mounted.

There is no need to register a photograph before marking any prints of it "Copyright," because registration is not a condition of copyright, but only the notification that a formal claim is made to a right that the photographer possesses as soon as he makes his picture. The word "copyright" is generally all the protection that a photograph needs, as it acts as a warning that the photographer proposes to assert his rights; but he cannot take proceedings for any copying or sale of copies effected before his photograph is registered, though if copies were made before registration, he could stop the sale of them after registration. The sale of a print without any stipulation as to permission to reproduce it does not convey the right to reproduce it, still less does it convey the copyright, but the sale of the original negative without any agreement as to copyright destroys all copyright in it, and the seller, the buyer, and any one else may copy the picture free from all risk of legal interference. There are many fine points in copyright law which would be quite beyond our scope at present; and, generally speaking, these are matters for duly qualified legal advisers. The Photographic Copyright Union (secretary, Henry Gower, 23, Soho Square, London, W.) is a body which has been formed to protect the interest of photographers in the publication of their work, and membership is open to any photographer who cares to join. It is an association which deserves the support of all those who believe that the labourer is worthy of his hire. The mere knowledge that the Copyright Union is behind a photographer whose rights have been infringed is often a most powerful lever in moving the infringer to a recognition of the danger of his position.


Now let us see what steps a photographer may take who has succeeded in producing a picture which he thinks good enough to exhibit or to get reproduced. He will be wise to register it at the very first, and in doing so he can either send a contact print from the negative or one of the finished dodged or "faked" prints. Unless the difference between the two is altogether extraordinary, either will do to protect both. If the exhibition has an illustrated catalogue, he will probably find that the entry of the picture is taken as an agreement to the conditions, and that one of these is that the committee may reproduce in the catalogue any picture in the exhibition. If

he is applied to by a publisher or editor for permission to reproduce the picture he should make it quite clear that he does so for one specific purpose, and on one occasion only. The Photographic Copyright Union supplies forms for this purpose to its members. If a print is sent without such stipulation, the photographer may find himself in a very difficult position if he tries to stop the use of his picture for other purposes. Some publishers in paying for a print send a printed form of receipt stating that it is for payment of a photograph of So-and-so "and all rights therein." This should be crossed out before signing the receipt. In allowing its reproduction in a paper, the photographer does not necessarily part with his copyright, even if he has not limited its reproduction to that paper; but he has parted with his power to prevent its reproduction, and this may have made any remaining rights he may have in it of little or no value to any one else.

The customary fee for a print and the right to reproduce it up to, say, about half-plate is half a guinea; but if the print has any special interest of any kind its value may be much higher, and the half-guinea should be looked upon as a minimum. For photographs of special value, or of an unique character, the photographer should consider whether he is likely to make most by selling a print to one paper exclusively, at an enhanced price in consequence, or by selling it at a lower figure to all who will take it.

Most editors like glossy silver prints best for reproduction purposes, but smooth or glossy bromide prints, platinotypes, and smooth, black carbon prints will all make excellent blocks. Bromide enlargements on rough papers, especially when toned, and rough surface sepia or colour carbon prints are not suitable for reproduction in the ordinary way, nor are blue prints.

Some workers also who have taken up photography as a hobby have been able to turn it into a remunerative occupation by the sale of prints for reproduction; as, since the half-tone process has leapt into universal use, the call for photographs wherewith to meet its insatiable demands has grown enormously. This has now become a recognized branch of journalism, and must be approached in the same way as any other. That is to say, the papers to which prints are to be sent must be noted,



THE OLIVE BRANCH  
BY ALEXANDER KEIGHTLY





and their needs studied. It is a waste of time to send prints closely similar to those that have just appeared, and almost as great a mistake to send prints of a character totally different from those usually employed by the paper in question. The photographer must be prepared for rebuffs, and will want patience and photographic skill; but over and above this he will need what has been called the "journalistic instinct," to teach him what of the things which lie all about his daily path he can use as subjects for his camera. The least likely ground of success is the photography of great events, Royal visits, horse or boat races, and so on, which are arranged beforehand, and at which most of the illustrated papers concerned are represented.

Is the photographer who makes money in this way an amateur or a professional? asks the reader. Fortunately for photography the distinction between these two classes has never been drawn by anybody whose decision or example is of importance. The great photographic exhibitions do not recognize it at all, membership and fellowship of the Royal Photographic Society is open to all photographers; most Photographic Societies have followed suit, and it is only here and there that the professional photographer is excluded from them, and then only by implication. Even then the construction of the word "amateur" would be broad enough to include any photographer who did not actually have a shop, showcase, or professional studio. The leading society has set an excellent example in this respect, and no one need hesitate to sell a photograph for fear of disqualifying himself as an "amateur"; the competitions or exhibitions where any distinction is drawn being very few and quite unimportant. This is only a natural outcome from the fact that, contrary to the case in other branches of work, the practice of photography as a profession is not any great help to success at photographic exhibitions. The professional photographer has to please his customers, and it is no exaggeration to say that the class of work which the public demands from him is not calculated to appeal to the judges at a photographic exhibition, nor would it be likely even to secure admission where there was any selecting committee. The professional has therefore to alter his aims and even his methods, if he would compete with other

photographers ; and the change is so great that his practice of photography, so far from being a help, is positively a hindrance, as far as the best exhibitions are concerned.

In Great Britain and Ireland there are now some three or four hundred societies and clubs of photographers ; there are nearly as many in the United States, and a fair number elsewhere. Some of these societies provide dark-room accommodation for their members, but most of them limit their activities to meetings once a week, or less frequently, and to excursions or outings during the summer months. Joining one of these societies is the easiest and quickest way to become familiar with the technics of elementary photography. Most of their members are beginners, or have been beginners not very long ago, and there is a co-operative spirit abroad in the clubs, which is very pleasant and helpful. As far as pictorial work is concerned, the postal clubs are perhaps the most useful. Each of these has a circulating portfolio, to which the members contribute prints and a criticism of the prints of their fellow-members. The album often reveals the fact that a member may be a very clever photographer, and a very poor critic, or *vice versa* ; but the helpfulness of these clubs is shown by the fact that almost all prominent exhibitors have reached their position *via* a postal club.

Photographers are well catered for in the journalistic way, since in this country there are three weekly papers and one monthly photographic magazine. The United States has only one weekly, but makes up by a profusion of well-printed monthly magazines. There are also in both countries many hand-books on the technical side of photography. The best known of these are, "Instruction on Photography," by Sir William Abney, and "The Science and Practice of Photography," by Chapman Jones, the latter being the recognized text-book at the Photographic Technical Classes.

Most of the larger Polytechnics in the big cities have their photographic classes, and, as a rule, these are open for a small fee to any one, whether intending to pursue photography for a living or only for a hobby. Each year the City and Guilds of London Technical Institute holds examinations, both theoretical and practical, which are open to students who can manage to attend at an examination centre. Such

classes and examinations form a very sound basis for the photographer, but while going far beyond anything that is needed to produce exhibition work, or to follow pictorial photography, they in no sense offer anything of an art training to the student, who therefore has to approach pictorial photography far less well equipped than any one following one of the other graphic arts. In the absence, therefore, of a distinct taste for the scientific side of photography, the classes are not of much service ; and all that is necessary can be learned at a photographic society, or from some teacher who has not one eye fixed all the time on the requirements of examiners, who are technical experts, and nothing more.

## CHAPTER XXVI

### PHOTOGRAPHY AND THE PRINTING PRESS

Printing is of two kinds, intaglio and relief—Photogravure—Laying the ground—  
Printing the resist—Etching—Rendering half-tone—Line processes—The half-tone  
process—Ruled screens—Woodburytype—Collotype—Oil printing—Bromoil.

SOME of the earliest photographic experiments had for their object the improvement of printing processes, and the connection between the camera and the printing press has been continuous. It remained for what is called the "half-tone" process, which has been perfected within the last ten or fifteen years, to unite photography to ordinary printing so closely that it will soon be the exception for a book or newspaper to be free from photographic illustration. In fact, it is hardly too much to say that that stage has already been reached.

Before we can understand how a photograph can be used by the printer, we must realize the distinction which exists between two fundamentally different printing processes. The type with which this book is printed, as every one knows, has its printing face standing up above the rest, so that when the inking rollers pass over it, the ink is left on that face, and is then transferred to the paper; in other words, it is printed from a surface in relief. Nearly all printing is now done in this manner. But there is a different plan—"intaglio printing." The frontispiece may be taken as a type of this method. In this case the parts which are to carry the ink instead of standing up above the rest are hollowed out by hand or by photography on a smooth plate of copper. The whole is covered with a particular kind of ink, the raised surface is then wiped quite clean, and a sheet of paper is placed on it and subjected to great pressure. When the paper is taken off it carries with

it the ink from the hollows of the plate, and so bears an impression of whatever was on it. In one case we see the ink is carried on a surface raised above the rest, in the other in hollows sunk below, the general level. Both methods can be illustrated with an ordinary rubber stamp. Using it in the customary way, we are printing from it as a book or newspaper is printed—letterpress printing, as it is called ; if we press it firmly on a well-inked pad, and then dab it gently on paper until the surface of the letters is free from ink, we shall then be able to obtain a negative impression of the hollows between the letters by pressing it very heavily on a clean piece of paper—a method which might be taken as representing intaglio printing.

Etchings, "copper plates" and "photogravure," are examples of intaglio printing, the latter being strictly a photographic process. A word of caution is necessary against confusing "photogravure," a term limited to intaglio printing from plates prepared by photography, with photo-engraving, which may be used for all methods, but is generally limited to the manufacture of process blocks for printing in relief.

Photogravure, which we owe principally to Fox Talbot, at one time promised to become an amateur's process, and quite a number of workers were etching copper plates from their negatives. It was "tricky" in its behaviour, but very fascinating, and some fine results were shown ; but from the elaborate apparatus required if the amateur were to print from his plates as well as to etch them, or from the cost of copper-plate printing if the work were put out, photogravure seems to have lapsed into the keeping of professional engravers. The process is still unrivalled as far as quality of result is concerned, both for delicacy of gradation and richness of the deeper tones, the latter quality being due to the fact that in a photogravure print the surface of the shadows is a cast in ink of the hollow in the copper plate, which hollow has a peculiar and characteristic texture.

The process of making a photogravure plate is not very elaborate, although it calls for a good deal of skill. The first stage is the preparation of a reversed transparency ; that is to say, the kind of transparency obtained by the single transfer carbon process, using glass instead of paper as the support.

If the plate is to be larger or smaller than the original negative the transparency must be made in the camera or enlarger, and a lantern or an ordinary dry plate may be used, but a carbon transparency is generally preferred. When this has been made it may be touched up, spotted, or otherwise modified at will, as although a positive image it is to act as "the negative" from which to make the plate.

A polished sheet of copper, of a special and very pure kind, is taken, and has its surface treated in some way to give it a very fine grain or tooth of some substance which will not be attacked by the liquid used to etch the copper itself. Fine bitumen dust is generally employed, and as the coating must be exceedingly fine and even it is applied in a piece of apparatus called a dusting-box. This is a large wood box swinging on trunnions with a door in one side close to the bottom of the box. A quantity of powdered bitumen or of resin is kept in the box. When a plate is to be prepared the box is turned over and over a few times, so as to shake up the dust, and is then fixed vertically. After waiting some seconds the door is opened and the plate on a suitable holder is inserted and left for the finer dust, with which the air in the box is still filled, to settle upon it. Then on taking out the plate, taking great care not to disturb its coating, it can be heated gently so as just to melt the bitumen and cause it to adhere to the copper, but without making it so hot as to allow the particles to coalesce. This operation is called "laying the ground."

Using the transparency as a negative, a print is made on carbon tissue, a special form of which is supplied for this work. This print, which is called the "resist," is laid down upon the prepared copper plate and is developed there with warm water in the usual way. This is allowed to dry, and then the back of the copper plate and the margins of the picture are protected with varnish and it is ready for etching. Etching is generally done by means of solutions of iron perchloride, in which the plate is immersed and rocked, being watched the while. The perchloride makes its way through the film of gelatine forming the print, passing quickest through those parts, of course, where the film is thinnest. Here, therefore, the copper is most eaten away, and will hold the most ink when it is printed ;

these must be the darkest parts of the picture, hence the necessity for printing from a positive and not a negative. The carbon print on the copper is a negative, and it is possible to watch the progress of the etching through its film. Different baths of perchloride are employed, starting with the strongest and finishing with the weakest, a paradoxical procedure which is explained by the fact that the weakest solution is the most rapid in its action, because it passes through the gelatine film more speedily than the stronger solutions. The strength of the etching liquid is generally measured with a hydrometer. The etching is the crux of the whole process. When it has gone far enough the plate is held under a strong stream of water and the film cleaned off it as quickly as possible, to stop further action. After washing it is dried, well cleaned with benzol to get rid of the varnish and of any remaining grain, washed again in weak acid, and polished. The plate is then ready for printing.

It would be quite outside the scope of this book to provide working details either of this or of any other process of photo-engraving; but from the sketch just given, the reader will be able to form some idea of the way in which a photograph such as the magnificent portrait of Irving by William Crooke, of Edinburgh, which forms the frontispiece, can be reproduced in minute facsimile. There are many modifications of detail in photogravure processes, but the "Talbot-Klic" process, as the one just described is called, may be taken as the basis. The most notable departure is the secret method by which the "Rembrandt photogravures" are produced. The great limitation of photogravure has been the necessity of printing the plate by hand, which makes an impression a very costly affair beside anything that can be produced mechanically. Now, the "Rembrandt" process is one by which the plates can be printed by a machine; and, while the results are not so good as the best hand-printed work, they are still far in advance of any that can be obtained by the "half-tone" process to be described later on. The Rembrandt machine-printed photogravures can always be distinguished from others by the character of the grain, which is a regular one of crossed lines, and not irregular such as the dusting-box gives.



The difficulty encountered by all the early experimenters in process work was that of the rendering of half-tones. A photograph in the ordinary way has for its highest light white or nearly white paper, and its deepest shadows of all may be black, but the intermediate tones are different shades of grey or brown, as the case may be. While white paper and black printing ink may very well stand for the highest lights and deepest shadows respectively, they cannot be mingled so as to form a grey; the impression given by the type must result either in the black of the ink or the white of the uninked paper. So long as we are dealing with subjects which are limited to these two, photo-engraving processes are much simplified. This is the case with what are called line subjects, which have a design made up of lines of black ink on white paper. In these the bitumen ground in the photogravure method just described would only be wanted with such a subject in order to hold the carbon "resist" to the copper; in practice a fine ground is always used, even for line subjects. The half-tones of a photogravure result from the thin coating of ink broken up by the grain of the etched surface, and as soon as Klic introduced the method of applying a bitumen dust to the plate before putting the resist down upon it, the problem of rendering the intermediate tones of a photograph by means of the black ink and white paper of a photogravure was found to be solved.

In relief printing, using the ordinary printing press and inking the top surface of the type instead of the hollows, the problem was not so easy, and it is only in very recent years that the difficulty has been overcome. As this form of printing is far cheaper, and as it is in universal use for books, magazines, newspapers, and all the other applications of type and press, as soon as it was found to be possible to print photographs and letterpress together, the method leaped into a popularity that photogravure could never hope to enjoy; and the modern half-tone block was used for all kinds of illustration. The separate plates in this book, except the frontispiece, are printed from half-tones; and a sketch of the way in which these have been produced may be taken as a type of the process, which has many modifications in the hands of different workers. Unlike photogravure, it has never been an amateur's process, nor is it likely to become so.

The basis upon which these "half-tone" processes rest is that if the dots or stipple are small enough for the distance from which the picture is to be seen, the eye no longer realizes them as separate dots, but they appear like an even tint, dark or light according to the relative area of white paper and black ink exposed. If any of the plates in this book are examined at the usual distance from the eyes, they will appear to contain the most delicate shades of grey or brown; but if the same shades are examined with a magnifier, it will be seen that they are all made up of nothing but the full black of the ink and the full white of the paper, the only difference being in the size of the black dots, fine and widely separated in the lighter parts, large and joined up in the deepest shadows.

The original photograph from which a half-tone block is to be made can be either a print or a transparency. It must be a positive. The first stage is the crux of the whole process, and is the formation, from the print, of a negative in which the half-tones of the original photograph shall all be represented by black dots of different sizes on a clear-glass ground. To do this, the original is photographed on to a plate, usually a wet collodion plate, a glass plate ruled with black lines crossing each other at right angles—the "half-tone screen" or "tint"—being placed just in front of the wet plate in the camera. In the earlier experiments fabric was used for this purpose, gauze, crape, and muslin all being employed. The results were very poor, until it was recognized that the separation of the screen from the plate had a very important influence on the result. The theory of the action of the screen has been the subject of the most plentiful discussion, which need not concern us. Suffice it to say that the negative so obtained should be as free as possible from what the photographer calls half-tones, the high lights consisting of large black dots joined up at their corners so as to leave only small transparent spaces between them, while the shadows have clear glass with small distinct dots scattered over them. The half-tones of the original should be represented by dots of intermediate sizes according to the depth of the tone, but all the dots, as far as possible, should be opaque, and all the ground work transparent, and the edges of the dots as abrupt as possible. This effect can be helped by certain methods of intensification. The lens of the camera in

which this negative is made is fitted with a prism to reverse the image, right for left.

A copper or zinc plate is coated with an even thin layer of, a preparation of fish glue, a kind of viscid gelatine, and bichromate. This is dried, and the plate is then placed beneath the half-tone negative just described, and printed. The effect of printing is to make the coating insoluble where the light has acted, just as in the carbon process. The plate, after printing, is wetted, immersed in aniline dye to stain the film and so assist the watching of the development, which is then carried out by means of cold water. The result is a metal plate, with an image upon it made up of dots and spaces of bare metal and of an insoluble gelatinous coating. This plate is then heated, by which the coating is "burnt in"—that is to say, made very hard and resistant, so that it will withstand the etching fluid. This may be dilute nitric acid for zinc, or iron perchloride for zinc or for copper. At this stage handwork is often introduced, portions of the plate being protected by varnish and the rest re-etched, the lengths to which this is sometimes carried being surprising. When originals are poor, and what is wanted is not so much a copy of the original as a good-looking result, "fine etching," as it is called, is very useful, but it may be considered to be carried too far when it leads to a pine tree being turned into a church spire, as it did recently in the case of a half-tone ordered by the author. The plate, when finally etched, is trimmed up, mounted on a block of wood so that its surface is level with that of the type with which it is to be printed, and is then finished.

The glass screen through which the half-tone negative is made is formed by ruling parallel lines on glass with a diamond, and filling them in with pigment. Two such plates are cemented together with the lines crossing each other at right angles. The distance apart of these lines settles the fineness or coarseness of the texture of the block. A very coarse block is wanted for printing on newspaper, a finer one may be used on the better class of letterpress paper used in bookwork, such as that on which this is printed. For newspaper work the ruling of the screen may be such that sixty or fewer of the lines go to the inch. By using what is, most unhappily, called "art paper"—*for it is anything but artistic, and is only a sad necessity—*

much finer results can be obtained. This paper is provided with a very fine glossy surface, so that there is no need to have blocks with as coarse a texture as sixty lines to the inch. A hundred and fifty is more common in such cases. Two hundred lines to the inch is a very fine grain indeed, but blocks have been made with four hundred. These fine-grain blocks lose in richness what they gain in delicacy, and the best result is generally found to be got with from 133 to 175 lines to the inch, such as has been used for the plates in this book.

If the original, from which a block is to be made, has no half-tone, but is simply a drawing in black ink on white paper, the process is simplified. Take the case of the sketch reproduced on p. 208. There was no half-tone in this case at all; what was not black ink was white paper, so that no screen was necessary. The sketch was photographed to the required size, taking great care to get, a negative with as clear lines as possible on a dark ground, and this was printed on a metal plate covered with some sensitive preparation, and then etched. The lines being clear, the coating under them is rendered insoluble, so that it remains and protects the plate, while its surface elsewhere is etched away and lowered. Then, when such a block is put into the printing press, the lines stand out above the rest, and take the ink and print as black lines on the paper. There being no half-tone to be rendered by fine dots, such blocks do not require "art paper," but can be printed with type on that paper with a duller surface that is generally used for bookwork, which is much pleasanter to the eye than the shiny coating of the "art" paper.

These processes by no means exhaust the connection between photography and the printing press. One of the most ingenious of all is called "Woodburytype" from its inventor, and is still in commercial use. In this process the first proceeding is to sensitize a thick sheet of gelatine with bichromate, to print it under a negative, and to wash away the soluble gelatine with warm water. The result is a relief, a film in which the shadows are represented by the thickest parts, and the high lights by the thinnest, intermediate thicknesses standing for intermediate tones. This relief is placed on a smooth sheet of lead, and the two are put into a hydraulic press. The relief is forced into the lead, and every detail of the original

photograph is faithfully reproduced by corresponding depressions in the metal. The gelatine relief is uninjured by the process, and may be pulled off the lead and used to form other moulds in the same way. To print from such a lead surface an ink is used which is made by mixing finely ground colour with a solution of gelatine. The solution is of such a consistency that when cold it is a jelly, and it is applied to the mould hot. Some of the liquid ink being poured into the mould, a sheet of smooth paper is placed on top, a piece of plate glass is pressed down upon it, and the whole is put aside for a minute or two. The glass squeezes out the surplus fluid ink, and what is left sets into a firm jelly on cooling. When the paper is pulled off, it brings with it a cast of the lead mould in this jelly, which dries down into a faithful replica of the original. A good Woodburytype is almost indistinguishable from a carbon print; and, as in a carbon print, its half-tones are beautifully rendered by varying thicknesses of pigment in gelatine. The process fails when there is any large area of an even tone to be reproduced, especially if it is a light tone, as slight irregularities in the paper lead to corresponding irregularities in the thickness of the film. The squeezing out of the surplus ink also necessitates trimming the prints, and they have to be mounted. As printing is also very slow, the process has only enjoyed a moderate popularity for limited editions; but under such circumstances, with subjects that suit it, a Woodburytype is the finest photo-mechanical rendering of a photograph that any one could wish to have.

Another process which cannot be passed by is collotype. This employs a principle to which no reference, so far, has been made. It was early found that if a sheet of glass were coated with bichromated gelatine, and parts of it were exposed to light while other parts were not, and subsequently its surface were dampened, that a roller with greasy ink passing over it, inked the surface where the light had acted, but left no ink on the parts where there had been no light action.

Here was a phenomenon which pointed directly to a printing process employing photography, and the idea was soon worked out by Poitevin, Tessie du Motay, and others, and elaborated into one commercially practicable by Albert, of Munich. The method in outline is to treat the glass plate first

with a substratum of albumen, gelatine, and bichromate, which, drying and becoming insoluble, holds the actual printing coating firmly down. Albumen and sodium silicate (water glass, as it is called) is sometimes used as the substratum. The glass is then coated with bichromated gelatine, which may or may not contain albumen and other substances. Here arises the trouble which held back the half-tone process for so long. If we have black ink and white paper, how can we render the intermediate tones? In collotype this is surmounted in a very simple way. By drying the glass with its sensitized coating by carefully regulated heat, it will be found to dry with a fine grain, which splits up the image exactly as we want it. The plate so prepared is printed under a negative, and is then soaked for half an hour. If plain water were used for the purpose, the plate would have to be soaked for each print, but by using one part of glycerine to three of water this is not necessary. After soaking, the surplus liquid may be wiped off with a sponge, and the plate is ready to be inked up.

The inking of a collotype plate, and indeed of any plate that is akin to lithography, is a curious process. Let us suppose we have our roller well coated with greasy ink and we run it slowly over the glass, using a fair pressure, after a few strokes the entire surface of the glass will be covered with ink. Then, instead of continuing to roll slowly and heavily, we roll as quickly and lightly as we possibly can, and we shall find that we can remove almost all the ink from the glass. Between these two methods is an intermediate one, which will leave just the right quantity of ink on the glass to give the impression required. A piece of paper being laid on the glass, it is brought into contact with it in a press of a particular type. Behind the paper is placed what is called a tympan, a sheet of thin metal or other material in a frame. The flat, rounded edge of a "scraper" presses on the tympan, and the glass, paper, and tympan being drawn under the scraper, the paper as it passes is brought into close contact with the glass plate. The tympan being raised the paper print is taken off, the plate re-wetted if it need it, inked up again, and a fresh impression is pulled.

Modified collotype is quite within the power of an amateur photographer, and wants very little in the way of apparatus ;

and there are at least two processes—"Sinop" and the "Photo-autocopyist"—which are on the market to meet his needs. In these a letter-copying press can be used for printing, or even the domestic wringer can be employed at a pinch; while in the photo-autocopyist, paper coated with gelatine and stretched on a frame is used instead of the glass plate. Either method will give very fair results without much practice, and, where more than a very few prints are required, is worth consideration.

It was suggested some few years ago by Mr. G. L. H. Rawlins that the property of bichromated gelatine, which is the foundation of the collotype process, might also be used for preparing single prints direct, for exhibition work. The method first employed was to sensitize paper, that had been coated with gelatine, by immersing it in a solution of bichromate. After drying it was printed under a negative, soaked in cold water for some little time, and then blotted off and laid face upwards on a sheet of glass. Lithographic ink or similar oil pigment was then applied to it with a roller, just as to a collotype plate, except that in this case the support was paper and not glass, and the picture was left where it was inked up and not printed off on to a sheet of paper. The roller was soon found to be impracticable, and the pigment was applied by dabbing with brushes.

The control which this process affords to the pictorial worker has caused it to come to the front very rapidly, and few exhibitions are held that do not contain several oil prints. In the hands of M. Demachy and of Mr. J. H. Gear it has shown itself remarkably flexible, and it bids fair to rival gum-bichromate as the favourite with exhibitors. Single transfer carbon paper is the favourite with most of the leading workers, but paper, ink, and brushes are now specially made for the process.

As a further development of ozobrome, it has been proposed to turn bromide prints or enlargements into oil prints, by immersing them in a modified form of Mr. Manly's ozobrome sensitizing solution, washing, fixing in hypo, and then applying oil pigment in the method just described. Prints have been exhibited that were produced in this manner, and showed that the process, which has been termed "Bromoil," is a perfectly practical one.

Strictly speaking, neither of these processes come under the heading of this chapter, since they are certainly not examples of photography allied to the printing press. But their basis is

identical with that of collotype, and so it seemed best to refer to them here rather than elsewhere ; but such reference is a digression, and we must return to the methods which come under the general head of reproduction work.

The processes above described do not exhaust the list. Photozincography, photolithography, stannotype, and other methods might all be dealt with, as links between the camera and the printing press. But some of these are obsolete, and others have limited applications only, so that the merest mention must suffice. The growth of half-tone, not only in popularity, but in the quality of the results, has already made it overshadow all other processes ; and although, for reasons inherent in it, it is not likely ever to surpass photogravure, it is not at its best so very inferior, while the cheapness with which good work can be turned out makes it fill a far wider field of usefulness. •



## L'ENVOI

**T**HE broad roads of landscape and portraiture are followed by the great majority of amateur photographers, and the processes which have occupied us so far seem enough to meet the needs of most of them. But the camera can be applied to so many purposes, and so many processes and methods can be applied to it, that the bypaths open to the photographer are almost countless. Delightful, too, is it to follow whither our tastes lead us, to photograph crocuses or comets, to show our pictures burnt in on porcelain or in the fleeting blue print. There are a dozen or more of such bypaths which has each a treatise to itself.

Take wet-plate work for an example. The very smell of the ether has a fascination for some, while the direct personal contact between worker and process has no parallel in any other photographic method. The wet-plate photographer cleans his glass and dirts his fingers, coats his plate, sensitizes it, exposes it, develops it, and dries or smashes it as he may think fit, and all within an hour. Dirty glass at ten, at eleven may be in the printing-frame. There is no such feeling of "Alone I did it" to be obtained by the user of the dry plate of commerce, containing he knows not what, and made he knows not how. The wet plate is looked upon as obsolete; yet the collodion makers tell us that there never was a time when collodion, the staple material of the process, was in such great demand. Process workers use it extensively, and here and there a few enthusiasts may make slides by it. It is said to yield very fine slides; yet comparatively few amateurs have tried it. There are some very pleasant hours before any one, whose tastes run more towards processes than pictures, in learning to make a good wet-plate lantern slide.

Own brother to the wet plate is collodio-bromide. The

pundits who differ on all else agree that never were such slides as those which can be made on collodio-bromide. The process is not so messy as the wet plate, since although silver nitrate plays a part in it, that part is played in the seclusion of a bottle, where bromide soon renders it harmless to the skin of the photographer. In collodio-bromide we have the realization of Gaudin's dream, a fluid which is poured over a plate, dried, and it is at once ready for exposure in the camera. It is the wet plate with the coating of the glass put last instead of first. The collodion has silver nitrate and a soluble bromide added to it in the dark room, and thus has silver bromide formed within it. The creamy liquid is poured out into a dish for its ether and alcohol to evaporate, and the leathery mass so left is washed in water to get rid of the soluble salts, the result of the emulsification, and is then once more redissolved to form a collodion. These earlier stages of collodio-bromide work need not be carried out by him who would use the emulsion. He can buy it ready made. He cleans his glass, pours on the emulsion, and in a few minutes it is dry and ready for exposure. The plate is not quite so fast as an ordinary lantern plate, but is rapid enough for slides by reduction in the camera. It is developed with pyro-ammonia, fixed with hypo, and, like the wet plate, can be washed thoroughly, thanks to its thin film, and dried off by heat in a very few minutes. Without going so far as to say that slides, as good as collodio-bromide slides, cannot be made on gelatine lantern plates—we believe they can—it is only bare justice to a very beautiful method to admit that when it was *par excellence* the slide-making process, the average of lantern slides that were shown was very much higher than it is to-day.

If we go from these to printing methods, there is the simple "blue print," which survives, as the Darwinians tell us some of the lower forms of life survive, from the extreme simplicity of its structure. The blue print needs nothing but a good washing in water to reveal its full vigour (such as it is) and to confer its greatest permanence (with the same proviso understood). Blue printing-paper has its uses outside that chief one which it finds in engineers' and architects' offices. An ingenious photographer has told how he papered a room with highly glazed blue prints from his negatives,

simulating thereby Dutch tiles. This, perhaps, is not so much a use as an abuse. Blue prints are handy as furnishing the simplest method of cataloguing negatives. There are certain subjects which the colour is said to suit, and we live in the hope that one day we may see such a subject. The paper is simplicity itself—not merely to use, but to make. The sensitizing solution is made by dissolving a quarter of an ounce each of green ammoniocide of iron and of potassium ferricyanide in an ounce of water each, and mixing the two solutions. It can be applied with a brush or sponge to the paper, and the blue print is not at all particular about its paper; so long as it is fairly well sized it may be anything almost, and as soon as it is dried the paper is ready. It takes longer to print than P.O.P., but not so much longer; while half an hour's washing in cold water is all the after treatment. The picture so obtained can be toned in many ways, and made to yield every colour from black to yellow or green, according to the treatment adopted.

Kallitype is another printing process—or rather was, for little is heard of it now—and a batch of kallitype prints turned out of a drawer the other day bore no sign to distinguish the front of the paper from the back. The image which once had been vigorous enough, had folded its tents like the Arab and had silently stolen away. The sensitizing solution in this case was a mixture of silver nitrate and ferric oxalate, and the developer Rochelle salt and borax. Prints made on plain "salted" paper, as it is called, at about the same date, were as good as ever; and many may like to try that method, because, while giving any of the colours we are accustomed to get on a silverprint, we can select any paper for the purpose that suits us, provided only it is reasonably pure. The paper is floated on the surface of a warm solution of gelatine, salt, and citric acid. Half an ounce of gelatine, 1 dram of common salt, and 2 drams of citric acid to 7 ozs. of water will serve as a type of the solution used. It is then dried, and keeps in this condition indefinitely. It is insensitive; and so, not more than a day or two before it is to be used, it is floated on a solution of silver nitrate of a strength of 40 grains to 1 oz. of water. After two minutes floating, it is hung up and dried in the dark. Such paper prints very quickly, and, when



THE DOWNFALL, PEAK OF DERBYSHIRE  
BY W. R. STAND



printed, is washed and toned either with gold or platinum. The platinum toning bath, as used for P.O.P., is very suitable for it. Rough drawing papers, such as Whatman or Joynson, answer very well, and there are many who like the results obtained in that way more than those on rough bromide or platinum paper. The process is very simple, and the image prints right out. It is a bypath likely to appeal to the picture maker more than most.

The Stereoscope is an instrument which is a capital test for separating the sheep from the goats, the scientific from the pictorial photographer. Readers must decide for themselves which group shall be represented by the sheep. Certain only is it that while those people who are most interested in the technical side of photography are fascinated by the stereoscope and the effect it gives, even if they are not stereoscopic workers themselves, the artist feels that what one regards as extraordinary realism is to him glaringly and repulsively false. The question, like so many others, is one of standpoint or mental attitude. To one concerned with things as they are, the way in which the stereoscope gives a sensation of relief or depth to the picture seems true enough; to the other, the suggestion of reality, instantly contradicted by the absolute rigidity of every part, is a discord of the harshest kind. The author is, perhaps, prejudiced against the stereoscope. Its pictures seem so brittle in every part; they are regarded under conditions of discomfort, peering into eye-pieces for a result which hardly justifies even so slight a trouble; the relief is so assertive that the view in the stereoscope cannot be looked at in the light of a conventional representation, as every true picture is, quite unconsciously. It masquerades as the real thing, but the disguise is not good enough. The cinematograph, joy alike of music hall and Sunday school, offends in a parallel manner; while its incurable habit of winking brings on a headache which an artistic masterpiece would not repay. Both stereoscope and cinematograph are within the powers of the photographer who can appreciate their productions; but let us not be an accessory before the fact, by imparting so much as a hint as to the manipulation.

The latest process, the Donisthorpe, will print from an opaque negative! By treating the 'ordinary negative with a vanadium

toning bath, its power of absorbing dye is so far affected that it may be allowed to soak in a solution of suitable dye, and then be brought into contact with a piece of gelatinized paper. The paper sucks the dye out of the negative, becoming a very effective print while so doing. The possibilities here would seem to be almost boundless.

Twenty years or so ago, more was heard than is heard to-day of a very beautiful process, giving results of greater permanence in all probability than any other. Photo-ceramics, or photographic enamels are photographs which have been transferred to the surface of porcelain or enamel; the vehicle supporting the photographic image being removed and the picture itself fixed into the porcelain and glazed over, so as to be almost indestructible, except by actual smashing.

Porcelain is not the only substance available. Photographs may be absolutely incorporated into the surface of a glass plate, and a Leeds amateur has adopted "the pepper process," as it is called, for making lantern slides which thus need no cover glasses. The name is due to the sensitizing solution, which is an extract of pure white pepper obtained by means of benzol. Glass is coated with this and dried, and is then printed under a positive transparency, not a negative. When sufficiently printed, it is brushed over with finely powdered enamel colour, which adheres to the parts which were protected by the positive, but not to the parts on which the light has acted. In this way a picture, composed of the enamel colour, is built up on the glass, and when it is seen to be strong enough, the glass is heated until its surface and the enamel fuse together. Slides made in this way need neither binding nor cover glass.

Turning for the moment from processes to their applications, what a vision opens out of the usefulness of the camera. The photographer no longer appears merely the suave gentleman in frock-coat and immaculate cuffs, who asks to have the "head a little up, please," or "there, like that's" us, at a charge not so far removed from that of the dentist; nor seems he the humbler follower of the craft, with stained fingers and persuasive air, who offers to do us "just as you are for ninepence;" nor even as the stolid automatic machine that expresses, in print, its willingness to be put into operation by a couple of pennies—a willingness which too often, alas! is contradicted flatly by its

subsequent behaviour. We see the photographer in his wider sphere directing the camera-telescope towards the heavens hour after hour, while stars forever invisible to the human eye aided no matter by what triumph of the optician, pile up the accumulating record of their existence into a developable speck that is our only hint of a universe more wondrous and perhaps more vast than our own. Or, at the other end of the scale, the same principles and the same methods are recording those modern demons that can sit in myriads on a pin-point, yet whose internecine strife in blood and tissue may be fraught with life and death to any one of us. The bacteriologist finds his greatest auxiliary the camera ; the astronomer learns from it the composition of the comet and the structure of the stars ; the spectro-scope writes in invisible light a visible inscription on the plate : and we may yet see the day when the correspondence of the nations can be conducted through a single wire and written at the speed of light itself on the photographic film. That is more than the vision of a dreamer, and already, experimentally at least, the speed of recording telegraphy has reached a point almost beyond conception. When the provoking moralist flaunts before us the wondrous adaptability of the elephantine trunk to uproot a tree or uplift a needle, or the hackneyed steam-hammer is put into operation to forge a propeller or to crack a nut, let us remember that we need not go beyond our own hobby to point the moral and adorn the tale to a far more wonderful extent. The process that is helpmeet of the sciences and recorder to the world, is equally ready to while away an hour for us as the freshest and most fascinating of hobbies.





# INDEX

## A

Abbe, 26  
 Abbe and Schott, 73  
 Aberration, chromatic, 7, 53  
     spherical, 7, 52  
 Abney, Sir W., 91, 113, 218, 275, 378  
 Acetylene for enlarging, 259  
 Achromatism, 7, 53  
 Actinograph, 113, 119  
 Actinometers, 211  
 Acid fixing bath, 134  
 Acid fixing bath for bromide prints, 250  
 Adapter, folding tripod, 37  
 Adon lens, 79  
 Aerial perspective, 352  
 Affiliation Red Book, 327  
 Agricola, 9  
 Alberti, 3  
 Albumen process, 98  
 Albumenized paper, 25, 179  
 Albums, 368  
 Aldis, 26  
 Aldis anastigmat, 74  
 Amateur and professional, 377  
 Animal photography, 342  
 Animated photography, 395  
 Annan, J. Craig, 167  
 Anastigmat lenses, 74  
     Aldis, 74  
     Goerz, 74  
     Homocentric, 75  
     Protar, 69, 75, 82  
     Tessar, 74  
     Unar, 74  
     Zeiss, 69, 74, 75, 82  
 Aperture, the importance of, 85  
 Arago, 12  
 Archer, 22  
 Architectural photography, 319

Aristotle, 2, 8  
 Ashford tripod, 38  
 Astigmatism, 50  
 Astronomy and the camera, 397  
 Autocopyist, 390  
 Autotype Co., 215  
 Autotype A.B.C., 224  
 Autotype carbon process, 206

## B

Backgrounds, 332, 334  
 Backing, 94  
     the removal of, 133  
 Bacon, 3, 5  
 Barbaro, 3  
 Barnet bromide papers, 246  
 Baskett, R. H., 303  
     reducer, 271, 294  
 Beccari, 11  
 Benedetti, 4  
 Bennett, C., 24  
 Bennett, H. W., 213  
 "Bi-gum" process, 23, 232  
 Bichromate disease, 230  
 Birch and bracken, 314  
 Blair, 23  
 Blake-Smith process, 252  
 Blanchard, Valentine, 207  
 Bland, W. R., 326  
 Blistering, 136  
 Blue printing, 23, 393  
 Bolting silk, 301  
 Bolton, 22, 24  
 Bracken subjects, 314  
 Breadth, 351  
 Bromide paper and prints (includes gas-light papers)—  
     acid fixer for, 250

**Bromide paper and prints—*continued***

- amidol for, 250
  - Barnet, 246
  - Blake-Smith process, 252
  - and bolting cloth, 302
  - combination printing, 303
  - contact printing, 243
  - development of, 245
  - enlarging on, 263
  - exposures with, 244
  - ferrous oxalate for, 250
  - fixing, 250
  - and gaslight, difference between, 243
  - and green glass, 246
  - hypo-alum and, 252
  - Ilford, 246
  - illumination for printing, 243
  - incandescent gas for printing, 243
  - in the camera, 35, 310
  - Kodak, 246
  - machine printing on, 243
  - Marion's speed-testing frame, 247
  - Morgan and Kidd, 246
  - negatives on, 35, 90, 310
  - ozobrome and, 252
  - Paget, 246
  - platino-matt, 252
  - patented, 242
  - pressure marks on, 251
  - printing-frames for, 244
  - suitable negatives for, 246
  - speeds of different makes, 246
  - spotting, 300
  - sulphur toning, 252
  - to tone, 252
  - toning by development, 252
  - trial exposures, 265
  - vignetting by reduction, 305
  - washing, 251
  - Wellington and Ward's, 243
- Bromide in the developer, 132**
- Bromoil, 390**
- Burnet, 348**
- Burnett, 23**

**C**

- Cadett "Spectrum" plates, 102**
- Calotype, 20**
- Camera (*see also* Hand-camera)—**  
for architecture, 322

**Camera—*continued***

- cases for, 33
  - changing boxes, 35
  - for copying, 87
  - cross-front for, 30
  - Daguerre's, 16
  - dark slides for, 32
  - detective, 147
  - dust in the, 41
  - for films, 35
  - first described, 3
  - fixed focus, 29, 149
  - focussing screen, 32
  - functions of, 27
  - ghosts in the, 28
  - "landscape" pattern, 40
  - for landscape work, 309
  - levels for, 159
  - light-tightness, 28
  - marking a scale on, 86
  - movements of, 28
  - panoramic, 66
  - for portraiture, 332
  - rising front, 30
  - reflections in, 29
  - reversing back, 32
  - roll holders, 37
  - slides, 34
  - stands for, 37
  - swing back, 31
  - turn-tables, 38
  - the weight question, 39
- Camera Club, 357**
- Camera Club of Vienna, 362**
- "Camera Notes," 359**
- "Camera Work," 359**
- Cameron, Mrs., 356**
- Canaletto, 5**
- Caramel, 94**
- Carbograph, 251**
- Carbon process—**
- actinometers for, 211
  - apparatus for sensitizing, 215
  - Bennett's sensitizing formula, 213
  - bichromate for, 215
  - bichromate disease, 230
  - on celluloid base, 207
  - clearing, 223
  - clouds in, 226
  - colours in, 209
  - continuing action, 218
  - developing, 221

Carbon process—*continued*

process discovered, 20  
 double transfer, 225  
 • duplicating negatives, 228  
 Johnson's actinometer, 211  
 Johnson's improved process, 208  
 Mariotype, 230  
 Ozobrome, 252  
 Ozotype, 231  
 Pouncy's process, 233  
 principles of, 207  
 printing-frames for, 216  
 print meters for, 211  
 reversing prism for, 220  
 reversed negatives for, 220  
 Rotary Co.'s films, 207  
 safe edge for, 217  
 Sawyer's temporary support, 209  
 sensitized tissue, 209  
 sensitizing tissue, 213  
 single transfer, 219  
 speed of tissues, 213  
 spotting, 227  
 Swan's improvements, 208  
 tinted papers for, 225  
 transfer papers, 210  
 transfer paper to make, 224  
 transferring, 221  
 transparency tissue, 209  
 transparencies to make, 227  
 tissue to store, 210  
 Wellington and Ward's tissue, 214  
 Carriers, 33, 34  
 Cartridges for film, 35, 162  
 Catalogues of negatives, 367  
 Catechu, 203  
 Celestial photography, 397  
 Celluloid films, 88  
 Centring of lenses, 47  
 Changing plates, boxes for, 34  
     the Frena method, 161  
     the Tella method, 161  
 Charles, 12  
 Chaussier, 14  
 Cherrill printing-frame, 300  
 Chiaroscuro, 350  
 Chicholm, 11, 13  
 Choice of a size, 39  
 Chromatic aberration, 7, 53  
 Cinematograph, 395  
 City and Guilds examinations, 378  
 Classes in photography, 378

Cloth, bolting, 301  
 Claudet, 21  
 Clerk-Maxwell, 284  
 Clouds in landscape, 352  
 Clouds, printing in, 304  
 Collodion, 21  
 Collodio-bromide, 392  
 Collodio-chloride paper, 174  
 Collotype, 388  
 Colour contrast, 275  
 Colour screens, 281  
 Colour photography—  
     autochrome plate, 285  
     Clerk-Maxwell and, 284  
     copying autochromes, 290  
     development of autochromes, 288  
     du Hauron and, 283  
     Lippmann method, 283  
     reproducing autochromes, 290  
     starch grain, 286  
     theory of the autochrome process, 289  
     three-colour process and paper, 290  
     three-colour process in outline, 284  
     Uto paper, 290  
     Young-Helmholtz theory, 283  
 Combination printing, 303  
 Composition, 349  
 Condenser in enlarging, 255  
 Continuing action of light, 218  
 Cooke lens, 74, 149  
 Cooper-Hewitt mercury lamp, 193  
 Copyright, 373  
     registration of, 374  
     Union, the Photographic, 375  
 Coulthurst, S. L., 204, 355  
 Covering power, 48  
 Cristoid film, 90, 92  
 Crofts, 5  
 Crooke, W., 383  
 Cross front, 29  
 Curtois, 15  
 Curvature of the field, 49  
 Cut films, 34  
 Cylindrical perspective, 67

D

Daguerre, 2, 16  
 Daguerreotype, 17  
 Dallmeyer, J. H., 26, 71, 331

Dallmeyer, T. R., 26  
 Dallmeyer Adon lens, 79  
   stigmatic lens, 74  
 Dallmeyer-Bergheim lens, 80, 331  
 Dark room, light in, 98, 100, 101  
   ventilation of, 99  
 Dark slides, 32  
   metal, 33  
 Davison, 357  
 Davy, 14  
 Defining power, 48  
 Demachy, R., 232, 362  
 Depth of focus, 151  
 Detective cameras, 147  
 Development—  
   of bromide paper, 248  
   bromide in the, 132  
   of carbon prints, 221  
   of a daguerreotype, 17  
   discovered, 21  
   dishes for, 105, 131  
   of gaslight papers, 249  
   of gum-bichromate prints, 238  
   of lantern slides, 268  
   by machine, 129  
   machines for, 124, 129, 161  
   of plates and films, 123  
   of platinum prints, 195  
   of P.O.P., 181  
   of autochromes, 288  
   time, 129  
 Diaphragms, 44  
   the Uniform system, 45  
   the Zeiss system, 46  
 Differential focussing, 56  
 Dishes for developing, 105, 131  
 Distances to estimate, 166  
   and exposure, in printing, 245  
 Distortion, 50, 62  
 "Dodging" slides, 271  
   prints and negatives, 292  
 Dollond, 7  
 Donisthorpe process, 395  
 Draper, 23  
 Dry mounting, 190  
 Dumas, Mrs. 308, 315

## E

Eastman, 25  
 Eder, 113  
 Education, photographic, 378

Edwards' metal slides, 33  
 Efficiency of shutters, 157  
 Electric light, 259  
 Emerson, P. H., 56, 175, 357  
 Emmanuel, C. L. H., 355  
 Emulsion, collodion, 392  
   gelatine, 24  
 Enamels, 396  
 Enamelling, 184  
 English, Douglas, 342  
 Enlarged negative, 264  
 Enlarging (*see also* Bromide paper)—  
   with acetylene, 259  
   adjustment of the lantern, 257  
   apparatus for, 259  
   with a condenser, 255  
   daylight, 261  
   diffusers in, 258  
   distortion and the cure, 262  
   dry plates, 264  
   electric light for, 257, 259  
   exposures in, 265  
   fixed focus apparatus, 261  
   focussing in, 264  
   Hume's apparatus, 259  
   illumination, when, 255  
   incandescent gas for, 259  
   optical principles involved, 254  
   positives for, 264  
   reflectors for, 260  
   stops and, 256  
 Estimating distances, 166  
 Ethics of hand-camera work, 167  
 Euclid, 3  
 Euryscopes, 71  
 Evans, F. H., 266, 340  
 Examinations in photography, 378  
 Exhibitions, 366  
   Salon and Royal, 359, 373  
 Exposure, at different distances, 245  
   factors in, 112  
   meter, the Watkins, 116, 120  
   meter, the Wynne, 116  
   the problem of, 109  
   shutters, 156

## F

Fabricius, 9  
 Fabrics, platinum prints on, 20  
 Fabrics in exposure, 112

"Faking" negatives and prints, 292  
 Falling front, 29  
 Faraday, 19  
 Fargier, 23  
 Fees for reproduction, 376.  
 Fenelon, 12  
 Ferro-prussiate process, 23, 393  
 Field, curvature of the, 49  
 Films, carriers, 34  
     cartridges for, 35, 162  
     celluloid, 88  
     Cristoid, 90, 92  
     cut, 34  
     Kodak, 25, 161  
     Premo pack, 35, 161  
     sheaths for, 34  
 Filters, light, 281  
 Finders, 154  
 Fixed focus cameras, 149  
 Fixing bath, acid, 134  
     for bromide prints, 250  
     for P.O.P., 183  
     for plates, 134  
 Fizeau, 18  
 Flange, a makeshift, 48  
 Flare spot, 52  
 Flexible support in carbon printing, 224  
 Focus, to measure, 43  
     depth of, 151  
     differential, 56  
     fixed, 69  
 Focussing, 30  
     differential, 56  
 Focussing screens, 32  
 Folding tripod adapter, 37  
 Formaline for negatives, 140  
 Frames, printing, 177  
     the Cherrill, 300  
     Marion's print testing, 247  
 Framing, 370  
 Frena changing method, 161  
     shutter, 158  
 Frilling, 136  
 Front, rising and cross, 29  
     Sanderson, 40  
 Frost pictures, 317.

## G

Gaslight papers and printing (see Bromide)  
 "Geka" light filters, 101

Gelatine emulsion, 24  
 Ghosts, 28  
 Giphantie, 12  
 Glass, green for bromide printing, 246  
     green, for P.O.P. printing, 176  
     ground, for focussing screens, 32  
     Jena, 73  
     ruby, 102  
     yellow, 248  
 "Globe polish" reducer, 294  
 Goddard, 18  
 Goerz anastigmats, 74  
     Hypergon, 76  
 Gold toning lantern slides, 270  
 Gold toning P.O.P., 180  
 Green glass for printing, 246  
 Green, John Richard, 344  
 Ground glass, 32  
 Grün lens, 76  
 Gum-bichromate, 23, 232  
 Gum-ozotype, 241

## H

Halation, 92  
 Half-tone reproductions, 384  
 Hall, Chester More, 7  
 Hand-camera—  
     for architecture, 168  
     cheap, 149  
     defects in, 163  
     depth of focus with, 151  
     developing, 162  
     essential features, 148  
     estimating distances, 166  
     ethics of, 167  
     exposure with, 168  
     finders for, 154  
     fixed focus, 149  
     focal plane, 158  
     focussing arrangements for, 149  
     holding the, 164  
     the Kodak, 25, 161  
     levels, 159  
     magazine, 149  
     magnifier for, 154  
     plate changers, 159  
     reflector, 182  
     scale focussing, 150, 152  
     shutters, 156  
     street scenes, 170

Hardening negatives, 140

Harrison, C. J., 298

du Hauron, 283

Henneberg, 362

Herschel, 18, 20, 23

Higgins' mountant, 189

Hill, D. O., 21, 356

Hoar-frost pictures, 317

Hoffmeister, 362

Holders plate, 32

roll, 37

Horn silver, 8

Houh, E. von, 26

Hume enlarging apparatus, 259

Hunt, 23

Hurter and Driffeld, 110, 113, 123

Hyperfocal distance, 152

Hypergon, 76

Hypo, 18, 135

acid, 134

for bromide prints, 250

Hypo-eliminators, 237

## I

Ilford bromide paper, 246

P.O.P., 25

Illumination of the dark room, 98, 100

for bromide printing, 244

for enlarging, 225

Instantaneous shutters, 156,

efficiency, 157

the Frena, 158

Inston, C. F., 197

"Instruction in photography," 378

Intaglio printing, 380

Intensification methods, 143

with mercuric chloride, 144

Monckhoven's method, 144

of platinum prints with gold, 202

Wellington's silver method, 144

Iron processes, 23

Isochromatic (*see* Orthochromatic)

## J

Jena glass, 73

Job, C., 308, 315\*

Johnson, J. R., 23, 208

Jones, Chapman, 197, 202, 204, 378

## K

Kallitype, 394

Kasebier, Mrs., 340

Keiley, J. T., 201

Kennett, 24

Kentmann, 9

Kepler, 5

Kinematograph, 395

Kodak, 25, 61

Kodak bromide paper, 346

developing machines, 124, 120, 161

platinum paper, 205

## I

Lamp, Cooper-Hewitt mercury vapour,

193

Landscape photography—

cameras for, 40, 309

clouds in, 297, 304, 352

exposures in, 312

focussing, 86

lenses, 81, 309

negative paper for, 90

orthochromatic plates for, 282

plates for, 91

subjects, 313

view meters in, 311

Lantern, portable screen for, 273

Lantern slides—

black tones on, 268

clearing, 269

clouds in, 270

collodion emulsion for, 268, 392

contact method, 266

cover glasses for, 272

development of, 268

dodging, 271

gold toning, 270

intensification of, 269

masking, 272

mounting, 272

and pictorial photography, 266

plates for, 266

printing frame for, 267

showing on a small scale, 273

spotting, 273

by reduction, 267

reduction of, 269, 271

standard sizes, 267

Lantern slides—*continued*

- sulphur toning, 270
- varnishing, 271
- warm tones |by development, 269

Law of copyright, 373

Learning photography, 378

Lens—

- Adon, 79
- Cooke, 74, 149
- Dallmeyer-Bergheim, 80, 331
- Doublet, 70
- Euryscope, 71
- Goerz anastigmats, 74
- Grün, 76
- Homocentric, 75
- Hypergon, 76
- Meniscus, 70
- Periscopic, 69
- Petzval portrait, 70, 330
- Protar, 75, 82
- Pulligny, 80, 364
- Rectilinear, 70
- Ross' portable symmetrical, 71
- stigmatic, 74
- telephotographic, 77
- Tessar, 74
- Unar, 74
- uncorrected, 70
- Zeiss anastigmats, 69, 75, 82

Lenses—

- centring of, 47
- defects in, 46
- depth of focus, 151
- drawing with, 61
- fixed focus, 149
- focus of, 43
- to focus, 30, 83, 84, 150
- focussing by scale, 150
- hyperfocal distance, 152
- magnifiers for, 154
- myths, about, 42
- Jena glass for, 73
- to measure the focus of, 43
- mounting, 47
- the pinhole, 57, 58
- selection of, 47, 68
- stops for, 44
- striae in, 46
- supplementary, 154
- systems of diaphragms, 44
- to test, 46
- using half doublet, 82

Levels for cameras, 159

Lewis, Dr. W., 11

Light, continuing action of, 218

- dark room, 98, 100
- electric for enlarging, 259
- filters, 281

Geka, 101

Linked Ring, 358

Lippmann process, 283

Liquid lenses, 76

Lumière and Seyewetz, 137, 183

Lumière autochrome process, 285

Luna cornea, 10

M

Machine for bromide printing, 243

Machines for developing, 124, 129, 161

McIntosh, J., 280

Mackenzie-Wishart slide, 33

Maddox, 24

Magazines for plates, 34

Magnesium light, 245

Magnifiers, 154

Manly, T., 231, 252

Mansfield, 24

Marion and Co., 243, 246

Marion's print-testing frame, 247

Mariotype, 231

Marks on gaslight papers, 251

Marriage, E., 78

Maurolycus, 5

Mercury vapour lamp, 193

Metal dark slides, 33

Meter, the Watkins, 116, 120  
the Wynne, 116

Methven screen, 244

Microscope and the camera, 397

Miethe, 101

Monckhoven, 24

Morgan and Kidd, 246

Mortimer, F. W., 315

Mounting lenses, 47

Mounting prints, 186

dry, 190

slides, 272

starch for, 189

Mummery, J. C. S., 232



## N

- Namias, R., 213  
 Natural history subjects, 342  
 Naturalism, 357  
 Naturalistic photography, 357  
 Negatives—  
   for bromide printing, 246  
   catalogues of, 367  
   dodging and faking, 292  
   duplicating, 228  
   enlarged, 264  
   to harden, 140  
   the perfect, 111  
   to varnish, 141  
   to wash, 137  
 Nernst electric light, 259  
 Newton, 7  
 Niagara as a background, 334  
 Niépce, 2, 15  
 Nolet, 6  
 Nonactinic light for the dark room, 98,  
   100

## O

- Obernetter, 25  
 Oil printing, 390  
 Orthochromatic photography—  
   colour contrast, 276  
   colour screens, 277  
   dark room, light for, 101, 277  
   development in, 282  
   discovery of, 24  
   exposures in, 278, 281  
   light filters, 277  
   plates for, 92  
   "safe lights," 277  
   undyed plates for, 275  
 Ozobrome, 252  
 Ozotype, 231

## P

- Packham's toning process, 202  
 Paget bromide paper, 246  
 Paget Prize Plate Co., 174, 181  
 Panoramic perspective, 67, 314  
 Panoram, Kodak, 314  
*Papier mineral*, 295

## Paper—

- albumenized, 25, 179  
 Barnet bromide, 246  
 blue print, 23, 393  
 bromide, 25, 242  
 collodio-chloride, 174  
 ferro-prussiate, 23, 393  
 gaslight, 242  
 gum-bichromate, 234  
 Ilford bromide, 246  
   P.O.P., 25  
 Kodak bromide, 246  
   platinum, 205  
 Morgan and Kidd's bromide, 246  
 mounting on, 371  
 negatives on, 35, 90, 310  
 ozotype, 231  
 Paget bromide, 246  
 platinum, 192  
 printing out, 174  
 Talbot's process on, 21  
 self-toning, 131  
 transfer, for carbon, 210  
   to prepare, 224  
 waterproof for squeegeeing, 189  
 waxed, 21  
 Wellington and Ward's bromide, 243  
*Passe-partouts*, 371  
 Payne, A., 278  
 Pepper process, 396  
 Periscopic lenses, 69  
 Permanence, 175  
 Permits to photograph, 327  
 Perspective, 61  
   aerial, 352  
   cylindrical, 67  
   plane, 67  
   panoramic, 67, 314  
 Petzval, 26, 72  
 Photo-autocopyist, 390  
 Photo-ceramics, 396  
 Photo-filgrain, 390  
 Photographic Copyright Union, 375  
   Red book, 327  
   Society, 359, 373  
 Photographs, Copyright in, 373  
 Photography—  
   animated, 395  
   architectural, 319  
   in colours, 283  
   evolution of, 1  
   landscape, 308

**Photography—continued**

- naturalistic, 357
- orthochromatic, 275
- perspective and, 61
- pictorial, 343
- pinhole, 56
- portrait, 329
- printing press and, 380
- stereoscopic, 395
- three colour, 283
- Photogravure, 381
- Photo-lithography, 390
- Photo-micrography, 397
- Photo Secession, 359
- Photo-zincography, 390
- Physical reduction, 294
- Pinholes, to make, 57
  - to measure, 58
- Pictorial photography, 343
- Plane perspective, 67
- Plate-changing mechanism, 159
- Plate holders (*see* Dark slides)
- Plate speed, 123
- Plates, standard sizes of, 38
- Platino-matt bromide paper, 252
- Platinum process—
  - acid baths for, 198
  - actinometers for, 194
  - artificial light and, 193
  - unmounted prints for albums, 368
  - catechu toning, 203
  - damp and, 193
  - development, 192, 195
  - discoloration of prints, 203
  - fabrics for, 204
  - glycerine method, 200
  - hot-bath process, 195
  - intensification with gold, 202
  - invention of, 23
  - Kodak paper, 205
  - mercury in, 196
  - mildew and, 199
  - negatives for, 194
  - Packham's process, 202
  - restoring prints, 204
  - sepia tones, 197
  - stale paper, 205
  - toning methods for, 203
  - two colours by, 201
  - uranium in, 203
  - warm tones by development, 196
- Platinum toning P.O.P., 182

- Pluvinel, La Baume, 113
- Poitevin, 22, 206
- Ponton, 20, 22, 206
- P.O.P. (*see* Printing-out paper)
- Porta, G. B. della, 3, 9
- Portrait lenses, 330
- Portraits, backgrounds for, 332
- Portraiture, 329
- Pouncy, 23, 233
- Premo film pack, 35, 161
- Pressure marks, 251
- Prices for prints, 373
- Printing-frame, Cherrill, 300
  - Marion's, 247
  - to dispense with, 299
- Printing-out paper (P.O.P.)—
  - collodio-chloride, 174
  - colours and surfaces, 175
  - developing, 181
  - double tones on, 180
  - dry mounting, 190
  - enamelling, 184
  - gelatino-chloride, 174
  - gold toning, 180
  - Ilford, 25
  - mounting, 186, 190
  - Paget, 174, 181
  - platinum toning, 182
  - printing under green glass, 176
  - self-toning, 180
  - sensitiveness of, 175
  - soluble salts in, 179
  - squeegeeing, 184
  - vignetting on, 176
  - washing, 183
- Printing press and photography, 380
- Print washers, 183
- Prints, prices for, 373
- Prism for reversing, 220
- Process—
  - albumen, 98
  - autochrome, 285
  - bromide, 242
  - bromoil, 390
  - calotype, 20
  - carbograph, 251
  - carbon, 206
  - collodio-bromide, 392
  - collodio-chloride, 174
  - collotype, 388
  - colour photography, 283
  - daguerreotype, 17

**Process—continued**

- development, 124
  - Donisthorpe, 395
  - dry mounting, 190
  - enamelling, 184
  - ferro-prussiate, 23, 393
  - gaslight, 243
  - gelatine, 24
  - gum-bichromate, 23, 232
  - iron, 23
  - intensification, 143
  - kallitype, 394
  - Lippmann, 283
  - Lumière autochrome, 285
  - Mariotype, 231
  - mounting, 186
  - oil printing, 390
  - orthochromatic, 23, 275
  - ozobrome, 252
  - ozotype, 241
  - Packham's, 202
  - pepper, 396
  - photoceric, 396
  - photo-filigrain, 390
  - photogravure, 381
  - Rembrandt photogravure, 383
  - platinum, 192
  - P.O.P., 174
  - reduction, 145
    - physical, 294
  - Sanger Shepherd, 281
  - stannotype, 390
  - Talbot-Klic, 383
  - Talbotype, 19
  - three colour, 24, 283
  - trimming, 187
  - waxed paper, 21
  - wet plate, 22, 392
  - Woodburytype, 387
  - work (*see* Reproduction methods)
- Professional and amateur, 377
- Protars, 75, 82
- Pugin, 62
- Pulligny, 80, 364
- Puyo, C., 362

**R**

- Rawlins, G. E. H., 390
- Reade, Rev. J. B., 20
- Rectilinear, 71
- Red book, 327

**Reduction, 145**

- with ammonium persulphate, 145
  - Baskett's method, 271, 294
  - dangers of, 145
  - with ferricyanide and hypo, 145
  - of lantern slides, 145
  - methods compared, 145
  - physical, 294
  - with potassium permanganate, 145
  - to prepare negatives for, 145
  - with Sanzol, 145
  - of varnished negatives, 146
  - vignetting by, 305
- Reduction in size, by copying, 268
- Registration of copyright, 374
- Reinhold, 5
- Rejlander, O., 356
- Relief blocks, 384
- Rembrandt photogravures, 383
- Reproduction, fees for, 376
- methods, Collotype, 388
    - half-tone, 384
    - photogravure, 381
    - photo-lithography, 390
    - photo-zincography, 390
    - Woodburytype, 387
- Retouching, 304
- Reversing back, 32
- prism, 220
- Richards, Cruwys, 232
- Ring, the Linked, 358
- Rising front, 29
- Sanderson, 40
- Ritter, 12
- Robinson, H. P., 349, 356
- Roll film, 35
- Roll-film cartridges, 162
- Roll holders, 37
- Ross, 21, 26
- Ross' portable symmetricals, 71
- Rotary Photographic Co., 207, 243, 246
- Royal Photographic Society, 359, 373
- Ruby Christia, 102
- films, the Geka, 101
  - glass, 102
- Rudolph, 26

**S**

- Safe lights, 277
- Salon exhibition, 359, 373
- Sanderson front, 40

Sanger Shepherd process, 281  
 Sansol, 145  
 Sawyer, J. R., 23, 208  
 Sawyer's flexible support, 224  
 Sayce, 22  
 Scheele, 11, 23  
 Schonbein, 21  
 Schott, 26, 73  
 Schröder, 26  
 Schulze, 9  
 Scioptricks, 5  
 Scott's tables, 113  
 Screens, colour, 281  
     for lantern, 273  
     for dark-room windows, 101  
     Methven, 244  
 Selection of a lens, 68  
 Self-toning P.O.P., 181  
 Selling prints, 373  
 Sepia platinum prints, 197  
 Sheaths for films, 34  
 Sherar, 64  
 Shutters, 156  
     efficiency of, 157  
     the Frena, 158  
 Silk, bolting, 301  
 Sinop, 390  
 Sizes of plates, 38, 39  
 Slides (*see* Lantern slides)  
 Slides, dark, 32  
     Mackenzie-Wishart, 33  
     metal, 33  
 Snow and hoar-frost, 317  
 Squeezing P.O.P., 184  
 Society, the Royal Photographic, 359,  
     373  
 Spectrum plates, 102  
 Speed of a plate, 123  
 Spherical aberration, 7, 52  
 Spotting, 300  
 Stands for cameras, 37  
     tripod, 38  
     Ashford's patent, 38  
     folding adapter, 37  
     for portraits, 37, 332  
 Stannotype, 390  
 Steichen, 357  
 Steinheil, 26  
 Stereoscope, 395  
 Stieglitz, 201, 266, 359, 360  
 Stigmatic lens, 74  
 Stops, 44

Stops, the Uniform system, 45  
     Zeiss' system, 46  
 Stop, the selection of, 85  
 Striae in a lens, 46  
 Studio stands, 37, 332  
 Subject numbers, 121  
 Sunning down, 301  
 Swan, 23, 25, 206, 208, 242  
 Swing back, 31  
 Switzerland, plates for, 91  
 Symmetricals, 71  
 Systems of stops, 44

T

Tables, Dr. Scott's, 113  
 Talbot, Fox, 14, 19, 381  
 Talbot-Klic process, 383  
 Talbotype, 19  
 Taylor, Dennis, 26  
 Taylor, Taylor, and Hobson, 74  
 Technical education in photography, 378  
 Telephotographic lenses, 77  
 Telescope and the camera, 397  
 Tella changing device, 161  
 Tessar anastigmat, 74  
 Testing lenses, 46  
 Text-books, 378  
 Thomas, W., 315  
 Three-colour photography (*see* Colour  
     photography)  
 Time development, 124  
 Tonality, 354  
 Toning—  
     bromide prints, Blake-Smith's method,  
         252  
     bromide prints, hypo-alum, 252  
     double, 180  
     and fixing combined, 180  
     gaslight prints by development, 251  
     platinum prints with gold, 202  
         Packham's method, 202  
         with uranium, 203  
     P.O.P. with gold, 180  
         with platinum, 182  
     self, 181  
     slides by development, 268  
         with gold, 270  
 Transfer paper, to prepare, 224  
 Transparencies in carbon, 228  
 Trimming prints, 186

Tripod stands, 37  
     the Ashford, 38  
     the folding adapter, 37  
 Turn-tables, 38

## U

Unar anastigmat, 74  
 Uniform system, 45  
 Union, Photographic Copyright, 375

## V

Varnishing negatives, 141  
 Ventilating the dark room, 99  
 Vienna, Camera Club of, 362  
 Vignetting, 176  
     by reduction, 305  
 Vinci, Leonardo da, 3  
 Vogel, H. W., 23, 275  
 Voightlander, 26, 71

## W

Water-marks by photography, 390  
 Washers for prints, 183  
 Washing negatives, 137  
 Wastell, 342

Waterhouse, Major-Gen. J., 4  
 Watkins, 60  
 Watkins' development factors, 127  
 Watkins' meter, 116, 120, 320  
 Wave photography, 315  
 Waxed paper process, 21  
 Wedgwood, 10, 13, 20  
 Wellington's intensifier, 144, 269  
 Wellington and Ward, 243  
 Wet-plate process, 22, 392  
 Wild, 271, 305  
 Willis, 23  
 Window, screens for the dark room, 101  
 Woodbury, W. B., 206  
 Woodburytype, 387  
 Wotton, 5  
 Wynne's meter, 116

## Y

Yellow films, the "Geka," 101  
 Yellow glass for the dark room, 248  
 Young-Helmholtz theory, 283

## Z

Zahnsdorf albums, 368  
 Zeiss Protars, 69, 75, 82  
 Zeiss' stop system, 46  
 Zoological photography, 342



PRINTED BY  
WILLIAM CLOWES AND SONS, LIMITED,  
LONDON AND BECCLES.

# A CATALOGUE OF BOOKS PUBLISHED BY METHUEN AND COMPANY: LONDON 36 ESSEX STREET W.C.

## CONTENTS

	PAGE		PAGE
General Literature, . . .	1-32	Little Galleries, . . .	28
Ancient Cities, . . .	22	Little Guides, . . .	28
Antiquary's Books, . . .	22	Little Library, . . .	29
Arden Shakespeare . . .	23	Little Quarto Shakespeare, . . .	30
Beginner's Books, . . .	23	Miniature Library, . . .	30
Business Books, . . .	23	Oxford Biographies, . . .	30
Byzantine Texts, . . .	24	School Examination Series, . . .	31
Churchman's Bible, . . .	24	School Histories, . . .	31
Churchman's Library, . . .	24	Simplified French Texts, . . .	31
Classical Translations, . . .	24	Standard Library, . . .	31
Classics of Art, . . .	24	Textbooks of Science, . . .	32
Commercial Series, . . .	25	Textbooks of Technology, . . .	32
Connoisseur's Library, . . .	25	Handbooks of Theology, . . .	32
Illustrated Pocket Library of Plain and Coloured Books, . . .	25	Westminster Commentaries, . . .	32
Junior Examination Series, . . .	26		
Junior School-Books, . . .	27	Fiction, . . . . .	33-39
Leaders of Religion, . . .	27	Books for Boys and Girls, . . .	39
Library of Devotion, . . .	27	Novels of Alexandre Dumas, . . .	39
Little Books on Art, . . .	28	Methuen's Sixpenny Books, . . .	39

OCTOBER 1908



# A CATALOGUE OF MESSRS. METHUEN'S PUBLICATIONS

In this Catalogue the order is according to authors. An asterisk denotes that the book is in the press.

Colonial Editions are published of all Messrs. METHUEN'S Novels issued at a price above 2s. 6d., and similar editions are published of some works of General Literature. These are marked in the Catalogue. Colonial editions are only for circulation in the British Colonies and India.

All books marked net are not subject to discount, and cannot be bought at less than the published price. Books not marked net are subject to the discount which the bookseller allows.

Messrs. METHUEN'S books are kept in stock by all good booksellers. If there is any difficulty in seeing copies, Messrs. Methuen will be very glad to have early information, and specimen copies of any books will be sent on receipt of the published price *plus* postage for net books, and of the published price for ordinary books.

I.P.L. represents Illustrated Pocket Library

## PART I.—GENERAL LITERATURE

**Abbott (J. H. M.). AN OUTLANDER IN ENGLAND: Second Edition. Cr. 8vo. 6s**

A Colonial Edition is also published.

**Abraham (George D.) THE COMPLETE MOUNTAINEER. With 75 Illustrations. Second Edition. Demy 8vo. 15s. net.**

A Colonial Edition is also published.

**Acates (M. J.).** See Junior School Books.

**Adams (Frank). JACK SPRAT. With 24**

Coloured Pictures *Super Royal 16mo. 2s.*

**Adeney (W. F.), M.A. See Bennett (W. H.)**

**Ady (Cecilia M.). A HISTORY OF MILAN UNDER THE SPORZA. With 30 Illustrations and a Map. Demy 8vo. 10s. 6d. net.**

**Æschylus.** See Classical Translations.

**Æsop.** See I.P.L.

**Ainsworth (W. Harrison).** See I.P.L.

**Aldis (Janet). THE QUEEN OF LETTER WRITERS, MARQUISE DE SÉVIGNÉ, DAME DE BOURBILLY, 1626-96. With 18 Illustrations. Second Edition. Demy 8vo. 15s. 6d. net.**

A Colonial Edition is also published.

**Alexander (William). D.D., Archbishop of Armagh. THOUGHTS AND COUNSELS OF MANY YEARS. Demy 16mo. 2s. 6d.**

**Alikan (Henry).** See I.P.L.

**Allen (Charles C.).** See Textbooks of Technology.

**Allen (L. Jessie).** See Little Books on Art.

**Allen (J. Remilly), F.S.A. See Antiquary's Books.**

**Almack (E.), F.S.A. See Little Books on Art.**

**Ancherst (Lady). A SKETCH OF EGYPTIAN HISTORY FROM THE EARLIEST TIMES TO THE PRESENT DAY. With many Illustrations**

and Maps. *A New and Cheaper Issue. Demy 8vo. 7s. 6d. net.*

**Anderson (F. M.). THE STORY OF THE BRITISH EMPIRE FOR CHILDREN.**

With 42 Illustrations. *Cr. 8vo. 2s.*

**Anderson (J. G.), B.A. NOUVELLE GRAMMAIRE FRANÇAISE, À L'USAGE DES ÉCOLES ANGLAISES. Crown 8vo. 21. EXERCICES DE GRAMMAIRE FRANÇAISE. Cr. 8vo. 1s. 6d.**

**Andrewes (Bishop). PRECES PRIVATÆ. Translated and edited, with Notes, by F. E. BRIGHTMAN. M.A., of Pusey House, Oxford. Cr. 8vo. 6s.**

See also Library of Devotion.

**'Anglo-Australian.' AFTER-GLOW MEMORIES. Cr. 8vo. 6s.**

**ANON. HEALTH, WEALTH, AND WISDOM. Crown 8vo. 1s. net.**

**Aristotle. THE ETHICS OF. Edited, with an Introduction and Notes by JOHN BURNET, M.A., Cheaper Issue. Demy 8vo. 10s. 6d. net.**

**Asman (H. N.), M.A., LL.D. See Junior School Books.**

**Atkins (H. G.).** See Oxford Biographies.

**Atkinson (C. M.). JEREMY BENTHAM. Demy 8vo. 5s. net.**

**\*Atkinson (C. T.), M.A., Fellow of Exeter College, Oxford, sometime Fellow of Magdalen College. A HISTORY OF GERMANY, from 1713 to 1815. With many Maps. Demy 8vo. 15s. net.**

**Atkinson (T. D.). ENGLISH ARCHITECTURE. With 196 Illustrations. Second Edition. Fcap. 8vo. 3s. 6d. net.**

**A GLOSSARY OF TERMS USED IN ENGLISH ARCHITECTURE. With 265 Illustrations. Second Edition. Fcap. 8vo. 3s. 6d. net.**

**Auden (T.), M.A., F.S.A.** See *Ancient Cities*.  
**Aurelius (Marcus).** **WORDS OF THE ANCIENT WISE.** Thoughts from Epicurus and Marcus Aurelius. Edited by W. H. D. ROVER, M.A., Litt. D. *Fcap. 8vo.* 3s. 6d. net.

See also Standard Library.

**Austen (Jane).** See Standard Library, Little Library and Mitton (G. E.).

**Aves (Ernest).** **CO-OPERATIVE INDUSTRY.** *Crown 8vo.* 5s. net.

**Bacon (Francis).** See Standard Library and Little Library.

**Baden-Powell (R. S. S.)** **THE MATABELE CAMPAIGN, 1896.** With nearly 100 Illustrations. *Fourth Edition. Large Cr. 8vo.* 6s.

**Bagot (Richard).** **THE LAKES OF NORTHERN ITALY.** With 37 Illustrations and a Map. *Fcap. 8vo.* 5s. net.

**Bailey (J. C.), M.A.** See Cowper (W.).

**Baker (W. G.), M.A.** See Junior Examination Series.

**Baker (Julian L.), F.I.C., F.C.S.** See Books on Business.

**Balfour (Graham).** **THE LIFE OF ROBERT LOUIS STEVENSON.** With a Portrait. *Fourth Edition in one Volume. Cr. 8vo.* Buckram, 6s.

A Colonial Edition is also published.

**Ballard (A.), B.A., LL.D.** See Antiquary's Books.

**Bally (S. E.).** See Commercial Series.

**Banks (Elizabeth L.).** **THE AUTOBIOGRAPHY OF A 'NEWSPAPER GIRL.'** *Second Edition. Cr. 8vo.* 6s.

**Barham (R. H.).** See Little Library.

**Baring (The Hon. Maurice).** **WITH THE RUSSIANS IN MANCHURIA.** *Third Edition. Demy 8vo.* 7s. 6d. net.

A Colonial Edition is also published.

**A YEAR IN RUSSIA.** *Second Edition. Demy 8vo.* 10s. 6d. net.

A Colonial Edition is also published.

**Baring-Gould (S.).** **THE LIFE OF NAPOLEON BONAPARTE.** With nearly 200 Illustrations, including a Photogravure Frontispiece. *Second Edition. Wide Royal 8vo.* 10s. 6d. net.

A Colonial Edition is also published.

**THE TRAGEDY OF THE CÆSARS: A STUDY OF THE CHARACTERS OF THE CÆSARS OF THE JULIAN AND CLAUDIAN HOUSES.** With numerous Illustrations from Busts, Gems, Cameos, etc. *Sixth Edition. Royal 8vo.* 10s. 6d. net.

**A BOOK OF FAIRY TALES.** With numerous Illustrations by A. J. GASKIN. *Third Edition. Cr. 8vo.* Buckram. 6s., also Demy 8vo. 6d.

**OLD ENGLISH FAIRY TALES.** With numerous Illustrations by F. D. BEDFORD. *Third Edition. Cr. 8vo.* Buckram. 6s.

**THE VICAR OF MORWENTHLOW.** Revised Edition. With a Portrait. *Third Edition. Cr. 8vo.* 3s. 6d.

**OLD COUNTRY LIFE.** With 69 Illustrations. *Fifth Edition. Large Crown 8vo.* 6s.

**A GARLAND OF COUNTRY SONGS: English Folk Songs with their Traditional Melodies.** Collected and arranged by S. BARING-GOULD and H. F. SHEPPARD. *Demy 4to.* 6s.

**SONGS OF THE WEST: Folk Songs of Devon and Cornwall.** Collected from the Mouths of the People. By S. BARING-GOULD, M.A., and H. FLEETWOOD SHEPPARD, M.A. New and Revised Edition, under the musical editorship of CECIL J. SHARP. *Large Imperial 8vo.* 5s. net.

**A BOOK OF NURSERY SONGS AND RHYMES.** Edited by S. BARING-GOULD. Illustrated. *Second and Cheaper Edition. Large Cr. 8vo.* 2s. 6d. net.

**STRANGE SURVIVALS: SOME CHAPTERS IN THE HISTORY OF MAN.** Illustrated. *Third Edition. Cr. 8vo.* 2s. 6d. net.

**YORKSHIRE ODDITIES: INCIDENTS AND STRANGE EVENTS.** *Fifth Edition, Cr. 8vo.* 2s. 6d. net.

**THE BARING-GOULD SELECTION READER.** Arranged by G. H. ROSE. Illustrated. *Crown 8vo.* 1s. 6d.

**THE BARING-GOULD CONTINUOUS READER.** Arranged by G. H. ROSE. Illustrated. *Crown 8vo.* 1s. 6d.

**A BOOK OF CORNWALL.** With 33 Illustrations. *Second Edition. Cr. 8vo.* 6s.

**A BOOK OF DARTMOOR.** With 60 Illustrations. *Second Edition. Cr. 8vo.* 6s.

**A BOOK OF DEVON.** With 35 Illustrations. *Second Edition. Cr. 8vo.* 6s.

**A BOOK OF NORTH WALES.** With 49 Illustrations. *Cr. 8vo.* 6s.

**A BOOK OF SOUTH WALES.** With 57 Illustrations. *Cr. 8vo.* 6s.

**A BOOK OF BRITANNY.** With 69 Illustrations. *Cr. 8vo.* 6s.

**A BOOK OF THE RHINE:** From Cleve to Mainz. With 8 Illustrations in Colour by TREVOR HADDEN, and 48 other Illustrations. *Second Edition. Cr. 8vo.* 6s.

A Colonial Edition is also published.

**A BOOK OF THE RIVIERA.** With 40 Illustrations. *Cr. 8vo.* 6s.

A Colonial Edition is also published.

**A BOOK OF THE PYRENEES.** With 25 Illustrations. *Cr. 8vo.* 6s.

A Colonial Edition is also published.

See also Little Guides.

**Barker (Aldred F.).** See Textbooks of Technology.

**Barker (E.), M.A. (Late) Fellow of Merton College, Oxford.** **THE POLITICAL THOUGHT OF PLATO AND ARISTOTLE.** *Demy 8vo.* 10s. 6d. net.

**Barnes (W. E.), D.D.** See Churchman's Bible.

**Barnett (Mrs. P. A.).** See Little Library.  
**Barton (R. R. N.), M.A.** **FRENCH PROSE COMPOSITION.** *Third Edition. Cr. 8vo.* 1s. 6d. Key, 3s. net.

See also Junior School Books.

**Barrow (H. M.), M.A., Wadham College, Oxford.** **TEXTS FOR SERMONS.** With

- is Prefaced by Canon SCOTT HOLLAND.  
Cr. 8vo. 3s. 6d.
- Bartholomew (J. G.), F.R.S.E.** See C. G. Robertson.
- Bastable (C. F.), LL.D.** THE COMMERCE OF NATIONS. *Fourth Ed.* Cr. 8vo. 2s. 6d.
- Baileston (H. Charlton), M.A., M.D., F.R.S.** THE EVOLUTION OF LIFE. With Diagrams and many Photomicrographs. *Demy 8vo. 7s. 6d. net.*
- Batson (Mrs. Stephen).** A CONCISE HANDBOOK OF GARDEN FLOWERS. *Poap. 8vo. 3s. 6d.*
- BATEMAN (Mrs. Stephen).** THE SUMMER GARDEN OF PLEASURE. With 36 Illustrations in Colour by OSWUND PITTMAN. *Wide Demy 8vo. 15s. net.*
- Batten (Loring W.), Ph.D., S.T.D.** THE HEBREW PROPHET *Cr. 8vo. 3s. 6d. net*
- Bayley (R. Child).** THE COMPLETE PHOTOGRAPHER. With over 100 Illustrations. *Third Edition. With Note on Direct Colour Process. Demy 8vo. 10s. 6d. net.*
- A Colonial Edition is also published.
- Beard (W. S.).** EASY EXERCISES IN ALGEBRA FOR BEGINNERS. *Cr. 8vo. 1s. 6d. With Answers. 1s. 9d.*
- See also Junior Examination Series, and Beginner's Books.
- Beckford (Peter).** THOUGHTS ON HUNTING. Edited by J. OTHO PAGE, and illustrated by G. H. JALLAND. *Second Edition. Demy 8vo. 6s.*
- Beckford (William).** See Little Library.
- Beeching (H. C.), M.A.** Canon of Westminster. See Library of Devotion.
- Beerhelm (Max).** A BOOK OF CARICATURES. *Imperial 4to. 21s. net.*
- Begbie (Harold).** MASTER WORKERS. Illustrated. *Demy 8vo. 7s. 6d. net.*
- Behmen (Jacob).** DIALOGUES ON THE SUPERSENSUAL LIFE. Edited by BERNARD HOLLAND. *Cr. 8vo. 7s. 6d.*
- Bell (Mrs. Arthur G.).** THE SKIRTS OF THE GREAT CITY. With 16 Illustrations in Colour by ARTHUR G. BELL, 17 other Illustrations, and a Map. *Second Edition. Cr. 8vo. 6s.*
- Bellac (Milaire), M.P.** PARIS. With 7 Maps and a Frontispiece in Photogravure. *Second Edition, Revised. Cr. 8vo. 6s.*
- HILLS AND THE SEA** *Second Edition. Crown 8vo. 6s.*
- ON NOTHING AND KINDRED SUBJECTS.** *Poap. 8vo. 5s.*
- A Colonial Edition is also published.
- Bellot (H. H. L.), M.A.** See Jones (L. A. A.).
- Bennett (W. H.), M.A.** A PRIMER OF THE BIBLE. With a concise Bibliography. *Fourth Edition. Cr. 8vo. 2s. 6d.*
- Bennett (W. H.) and Adams (W. F.).** A BIBLICAL INTRODUCTION. *Fifth Edition. Cr. 8vo. 7s. 6d.*
- Benson (Abraham).** GOD'S BOARD Communion Addresses. *Second Edition. Poap. 8vo. 3s. 6d. net.*
- Benson (A. C.), M.A.** See Oxford Biographies.
- Benson (R. M.).** THE WAY OF HOLINESS: a Devotional Commentary on the 119th Psalm. *Cr. 8vo. 5s.*
- Bernard (E. R.), M.A.** Canon of Salisbury. THE ENGLISH SUNDAY: ITS ORIGINS AND ITS CLAIMS. *Poap. 8vo. 1s. 6d.*
- Bertouch (Baroness de).** THE LIFE OF FATHER IGNATIUS. Illustrated. *Demy 8vo. 10s. 6d. net.*
- Bernete (A. de).** See Classics of Art.
- Betham-Edwards (Miss).** HOME LIFE IN FRANCE. With 20 Illustrations. *Fifth Edition. Crown 8vo. 6s.*
- A Colonial Edition is also published.
- Bethune-Baker (J. F.), M.A.** See Handbooks of Theology.
- Bidez (J.).** See Byzantine Texts.
- Biggs (C. R. D.), D.D.** See Churchman's Bible.
- Bindley (T. Herbert), B.D.** THE JECUMENICAL DOCUMENTS OF THE FAITH. With Introductions and Notes. *Second Edition. Cr. 8vo. 6s. net.*
- Binn (H. B.).** THE LIFE OF WALT WHITMAN. Illustrated. *Demy 8vo. 10s. 6d. net.*
- A Colonial Edition is also published.
- Binyon (Mrs. Laurence).** NINETEENTH CENTURY PROSE. Selected and arranged by. *Crown 8vo. 6s.*
- Binyon (Laurence).** THE DEATH OF ADAM AND OTHER POEMS. *Cr. 8vo. 3s. 6d. net.*
- See also Blake (William).
- Birch (Walter de Gray), LL.D., F.S.A.** See Connoisseur's Library.
- Strunz (Ethel).** See Little Books on Art.
- Blackmantle (Bernard).** See I.P.L.
- Blair (Robert).** See I.P.L.
- Blake (William).** THE LETTERS OF WILLIAM BLAKE, TOGETHER WITH A LIFE BY FREDERICK TATMAN. Edited from the Original Manuscripts, with an Introduction and Notes, by ARCHIBALD G. B. RUSSELL. With 12 Illustrations. *Demy 8vo. 7s. 6d. net.*
- ILLUSTRATIONS OF THE BOOK OF JOB.** With General Introduction by LAURENCE BINYON. *Quarto. 21s. net.*
- See also Blair (Robert), I.P.L., and Little Library.
- Bloom (J. Harvey), M.A.** SHAKESPEARE'S GARDEN. Illustrated. *Poap. 8vo. 3s. 6d.; leather, 4s. 6d. net.*
- See also Antiquary's Books.
- Blount (Henri).** See Beginner's Books.
- Boardman (T. H.), M.A.** See T. H. (W.).
- Bodley (J. E. C.), Author of 'France,'** THE CORONATION OF EDWARD VII. *Demy 8vo. 21s. net.* By Command of the King.
- Boddy (George), D.D.** THE SOUL'S PILGRIMAGE: Devotional Readings from the Published and Unpublished writings of George Boddy, D.D. Selected and arranged by J. H. BURN, B.D., F.R.S.E. *Demy 16mo. 2s. 6d.*

**Beas (Cardinal).** See Library of Devotion.  
**Beon (P. C.), B.A.** See Commercial Series.  
**Barrow (George).** See Little Library.

**Bees (J. Fitzma).** AGRICULTURAL ZOOLOGY. Translated by J. R. AINSWORTH DAVIS, M.A. With 155 illustrations. *Third Edition.* Cr. 8vo. 2s. 6d.

**Betting (C. G.), B.A.** EASY GREEK EXERCISES. Cr. 8vo. 2s.

See also Junior Examination Series.

**Boulting (W.)** TASSO AND HIS TIMES. With 24 illustrations. *Demy 8vo.* 20s. 6d. net.

**Boulton (E. S.), M.A.** GEOMETRY ON MODERN LINES. Cr. 8vo. 2s.

**Beaumont (William B.),** THOMAS GAINSBOROUGH. His Life and Work, Friends and Sitters. With 40 illustrations. *Second Ed.* *Demy 8vo.* 7s. 6d. net.

**Shimoshua Reynolds, P.R.A.** With 49 illustrations. *Demy 8vo.* 7s. 6d. net.

**Bowden (E. M.),** THE IMITATION OF BUDDHA: Being Quotations from Buddhist Literature for each Day in the Year. *Fifth Edition.* Cr. 16mo. 2s. 6d.

**Boyle (W.),** CHRISTMAS AT THE ZOO. With Verses by W. BOYLE and 24 Coloured Pictures by H. B. NEILSON. *Super Royal 16mo.* 2s.

**Brabant (F. G.), M.A.** See Little Guides  
**Bradley (A. G.),** ROUND ABOUT WILTSHIRE. With 14 illustrations, in Colour by T. C. GOTH, 16 other illustrations, and a Map. *Second Edition.* Cr. 8vo. 6s.

A Colonial Edition is also published.

**THE ROMANCE OF NORTHUMBERLAND.** With 16 illustrations in Colour by FRANK SOUFGATE, R.B.A., and 12 from Photographs. *Second Edition.* *Demy 8vo.* 7s. 6d. net.

A Colonial Edition is also published.

**Bradley (John W.),** See Little Books on Art.  
**Braid (James),** Open Champion, 1901, 1905 and 1906. ADVANCED GOLF. With 88 Photographs and Diagrams. *Fourth Edition.* *Demy 8vo.* 10s. 6d. net.

A Colonial Edition is also published.

**Braid (James) and Others,** GREAT GOLFERS IN THE MAKING. Edited by HENRY LEACH. With 24 illustrations. *Second Edition.* *Demy 8vo.* 7s. 6d. net.

A Colonial Edition is also published.

**Brailford (H. N.),** MACEDONIA: ITS RACES AND THEIR FUTURE. With Photographs and Maps. *Demy 8vo.* 12s. 6d. net.

**Brodrick (Mary) and Morton (A. Anderson),** A CONCISE DICTIONARY OF EGYPTIAN ARCHAEOLOGY. A Handbook for Students and Travellers. With 80 illustrations and many Cartouches. Cr. 8vo. 3s. 6d.

**Brooks (E. E.), B.Sc. (Lead),** Leicester Municipal Technical School, and **James (W. H. N.), A.R.C.S., A.M.I.E.E.,** Municipal School of Technology, Manchester. See Textbooks of Technology.

**Brooks (E. W.),** See Hamilton (F. J.)

**Brown (P. H.), LL.D.,** SCOTLAND IN THE TIME OF QUEEN MARY. *Demy 8vo.* 7s. 6d. net.

**Brown (S. E.), M.A., B.Sc.,** Senior Science Master at Uppingham. A PRACTICAL CHEMISTRY NOTE-BOOK FOR MATRICULATION AND ARMY CANDIDATES. Easy Experiments on the Commoner Substances. Cr. 4to. 1s. 6d. net.

**Brown (J. Wood), M.A.,** THE BUILDERS OF FLORENCE. With 74 illustrations by HERBERT RAILTON. *Demy 4to.* 12s. 6d. net.

**Browne (Sir Thomas).** See Standard Library.

**Brownell (C. L.),** THE HEART OF JAPAN. Illustrated. *Third Edition.* Cr. 8vo. 6s.; also *Demy 8vo.* 6d.

**Browning (Robert).** See Little Library.  
**Bryant (Walter W.), B.A., F.R.A.S., F.R.** Met Soc. of the Royal Observatory, Greenwich. A HISTORY OF ASTRONOMY. With 35 illustrations. *Demy 8vo.* 7s. 6d. net.

**Buckland (Francis T.),** CURIOSITIES OF NATURAL HISTORY. Illustrated by H. B. NEILSON. Cr. 8vo. 2s. 6d.

**Buckton (A. M.),** THE BURDEN OF ENGELA. *Second Edition.* Cr. 8vo. 7s. 6d. net.

**EAGER HEART: A Mystery Play.** *Seventh Edition.* Cr. 8vo. 1s. net.

**KINGS IN BABYLON: A Drama.** Cr. 8vo. 1s. net.

**SONGS OF JOY.** Cr. 8vo. 1s. net.

**Budge (E. A. Wallis),** THE GODS OF THE EGYPTIANS. With over 100 Coloured Plates and many illustrations. *Two Volumes.* *Royal 8vo.* £3. 2s. net.

**Bull (Paul),** Army Chaplain. GOD AND OUR SOLDIERS. *Second Edition.* Cr. 8vo. 6s.

A Colonial Edition is also published.

**Bulley (Miss).** See Dilke (Lady).

**Burman (John).** See Standard Library and Library of Devotion.

**Burch (G. J.), M.A., F.R.S.** A MANUAL OF ELECTRICAL SCIENCE. Illustrated. Cr. 8vo. 3s.

**Burgess (Gelett),** GOOPS AND HOW TO BE THEM. Illustrated. *Small 4to.* 6s.

**Burke (Edmund).** See Standard Library.

**Burn (A. E.), D.D.,** Rector of Handsworth and Prebendary of Lichfield. See Handbooks of Theology.

**Burn (J. H.), B.D., F.R.S.E.,** THE CHURCHMAN'S TREASURY OF SONG: Gathered from the Christian poetry of all ages. Edited by *Ficq.* 8vo. 3s. 6d. net. See also Library of Devotion.

**Burnand (Sir F. C.),** RECORDS AND REMINISCENCES. With a Portrait by H. v. HERKIMER. Cr. 8vo. *Fourth and Cheaper Edition.* 6s.

A Colonial Edition is also published.

**Burns (Robert),** THE POEMS. Edited by ANDREW LANG and W. A. CRANES. With Portrait. *Third Edition.* *Demy 8vo.* 4d. 6s.

See also Standard Library.

- Burnside (W. F.), M.A. OLD TESTAMENT HISTORY FOR USE IN SCHOOLS.** *Third Edition.* Cr. 8vo. 3s. 6d.
- Burton (Alfred).** See I.P.L.
- Beasell (F. W.), D.D. CHRISTIAN THEOLOGY AND SOCIAL PROGRESS** (The Bampton Lectures of 1905). Demy 8vo. 10s. 6d. net.
- Berter (Joseph), D.D.** See Standard Library.
- Caldacott (Alfred), D.D.** See Handbooks of Theology.
- Caldarwood (D. S.), Headmaster of the Normal School, Edinburgh. TEST CARDS IN EUCLID AND ALGEBRA.** In three packets of 40, with Answers. 1s. each. Or in three Books, price 2d., 2d., and 3d.
- Canning (George).** See Little Library.
- Capey (E. F. H.).** See Oxford Biographies.
- Carless (John).** See I.P.L.
- Carlyle (Thomas). THE FRENCH REVOLUTION.** Edited by C. R. L. FLETCHER, Fellow of Magdalen College, Oxford. *Three Volumes.* Cr. 8vo. 18s.
- THE LIFE AND LETTERS OF OLIVER CROMWELL.** With an Introduction by C. H. FURTH, M.A., and Notes and Appendices by Mrs. S. C. LOMAS. *Three Volumes.* Demy 8vo. 18s. net.
- Carlyle (R. M. and A. J.), M.A.** See Leaders of Religion.
- Carmichael (Philip). ALL ABOUT PHILIPPINE.** With 8 Illustrations. Cr. 8vo. 2s. 6d.
- Carpenter (Margaret Boyd). THE CHILD IN ART.** With 50 Illustrations. *Second Edition.* Large Cr. 8vo. 6s.
- Cavanagh (Francis), M.D. (Edin.). THE CARE OF THE BODY.** *Second Edition.* Demy 8vo. 7s. 6d. net.
- Celano (Thomas of). THE LIVES OF ST. FRANCIS OF ASSISI.** Translated into English by A. G. FERRERS HOWELL. With a Frontispiece. Cr. 8vo. 5s. net.
- Channer (C. C.) and Roberts (M. E.). LACEMAKING IN THE MIDLANDS, PAST AND PRESENT.** With 16 full-page Illustrations. Cr. 8vo. 2s. 6d.
- Chapman (S. J.).** See Books on Business.
- Chatterton (Thomas).** See Standard Library.
- Chatterfield (Lord). THE LETTERS OF, TO HIS SON.** Edited, with an Introduction by C. STRACHEY, with Notes by A. CALTHROP. *Two Volumes.* Cr. 8vo. 12s.
- Chatterton (G. K.). CHARLES DICKENS.** With two Portraits in Photogravure. *Fifth Edition.* Cr. 8vo. 6s.
- Childs (Charles P.), B.A., F.R.C.S. THE CONTROL OF A SCOURGE: OR, HOW CANCER IS CURABLE.** Demy 8vo. 7s. 6d. net.
- Christian (F. W.). THE CAROLINE ISLANDS.** With many Illustrations and Maps. Demy 8vo. 12s. 6d. net.
- Claude.** See Chemical Translations.
- Clapham (J. H.), Professor of Economics in the University of Leeds. THE WOOLLEN AND WORSTED INDUSTRIES.** With 21 Illustrations and Diagrams. Cr. 8vo. 6s.
- Clarke (F. A.), M.A. See Leaders of Religion.**
- Clausen (George), A.R.A. SIX LECTURES ON PAINTING.** With 19 Illustrations. *Third Edition.* Large Post 8vo. 3s. 6d. net.
- AIMS AND IDEALS IN ART.** Eight Lectures delivered to the Students of the Royal Academy of Arts. With 32 Illustrations. *Second Edition.* Large Post 8vo. 5s. net.
- Cleather (A. L.).** See Wagner (R).
- Clinch (G.), F.G.S. See Antiquary's Books and Little Guides.**
- Clough (W. T.) and Dunstan (A. E.).** See Junior School Books and Textbooks of Science.
- Clouston (T. S.), M.D., C.C.D., F.R.S.E. THE HYGIENE OF MIND.** With 10 Illustrations. *Fourth Edition.* Demy 8vo. 7s. 6d. net.
- Coast (W. G.), B.A. EXAMINATION PAPERS IN VERGIL.** Cr. 8vo. 2s.
- Cobb (W. F.), M.A. THE BOOK OF PSALMS: with a Commentary.** Demy 8vo. 10s. 6d. net.
- Coleridge (S. T.). POEMS.** Selected and Arranged by ARTHUR SYMONS. With a Photogravure Frontispiece. Fcap. 8vo. 2s. 6d. net.
- Collingwood (W. G.), M.A. THE LIFE OF JOHN RUSKIN.** With Portrait. *Sixth Edition.* Cr. 8vo. 2s. 6d. net.
- Collins (W. E.), M.A.** See Churchman's Library.
- Combe (William).** See I.P.L.
- Conrad (Joseph). THE MIRROR OF THE SEA: Memories and Impressions.** *Third Edition.* Cr. 8vo. 6s.
- Cook (A. M.), M.A., and Marchant (E. C.), M.A. PASSAGES FOR UNSEEN TRANSLATION.** Selected from Latin and Greek Literature. *Fourth Ed.* Cr. 8vo. 3s. 6d.
- LATIN PASSAGES FOR UNSEEN TRANSLATION.** *Third Ed.* Cr. 8vo. 1s. 6d.
- Cooke-Taylor (R. W.). THE FACTORY SYSTEM.** Cr. 8vo. 2s. 6d.
- Coolidge (W. A. B.), M.A. THE ALPS.** With many Illustrations. Demy 8vo. 7s. 6d. net.
- A Colonial Edition is also published.
- Correll (Marie). THE PASSING OF THE GREAT QUEEN.** *Second Edition.* Fcap. 4to. 1s.
- A CHRISTMAS GREETING.** Cr. 4to. 1s.
- Corkran (Alice).** See Little Books on Art.
- Cotes (Everard). SIGNS AND PORTENTS IN THE FAR EAST.** With 35 Illustrations. *Second Edition.* Demy 8vo. 7s. 6d. net.
- A Colonial Edition is also published.
- Cotes (Rosemary). DANTE'S GARDEN.** With a Frontispiece. *Second Edition.* Fcap. 8vo. 2s. 6d.; leather, 3s. 6d. net.
- BIBLE FLOWERS.** With a Frontispiece and Plan. Fcap. 8vo. 2s. 6d. net.

# GENERAL LITERATURE.

7

**Cowley (Abraham).** See Little Library.

**Cowper (William).** THE POEMS. Edited with an Introduction and Notes by J. C. BARREY, M.A. Illustrated, including two unpublished designs by WILLIAM BLAKE. Demy 8vo. 10s. 6d. net.

**Cox (J. Charles).** See Ancient Cities, Antiquary's Books, and Little Guides.

**Cox (Harold).** B.A., M.P. LAND NATIONALIZATION AND LAND TAKATION. Second Edition revised. Cr. 8vo. 3s. 6d. net.

**Crabbe (George).** See Little Library.

**Craik (Mrs.).** See Little Library.

**Crane (C. P.).** D.S.O. See Little Guides.

**Crane (Walter).** R.W.S. AN ARTIST'S REMINISCENCES. With 123 Illustrations by the Author and others from Photographs. Second Edition. Demy 8vo. 18s.

A Colonial Edition is also published.  
**INDIA IMPRESSIONS.** With 84 Illustrations from Sketches by the Author. Second Edition. Demy 8vo. 7s. 6d. net.

A Colonial Edition is also published.

**Crashaw (Richard).** See Little Library.

**Crawford (F. G.).** See Danson (Mary C.)

**Crofts (T. R. N.).** M.A., Modern Language Master at Merchant Taylors' School. See Simplified French Texts.

**Cross (J. A.).** M.A. THE FAITH OF THE BIBLE. Fcap. 8vo. 2s. 6d. net.

**Cruikshank (G.).** THE LOVING BALAD OF LORD BATEMAN. With 11 Plates. Cr. 16mo. 1s. 6d. net.

**Crump (B.).** See Wagner (R.).

**Cunliffe (Sir F. H. E.).** Fellow of All Souls' College, Oxford. THE HISTORY OF THE BOER WAR. With many Illustrations, Plans, and Portraits. In 2 vols. Quarto. 15s. each.

**Cunynghame (H. H.).** C.B. See Connors's Library.

**Cutts (E. L.).** D.D. See Leaders of Religion.

**Danilei (G. W.).** M.A. See Leaders of Religion.

**Dante (Alighieri).** LA COMMEDIA DI DANTE. The Italian Text edited by PAGET TOYNBEE, M.A., D.Litt. Cr. 8vo. 6s.

**THE DIVINE COMEDY.** Translated by H. F. CARY. Edited with a Life of Dante and Introductory Notes by PAGET TOYNBEE, M.A., D.Litt. Demy 8vo. 6d.

**THE PURGATORIO OF DANTE.** Translated into Spenserian Prose by C. GORDON WRIGHT. With the Italian text. Fcap. 8vo. 2s. 6d. net.

See Little Library, Toynbee (Paget), and Vernon (Hon W. Warren).

**Darley (George).** See Little Library.

**D'Arcy (R. F.).** M.A. A NEW TRIGONOMETRY FOR BEGINNERS. With numerous diagrams. Cr. 8vo. 2s. 6d.

**Davenport (Cyril).** See Connors's Library and Little Books on Art.

**Davenport (James).** THE WASHBOURNE FAMILY. With 15 Illustrations and a Map. Royal 8vo. 21s. net.

**Davey (Richard).** THE PAGEANT OF LONDON. With 40 Illustrations in Colour by JOHN FULLERLOVE, R.I. In Two Volumes. Demy 8vo. 12s. net.

**Davis (H. W. C.).** M.A., Fellow and Tutor of Balliol College. ENGLAND UNDER THE NORMANS AND ANGEVINS: 1066-1272. With Maps and Illustrations. Demy 8vo. 10s. 6d. net.

**Dawson (Nelson).** See Connors's Library.

**Dawson (Mrs. Nelson).** See Little Books on Art.

**Deane (A. C.).** See Little Library.

**Deans (Story R.).** THE TRIALS OF FIVE QUEENS: KATHARINE OF ARAGON, ANNE BOLEYN, MARY QUEEN OF SCOTS, MARIE ANTOINETTE and CAROLINE OF BRUNSWICK. With 22 Illustrations. Demy 8vo. 10s. 6d. net.

A Colonial Edition is also published.

**Deanner (Mabel).** A CHILD'S LIFE OF CHRIST. With 8 Illustrations in Colour by E. FORTESCUE-BRICKDALE. Large Cr. 8vo. 6s.

**Delbos (Leon).** THE METRIC SYSTEM. Cr. 8vo. 2s.

**Demosthenes.** AGAINST CONON AND CALLICLES. Edited by F. DARWIN SWIFF, M.A. Second Edition. Fcap. 8vo. 2s.

**Dickens (Charles).** See Little Library, I P.L., and Chesterton (G. K.)

**Dickinson (Emily).** POEMS. Cr. 8vo. 4s. 6d. net.

**Dickinson (G. L.).** M.A., Fellow of King's College, Cambridge. THE GREEK VIEW OF LIFE. Sixth Edition. Cr. 8vo. 2s. 6d.

**Dilke (Lady), Bulley (Miss), and Whitley (Miss).** WOMEN'S WORK. Cr. 8vo. 2s. 6d.

**Dillon (Edward).** M.A. See Connors's Library and Little Books on Art.

**Ditchfield (P. H.).** M.A., F.S.A. THE STORY OF OUR ENGLISH TOWNS. With an Introduction by AUGUSTUS JESSOPP, D.D. Second Edition. Cr. 8vo. 6s.

**OLD ENGLISH CUSTOMS:** Extant at the Present Time. Cr. 8vo. 6s.

**ENGLISH VILLAGES.** With 100 Illustrations. Second Edition. Cr. 8vo. 2s. 6d. net.

**THE PARISH CLERK.** With 21 Illustrations. Third Edition. Demy 8vo. 7s. 6d. net.

**Dixon (W. M.).** M.A. A PRIMER OF TENNYSON. Second Edition. Cr. 8vo. 2s. 6d.

**ENGLISH POETRY FROM BLAKE TO BROWNING.** Second Edition. Cr. 8vo. 2s. 6d.

**Dobbs (W. J.).** M.A. See Textbooks of Science.

**Donay (May).** SONGS OF THE REAL. Cr. 8vo. 3s. 6d. net.

**Douglas (Hugh A.).** VENICE ON FOOT. With the Itinerary of the Grand Canal. With 75 Illustrations and 11 Maps. Royal 8vo. 3s. net.

**Douglas (James).** THE MAN IN THE PULPIT. *Cr. 8vo. 2s. 6d. net.*  
**Howison (L. D.D.,** Lord Bishop of Edinburgh. FURTHER STUDIES IN THE PRAYER BOOK. *Cr. 8vo. 6s.*  
 See also Churchman's Library.  
**Drage (G.).** See Books on Business.  
**Draper (F. W. M.).** See Simplified French Texts.

**Driver (E. R.), D.D., D.C.L.,** Regius Professor of Hebrew in the University of Oxford. SERMONS ON SUBJECTS CONNECTED WITH THE OLD TESTAMENT. *Cr. 8vo. 6s.*

See also Westminster Commentaries.

**Dry (Wakeling).** See Little Guides.

**Dryhurst (A. R.).** See Little Books on Art.  
**Druidson (J. C.), M.A.** See Churchman's Bible.

**Druid (Charles).** See Books on Business.

**Dumas (Alexandre).** THE CRIMES OF THE BORGAS AND OTHERS. With an Introduction by R. S. GARNETT. With 9 Illustrations. *Cr. 8vo. 6s.*

**THE CRIMES OF URBAIN GRANDIER AND OTHERS.** With 8 Illustrations. *Cr. 8vo. 6s.*

**THE CRIMES OF THE MARQUISE DE BRINVILLIERS AND OTHERS.** With 8 Illustrations. *Cr. 8vo. 6s.*

**THE CRIMES OF ALI PACHA AND OTHERS.** With 8 Illustrations. *Cr. 8vo. 6s.*

Colonial Editions are also published.

**MY MEMOIRS.** Translated by E. M. WALLER. With an Introduction by ANDREW LANG. With Frontispieces in Photogravure in six Volumes. *Cr. 8vo. 6s. each volume.*  
 A Colonial Edition is also published.

**VOL. I.** 1802-1807. **VOL. III.** 1826-1830.

**VOL. II.** 1807-1826. **VOL. IV.** 1830-1837.

**Duncan (David), D.Sc., LL.D.** THE LIFE AND LETTERS OF HERBERT SPENCER. With 15 Illustrations. *Demy 8vo. 15s.*

**Dunn (J. T.), D.Sc., and Mundella (V. A.).** GENERAL ELEMENTARY SCIENCE. With 124 Illustrations. *Second Edition. Cr. 8vo. 3s. 6d.*

**Dunstan (A. E.), R.Sc. (Lond.),** East Ham Technical College. See Textbooks of Science and Junior School Books.

**Durham (The Earl of).** A REPORT ON CANADA. With an Introductory Note. *Demy 8vo. 1s. 6d. net.*

**Dutt (W. A.).** THE NORFOLK BROADS. With coloured Illustrations by FRANK SOUTHGATE, R.B.A. *Second Edition. Cr. 8vo. 6s.*

**WILD LIFE IN EAST ANGLIA.** With 16 Illustrations in colour by FRANK SOUTHGATE, R.B.A. *Second Edition. Demy 8vo. 7s. 6d. net.*

**SOME LITERARY ASSOCIATIONS OF EAST ANGLIA.** With 16 Illustrations in Colour by W. DEXTER, R.B.A., and 16 other Illustrations. *Demy 8vo. 2ss. 6d. net.*  
 See also Little Guides.

**Harle (John), Bishop of Salisbury.** MICRO-COSMOGRAPHIE, OR A PIECE OF THE WORLD DISCOVERED. *Part 16mo. 2s. net.*

**Edmonds (Major J. E.), R.E.; D.A.Q.-M.G.** See Wood (W. Birkbeck).

**Edwards (Clement), M.P.** RAILWAY NATIONALIZATION. *Second Edition, Revised. Crown 8vo. 2s. 6d. net.*

**Edwards (W. Douglas).** See Commercial Series.

**Edwardes (Tickner).** THE LORE OF THE HONEY BEE. With many Illustrations. *Cr. 8vo. 6s.*

**Egan (Pierce).** See I.P.L.

**Egerton (H. E.), M.A.** A HISTORY OF BRITISH COLONIAL POLICY. A Cheaper Issue, with a supplementary chapter. *Second Ed., Revised. Demy 8vo. 7s. 6d. net.*  
 A Colonial Edition is also published.

**Ellaby (C. G.).** See Little Guides.

**Ellerton (F. G.).** See Stone (S. J.).

**Epictetus.** See Aurelius (Marcus).

**Erasmus.** A Book called in Latin ENCHIRIDION MILITIS CHRISTIANI and in English the Manual of the Christian Knight. *Cap 8vo. 7s. 6d. net.*

**Ewald (Carl).** TWO LEGS, AND OTHER STORIES. Translated from the Danish by ALEXANDER TEIXEIRA DE MATTOZ. Illustrated by AUGUSTA GUEST. *Large Cr. 8vo. 6s.*

**Fairbrother (W. H.), M.A.** THE PHILOSOPHY OF I. H. GREEN. *Second Edition. Cr. 8vo. 2s. 6d.*

**Fen (Allen).** SOME BEAUTIES OF THE SEVENTEENTH CENTURY. With 82 Illustrations. *Second Edition. Demy 8vo. 12s. 6d. net.*

**THE FLIGHT OF THE KING.** With over 70 Sketches and Photographs by the Author. *New and revised Edition. Demy 8vo. 7s. 6d. net.*

A Colonial Edition is also published  
**SECRET CHAMBERS AND HIDING-PLACES.** With 80 Illustrations. *New and revised Edition. Demy 8vo. 7s. 6d. net.*

A Colonial Edition is also published.

**Ferrier (Susan).** See Little Library.  
**Fidler (T. Claxton), M.Inst. C.E.** See Books on Business.

**Fielding (Henry).** See Standard Library.

**Finn (S. W.), M.A.** See Junior Examination Series.

**Firth (J. B.).** See Little Guides.

**Firth (C. H.), M.A.,** Regius Professor of Modern History at Oxford. CROMWELL'S ARMY; A History of the English Soldier during the Civil War, the Commonwealth, and the Protectorate. *Cr. 8vo. 6s.*

**Firth (Edith E.).** See Beginner's Books.  
**FitzGerald (Edward).** THE RUBAIYAT OF OMAR KHAYYAM. Printed from the Fifth and last Edition. With a Commentary by Mrs. STEPHEN BATSON, and a Biography of Omar by E. D. ROSE. *Cr. 8vo. 6s.* See also Miniature Library.

**FitzGerald (H. P.).** A CONCISE HANDBOOK OF CLIMBERS, TWINERS, AND WALL SHRUBS. Illustrated. *Fcap. 8vo. 2s. 6d. net.*

**Fitzpatrick (S. A. O.).** See Ancient Cities.

**Flecker (W. H.).** M.A., D.C.L., Headmaster of the Dean Close School, Cheltenham. THE STUDENT'S PRAYER BOOK. THE TEXT OF MORNING AND EVENING PRAYER AND LITANY. With an Introduction and Notes. *Cr. 8vo. 2s. 6d.*

**Fletcher (J. S.).** A BOOK OF YORKSHIRE. With 26 Illustrations in Colour by WAL PAGET and FRANK SOUTHGATE, R.B.A., and 22 from Photographs. *Demy 8vo. 7s. 6d. net.*

A Colonial Edition is also published.

**Max (A. W.).** M.A., William Dow Professor of Political Economy in McGill University, Montreal. ECONOMIC PRINCIPLES. *Demy 8vo. 7s. 6d. net.*

**Foot (F. W. G.).** D. Litt., M.A., Assistant Master at the City of London School. LONDON: A READER FOR YOUNG CITIZENS. With Plans and Illustrations. *Cr. 8vo. 1s. 6d.*

**Ford (H. G.).** M.A., Assistant Master at Bristol Grammar School. See Junior School Books.

**Forel (A.).** THE SENSES OF INSECTS. Translated by MACLEOD YEARSLEY. With 2 Illustrations. *Demy 8vo. 10s. 6d. net.*

**Fortescue (Mrs. G.).** See Little Books on Art.

**Fraser (J. F.).** ROUND THE WORLD ON A WHEEL. With 200 Illustrations. *Fifth Edition. Cr. 8vo. 6s.*

A Colonial Edition is also published.

**French (W.).** M.A. See Textbooks of Science. **Freudenreich (Ed. von).** DAIRY BACTERIOLOGY. A Short Manual for Students. Translated by J. R. AINSWORTH DAVIS, M.A. *Second Edition. Revised. Cr. 8vo. 2s. 6d.*

**Fulford (H. W.).** M.A. See Churchman's Bible.

**Fuller (W. P.).** M.A. See Simplified French Texts.

**\*Fvvie (John).** TRAGEDY QUEENS OF THE GEORGIAN ERA. With 26 Illustrations. *Second Ed. Demy 8vo. 12s. 6d. net.*

**Gallaher (D.) and Stead (W. J.).** THE COMPLETE RUGBY FOOTBALLER, ON THE NEW ZEALAND SYSTEM. With 35 Illustrations. *Second Ed. Demy 8vo. 10s. 6d. net.*

A Colonial Edition is also published.

**Gallichan (W. M.).** See Little Guides.

**Gambado (Geoffrey, Esq.).** See I.P.L.

**Gaskell (Mrs.).** See Little Library, Standard Library and Sixpenny Novels.

**Gasquet, the Right Rev. Abbot, O.S.B.** See Antiquary's Books.

**George (H. B.).** M.A., Fellow of New College, Oxford. BATTLES OF ENGLISH HISTORY. With numerous Plans. *Fourth Edition. Cr. 8vo. 2s. 6d.*

A HISTORICAL GEOGRAPHY OF THE

BRITISH EMPIRE. *Third Edition. Cr. 8vo. 2s. 6d.*

**Gibbins (H. de B.).** Litt.D., M.A. INDUSTRY IN ENGLAND: HISTORICAL OUTLINES. With 5 Maps. *Fifth Edition. Demy 8vo. 10s. 6d.*

THE INDUSTRIAL HISTORY OF ENGLAND. With Maps and Plans. *Fifteenth Edition, Revised. Cr. 8vo. 7s.*

ENGLISH SOCIAL REFORMERS. *Second Edition. Cr. 8vo. 2s. 6d.*

See also Hadfield (R. A.), and Commercial Series.

**Gibbon (Edward).** MEMOIRS OF MY LIFE AND WRITINGS. Edited by G. BIRKBECK HILL, LL.D. *Cr. 8vo. 6s.*

THE DECLINE AND FALL OF THE ROMAN EMPIRE. Edited, with Notes, Appendices, and Maps, by J. B. BURY, M.A., Litt.D., Regius Professor of Greek at Cambridge. In Seven Volumes. *Demy 8vo. Gilt top. 8s. 6d. each. Also, Crown 8vo. 6s. each.*

See also Standard Library.

**Gibbs (Philip).** THE ROMANCE OF GEORGE VILLIERS: FIRST DUKE OF BUCKINGHAM, AND SOME MEN AND WOMEN OF THE STUART COURT. With 20 Illustrations. *Second Edition. Demy 8vo. 15s. net.*

A Colonial Edition is also published.

**Gibson (E. C. S.).** D.D., Lord Bishop of Gloucester. See Westminster Commentaries, Handbooks of Theology, and Oxford Biographies.

**Gilbert (A. R.).** See Little Books on Art. **Gilong (M. R.) and Wyatt (Kate M.).** A BOOK OF ENGLISH GARDENS. With 24 Illustrations in Colour. *Demy 8vo. 10s. 6d. net.*

**Godfrey (Elizabeth).** A BOOK OF REMEMBRANCE. Being Lyrical Selections for every day in the Year. Arranged by. *Fcap. 8vo. 2s. 6d. net.*

ENGLISH CHILDREN IN THE OLDEN TIME. With 32 Illustrations. *Second Edition. Demy 8vo. 7s. 6d. net.*

**Godley (A. D.).** M.A., Fellow of Magdalen College, Oxford. LYRA FRIVOLA. *Fourth Edition. Fcap. 8vo. 2s. 6d.*

VERSES TO ORDER. *Second Edition. Fcap. 8vo. 2s. 6d.*

SECOND STRINGS. *Fcap. 8vo. 2s. 6d.*

**Goldsmith (Oliver).** THE VICAR OF WAKEFIELD. With 10 Plates in Photogravure by Tony Johannot. *Leather, Fcap. 32mo. 2s. 6d. net.*

See also I.P.L. and Standard Library.

**Gomme (G. L.).** See Antiquary's Books.

**Goodrich-Freer (A.).** IN A SYRIAN SADDLE. *Demy 8vo. 7s. 6d. net.*

A Colonial Edition is also published.

**Goert (Rt. Hon. Sir John).** THE CHILDREN OF THE NATION. *Second Edition. Demy 8vo. 7s. 6d. net.*

**Goudge (H. L.).** M.A., Principal of Wells Theological College. See Westminster Commentaries.



- Graham (P. Anderson).** THE RURAL EXODUS. The Problem of the Village and the Town. Cr. 8vo. 2s. 6d.
- Granger (F. S.), M.A., Litt.D.** PSYCHOLOGY. Third Edition. Cr. 8vo. 2s. 6d.
- THE SOUL OF A CHRISTIAN.** Cr. 8vo. 6s.
- Gray (E. M'Queen).** GERMAN PASSAGES FOR UNSEEN TRANSLATION. Cr. 8vo. 2s. 6d.
- Gray (P. L.), B.Sc.** THE PRINCIPLES OF MAGNETISM AND ELECTRICITY. With 78 Diagrams. Cr. 8vo. 3s. 6d.
- Green (G. Buckland), M.A.,** late Fellow of St. John's College, Oxon. NOTES ON GREEK AND LATIN SYNTAX. Second Ed. revised. Crown 8vo. 3s. 6d.
- Greenidge (A. H. J.), M.A., D.Litt.** A HISTORY OF ROME: From the Tribunate of Tiberius Gracchus to the end of the Jugurthine War, B.C. 133-104. Demy 8vo. 10s. 6d. net.
- Greenwell (Dora).** See Miniature Library.
- Gregory (R. A.).** THE VAULT OF HEAVEN. A Popular Introduction to Astronomy. Illustrated. Cr. 8vo. 2s. 6d.
- Gregory (Miss E. C.).** See Library of Devotion.
- Grubb (H. C.).** See Textbooks of Technology.
- Hadfield (R. A.) and Gibbins (H. de B.).** A SHORTER WORKING DAY. Cr. 8vo. 2s. 6d.
- Hall (Mary).** A WOMAN'S TREK FROM THE CAPE TO CAIRO. With 64 Illustrations and 2 Maps. Second Edition. Demy 8vo. 16s. net.
- Hall (R. N.) and Neal (W. G.).** THE ANCIENT RUINS OF RHODESIA. Illustrated. Second Edition, revised. Demy 8vo. 10s. 6d. net.
- A Colonial Edition is also published.
- Hall (R. N.).** GREAT ZIMBABWE. With numerous Plans and Illustrations. Second Edition. Demy 8vo. 10s. 6d. net.
- Hamel (Frank).** FAMOUS FRENCH SALONS. With 20 Illustrations. Demy 8vo. 12s. 6d. net.
- A Colonial Edition is also published.
- Hamilton (F. J.), D.D.** See Byzantine Texts.
- Hannay (D.).** A SHORT HISTORY OF THE ROYAL NAVY, 1200-1688. Illustrated. Demy 8vo. 7s. 6d.
- Hannay (James O.), M.A.** THE SPIRIT AND ORIGIN OF CHRISTIAN MONASTICISM. Cr. 8vo. 6s.
- THE WISDOM OF THE DESERT.** Fcap. 8vo. 3s. 6d. net.
- Hardie (Martin).** See Connoisseur's Library.
- Hare (A. T.), M.A.** THE CONSTRUCTION OF LARGE INDUCTION COILS. With numerous Diagrams. Demy 8vo. 6s.
- Harvey (Alfred), M.B.** See Ancient Cities and Antiquary's Books.
- Hawthorne (Nathaniel).** See Little Library.
- Heath (Frank R.).** See Little Guides.
- Heath (Dudley).** See Connoisseur's Library.
- Hello (Ernest).** STUDIES IN SAINTSHIP. Fcap. 8vo. 3s. 6d.
- Henderson (B. W.),** Fellow of Exeter College, Oxford. THE LIFE AND PRINCIPATE OF THE EMPEROR NERO. Illustrated. New and cheaper issue. Demy 8vo. 7s. 6d. net.
- AT INTERVALS.** Fcap. 8vo. 2s. 6d. net.
- Henderson (M. Sturge).** GEORGE MEREDITH: NOVELIST, POET, REFORMER. With a Portrait in Photogravure. Second Edition. Crown 8vo. 6s.
- Henderson (T. F.).** See Little Library and Oxford Biographies.
- Henderson (T. F.), and Watt (Francis).** SCOTLAND OF TO-DAY. With 20 Illustrations in colour and 24 other Illustrations. Second Edition. Cr. 8vo. 6s.
- A Colonial Edition is also published.
- Henley (W. E.).** ENGLISH LYRICS. CHAUCER TO POE, 1340-1849. Second Edition. Cr. 8vo. 2s. 6d. net.
- Henley (W. E.) and Whibley (C.).** A BOOK OF ENGLISH PROSE, CHARACTER, AND INCIDENT, 1387-1649. Cr. 8vo. 2s. 6d. net.
- Henson (H. H.), B.D.,** Canon of Westminster. LIGHT AND LEAVEN: HISTORICAL AND SOCIAL SERMONS. Cr. 8vo. 6s.
- Herbert (George).** See Library of Devotion.
- Herbert of Cherbury (Lord).** See Miniature Library.
- Hewins (W. A. S.), B.A.** ENGLISH TRADE AND FINANCE IN THE SEVENTEENTH CENTURY. Cr. 8vo. 2s. 6d.
- Hewitt (Ethel M.).** A GOLDEN DIAL. A Day Book of Prose and Verse. Fcap. 8vo. 2s. 6d. net.
- Hey (H.),** Inspector, Surrey Education Committee, and **Rose (G. H.),** City and Guilds Woodwork Teacher. THE MANUAL TRAINING CLASSROOM: Woodwork. Book I. 4to. 1s.
- Heywood (W.).** PALIO AND PONTE. A Book of Tuscan Games. Illustrated. Royal 8vo. 21s. net.
- See also St. Francis of Assisi.
- Hill (Clare).** See Textbooks of Technology.
- Hill (Henry), B.A.,** Headmaster of the Boy's High School, Worcester, Cape Colony. A SOUTH AFRICAN ARITHMETIC. Cr. 8vo. 3s. 6d.
- Hind (C. Lewis).** DAYS IN CORNWALL. With 16 Illustrations in Colour by WILLIAM PASCOE, and 20 other Illustrations and a Map. Second Edition. Cr. 8vo. 6s.
- Hirst (F. W.).** See Books on Business.
- Hoare (J. Douglas).** A HISTORY OF ARCTIC EXPLORATION. With 20 Illustrations & Maps. Demy 8vo. 7s. 6d. net.
- Hobhouse (L. T.),** late Fellow of C.C.C., Oxford. THE THEORY OF KNOWLEDGE. Demy 8vo. 10s. 6d. net.
- Hobson (J. A.), M.A.** INTERNATIONAL TRADE: A Study of Economic Principles. Cr. 8vo. 2s. 6d. net.
- PROBLEMS OF POVERTY.** An Inquiry into the Industrial Condition of the Poor. Sixth Edition. Cr. 8vo. 2s. 6d.

**THE PROBLEM OF THE UNEMPLOYED.** *Third Edition.* Cr. 8vo. 2s. 6d.

**Hodgetts (E. A. Brayley).** **THE COURT OF RUSSIA IN THE NINETEENTH CENTURY.** With 20 Illustrations. *Two Volumes.* Demy 8vo. 24s. net.

A Colonial Edition is also published.

**Hodgkin (T.), D.C.L.** See **Leaders of Religion.**

**Hodgson (Mrs. W.)** **HOW TO IDENTIFY OLD CHINESE PORCELAIN.** With 40 Illustrations. *Second Edition.* Post 8vo. 6s.

**Hogg (Thomas Jefferson).** **SHELLEY AT OXFORD.** With an Introduction by R. A. STREATFIELD. Fcap. 8vo. 2s. net.

**Holden-Stone (G. de).** See **Books on Business.**

**Hodrich (Sir T. H.), K.C.I.E.** **THE INDIAN BORDERLAND:** being a Personal Record of Twenty Years. Illustrated. Demy 8vo. 10s. 6d. net.

A Colonial Edition is also published.

**Holdsworth (W. S.), M.A.** **A HISTORY OF ENGLISH LAW.** In *Two Volumes.* Vol. 1. Demy 8vo. 10s. 6d. net.

**Holland (H. Scott),** Canon of St. Paul's. See **Newman (J. H.).**

**Hollway-Calthrop (H. C.),** late of Balliol College, Oxford; Rector of Eton College. **PETRARCH: HIS LIFE, WORK, AND TIMES.** With 24 Illustrations. Demy 8vo. 12s. 6d. net.

A Colonial Edition is also published.

**Holt (Emily).** **THE SECRET OF POPULARITY:** How to Achieve Social Success. Cr. 8vo. 3s. 6d. net.

A Colonial Edition is also published.

**Holyoake (G. J.).** **THE CO-OPERATIVE MOVEMENT OF TO-DAY.** *Fourth Ed.* Cr. 8vo. 2s. 6d.

**Hone (Nathaniel J.).** See **Antiquary's Books.**

**Hook (A.).** **HUMANITY AND ITS PROBLEMS.** Cr. 8vo. 5s. net.

**Hoppner.** See **Little Galleries.**

**Horace.** See **Classical Translations.**

**Horsburgh (E. L. S.), M.A.** **WATERLOO:** With Plans. *Second Edition.* Cr. 8vo. 5s.

See also **Oxford Biographies.**

**Horth (A. C.).** See **Textbooks of Technology.**

**Horton (R. F.), D.D.** See **Leaders of Religion.**

**Hosie (Alexander).** **MANCHURIA.** With Illustrations and a Map. *Second Edition.* Demy 8vo. 7s. 6d. net.

A Colonial Edition is also published.

**How (F. D.).** **SIX GREAT SCHOOL-MASTERS.** With Portraits and Illustrations. *Second Edition.* Demy 8vo. 7s. 6d.

**Howell (A. G. Ferrers).** **FRANCISCAN DAYS.** Being Selections for every day in the year from ancient Franciscan writings. Cr. 8vo. 3s. 6d. net.

**Howell (G.).** **TRADE UNIONISM—NEW AND OLD.** *Fourth Edition.* Cr. 8vo. 2s. 6d.

**Huggins (Sir William), K.C.B., O.M., D.C.L., F.R.S.** **THE ROYAL SOCIETY.** With 25 Illustrations. *Wide Royal* 8vo. 4s. 6d. net.

**Hughes (C. E.).** **THE PRAISE OF SHAKESPEARE.** An English Anthology. With a Preface by **SIDNEY LEE.** Demy 8vo. 3s. 6d. net.

**Hughes (Thomas).** **TOM BROWN'S SCHOOLDAYS.** With an Introduction and Notes by **VERNON KENDALL.** *Leather.* Royal 32mo. 2s. 6d. net.

**Hutchinson (Horace G.).** **THE NEW FOREST.** Illustrated in colour with 50 Pictures by **WALTER TYNDALE** and 4 by **LUCY KEMP-WELCH.** *Third Edition.* Cr. 8vo. 6s.

**Hutton (A. W.), M.A.** See **Leaders of Religion and Library of Devotion.**

**Hutton (Edward).** **THE CITIES OF UMBRIA.** With 20 Illustrations in Colour by **A. PISA,** and 12 other Illustrations. *Third Edition.* Cr. 8vo. 6s.

A Colonial Edition is also published.

**THE CITIES OF SPAIN.** With 24 Illustrations in Colour, by **A. W. RIMINGTON,** 20 other Illustrations and a Map. *Second Edition.* Cr. 8vo. 6s.

A Colonial Edition is also published.

**FLORENCE AND THE CITIES OF NORTHERN TUSCANY, WITH GENOA.** With 16 Illustrations in Colour by **WILLIAM PARKINSON,** and 16 other Illustrations. *Second Edition.* Cr. 8vo. 6s.

A Colonial Edition is also published.

**ENGLISH LOVE POEMS.** Edited with an Introduction. Fcap. 8vo. 3s. 6d. net.

**Hutton (R. H.).** See **Leaders of Religion.**

**Hutton (W. H.), M.A.** **THE LIFE OF SIR THOMAS MORE.** With Portraits after Drawings by **HOLBEIN.** *Second Ed.* Cr. 8vo. 5s.

See also **Leaders of Religion.**

**Hyde (A. G.)** **GEORGE HERBERT AND HIS TIMES.** With 32 Illustrations. Demy 8vo. 10s. 6d. net.

**Hyett (F. A.).** **FLORENCE: HER HISTORY AND ART TO THE FALL OF THE REPUBLIC.** Demy 8vo. 7s. 6d. net.

**Ibsen (Henrik).** **BRAND.** A Drama. Translated by **WILLIAM WILSON.** *Third Edition.* Cr. 8vo. 3s. 6d.

**Inge (W. R.), M.A.,** Fellow and Tutor of Hertford College, Oxford. **CHRISTIAN MYSTICISM.** (The Bampton Lectures of 1899.) Demy 8vo. 12s. 6d. net.

See also **Library of Devotion.**

**Ingham (B. P.).** See **Simplified French Texts.**

**Innes (A. D.), M.A.** **A HISTORY OF THE BRITISH IN INDIA.** With Map and Plans. Cr. 8vo. 6s.

**ENGLAND UNDER THE TUDORS.** With Maps. *Second Edition.* Demy 8vo. 10s. 6d. net.

**Jackson (C. E.), B.A.,** Senior Physics Master, Bradford Grammar School. See **Textbooks of Science.**

**Jackson (S.), M.A.** See **Commercial Series.**

**Jackson (F. Hamilton).** See **Little Guides.**

**Jacob (F.), M.A.** See **Junior Examination Series.**

**James (W. H. N.).** See Brooks (E. E.).

**Jeans (J. Stephen).** TRUSTS, POOLS, AND CORNERS AS AFFECTING COMMERCE AND INDUSTRY. Cr. 8vo. 2s. 6d.

See also Books on Business.

**Jebb (Camilla).** A STAR OF THE SALONS: JULIE DE LESPINASSE. With 20 Illustrations. Demy 8vo. 10s. 6d. net.

A Colonial Edition is also published.

**Jeffery (Reginald W.), M.A.** THE THIRTEEN COLONIES OF NORTH AMERICA. With 8 Illustrations and a Map. Demy 8vo. 7s. 6d. net.

A Colonial Edition is also published.

**Jeffreys (D. Gwyn).** DOLLY'S THEATRICALS. Super Royal 16mo. 2s. 6d.

**Jenks (E.), M.A., B.C.L.** AN OUTLINE OF ENGLISH LOCAL GOVERNMENT. Second Ed. Revised by R. C. K. ENSOR, M.A. Cr. 8vo. 2s. 6d.

**Jenner (Mrs. H.).** See Little Books on Art.

**Jennings (Oscar), M.D.** EARLY WOODCUT INITIALS. Demy 4to. 21s. net.

**Jessopp (Augustus), D.D.** See Leaders of Religion.

**Jevons (F. B.), M.A., Litt.D.,** Principal of Hatfield Hall, Durham. RELIGION IN EVOLUTION. Cr. 8vo. 3s. 6d. net.

See also Churchman's Library and Handbooks of Theology.

**Johnson (Mrs. Barham).** WILLIAM RODHAM DONNE AND HIS FRIENDS. Illustrated. Demy 8vo. 10s. 6d. net.

**Johnston (Sir H. H.), K.C.B.** BRITISH CENTRAL AFRICA. With nearly 200 Illustrations and Six Maps. Third Edition. Cr. 4to. 18s. net.

A Colonial Edition is also published.

**Jones (H.).** See Commercial Series.

**Jones (H. F.).** See Textbooks of Science.

**Jones (L. A. Atherley), K.C., M.P., and Bellot (Hugh H. L.), M.A., D.C.L.** THE MINER'S GUIDE TO THE COAL MINES REGULATION ACTS AND THE LAW OF EMPLOYERS AND WORKMEN. Cr. 8vo. 7s. 6d. net.

**COMMERCE IN WAR.** Royal 8vo. 21s. net.

**Jones (R. Compton), M.A.** POEMS OF THE INNER LIFE. Selected by. Thirtieth Edition. Fcap. 8vo. 2s. 6d. net.

**Jenson (Ben).** See Standard Library.

**Juliana (Lady) of Norwich.** REVELATIONS OF DIVINE LOVE. Ed. by GRACE WARRACK. Second Ed. Cr. 8vo. 3s. 6d.

**Juvenal.** See Classical Translations.

**'Kappa.'** LET YOUTH BUT KNOW: A Plea for Reason in Education. Cr. 8vo. 3s. 6d. net.

**Kaufmann (M.), M.A.** SOCIALISM AND MODERN THOUGHT. Second Edition Revised and Enlarged. Cr. 8vo. 2s. 6d. net.

**Keating (J. F.), D.D.** THE AGAPÉ AND THE EUCHARIST. Cr. 8vo. 3s. 6d.

**Kears (John).** THE POEMS. Edited with Introduction and Notes by E. de SELINCOURT, M.A. With a Frontispiece in

Photogravure. Second Edition Revised. Demy 8vo. 7s. 6d. net.

**REALMS OF GOLD.** Selections from the Works of. Fcap. 8vo. 3s. 6d. net.

See also Little Library and Standard Library.

**Keble (John).** THE CHRISTIAN YEAR. With an Introduction and Notes by W. LOCK, D.D., Warden of Keble College. Illustrated by R. ANNING BELL. Third Edition. Fcap. 8vo. 3s. 6d.; padded morocco, 5s.

See also Library of Devotion.

**Kelynaek (T. N.), M.D., M.R.C.P.** THE DRINK PROBLEM IN ITS MEDICO-SOCIOLOGICAL ASPECT. By fourteen Medical Authorities. Edited by. With 2 Diagrams. Demy 8vo. 7s. 6d. net.

**Kempis (Thomas à).** THE IMITATION OF CHRIST. With an Introduction by DEAN FARRAR. Illustrated by C. M. GERR. Third Edition. Fcap. 8vo. 3s. 6d.; padded morocco, 5s.

Also Translated by C. BIGG, D.D. Cr. 8vo. 3s. 6d.

See also Montmorency (J. E. G. de), Library of Devotion, and Standard Library.

**Kennedy (Bart.).** THE GREEN SPHINX. Cr. 8vo. 3s. 6d. net.

**Kennedy (James Houghton), D.D.,** Assistant Lecturer in Divinity in the University of Dublin. ST. PAUL'S SECOND AND THIRD EPISTLES TO THE CORINTHIANS. With Introduction, Dissertations and Notes. Cr. 8vo. 6s.

**Kimmins (C. W.), M.A.** THE CHEMISTRY OF LIFE AND HEALTH. Illustrated. Cr. 8vo. 2s. 6d.

**Kingslake (A. W.).** See Little Library.

**Kipling (Rudyard).** BARRACK-ROOM BALLADS. 83rd Thousand. Twenty-fourth Edition. Cr. 8vo. 6s. Also Leather. Fcap. 8vo. 5s.

A Colonial Edition is also published.

**THE SEVEN SEAS.** 70th Thousand. Thirteenth Edition. Cr. 8vo. 6s. Also Leather. Fcap. 8vo. 5s.

A Colonial Edition is also published.

**THE FIVE NATIONS.** 62nd Thousand. Fourth Edition. Cr. 8vo. 6s. Also Leather. Fcap. 8vo. 5s.

A Colonial Edition is also published.

**DEPARTMENTAL DITTIES.** Sixteenth Edition. Cr. 8vo. 6s. Also Leather. Fcap. 8vo. 5s.

A Colonial Edition is also published.

**Knight (Albert E.).** THE COMPLETE CRICKETER. With 50 Illustrations. Demy 8vo. 7s. 6d. net.

A Colonial Edition is also published.

**Knight (H. J. C.), B.D.** See Churchman's Bible.

**Knowling (R. J.), M.A.,** Professor of New Testament Exegesis at King's College, London. See Westminster Commentaries.

**Lamb (Charles and Mary), THE WORKS.** Edited by E. V. LUCAS. Illustrated. In Seven Volumes. Demy 8vo. 7s. 6d. each.

See also Little Library and Lucas (E. V.).

**Lambert (F. A. H.).** See Little Guides.  
**Lambros (Professor S. P.).** See Byzantine Texts.

**Lane-Poole (Stanley).** **A HISTORY OF EGYPT IN THE MIDDLE AGES.** Fully Illustrated. *Cr. 8vo. 6s.*

**Langbridge (F.).** **M.A. BALLADS OF THE BRAVE:** Poems of Chivalry, Enterprise, Courage, and Constancy. *Third Edition. Cr. 8vo. 2s. 6d.*

**Law (William).** See Library of Devotion and Standard Library.

**Leach (Henry).** **THE DUKE OF DEVONSHIRE.** A Biography. With 12 Illustrations. *Demy 8vo. 12s. 6d. net.*

**THE SPIRIT OF THE LINKS.** *Cr. 8vo. 6s.*  
 A Colonial Edition is also published.  
 See also Braid (James).

**Is. Braz (Anastole).** **THE LAND OF JARDONS.** Translated by FRANCES M. GOSWING. With 12 Illustrations in Colour by T. C. GOTCH, and 40 other Illustrations. *Second Edition. Crown 8vo. 6s.*

**Lee (Captain L. Melville).** **A HISTORY OF POLICE IN ENGLAND.** *Cr. 8vo. 3s. 6d. net.*

**Lewis (V. B.).** **M.A. AIR AND WATER.** Illustrated. *Cr. 8vo. 2s. 6d.*

**Lewis (B. M. Gwyn).** **A CONCISE HANDBOOK OF GARDEN SHRUBS.** With 20 Illustrations. *Fcap. 8vo. 3s. 6d. net.*

**Lisle (Fortunéde).** See Little Books on Art.

**Littlehales (H.).** See Antiquary's Books.

**Lock (Walter), D.D.,** Warden of Keble College. **ST. PAUL, THE MASTER-BUILDER.** *Second Ed. Cr. 8vo. 7s. 6d.*  
**THE BIBLE AND CHRISTIAN LIFE.** *Cr. 8vo. 6s.*

See also Keble (J.) and Leaders of Religion.

**Locker (F.).** See Little Library.

**Lodge (Sir Oliver), F.R.S.** **THE SUBSTANCE OF FAITH ALLIED WITH SCIENCE:** A Catechism for Parents and Teachers. *Ninth Ed. Cr. 8vo. 2s. net.*

**Lofthouse (W. F.).** **M.A. ETHICS AND ATONEMENT.** With a Frontispiece. *Demy 8vo. 5s. net.*

**Longfellow (H. W.).** See Little Library.  
**Lorimer (George Horace).** **LETTERS FROM A SELF-MADE MERCHANT TO HIS SON.** *Sixteenth Edition. Cr. 8vo. 3s. 6d.*

A Colonial Edition is also published.  
**OLD GORGON GRAHAM.** *Second Edition. Cr. 8vo. 6s.*

A Colonial Edition is also published.  
**Lover (Samuel).** See I.P.L.

**E. V. L. and C. L. G.** **ENGLAND DAY BY DAY:** Or, The Englishman's Handbook to Efficiency. Illustrated by GEORGE MORROW. *Fourth Edition. Fcap. 4to. 1s. net.*

**Lucas (E. V.).** **THE LIFE OF CHARLES LAMB.** With 28 Illustrations. *Fourth and Revised Edition in One Volume. Demy 8vo. 7s. 6d. net.*

A Colonial Edition is also published.

**A WANDERER IN HOLLAND.** With 20 Illustrations in Colour by HERBERT MARSHALL, 34 Illustrations after old Dutch Masters, and a Map. *Eighth Edition. Cr. 8vo. 6s.*

A Colonial Edition is also published.  
**A WANDERER IN LONDON.** With 16 Illustrations in Colour by NELSON DAWSON, 36 other Illustrations and a Map. *Sixth Edition. Cr. 8vo. 6s.*

A Colonial Edition is also published.  
**THE OPEN ROAD:** a Little Book for Wayfarers. *Fourteenth Edition. Fcap. 8vo. 5s.; India Paper, 7s. 6d.*

**THE FRIENDLY TOWN:** a Little Book for the Urbane. *Fourth Edition. Fcap. 8vo. 5s.; India Paper, 7s. 6d.*

**FIRESIDE AND SUNSHINE.** *Third Edition. Fcap. 8vo. 5s.*

**CHARACTER AND COMEDY.** *Third Edition. Fcap. 8vo. 5s.*

**THE GENTLEST ART.** A Choice of Letters by Entertaining Hands. *Fourth Edition. Fcap. 8vo. 5s.*

**A SWAN AND HER FRIENDS.** With 24 Illustrations. *Demy 8vo. 12s. 6d. net.*

A Colonial Edition is also published.

**Lucian.** See Classical Translations.

**Lyde (L. W.), M.A.** See Commercial Series.

**Lydon (Noel S.).** See Junior School Books.

**Lyttelton (Hon. Mrs. A.).** **WOMEN AND THEIR WORK.** *Cr. 8vo. 2s. 6d.*

**Macaulay (Lord).** **CRITICAL AND HISTORICAL ESSAYS.** Edited by F. C. MONTAGUE, M.A. *Three Volumes. Cr. 8vo. 18s.*

**M'Allen (J. E. B.), M.A.** See Commercial Series.

**MacCulloch (J. A.).** See Churchman's Library.

**MacCunn (Florence A.).** **MARY STUART.** With 44 Illustrations, including a Frontispiece in Photogravure. *New and Cheaper Edition. Large Cr. 8vo. 6s.*

See also Leaders of Religion.

**McDermott (E. R.).** See Books on Business.

**M'Dowall (A. S.).** See Oxford Biographies.

**Mackay (A. M.).** B.A. See Churchman's Library.

**Mackenzie (W. Leslie), M.A., M.D., D.P.H., etc.** **THE HEALTH OF THE SCHOOL CHILD.** *Cr. 8vo. 2s. 6d.*

**Macklin (Herbert W.).** M.A. See Antiquary's Books.

**M'Neile (A. H.), B.D.** See Westminster Commentaries.

**'Mille Mori' (Author of).** **ST. CATHERINE OF SIENA AND HER TIMES.** With 28 Illustrations. *Demy 8vo. 7s. 6d. net.*

**Magnus (Laurie), M.A.** **A PRIMER OF WORDSWORTH.** *Cr. 8vo. 2s. 6d.*

**Mahaffy (J. P.), Litt.D.** **A HISTORY OF THE EGYPT OF THE PTOLEMIES.** Fully Illustrated. *Cr. 8vo. 6s.*

**Maitland (F. W.), M.A., LL.D.** **ROMAN CANON LAW IN THE CHURCH OF ENGLAND.** *Royal 8vo. 7s. 6d.*

**Major (H.), B.A., B.Sc. A HEALTH AND TEMPERANCE READER.** *Cr. 8vo. 1s. 6d.*

**Malden (H. E.), M.A. ENGLISH RECORDS.** A Companion to the History of England. *Cr. 8vo. 3s. 6d.*

**THE RIGHTS AND DUTIES OF A CITIZEN.** *Seventh Edition. Cr. 8vo. 1s. 6d.*

See also School Histories.

**Marchant (E. C.), M.A., Fellow of Peterhouse, Cambridge. A GREEK ANTHOLOGY.** *Second Edition. Cr. 8vo. 3s. 6d.*

See also Cook (A. M.)

**Marks (Jeannette), M.A. ENGLISH PASTORAL DRAMA** from the Restoration to the date of the publication of the 'Lyrical Ballads' (1660-1798). *Cr. 8vo. 5s. net.*

**Marr (J. E.), F.R.S., Fellow of St John's College, Cambridge. THE SCIENTIFIC STUDY OF SCENERY.** *Second Edition. Illustrated. Cr. 8vo. 6s.*

**AGRICULTURAL GEOLOGY.** Illustrated. *Cr. 8vo. 6s.*

**Marriott (J. A. R.), M.A. THE LIFE AND TIMES OF LORD FALKLAND.** With 23 Illustrations. *Second Edition. Demy 8vo. 7s. 6d. net.*

**Marvell (Andrew).** See Little Library.

**Masefield (John). SEA LIFE IN NELSON'S TIME.** Illustrated. *Cr. 8vo. 3s. 6d. net.*

A Colonial Edition is also published.  
**ON THE SPANISH MAIN: or, SOME ENGLISH FORAYS IN THE Isthmus OF DARIEN.** With 22 Illustrations and a Map. *Demy 8vo. 10s. 6d. net.*

A Colonial Edition is also published.  
**A SAILOR'S GARLAND.** Selected and Edited by. *Second Ed. Cr. 8vo. 3s. 6d. net.*  
**AN ENGLISH PROSE MISCELLANY.** Selected and Edited by. *Cr. 8vo. 6s.*

**Maskell (A.).** See Connoisseur's Library.

**Mason (A. J.), D.D.** See Leaders of Religion.

**Masterman (C. F. G.), M.A., M.P. TENNYSON AS A RELIGIOUS TEACHER.** *Cr. 8vo. 6s.*

**Matheson (E. F.). COUNSELS OF LIFE.** *Fcap. 8vo. 9s. 6d. net.*

**May (Phil). THE PHIL MAY ALBUM.** *Second Edition. 4to. 1s. net.*

**Meakin (Annette M. B.), Fellow of the Anthropological Institute. WOMAN IN TRANSITION.** *Cr. 8vo. 6s.*

**Mellows (Emma S.). A SHORT STORY OF ENGLISH LITERATURE.** *Cr. 8vo. 3s. 6d.*

**Methuen (A. M. S.), M.A. THE TRAGEDY OF SOUTH AFRICA.** *Cr. 8vo. 2s. net. Also Cr. 8vo. 3d. net.*  
**ENGLAND'S RUIN: DISCUSSED IN SIXTEEN LETTERS TO THE RIGHT HON. JOSEPH CHAMBERLAIN, M.P.** *Seventh Edition. Cr. 8vo. 3d. net.*

**Miles (Bustace), M.A. LIFE AFTER LIFE: OR, THE THEORY OF REINCARNATION.** *Cr. 8vo. 2s. 6d. net.*

**THE POWER OF CONCENTRATION: HOW TO ACQUIRE IT.** *Second Edition. Cr. 8vo. 3s. 6d. net.*

**Millais (J. G.). THE LIFE AND LETTERS OF SIR JOHN EVERETT MILLAIS,** President of the Royal Academy. With many Illustrations, of which 2 are in Photogravure. *New Edition. Demy 8vo. 7s. 6d. net.*

See also Little Galleries.

**Millin (G. F.). PICTORIAL GARDENING.** With 21 Illustrations. *Crown 8vo. 3s. 6d. net.*

**Millis (C. T.), M.I.M.E.** See Textbooks of Technology.

**Milne (J. G.), M.A. A HISTORY OF EGYPT UNDER ROMAN RULE.** Fully Illustrated. *Cr. 8vo. 6s.*

**Milton (John).** See Little Library and Standard Library.

**A DAY BOOK OF MILTON.** Edited by R. F. TOWNSEND. *Fcap. 8vo. 2s. 6d. net.*

**Minchin (H. C.), M.A.** See Peel (R.).  
**Mitchell (P. Chalmers), M.A. OUTLINES OF BIOLOGY.** Illustrated. *Second Edition. Cr. 8vo. 6s.*

**Mitton (G. E.). JANE AUSTEN AND HER TIMES.** With 21 Illustrations. *Second and Cheaper Edition. Large Cr. 8vo. 6s.*

A Colonial Edition is also published.

**Moffat (Mary M.). QUEEN LOUISA OF PRUSSIA.** With 20 Illustrations. *Fourth Edition. Crown 8vo. 6s.*

A Colonial Edition is also published.

**'MOM' (A.).** See Books on Business.

**Moir (D. M.).** See Little Library.

**Mollinos (Dr. Michael de).** See Library of Devotion.

**Money (L. G. Chiozza), M.P. RICHES AND POVERTY.** *Eighth Edition. Demy 8vo. 5s. net. Also Cr. 8vo. 1s. net.*

**SOCIAL AND INDUSTRIAL PROBLEMS.** *Demy 8vo. 5s. net.*

**Montagu (Henry), Earl of Manchester.** See Library of Devotion.

**Montaigne. A DAY BOOK OF.** Edited by C. F. POND. *Fcap. 8vo. 2s. 6d. net.*

**Montgomery (H. B.). THE EMPIRE OF THE EAST.** With a Frontispiece in Colour and 16 other Illustrations. *Second Edition. Demy 8vo. 7s. 6d. net.*

A Colonial Edition is also published.

**Montmorency (J. E. G. de), B.A., LL.B. THOMAS A KEMPIS, HIS AGE AND BOOK.** With 22 Illustrations. *Second Edition. Demy 8vo. 7s. 6d. net.*

**Moore (H. E.). BACK TO THE LAND.** *Cr. 8vo. 2s. 6d.*

**Moorhouse (E. Hallam). NELSON'S LADY HAMILTON.** With 51 Portraits. *Second Edition. Demy 8vo. 7s. 6d. net.*

A Colonial Edition is also published.

**Moran (Clarence G.).** See Books on Business.

**More (Sir Thomas).** See Standard Library.

- Morfill (W. R.)**, Oriel College, Oxford. A HISTORY OF RUSSIA FROM PETER THE GREAT TO ALEXANDER II. With Maps and Plans. *Cr. 8vo.* 3s. 6d.
- Morich (R. J.)**, late of Clifton College. See School Examination Series.
- Morley (Margaret W.)**, Founded on. THE BEE PEOPLE. With 74 Illustrations. *Sg. Crown 8vo.* 2s. 6d.
- LITTLE MITCHELL: THE STORY OF A MOUNTAIN SQUIRREL TOLD BY HIMSELF.** With many Illustrations. *Sg. Cr. 8vo.* 2s. 6d.
- Morris (J.)**, THE MAKERS OF JAPAN. With 24 Illustrations. *Demy 8vo.* 12s. 6d. net.
- Morris (Joseph E.)**. See Little Guides.
- Morton (A. Anderson)**. See Brodrick (M.).
- Moule (H. C. G.)**, D.D., Lord Bishop of Durham. See Leaders of Religion.
- Muir (M. M. Pattison)**, M.A. THE CHEMISTRY OF FIRE. Illustrated. *Cr. 8vo.* 2s. 6d.
- Mundella (V. A.)**, M.A. See Dunn (J. T.).
- Munro (R.)**, M.A., LL.D. See Antiquary's Books.
- Myers (A. Wallis)**, THE COMPLETE LAWN TENNIS PLAYER. With many Illustrations. *Second Edition. Demy 8vo.* 10s. 6d. net.
- Naval Officer (A.)**. See I. P. L.
- Neal (W. G.)**. See Hall (R. N.).
- Newman (Ernest)**. HUGO WOLF. With 13 Illustrations. *Demy 8vo.* 7s. 6d. net.
- Newman (George)**, M.D., D.P.H., F.R.S.E., INFANT MORTALITY, A SOCIAL PROBLEM. With 16 Diagrams. *Demy 8vo.* 7s. 6d. net.
- Newman (J. H.) and others.** See Library of Devotion.
- Newsholme (Arthur)**, M.D., F.R.C.P. THE PREVENTION OF TUBERCULOSIS. *Demy 8vo.* 10s. 6d. net.
- Nichols (Bowyer)**. See Little Library.
- Nicklin (T.)**, M.A. EXAMINATION PAPERS IN THUCYDIDES. *Cr. 8vo.* 7s.
- Nimrod**. See I. P. L.
- Norgate (D. Le Grys)**. THE LIFE OF SIR WALTER SCOTT. With 53 Illustrations by JENNY WYLIE. *Demy 8vo.* 7s. 6d. net.
- Norregaard (B. W.)**. THE GREAT SIEGE: The Investment and Fall of Port Arthur. With Maps, Plans, and 25 Illustrations. *Demy 8vo.* 10s. 6d. net.
- A Colonial Edition is also published.
- Norway (A. H.)**. NAPLES. PAST AND PRESENT. With 25 Coloured Illustrations by MAURICE GREIFFENHAGEN. *Second Edition. Cr. 8vo.* 6s.
- A Colonial Edition is also published.
- Novalis**. THE DISCIPLES AT SAIS AND OTHER FRAGMENTS. Edited by Miss UNA BIRCH. *Fcap. 8vo.* 3s. 6d. net.
- Officer (An)**. See I. P. L.
- Oldfield (W. J.)**, M.A., Prebendary of Lincoln. A PRIMER OF RELIGION. BASED ON THE CATECHISM OF THE CHURCH OF ENGLAND. *Crown 8vo.* 2s. 6d.
- Oldham (F. M.)**, B.A. See Textbooks of Science.
- Oliphant (Mrs.)**. See Leaders of Religion.
- Oliver, Thomas, M.D.** DISEASES OF OCCUPATION. With Illustrations. *Second Edition. Demy 8vo.* 10s. 6d. net.
- Oman (C. W. C.)**, M.A., Fellow of All Souls', Oxford. A HISTORY OF THE ART OF WAR IN THE MIDDLE AGES. Illustrated. *Demy 8vo.* 10s. 6d. net.
- Ottley (R. L.)**, D.D. See Handbooks of Theology and Leaders of Religion.
- Overton (J. H.)**. See Leaders of Religion.
- Owen (Douglas)**. See Books on Business.
- Oxford (M. N.)**, of Guy's Hospital. A HANDBOOK OF NURSING. *Fourth Edition. Cr. 8vo.* 3s. 6d.
- Pakes (W. C. C.)**. THE SCIENCE OF HYGIENE. Illustrated. *Demy 8vo.* 12s.
- Parker (Gilbert)**, M.P. A LOVER'S DIARY. *Fcap. 8vo.* 5s.
- A volume of poems.
- Parkes (A. K.)**. SMALL LESSONS ON GREAT TRUTHS. *Fcap. 8vo.* 1s. 6d.
- Parkinson (John)**. PARADISI IN SOLE PARADISUS TERRESTRIS, OR A GARDEN OF ALL SORTS OF PLEASANT FLOWERS. *Folio. 43.* 2s. net.
- Parmenter (John)**. HELIO-TROPES, OR NEW POSIES FOR SUNDIALS. Edited by PERCIVAL LONDON. *Quarto.* 3s. 6d. net.
- Parmentier (Prof. Leon)**. See Bidez (J.).
- Parsons (Mrs. C.)**. GARRICK AND HIS CIRCLE. With 36 Illustrations. *Second Edition. Demy 8vo.* 12s. 6d. net.
- A Colonial Edition is also published.
- Pascal**. See Library of Devotion.
- Paston (George)**. SOCIAL CARICATURE IN THE EIGHTEENTH CENTURY. With over 200 Illustrations. *Imperial Quarto. 43.* 12s. 6d. net.
- LADY MARY WORTLEY MONTAGU AND HER TIMES** With 24 Illustrations. *Second Edition. Demy 8vo.* 15s. net.
- See also Little Books on Art and I. P. L.
- Patterson (W. R.)** (Benjamin Swift). LIFE'S QUESTIONINGS. *Cr. 8vo.* 3s. 6d. net.
- Patterson (A. H.)**. NOTES OF AN EAST COAST NATURALIST. Illustrated in Colour by F. SOUTHGATE, R.B.A. *Second Edition. Cr. 8vo.* 6s.
- NATURE IN EASTERN NORFOLK.** With 12 Illustrations in Colour by FRANK SOUTHGATE, R.B.A. *Second Edition. Cr. 8vo.* 6s.
- WILD LIFE ON A NORFOLK ESTUARY.** With 40 Illustrations by the Author, and a Prefatory Note by Her Grace the DUCHESS OF BEDFORD. *Demy 8vo.* 10s. 6d. net.
- Peacock (Netta)**. See Little Books on Art.
- Patterson (J. B.)**. See Simplified French Texts.
- Peake (C. M. A.)**, F.R.H.S. A CONCISE HANDBOOK OF GARDEN ANNUAL AND BIENNIAL PLANTS. With 24 Illustrations. *Fcap. 8vo.* 3s. 6d. net.

- Peel (Robert), and Minchin (H. C.), M.A.** OXFORD. With 100 Illustrations in Colour. *Cr. 8vo.* 6s.  
A Colonial Edition is also published.
- Peel (Sidney)**, late Fellow of Trinity College, Oxford, and Secretary to the Royal Commission on the Licensing Laws. **PRACTICAL LICENSING REFORM.** *Second Edition. Cr. 8vo.* 1s. 6d.
- Petrie (W. M. Flinders), D.C.L., LL.D.,** Professor of Egyptology at University College. **A HISTORY OF EGYPT.** Fully Illustrated. *In six volumes. Cr. 8vo.* 6s. each.
- VOL. I. FROM THE EARLIEST KINGS TO XVIIth DYNASTY. Sixth Edition.**
- VOL. II. THE XVIIth AND XVIIIth DYNASTIES. Fourth Edition.**
- VOL. III. XIXth TO XXXth DYNASTIES.**
- VOL. IV. THE EGYPT OF THE PTOLEMIES.** J. P. MAHAFFY, Litt.D.
- VOL. V. ROMAN EGYPT.** J. G. MILNE, M.A.
- VOL. VI. EGYPT IN THE MIDDLE AGES.** STANLEY LANK-POOLK, M.A.
- RELIGION AND CONSCIENCE IN ANCIENT EGYPT.** Lectures delivered at University College, London. Illustrated. *Cr. 8vo.* 2s. 6d.
- SYRIA AND EGYPT, FROM THE TELL ELAMARNA TABLETS.** *Cr. 8vo.* 2s. 6d.
- EGYPTIAN TALES.** Translated from the Papyri. First Series, 18th to 19th Dynasty. Edited by W. M. FLINDERS PETRIE. Illustrated by TRISTRAM ELLIS. *Second Edition. Cr. 8vo.* 3s. 6d.
- EGYPTIAN TALES.** Translated from the Papyri. Second Series, 18th to 19th Dynasty. Illustrated by TRISTRAM ELLIS. *Crown 8vo.* 3s. 6d.
- EGYPTIAN DECORATIVE ART.** A Course of Lectures delivered at the Royal Institution. Illustrated. *Cr. 8vo.* 3s. 6d.
- Phillips (W. A.).** See Oxford Biographies.
- Phillipotts (Eden).** MY DEVON YEAR. With 38 Illustrations by J. LEE PETHYBRIDGE. *Second and Cheaper Edition. Large Cr. 8vo.* 6s.
- UP ALONG AND DOWN ALONG.** Illustrated by CLAUDE SHEPPERTON. *Cr. 4to.* 5s. net.
- Phythian (J. Ernest).** TREES IN NATURE, MYTH, AND ART. With 24 Illustrations. *Crown 8vo.* 6s.
- Plarr (Victor G.).** See School Histories.
- Plato.** See Standard Library.
- Plautus.** THE CAPTIVE. Edited, with an Introduction, Textual Notes, and a Commentary, by W. M. LINDSAY, Fellow of Jesus College, Oxford. *Demy 8vo.* 10s. 6d. net.
- Plowden-Wardlaw (J. T.), B.A.,** King's College, Cambridge. See School Examination Series.
- Podmore (Frank).** MODERN SPIRITUALISM. *Two Volumes. Demy 8vo.* 22s. net.
- Pollard (Alice).** See Little Books on Art.
- Pollard (Eliza F.).** See Little Books on Art.
- Pollack (David), M.I.N.A.** See Books on Business.
- Potter (M. C.), M.A., F.L.S.** AN ELEMENTARY TEXT-BOOK OF AGRICULTURAL BOTANY. Illustrated. *Second Edition. Cr. 8vo.* 4s. 6d.
- Power (J. O'Connor).** THE MAKING OF AN ORATOR. *Cr. 8vo.* 6s.
- Prance (G.).** See Wyon (R.).
- Prescott (O. L.).** ABOUT MUSIC, AND WHAT IT IS MADE OF. *Cr. 8vo.* 3s. 6d. net.
- Price (Eleanor C.).** A PRINCESS OF THE OLD WORLD. With 21 Illustrations. *Demy 8vo.* 12s. 6d. net.
- Price (L. L.), M.A.,** Fellow of Oriel College, Oxon. A HISTORY OF ENGLISH POLITICAL ECONOMY FROM ADAM SMITH TO ARNOLD TOYNBEE. *Fifth Edition. Cr. 8vo.* 2s. 6d.
- Primrose (Deborah).** A MODERN BACCHUS. *Cr. 8vo.* 6s.
- Protheroe (Ernest).** THE DOMINATION OF MAN. GEOGRAPHY IN ITS HUMAN ASPECT. With 32 full-page Illustrations. *Second Edition. Cr. 8vo.* 2s.
- Quevedo Villegas.** See Miniature Library.
- 'Q' (A. T. Quiller Couch).** THE GOLDEN POMP. A PROCESSION OF ENGLISH LYRICS FROM SURREY TO SHIRLEY. *Second and Cheaper Edition. Cr. 8vo.* 2s. 6d. net.
- G. R. and E. S. MR. WOODHOUSE'S CORRESPONDENCE.** *Cr. 8vo.* 6s.  
A Colonial Edition is also published.
- Rackham (R. B.), M.A.** See Westminster Commentaries.
- Ragg (Laura M.).** THE WOMEN ARTISTS OF BOLOGNA. With 20 Illustrations. *Demy 8vo.* 7s. 6d. net.
- Ragg (Lonsdale), B.D.,** Oxon. DANTE AND HIS ITALY. With 32 Illustrations. *Demy 8vo.* 12s. 6d. net.
- Rahitz (F. J.), M.A., B.Sc.,** Lecturer in English at Merchant Venturers' Technical College, Bristol. HIGHER ENGLISH. *Third Edition. Cr. 8vo.* 2s. 6d.
- Randolph (B. W.), D.D.** See Library of Devotion.
- Rannie (D. W.), M.A.** A STUDENT'S HISTORY OF SCOTLAND. *Cr. 8vo.* 3s. 6d.
- WORDSWORTH AND HIS CIRCLE.** With 20 Illustrations. *Demy 8vo.* 12s. 6d. net.
- Rashdall (Hastings), M.A.,** Fellow and Tutor of New College, Oxford. DOCTRINE AND DEVELOPMENT. *Cr. 8vo.* 6s.
- Raven (J. J.), D.D., F.S.A.** See Antiquary's Books.
- Raven-Hill (L.).** See Llewellyn (Owen).
- Rawstone (Lawrence, Esq.).** See I.P.L.
- Raymond (Walter).** See School Histories.
- \*Rea (Lilian).** MADAME DE LA FAYETTE. With many Illustrations. *Demy 8vo.* 10s. 6d. net.
- Real Paddy (A.).** See I.P.L.
- Reason (W.), M.A.** UNIVERSITY AND SOCIAL SETTLEMENTS. Edited by. *Cr. 8vo.* 2s. 6d.

**Redpath (H. A.), M.A., D.Litt.** See Westminster Commentaries.

**Rees (J. D.), C.I.E., M.P.** THE REAL INDIA. *Second Edition.* Demy 8vo. 10s. 6d. net.

A Colonial Edition is also published.

**\*Reich (Emil), Doctor Juris.** WOMAN THROUGH THE AGES. With 24 Illustrations. *Two Volumes.* Demy 8vo. 21s. net.

A Colonial Edition is also published.

**Reynolds (Sir Joshua).** See Little Galleries.

**Rhodes (J. F.).** See Simplified French Texts.

**Rhodes (W. E.).** See School Histories.

**Rieu (H.), M.A.** See Simplified French Texts.

**Roberts (M. E.).** See Channer (C. C.).

**Robertson (A.), D.D., Lord Bishop of Exeter.** REGNUM DEI. (The Bampton Lectures of 1901). *A New and Cheaper Edition.* Demy 8vo. 7s. 6d. net.

**Robertson (C. Grant), M.A., Fellow of All Souls' College, Oxford.** SELECT STATUTES, CASES, AND CONSTITUTIONAL DOCUMENTS, 1660-1832. Demy 8vo. 10s. 6d. net.

**Robertson (C. Grant) and Bartholomew (J. G.), F.R.S.E., F.R.G.S.** A HISTORICAL AND MODERN ATLAS OF THE BRITISH EMPIRE. Demy Quarto. 4s. 6d. net.

**Robertson (Sir G.S.), K.C.S.I.** CHITRAL: THE STORY OF A MINOR SIEGE. *Third Edition.* Illustrated. Cr. 8vo. 2s. 6d. net.

**Robinson (A. W.), M.A.** See Churchman's Bible.

**Robinson (Cecilia).** THE MINISTRY OF DEACONESSES. With an Introduction by the late Archbishop of Canterbury. Cr. 8vo. 3s. 6d.

**Robinson (F. S.).** See Connoisseur's Library.

**Rochefoucauld (La).** See Little Library.

**Rodwell (G.), B.A.** NEW TESTAMENT GREEK. A Course for Beginners. With a Preface by Walter Lock, D.D., Warden of Keble College. Fcap. 8vo. 3s. 6d.

**Roe (Fred).** OLD OAK FURNITURE. With many Illustrations by the Author, including a frontispiece in colour. *Second Edition.* Demy 8vo. 10s. 6d. net.

**Rogers (A. G. L.), M.A.** See Books on Business.

**Romney (George).** See Little Galleries.

**Roscoe (E. S.).** See Little Guides.

**Rose (Edward).** THE ROSE READER. Illustrated. Cr. 8vo. 2s. 6d. Also in 4 Parts. Parts I. and II. 6d. each; Part III. 8d.; Part IV. 10d.

**Rose (G. H.).** See Hey (H.), and Baring-Gould (S.).

**Rowntree (Joshua).** THE IMPERIAL DRUG TRADE. A RE-STATEMENT OF THE OPIUM QUESTION. *Third Edition Revised.* Cr. 8vo. 2s. net.

**Royce-Smith (N. G.).** THE PILLOW BOOK: A GARNER OF MANY MOODS. Collected by. *Second Edition.* Cr. 8vo. 4s. 6d. net.

**POETS OF OUR DAY.** Selected, with an Introduction, by. Fcap. 8vo. 5s.

**Rubie (A. E.), D.D.** See Junior School Books.

**Russell (Archibald G. B.).** See Blake (William).

**Russell (W. Clark).** THE LIFE OF ADMIRAL LORD COLLINGWOOD. With Illustrations by F. BRANGWYN. *Fourth Edition.* Cr. 8vo. 6s.

**Ryley (M. Beresford).** QUEENS OF THE RENAISSANCE. With 24 Illustrations. Demy 8vo. 10s. 6d. net.

**Sainsbury (Harrington), M.D., F.R.C.P.** PRINCIPIA THERAPEUTICA. Demy 8vo. 7s. 6d. net.

**St. Anselm.** See Library of Devotion.

**St. Augustine.** See Library of Devotion.

**St. Bernard.** See Library of Devotion.

**St. Cyres (Viscount).** See Oxford Biographies.

**St. Francis of Assisi.** THE LITTLE FLOWERS OF THE GLORIOUS MESSIAH, AND OF HIS PRIARS. Done into English, with Notes by WILLIAM HEYWOOD. With 40 Illustrations from Italian Painters. Demy 8vo. 5s. net. See also Wheldon (F. W.), Library of Devotion and Standard Library.

**St. Francis de Sales.** See Library of Devotion.

**'Saki' (H. Munro).** REGINALD. *Second Edition.* Fcap. 8vo. 2s. 6d. net.

**Salmon (A. L.).** See Little Guides.

**Sathas (C.).** See Byzantine Texts.

**Schmitt (John).** See Byzantine Texts.

**Schofield (A. T.), M.D., Hon. Phys.** FREIDENHAM HOSPITAL. FUNCTIONAL NERVE DISEASES. Demy 8vo. 7s. 6d. net.

**Scott (A. M.).** WINSTON SPENCER CHURCHILL. With Portraits and Illustrations. Cr. 8vo. 3s. 6d.

**Scudamore (Cyril).** See Little Guides.

**Selincourt (E. de.).** See Keats (John).

**Sells (V. P.), M.A.** THE MECHANICS OF DAILY LIFE. Illustrated. Cr. 8vo. 2s. 6d.

**Selous (Edmund).** TOMMY SMITH'S ANIMALS. Illustrated by G. W. ORD. *Tenth Edition.* Fcap. 8vo. 2s. 6d. *School Edition,* 1s. 6d.

**TOMMY SMITH'S OTHER ANIMALS.** Illustrated by AUGUSTA GUEST. *Fourth Edition.* Fcap. 8vo. 2s. 6d.

*School Edition,* 1s. 6d.

**Senter (George), B.Sc. (Lond.), Ph.D.** See Textbooks of Science.

**Shakespeare (William).**

THE FOUR FOLIOS, 1623; 1632; 1664; 1685. Each £4. 4s. net, or a complete set, £12. 12s. net.

Folios 3 and 4 are ready.

Folio 2 is nearly ready.

THE POEMS OF WILLIAM SHAKESPEARE. With an Introduction and Notes by GEORGE WYNDHAM. Demy 8vo. Buckram, gilt top, 10s. 6d.

See also Arden Shakespeare, Standard Library and Little Quarto Shakespeare.



**Sharp (A.). VICTORIAN POETS.** *Cr. 8vo. 2s. 6d.*

**Sharp (Cecil).** See Baring-Gould (S.).

**Sharp (Elizabeth).** See Little Books on Art.

**Shedlock (J. S.). THE PIANOFORTE SONATA.** *Cr. 8vo. 5s.*

**Shelley (Percy B.).** See Standard Library.

**Sheppard (H. F.), M.A.** See Baring-Gould (S.).

**Sherwell (Arthur), M.A. LIFE IN WEST LONDON.** *Third Edition. Cr. 8vo. 2s. 6d.*

**Shipley (Mary E.). AN ENGLISH CHURCH HISTORY FOR CHILDREN.** With a Preface by the Bishop of Gibraltar. With Maps and Illustrations. Part I. *Cr. 8vo. 2s. 6d. net.*

**Sichel (Walter).** See Oxford Biographies.

**Sidgwick (Mrs. Alfred). HOME LIFE IN GERMANY.** With 16 Illustrations. *Second Edition. Demy 8vo. 10s. 6d. net.*

A Colonial Edition is also published.

**Slime (John).** See Little Books on Art.

**Simonson (G. A.). FRANCESCO GUARDI.** With 41 Plates. *Imperial 4to. 5s. 2s. net.*

**Sketchley (R. E. D.).** See Little Books on Art.

**Skipton (H. P. K.).** See Little Books on Art.

**Sladen (Douglas). SICILY: The New Winter Resort.** With over 200 Illustrations. *Second Edition. Cr. 8vo. 5s. net.*

**Small (Evan), M.A. THE EARTH.** An Introduction to Physiography. Illustrated. *Cr. 8vo. 2s. 6d.*

**Smallwood (M. G.).** See Little Books on Art.

**Smedley (F. E.).** See I.P.L.

**Smith (Adam). THE WEALTH OF NATIONS.** Edited with an Introduction and numerous Notes by EDWIN CANNAN, M.A. *Two volumes. Demy 8vo. 21s. net.*

**Smith (H. Clifford).** See Connoisseur's Library.

**Smith (Horace and James).** See Little Library.

**Smith (H. Bompas), M.A. A NEW JUNIOR ARITHMETIC.** *Crown 8vo. Without Answers, 2s. With Answers, 2s. 6d.*

**Smith (R. Mudie). THOUGHTS FOR THE DAY.** Edited by. *Fcap. 8vo. 3s. 6d. net.*

**Smith (Newell C.).** See Wordsworth (W.).

**Smith (John Thomas). A BOOK FOR A RAINY DAY: Or, Recollections of the Events of the Years 1766-1833.** Edited by WILFRED WHITTEN. Illustrated. *Wide Demy 8vo. 12s. 6d. net.*

**Snell (F. J.). A BOOK OF EXMOOR.** Illustrated. *Cr. 8vo. 6s.*

**Snowden (C. E.). A HANDY DIGEST OF BRITISH HISTORY.** *Demy 8vo. 4s. 6d.*

**Sophocles.** See Classical Translations.

**Sornet (L. A.), and Acatos (M. J.).** See Junior School Books.

**South (R. Wilton), M.A.** See Junior School Books.

**Southey (R.). ENGLISH SEAMEN**

Edited by DAVID HANNAY.

Vol. 1. (Howard, Clifford, Hawkins, Drake, Cavendish). *Second Edition. Cr. 8vo. 6s.*

Vol. II. (Richard Hawkins, Grenville, Essex, and Raleigh). *Cr. 8vo. 6s.*

See also Standard Library.

**Spence (C. H.), M.A.** See School Examination Series.

**Spicer (A. Dykes), M.A. THE PAPER TRADE.** A Descriptive and Historical Survey. With Diagrams and Plans. *Demy 8vo. 12s. 6d. net.*

**Spooner (W. A.), M.A.** See Leaders of Religion.

**Spragge (W. Horton), M.A.** See Junior School Books.

**Staley (Edgcumbe). THE GUILDS OF FLORENCE.** Illustrated. *Second Edition. Royal 8vo. 16s. net.*

**Stanbridge (J. W.), B.D.** See Library of Devotion.

**'Stanciliffe.' GOLF DO'S AND DONT'S**

*Second Edition. Fcap. 8vo. 1s.*

**Stead (D. W.).** See Gallaher (D.).

**Stedman (A. M. M.), M.A.**

**INITIAL LATINA: Easy Lessons on Elementary Accidence.** *Eleventh Edition. Fcap. 8vo. 1s.*

**FIRST LATIN LESSONS.** *Eleventh Edition. Cr. 8vo. 2s.*

**FIRST LATIN READER.** With Notes adapted to the Shorter Latin Primer and Vocabulary. *Seventh Edition. 18mo. 1s. 6d.*

**EASY SELECTIONS FROM CÆSAR.** The Helvetian War. *Third Edition. 18mo. 1s.*

**EASY SELECTIONS FROM LIVY.** The Kings of Rome. *Second Edition. 18mo. 1s. 6d.*

**EASY LATIN PASSAGES FOR UNSEEN TRANSLATION.** *Twelfth Ed. Fcap. 8vo. 1s. 6d.*

**EXEMPLA LATINA.** First Exercises in Latin Accidence. With Vocabulary. *Fourth Edition. Cr. 8vo. 1s.*

**EASY LATIN EXERCISES ON THE SYNTAX OF THE SHORTER AND REVISED LATIN PRIMER.** With Vocabulary. *Twelfth and Cheaper Edition. Cr. 8vo. 1s. 6d. KEY, 3s. net.*

**THE LATIN COMPOUND SENTENCE:** Rules and Exercises. *Second Edition. Cr. 8vo. 1s. 6d. With Vocabulary, 2s.*

**NOTANDA QUÆDAM:** Miscellaneous Latin Exercises on Common Rules and Idioms. *Fifth Edition. Fcap. 8vo. 1s. 6d. With Vocabulary, 2s. KEY, 2s. net.*

**LATIN VOCABULARIES FOR REPE- TITION:** Arranged according to Sub- jects. *Fifteenth Edition. Fcap. 8vo. 1s. 6d.*

**A VOCABULARY OF LATIN IDIOMS.** *18mo. Fourth Edition. 2s.*

**STEPS TO GREEK.** *Third Edition, re- vised. 18mo. 1s.*

**A SHORTER GREEK PRIMER.** *Second Edition.* Cr. 8vo. 1s. 6d.

**EASY GREEK PASSAGES FOR UNSEEN TRANSLATION.** *Fourth Edition, revised.* Fcap. 8vo. 1s. 6d.

**GREEK VOCABULARIES FOR RE-PETITION.** Arranged according to Subjects. *Fourth Edition.* Fcap. 8vo. 1s. 6d.

**GREEK TESTAMENT SELECTIONS.** For the use of Schools. With Introduction, Notes, and Vocabulary. *Fourth Edition.* Fcap. 8vo. 2s. 6d.

**STEPS TO FRENCH.** *Eighth Edition.* 18mo. 8d.

**FIRST FRENCH LESSONS.** *Ninth Edition.* Cr. 8vo. 1s.

**EASY FRENCH PASSAGES FOR UNSEEN TRANSLATION.** *Sixth Edition.* Fcap. 8vo. 1s. 6d.

**EASY FRENCH EXERCISES ON ELEMENTARY SYNTAX.** With Vocabulary. *Fourth Edition.* Cr. 8vo. 2s. 6d. Key. 3s. net.

**FRENCH VOCABULARIES FOR RE-PETITION:** Arranged according to Subjects. *Thirteenth Edition.* Fcap. 8vo. 1s. See also School Examination Series.

**Steel (R. Elliott), M.A., F.R.S.** **THE WORLD OF SCIENCE.** With 147 Illustrations. *Second Edition.* Cr. 8vo. 2s. 6d. See also School Examination Series.

**Stephenson (C.),** of the Technical College, Bradford, and **Suddards (F.)** of the Yorkshire College, Leeds. **A TEXTBOOK DEALING WITH ORNAMENTAL DESIGN FOR WOVEN FABRICS.** With 66 full-page Plates and numerous Diagrams in the Text. *Third Edition.* Demy 8vo. 7s. 6d.

**Stephenson (J.), M.A.** **THE CHIEF TRUTHS OF THE CHRISTIAN FAITH.** Cr. 8vo. 3s. 6d.

**Sterne (Laurence).** See Little Library.

**Steuart (Katherine).** BY ALLAN WATER. *Second Edition.* Cr. 8vo. 6s.

**RICHARD KENNOWAY AND HIS FRIENDS.** A Sequel to 'By Allan Water.' Demy 8vo. 7s. 6d. net.

**Stevenson (R. L.)** **THE LETTERS OF ROBERT LOUIS STEVENSON TO HIS FAMILY AND FRIENDS.** Selected and Edited by SIDNEY COLVIN. *Third Edition.* 2 vols. Cr. 8vo. 12s.

**LIBRARY EDITION.** 2 vols. Demy 8vo. 25s. net.

A Colonial Edition is also published.

**VAILIMA LETTERS.** With an Etched Portrait by WILLIAM STRANG. *Sixth Edition.* Cr. 8vo. Buckram. 6s.

A Colonial Edition is also published.

**THE LIFE OF R. L. STEVENSON.** See Balfour (G.).

**Stevenson (M. I.).** **FROM SARANAC TO THE MARQUESAS.** Being Letters written by Mrs. M. I. STEVENSON during 1887-8. Cr. 8vo. 6s. net.

A Colonial Edition is also published.

**LETTERS FROM SAMOA, 1891-95.** Edited and arranged by M. C. BALFOUR. With

many Illustrations. *Second Edition.* Cr. 8vo. 6s. net.

A Colonial Edition is also published.

**Stoddart (Anna M.).** See Oxford Biographies.

**Stokes (F. G.), B.A.** **HOURS WITH RABELAIS.** From the translation of Sir T. URQUHART and P. A. MORTEUX. With a Portrait in Photogravure. Cr. 8vo. 3s. 6d. net.

**Stone (S. J.).** **POEMS AND HYMNS.** With a Memoir by F. G. ELLERTON, M.A. With Portrait. Cr. 8vo. 6s.

**Storr (Vernon F.), M.A.** **Canon of Winchester.** **DEVELOPMENT AND DIVINE PURPOSE.** Cr. 8vo. 5s. net.

**Story (Alfred T.).** **AMERICAN SHRINES IN ENGLAND.** With many Illustrations, including two in Colour by A. R. QUINTON. Crown 8vo. 6s.

See also Little Guides.

**Straker (F.).** See Books on Business.

**Streane (A. W.), D.D.** See Churchman's Bible.

**Streetfield (R. A.).** **MODERN MUSIC AND MUSICIANS.** With 24 Illustrations. *Second Edition.* Demy 8vo. 7s. 6d. net.

**Stroud (Henry), D.Sc., M.A.** **ELEMENTARY PRACTICAL PHYSICS.** With 115 Diagrams. *Second Edit., revised.* 4s. 6d.

**Sturch (F.),** Staff Instructor to the Surrey County Council. **MANUAL TRAINING DRAWING (WOODWORK).** With Solutions to Examination Questions, Orthographic, Isometric and Oblique Projection. With 50 Plates and 140 Figures. *Footscap.* 5s. net.

**Suddards (F.).** See Stephenson (C.).

**Surtees (R. S.).** See I.P.L.

**Sutherland (William).** **OLD AGE PENSIONS IN THEORY AND PRACTICE,** WITH SOME FOREIGN EXAMPLES. Cr. 8vo. 3s. 6d. net.

**Symes (J. E.), M.A.** **THE FRENCH REVOLUTION.** *Second Edition.* Cr. 8vo. 2s. 6d.

**Symption (E. Mansel), M.A., M.D.** See Ancient Cities.

**Tabor (Margaret E.).** **THE SAINTS IN ART.** With 20 Illustrations. Fcap. 8vo. 3s. 6d. net.

**Tacitus.** **AGRICOLA.** Edited by R. F. DAVIS, M.A. Fcap. 8vo. 2s.

**GERMANIA.** By the same Editor. Fcap. 8vo. 2s.

See also Classical Translations.

**Tallack (W.).** **HOWARD LETTERS AND MEMORIES.** Demy 8vo. 10s. 6d. net.

**Tatham (Frederick).** See Blake (William).

**Tauler (J.).** See Library of Devotion.

**Taylor (A. E.).** **THE ELEMENTS OF METAPHYSICS.** Demy 8vo. 10s. 6d. net.

**Taylor (F. G.), M.A.** See Commercial Series.

**Taylor (I. A.).** See Oxford Biographies.

**Taylor (John W.).** **THE COMING OF THE SAINTS.** With 26 Illustrations. Demy 8vo. 7s. 6d. net.

**Taylor (T. M.), M.A.**, Fellow of Gonville and Caius College, Cambridge. **A CONSTITUTIONAL AND POLITICAL HISTORY OF ROME.** To the Reign of Domitian. *Cr. 8vo. 7s. 6d.*

**Tennisdale-Buckell (G. T.).** **THE COMPLETE SHOT.** With 53 Illustrations. *Third Edition. Demy 8vo. 12s. 6d. net.*  
A Colonial Edition is also published.

**Tennyson (Alfred, Lord).** **EARLY POEMS.** Edited, with Notes and an Introduction, by J. CHURTON COLLINS, M.A. *Cr. 8vo. 6s.*

**IN MEMORIAM, MAUD, AND THE PRINCESS.** Edited by J. CHURTON COLLINS, M.A. *Cr. 8vo. 6s.*

See also Little Library.

**Terry (C. S.).** See Oxford Biographies.

**Thackeray (W. M.).** See Little Library.

**Theobald (F. V.), M.A.** **INSECT LIFE.** Illustrated. *Second Edition Revised. Cr. 8vo. 2s. 6d.*

**Thibaudeau (A. C.).** **BONAPARTE AND THE CONSULATE.** Translated and Edited by G. K. FORTESQUE, LL.D. With 12 Illustrations. *Demy 8vo. 10s. 6d. net.*

**Thompson (A. H.).** See Little Guides.

**Thompson (A. P.).** See Textbooks of Technology.

**Tilston (Mary W.).** **DAILY STRENGTH FOR DAILY NEEDS.** *Fifteenth Edition. Medium 16mo. 2s. 6d. net.* Also an edition in superior binding, 6s.

**Tompkins (H. W.), F.R.H.S.** See Little Books on Art and Little Guides.

**Townley (Lady Susan).** **MY CHINESE NOTE-BOOK.** With 16 Illustrations and 2 Maps. *Third Ed. Demy 8vo. 10s. 6d. net.*  
A Colonial Edition is also published.

**Toynee (Paget), M.A., D.Litt.** **IN THE FOOTPRINTS OF DANTE.** A Treasury of Verse and Prose from the works of Dante. *Small Cr. 8vo. 4s. 6d. net.*

See also Oxford Biographies and Dante.

**Trench (Herbert).** **DEIRDRE WEDDED AND OTHER POEMS.** *Second and Revised Edition. Large Post 8vo. 6s.*

**NEW POEMS.** *Second Edition. Large Post 8vo. 6s.*

**Trevelyan (G. M.),** Fellow of Trinity College, Cambridge. **ENGLAND UNDER THE STUARTS.** With Maps and Plans. *Third Edition. Demy 8vo. 10s. 6d. net.*

**Troutbeck (G. E.).** See Little Guides.

**Tyler (E. A.), B.A., F.C.S.** See Junior School Books.

**Tyrrill-Gill (Frances).** See Little Books on Art.

**Vardon (Harry).** **THE COMPLETE GOLFER.** With 63 Illustrations. *Ninth Edition. Demy 8vo. 10s. 6d. net.*

A Colonial Edition is also published.

**Vaughan (Henry).** See Little Library.

**Vaughan (Herbert M.), B.A. (Oxon.).** **THE LAST OF THE ROYAL STUARTS, HENRY STUART, CARDINAL, DUKE OF YORK.** With 20 Illustrations. *Second Edition. Demy 8vo. 10s. 6d. net.*

**THE NAPLES RIVIERA.** With 25 Illustrations in Colour by MAURICE GREIFFENHAGEN. *Second Edition. Cr. 8vo. 6s.*

**Vernon (Hon. W. Warren), M.A.** **READINGS ON THE INFERNO OF DANTE.** With an Introduction by the Rev. Dr. MOORE. *In Two Volumes. Second Edition. Cr. 8vo. 15s. net.*

**READINGS ON THE PURGATORIO OF DANTE.** With an Introduction by the late DEAN CHURCH. *In Two Volumes. Third Edition. Cr. 8vo. 15s. net.*

**Vincent (J. E.).** **THROUGH EAST ANGLIA IN A MOTOR CAR.** With 16 Illustrations in Colour by FRANK SOUTHGATE, R.B.A., and a Map. *Cr. 8vo. 6s.*

**Voegelin (A.), M.A.** See Junior Examination Series.

**Waddell (Col. L. A.), LL.D., C.B. LHASA AND ITS MYSTERIES.** With a Record of the Expedition of 1903-1904. With 155 Illustrations and Maps. *Third and Cheaper Edition. Medium 8vo. 7s. 6d. net.*

**Wade (G. W.), D.D.** **OLD TESTAMENT HISTORY.** With Maps. *Fifth Edition. Cr. 8vo. 76s.*

**Wade (G. W.), D.D., and Wade (J. H.), M.A.** See Little Guides.

**Wagner (Richard).** **RICHARD WAGNER'S MUSIC DRAMAS:** Interpretations, embodying Wagner's own explanations. By ALICE LEIGHTON CLEATHER and BASIL CRUMP. *In Three Volumes. Fcap 8vo. 2s. 6d. each.*

**VOL. I.—THE RING OF THE NIBELUNG.** *Third Edition.*

**VOL. II.—PARSIFAL, LOHENGGRIN, and THE HOLY GRAIL.**

**VOL. III.—TRISTAN AND ISOLDE.**

**Walkley (A. B.).** **DRAMA AND LIFE.** *Cr. 8vo. 6s.*

**Wall (J. C.).** See Antiquary's Books.

**Wallace-Hadrill (F.),** Second Master at Herne Bay College. **REVISION NOTES ON ENGLISH HISTORY.** *Cr. 8vo. 1s.*

**Walters (H. B.).** See Little Books on Art and Classics of Art.

**Walton (F. W.).** See School Histories.

**Walton (Izaak) and Cotton (Charles).** See I.P.L.

**Walton (Izaak).** See Little Library.

**Waterhouse (Elizabeth).** **WITH THE SIMPLE-HEARTED:** Little Homilies to Women in Country Places. *Second Edition. Small Post 8vo. 2s. net.*

See also Little Library.

**Watt (Francis).** See Hendersson (T.F.).

**Weatherhead (T. C.), M.A.** **EXAMINATION PAPERS IN HORACE.** *Cr. 8vo. 2s.*

See also Junior Examination Series.

**Webber (F. C.).** See Textbooks of Technology.

**Weir (Archibald), M.A.** **AN INTRODUCTION TO THE HISTORY OF MODERN EUROPE.** *Cr. 8vo. 6s.*

**Wells (Sidney H.).** See Textbooks of Science.

**Wells (J.), M.A.**, Fellow and Tutor of Wadham College. **OXFORD AND OXFORD LIFE**. *Third Edition. Cr. 8vo. 3s. 6d.*  
**A SHORT HISTORY OF ROME**. *Eighth Edition. With 3 Maps. Cr. 8vo. 3s. 6d.*  
 See also Little Guides.

**Wesley (John)**. See Library of Devotion.  
**Wheldon (F. W.)**, **A LITTLE BROTHER TO THE BIRDS**. The life-story of St. Francis retold for children. With 15 Illustrations, 7 of which are by A. H. BUCKLAND. *Large Cr. 8vo. 6s.*

**Whibley (C.)**. See Henley (W. E.).  
**Whibley (L.)**, M.A., Fellow of Pembroke College, Cambridge. **GREEK OLIGARCHIES: THEIR ORGANISATION AND CHARACTER**. *Cr. 8vo. 6s.*

**Whitaker (G. H.)**, M.A. See Churchman's Bible.

**White (Gilbert)**. See Standard Library.  
**Whitfield (E. E.)**, M.A. See Commercial Series.

**Whitehead (A. W.)**, **GASPARD DE COLIGNY, ADMIRAL OF FRANCE**. With Illustrations and Plans. *Demy 8vo. 12s. 6d. net.*

**Whiteley (R. Lloyd)**, F.I.C., Principal of the Municipal Science School, West Bromwich. **AN ELEMENTARY TEXT-BOOK OF INORGANIC CHEMISTRY**. *Cr. 8vo. 2s. 6d.*

**Whitley (Miss)**. See Dilke (Lady).

**Whitling (Miss L.)**, late Staff Teacher of the National Training School of Cookery. **THE COMPLETE COOK**. With 42 Illustrations. *Demy 8vo. 7s. 6d. net.*  
 A Colonial edition is also published.

**Whitten (W.)**. See Smith (John Thomas).

**Whyte (A. G.)**, B.Sc. See Books on Business.

**Wilberforce (Wilfrid)**. See Little Books on Art.  
**Wilde (Oscar)**. **DE PROFUNDIS**. *Eleventh Edition. Cr. 8vo. 5s. net.*  
 A Colonial Edition is also published.

**THE WORKS**.  
*A Uniform Edition. Demy 8vo. 12s. 6d. net each volume.*

**THE DUCHESS OF PADUA: A Play.**  
**POEMS.**

**INTENTIONS AND THE SOUL OF MAN.**  
**SALOMÉ. A FLORENTINE TRAGEDY,** and **VERA; or, THE NIHILISTS.**

**LADY WINDERMERE'S FAN: A Play** about a Good Woman.

**A WOMAN OF NO IMPORTANCE: A Play.**

**AN IDEAL HUSBAND: A Play.**

**THE IMPORTANCE OF BEING EARNEST: A Trivial Comedy for Serious People.**

**A HOUSE OF POMEGRANATES, THE HAPPY PRINCE, and OTHER TALES.**  
**LORD ARTHUR SAVILE'S CRIME and OTHER PROSE PIECES.**

**DE PROFUNDIS.**  
**Wilkins (W. H.)**, B.A. **THE ALIEN INVASION**. *Cr. 8vo. 2s. 6d.*

**Williams (A.)**, **PETROL PETER: or Pretty Stories and Funny Pictures**. Illustrated in Colour by A. W. MILLS. *Demy 4to. 3s. 6d. net.*

**Williamson (M. G.)**, M.A. See Ancient Cities.

**Williamson (W.)**, B.A. See Junior Examination Series, Junior School Books, and Beginner's Books.

**Wilmot-Buxton (E. M.)**, **MAKERS OF EUROPE**. Outlines of European History for the Middle Forms of Schools. With 12 Maps. *Ninth Edition. Cr. 8vo. 3s. 6d.*

**THE ANCIENT WORLD**. With Maps and Illustrations. *Cr. 8vo. 3s. 6d.*

**A BOOK OF NOBLE WOMEN**. With 16 Illustrations. *Cr. 8vo. 3s. 6d.*

**A HISTORY OF GREAT BRITAIN: FROM THE COMING OF THE ANGLES TO THE YEAR 1870**. With 20 Maps. *Cr. 8vo. 3s. 6d.*

See also Beginner's Books.

**Wilson (Bishop)**. See Library of Devotion.

**Wilson (A. J.)**. See Books on Business.

**Wilson (H. A.)**. See Books on Business.

**Wilson (J. A.)**. See Simplified French Texts.

**Wilton (Richard)**, M.A. **LYRA PAS-TORALIS: Songs of Nature, Church, and Home**. *Pott 8vo. 2s. 6d.*

**Winbolt (S. E.)**, M.A. **EXERCISES IN LATIN ACCIDENCE**. *Cr. 8vo. 1s. 6d.*

**LATIN HEXAMETER VERSE: An Aid to Composition**. *Cr. 8vo. 3s. 6d. KEY, 5s. net.*

**Windle (B. C. A.)**, D.Sc., F.R.S., F.S.A. See Antiquary's Books, Little Guides, Ancient Cities, and School Histories.

**Winterbotham (Canon)**, M.A., B.Sc., LL.B. See Churchman's Library.

**Wood (Sir Evelyn)**, F.M., V.C., G.C.B., G.C.M.G. **FROM MIDSHIPMAN TO FIELD-MARSHAL**. With Illustrations, and 29 Maps. *Fifth and Cheaper Edition. Demy 8vo. 7s. 6d. net.*  
 A Colonial Edition is also published.

**Wood (J. A. E.)**. See Textbooks of Technology.

**Wood (J. Hickory)**, **DAN LENO**. Illustrated. *Third Edition. Cr. 8vo. 6s.*  
 A Colonial Edition is also published.

**Wood (W. Birkbeck)**, M.A., late Scholar of Worcester College, Oxford, and **Edmonds (Major J. E.)**, R.E., D.A.Q.-M.G. **A HISTORY OF THE CIVIL WAR IN THE UNITED STATES**. With an Introduction by H. SPENSER WILKINSON. With 24 Maps and Plans. *Second Edition. Demy 8vo. 12s. 6d. net.*

**Wordsworth (Christopher)**, M.A. See Antiquary's Books.

**Wordsworth (W.)**, **THE POEMS OF**. With an Introduction and Notes by NOWELL C. SMITH, late Fellow of New College, Oxford. *In Three Volumes. Demy 8vo. 15s. net.*

**POEMS BY WILLIAM WORDSWORTH**. Selected with an Introduction by STEPHEN

- A. BROOKER** With 40 Illustrations by E. H. New, including a Frontispiece in Photogravure. *Cr. 8vo. 7s. 6d. net.*  
See also Little Library.
- Wordsworth (W.) and Coleridge (S. T.)**. See Little Library.
- Wright (Arthur), D.D.**, Fellow of Queen's College, Cambridge. See Churchman's Library.
- Wright (C. Gordon)**. See Dante.
- Wright (J. C.)**. TO-DAY. Thoughts on Life for every day. *Demy 16mo. 1s. 6d. net.*
- Wright (Sophie)**. GERMAN VOCABULARIES FOR REPETITION. *Fcap. 8vo. 1s. 6d.*
- Wyatt (Kate M.)**. See Gloag (M. R.).
- Wylde (A. B.)**. MODERN ABYSSINIA. With a Map and a Portrait. *Demy 8vo. 15s. net.*
- Wyllie (M. A.)**. NORWAY AND ITS FJORDS. With 16 Illustrations, in Colour by W. L. WYLLIE, R.A., and 17 other Illustrations. *Crown 8vo. 6s.*  
A Colonial Edition is also published.
- Wyndham (George)**. See Shakespeare (William).
- Wyon (R.) and Prance (G.)**. THE LAND OF THE BLACK MOUNTAIN. With 51 Illustrations. *Cr. 8vo. 2s. 6d. net.*
- Yeats (W. B.)**. A BOOK OF IRISH VERSE. *Revised and Enlarged Edition. Cr. 8vo. 3s. 6d.*
- Young (Filson)**. THE COMPLETE MOTORIST. With 138 Illustrations. *New Edition (Seventh), with many additions. Demy. 8vo. 12s. 6d. net.*  
A Colonial Edition is also published.
- THE JOY OF THE ROAD**: An Appreciation of the Motor Car. With a Frontispiece in Photogravure. *Small Demy 8vo. 5s. net.*
- Young (T. M.)**. THE AMERICAN COTTON INDUSTRY: A Study of Work and Workers. *Cr. 8vo. Cloth, 2s. 6d.; paper boards, 1s. 6d.*
- Zimmer (Antonia)**. WHAT DO WE KNOW CONCERNING ELECTRICITY? *Fcap. 8vo. 1s. 6d. net.*

### Ancient Cities

General Editor, B. C. A. WINDLE, D.Sc., F.R.S.

*Cr. 8vo. 4s. 6d. net.*

- CHESTER**. By B. C. A. Windle, D.Sc. F.R.S. Illustrated by E. H. New.
- SHREWSBURY**. By T. Auden, M.A., F.S.A. Illustrated by Katharine M. Roberts.
- CANTERBURY**. By J. C. Cox, LL.D., F.S.A. Illustrated by B. C. Boulter.
- EDINBURGH**. By M. G. Williamson, M.A. Illustrated by Herbert Railton.
- LINCOLN**. By E. Mansel Symson, M.A., M.D. Illustrated by E. H. New.
- BRISTOL**. By Alfred Harvey, M.B. Illustrated by E. H. New.
- DUBLIN**. By S. A. O. Fitzpatrick. Illustrated by W. C. Green.

### The Antiquary's Books

General Editor, J. CHARLES COX, LL.D., F.S.A.

*Demy 8vo. 7s. 6d. net.*

- ENGLISH MONASTIC LIFE**. By the Right Rev. Abbot Gasquet, O.S.B. Illustrated. *Third Edition.*
- REMAINS OF THE PREHISTORIC AGE IN ENGLAND**. By B. C. A. Windle, D.Sc., F.R.S. With numerous Illustrations and Plans.
- OLD SERVICE BOOKS OF THE ENGLISH CHURCH**. By Christopher Wordsworth, M.A., and Henry Littlehales. With Coloured and other Illustrations.
- CELTIC ART IN PAGAN AND CHRISTIAN TIMES**. By J. Romilly Allen, F.S.A. With numerous Illustrations and Plans.
- ARCHÆOLOGY AND FALSE ANTIQUITIES**. By R. Munro, LL.D. Illustrated.
- SHRINES OF BRITISH SAINTS**. By J. C. Wall. With numerous Illustrations and Plans.
- THE ROYAL FORESTS OF ENGLAND**. By J. C. Cox, LL.D., F.S.A. Illustrated.
- THE MANOR AND MANORIAL RECORDS**. By Nathaniel J. Hone. Illustrated.
- ENGLISH SEALS**. By J. Harvey Bloom. Illustrated.
- THE BELLS OF ENGLAND**. By Canon J. J. Raven, D.D., F.S.A. With Illustrations. *Second Edition.*
- PARISH LIFE IN MÆDIEVAL ENGLAND**. By the Right Rev. Abbot Gasquet, O.S.B. With many Illustrations. *Second Edition.*
- THE DOMESDAY INQUEST**. By Adolphus Ballard, B.A., LL.B. With 22 Illustrations.
- THE BRASSES OF ENGLAND**. By Herbert W. Macklin, M.A. With many Illustrations. *Second Edition.*
- ENGLISH CHURCH FURNITURE**. By J. C. Cox, LL.D., F.S.A., and A. Harvey, M.B. *Second Edition.*
- FOLK-LORE AS AN HISTORICAL SCIENCE**. By G. L. Gomme. With many Illustrations.
- \*ENGLISH COSTUME**. By George Clinch, F.G.S. With many Illustrations.

**The Arden Shakespeare***Demy 8vo. 2s. 6d. net each volume.*

An edition of Shakespeare in single Plays. Edited with a full Introduction, Textual Notes, and a Commentary at the foot of the page.

- |   |   |
|---|---|
| <p>HAMLET. Edited by Edward Dowden.<br/>         ROMEO AND JULIET. Edited by Edward Dowden.<br/>         KING LEAR. Edited by W. J. Craig.<br/>         JULIUS CAESAR. Edited by M. Macmillan.<br/>         THE TEMPEST. Edited by Moreton Luce.<br/>         OTHELLO. Edited by H. C. Hart.<br/>         TITUS ANDRONICUS. Edited by H. B. Baildon.<br/>         CYMBELINE. Edited by Edward Dowden.<br/>         *THE MERRY WIVES OF WINDSOR. Edited by H. C. Hart.<br/>         A MIDSUMMER NIGHT'S DREAM. Edited by H. Cuninghame.<br/>         KING HENRY V. Edited by H. A. Evans.<br/>         ALL'S WELL THAT ENDS WELL. Edited by W. O. Briscoe.<br/>         THE TAMING OF THE SHREW. Edited by R. Warwick Bond.<br/>         TIMON OF ATHENS. Edited by K. Deighton.</p> | <p>MEASURE FOR MEASURE. Edited by H. C. Hart.<br/>         TWELFTH NIGHT. Edited by Moreton Luce.<br/>         THE MERCHANT OF VENICE. Edited by C. Knox Pooler.<br/>         TROILUS AND CRESSIDA. Edited by K. Deighton.<br/>         THE TWO GENTLEMEN OF VERONA. Edited by R. Warwick Bond.<br/>         ANTONY AND CLEOPATRA. Edited by R. H. Case.<br/>         LOVE'S LABOUR'S LOST. Edited by H. C. Hart.<br/>         PERICLES. Edited by K. Deighton.<br/>         KING RICHARD III. Edited by A. H. Thompson.<br/>         THE LIFE AND DEATH OF KING JOHN. Edited by Ivor B. John.<br/>         THE COMEDY OF ERRORS. Edited by Henry Cuninghame.</p> |
|---|---|

**The Beginner's Books**

Edited by W. WILLIAMSON, B.A.

- |   |   |
|---|---|
| <p>EASY FRENCH RHYMES. By Henri Blouet. <i>Second Edition.</i> Illustrated. <i>Fcap. 8vo. 1s.</i><br/>         EASY STORIES FROM ENGLISH HISTORY. By E. M. Wilmot-Buxton. <i>Fourth Edition.</i> <i>Cr. 8vo. 1s.</i><br/>         STORIES FROM ROMAN HISTORY. By E. M. Wilmot-Buxton. <i>Cr. 8vo. 1s. 6d.</i><br/>         A FIRST HISTORY OF GREECE. By E. E. Firth. <i>Cr. 8vo. 1s. 6d.</i></p> | <p>EASY EXERCISES IN ARITHMETIC. Arranged by W. S. Beard. <i>Third Edition.</i> <i>Fcap. 8vo. Without Answers, 1s. With Answers, 1s. 3d.</i><br/>         EASY DICTATION AND SPELLING. By W. Williamson, B.A. <i>Seventh Ed. Fcap. 8vo. 1s.</i><br/>         AN EASY POETRY BOOK. Selected and arranged by W. Williamson, B.A. <i>Second Edition.</i> <i>Cr. 8vo. 1s.</i></p> |
|---|---|

**Books on Business***Cr. 8vo. 2s. 6d. net.*

- |   |  |
|---|--|
| <p>PORTS AND DOCKS. By Douglas Owen.<br/>         RAILWAYS. By E. R. McDermott.<br/>         THE STOCK EXCHANGE. By Chas. Duguid. <i>Second Edition.</i><br/>         THE BUSINESS OF INSURANCE. By A. J. Wilson.<br/>         THE ELECTRICAL INDUSTRY: LIGHTING, TRACTION, AND POWER. By A. G. Whyte, B.Sc.<br/>         THE SHIPBUILDING INDUSTRY: Its History, Practice, Science, and Finance. By David Pollock, M.I.N.A.<br/>         THE MONEY MARKET. By F. Straker.<br/>         *THE BUSINESS SIDE OF AGRICULTURE. By A. G. L. Rogers, M.A.<br/>         LAW IN BUSINESS. By H. A. Wilson.<br/>         THE BREWING INDUSTRY. By Julian L. Baker, F.I.C., F.C.S. Illustrated.</p> | <p>THE AUTOMOBILE INDUSTRY. By G. de Holden-Stone.<br/>         MINING AND MINING INVESTMENTS. By 'A. Moll.'<br/>         THE BUSINESS OF ADVERTISING. By Clarence G. Moran, Barrister-at-Law. Illustrated.<br/>         TRADE UNIONS. By G. Drage.<br/>         CIVIL ENGINEERING. By T. Claxton Fidler, M.Inst. C.E. Illustrated.<br/>         THE IRON TRADE OF GREAT BRITAIN. By J. Stephen Jeans. Illustrated.<br/>         MONOPOLIES, TRUSTS, AND KARTELLS. By F. W. Hirst.<br/>         THE COTTON INDUSTRY AND TRADE. By Prof. S. J. Chapman, Dean of the Faculty of Commerce in the University of Manchester. Illustrated.</p> |
|---|--|

**Byzantine Texts**

Edited by J. B. BURY, M.A., Litt.D.

THE SYRIAC CHRONICLE KNOWN AS THAT OF ZACHARIAH OF MITVLENE. Translated by F. J. Hamilton, D.D., and E. W. Brooks. *Demy 8vo. 12s. 6d. net.*

EVAGRIUS. Edited by L. Bidez and Léon Parmentier. *Demy 8vo. 10s. 6d. net.*

THE HISTORY OF PSELLUS. Edited by C. Sathas. *Demy 8vo. 15s. net.*

ECTHESIS CHRONICA AND CHRONICON ATHENARUM. Edited by Professor S. P. Lambros. *Demy 8vo. 7s. 6d. net.*

THE CHRONICLE OF MOREA. Edited by John Schmitt. *Demy 8vo. 15s. net.*

**The Churchman's Bible**

General Editor, J. H. BURN, B.D., F.R.S.E.

*Fcap. 8vo. 1s. 6d. net each.*

THE EPISTLE OF ST. PAUL THE APOSTLE TO THE GALATIANS. Explained by A. W. Robinson, M.A. *Second Edition.*

ECCLESIASTES. Explained by A. W. Streane, D.D.

THE EPISTLE OF ST. PAUL THE APOSTLE TO THE PHILIPPIANS. Explained by C. R. D. Biggs, D.D. *Second Edition.*

THE EPISTLE OF ST. JAMES. Explained by H. W. Fulford M.A.

ISAIAH. Explained by W. E. Barnes, D.D. *Two Volumes. With Map. 2s. net each.*

THE EPISTLE OF ST. PAUL THE APOSTLE TO THE EPHESIANS. Explained by G. H. Whitaker, M.A.

THE GOSPEL ACCORDING TO ST. MARK. Explained by J. C. Du Buisson, M.A. *2s. 6d. net.*

THE EPISTLE OF PAUL THE APOSTLE TO THE COLOSSIANS AND PHILEMON. Explained by H. J. C. Knight. *2s. net.*

**The Churchman's Library**

General Editor, J. H. BURN, B.D., F.R.S.E.

*Crown 8vo. 3s. 6d. each.*

THE BEGINNINGS OF ENGLISH CHRISTIANITY. By W. E. Collins, M.A. With Map.

THE KINGDOM OF HEAVEN HERE AND HERE-AFTER. By Canon Winterbotham, M.A., B.Sc., LL.B.

THE WORKMANSHIP OF THE PRAYER BOOK: Its Literary and Liturgical Aspects. By J. Dowden, D.D. *Second Edition, Revised and Enlarged.*

EVOLUTION. By F. B. Jevons, M.A., Litt.D. *SOME NEW TESTAMENT PROBLEMS.* By Arthur Wright, D.D. *6s.*

THE CHURCHMAN'S INTRODUCTION TO THE OLD TESTAMENT. By A. M. Mackay, B.A. *Third Edition.*

COMPARATIVE THEOLOGY. By J. A. MacCulloch. *6s.*

**Classical Translations***Crown 8vo.*

ÆSCHYLUS—The Oresteian Trilogy (Agamemnon, Choëphoroe, Eumenides). Translated by Lewis Campbell, LL.D. *5s.*

CICERO—De Oratore I. Translated by E. N. P. Moor, M.A. *Second Edition. 2s. 6d.*

CICERO—The Speeches against Cataline and Antony and for Murena and Milo. Translated by H. E. D. Blakiston, M.A. *5s.*

CICERO—De Natura Deorum. Translated by F. Brooks, M.A. *3s. 6d.*

CICERO—De Officiis. Translated by G. B. Gardiner, M.A. *2s. 6d.*

HORACE—The Odes and Epodes. Translated by A. D. Godley, M.A. *2s.*

LUCIAN—Six Dialogues. Translated by S. T. Irwin, M.A. *3s. 6d.*

SOPHOCLES—Ajax and Electra. Translated by E. D. Morshead, M.A. *2s. 6d.*

TACITUS—Agricola and Germania. Translated by R. B. Townshend. *2s. 6d.*

JUVENAL—Thirteen Satires. Translated by S. G. Owen, M.A. *2s. 6d.*

**Classics of Art**

Edited by DR. J. H. W. LAING

THE ART OF THE GREEKS. By H. B. Walters. With 112 Plates and 18 Illustrations in the Text. *Wide Royal 8vo. 12s. 6d. net.*

VELAZQUEZ. By A. de Belfuete. With 94 Plates. *Wide Royal 8vo. 10s. 6d. net.*

**Commercial Series***Crown 8vo.*

**BRITISH COMMERCE AND COLONIES FROM ELIZABETH TO VICTORIA.** By H. de B. Gibbins, Litt.D., M.A. *Third Edition.* 2s.

**COMMERCIAL EXAMINATION PAPERS.** By H. de B. Gibbins, Litt.D., M.A. 1s. 6d.

**THE ECONOMICS OF COMMERCE.** By H. de B. Gibbins, Litt.D., M.A. *Second Edition.* 1s. 6d.

**A GERMAN COMMERCIAL READER.** By S. E. Bally. With Vocabulary. 2s.

**A COMMERCIAL GEOGRAPHY OF THE BRITISH EMPIRE.** By L. W. Lyde, M.A. *Sixth Edition.* 2s.

**A COMMERCIAL GEOGRAPHY OF FOREIGN NATIONS.** By F. C. Boon, B.A. 2s.

**A PRIMER OF BUSINESS.** By S. Jackson, M.A. *Fourth Edition.* 1s. 6d.

**A SHORT COMMERCIAL ARITHMETIC.** By F. G. Taylor, M.A. *Fourth Edition.* 1s. 6d.

**FRENCH COMMERCIAL CORRESPONDENCE.** By S. E. Bally. With Vocabulary. *Third Edition.* 2s.

**GERMAN COMMERCIAL CORRESPONDENCE.** By S. E. Bally. With Vocabulary. *Second Edition.* 2s. 6d.

**A FRENCH COMMERCIAL READER.** By S. E. Bally. With Vocabulary. *Second Edition.* 2s.

**PRECIS WRITING AND OFFICE CORRESPONDENCE.** By F. E. Whitfield, M.A. *Second Edition.* 2s.

**A ENTRANCE GUIDE TO PROFESSIONS AND BUSINESS.** By H. Jones. 1s. 6d.

**THE PRINCIPLES OF BOOK-KEEPING BY DOUBLE ENTRY.** By J. F. B. M'Allen, M.A. 2s.

**COMMERCIAL LAW.** By W. Douglas Edwards. *Second Edition.* 2s.

**The Connoisseur's Library***Wide Royal 8vo. 25s. net.*

**MEZZOTINTS.** By Cyril Davenport. With 40 Plates in Photogravure.

**PORCELAIN.** By Edward Dillon. With 19 Plates in Colour, 20 in Collotype, and 5 in Photogravure.

**MINIATURES.** By Dudley Heath. With 9 Plates in Colour, 15 in Collotype, and 15 in Photogravure.

**IVORIES.** By A. Maskell. With 80 Plates in Collotype and Photogravure.

**ENGLISH FURNITURE.** By F. S. Robinson. With 160 Plates in Collotype and one in Photogravure. *Second Edition.*

**ENGLISH COLOURED BOOKS.** By Martin Hardie. With 28 Illustrations in Colour and Collotype.

**EUROPEAN ENAMELS.** By Henry H. Cunyng-hame, C.B. With 54 Plates in Collotype and Half-tone and 4 Plates in Colour.

**GOLD SMITHS' AND SILVER SMITHS' WORK.** By Nelson Dawson. With many Plates in Collotype and a Frontispiece in Photogravure. *Second Edition.*

**GLASS.** By Edward Dillon. With 37 Illustrations in Collotype and 12 in Colour.

**SEALS.** By Walter de Gray Birch. With 52 Illustrations in Collotype and a Frontispiece in Photogravure.

**JEWELLERY.** By H. Clifford Smith. With 50 Illustrations in Collotype, and 4 in Colour.

**The Illustrated Pocket Library of Plain and Coloured Books***Fcap 8vo. 3s. 6d. net each volume.***COLOURED BOOKS**

**OLD COLOURED BOOKS.** By George Paston. With 16 Coloured Plates. *Fcap. 8vo. 2s. net.*

**THE LIFE AND DEATH OF JOHN MYTTON, Esq.** By Nimrod. With 18 Coloured Plates by Henry Alken and T. J. Rawlins. *Fourth Edition.*

**THE LIFE OF A SPORTSMAN.** By Nimrod. With 35 Coloured Plates by Henry Alken.

**HANDLEY CROSS.** By R. S. Surtees. With 17 Coloured Plates and 100 Woodcuts in the Text by John Leech. *Second Edition.*

**MR. SPONGE'S SPORTING TOUR.** By R. S. Surtees. With 13 Coloured Plates and 90 Woodcuts in the Text by John Leech.

**JORROCKS' JAUNTS AND JOLLITIES.** By R. S. Surtees. With 15 Coloured Plates by H. Alken. *Second Edition.*

**ASK MAMM.** By R. S. Surtees. With 13 Coloured Plates and 70 Woodcuts in the Text by John Leech.

**THE ANALYSIS OF THE HUNTING FIELD.** By R. S. Surtees. With 7 Coloured Plates by Henry Alken, and 43 Illustrations on Wood.

**THE TOUR OF DR. SYNTAX IN SEARCH OF THE PICTURESQUE.** By William Combe. With 30 Coloured Plates by T. Rowlandson.

**THE TOUR OF DOCTOR SYNTAX IN SEARCH OF CONSOLATION.** By William Combe. With 24 Coloured Plates by T. Rowlandson.

**THE THIRD TOUR OF DOCTOR SYNTAX IN SEARCH OF A WIFE.** By William Combe. With 24 Coloured Plates by T. Rowlandson.

**THE HISTORY OF JOHNNY QUAE GENUS: the Little Foundling of the late Dr. Syntax.** By the Author of 'The Three Tours.' With 24 Coloured Plates by Rowlandson.

**THE ENGLISH DANCE OF DEATH,** from the Designs of T. Rowlandson, with Metrical Illustrations by the Author of 'Doctor Syntax.' *Two Volumes.*

This book contains 76 Coloured Plates.

[Continued.]



ILLUSTRATED POCKET LIBRARY OF PLAIN AND COLOURED BOOKS—*continued.*

**THE DANCE OF LIFE:** A Poem. By the Author of 'Doctor Syntax.' Illustrated with 26 Coloured Engravings by T. Rowlandson.

**LIFE IN LONDON:** or, the Day and Night Scenes of Jerry Hawthorn, Esq., and his Elegant Friend, Corinthian Tom. By Pierce Egan. With 36 Coloured Plates by I. R. and G. Cruikshank. With numerous Designs on Wood.

**REAL LIFE IN LONDON:** or, the Rambles and Adventures of Bob Tallyho, Esq., and his Cousin, The Hon. Tom Dashall. By an Amateur (Pierce Egan). With 31 Coloured Plates by Alken and Rowlandson, etc. *Two Volumes.*

**THE LIFE OF AN ACTOR.** By Pierce Egan. With 27 Coloured Plates by Theodore Lane, and several Designs on Wood.

**THE VICAR OF WAKEFIELD.** By Oliver Goldsmith. With 24 Coloured Plates by T. Rowlandson.

**THE MILITARY ADVENTURES OF JOHNNY NEWCOME.** By an Officer. With 15 Coloured Plates by T. Rowlandson.

**THE NATIONAL SPORTS OF GREAT BRITAIN.** With Descriptions and 50 Coloured Plates by Henry Alken.

**THE ADVENTURES OF A POST CAPTAIN.** By A Naval Officer. With 24 Coloured Plates by Mr. Williams.

**GAMONIA:** or the Art of Preserving Game; and an Improved Method of making Plantations and Covers, explained and illustrated by Lawrence Rawstorne, Esq. With 15 Coloured Plates by T. Rawlins.

**AN ACADEMY FOR GROWN HORSEMEN:** Containing the completest Instructions for Walking, Trotting, Cantering, Galloping, Stumbling, and Tumbling. Illustrated with 27 Coloured Plates, and adorned with a Portrait of the Author. By Geoffrey Gambado, Esq.

**REAL LIFE IN IRELAND,** or, the Day and Night Scenes of Brian Boru, Esq., and his Elegant Friend, Sir Shawn O'Dogherty. By a Real Paddy. With 19 Coloured Plates by Heath, Marks, etc.

**THE ADVENTURES OF JOHNNY NEWCOME IN THE NAVY.** By Alfred Burton. With 16 Coloured Plates by T. Rowlandson.

**THE OLD ENGLISH SQUIRE:** A Poem. By John Careless, Esq. With 20 Coloured Plates after the style of T. Rowlandson.

**THE ENGLISH SPY.** By Bernard Blackmantle. An original Work, Characteristic, Satirical, Humorous, comprising scenes and sketches in every Rank of Society, being Portraits of the Illustrious, Eminent, Eccentric, and Notorious. With 72 Coloured Plates by R. CRUIKSHANK, and many Illustrations on wood. *Two Volumes 7s. net.*

## PLAIN BOOKS

**THE GRAVE:** A Poem. By Robert Blair. Illustrated by 12 Etchings executed by Louis Schiavonetti from the original Inventions of William Blake. With an Engraved Title Page and a Portrait of Blake by T. Phillips, R.A. The illustrations are reproduced in photogravure.

**ILLUSTRATIONS OF THE BOOK OF JOB.** Invented and engraved by William Blake. These famous Illustrations—21 in number—are reproduced in photogravure.

**WINDSOR CASTLE.** By W. Harrison Ainsworth. With 22 Plates and 87 Woodcuts in the Text by George Cruikshank.

**THE TOWER OF LONDON.** By W. Harrison Ainsworth. With 40 Plates and 58 Woodcuts in the Text by George Cruikshank.

**FRANK FAIRLEIGH.** By F. E. Smedley. With 30 Plates by George Cruikshank.

**HANDY ANDY.** By Samuel Lover. With 24 Illustrations by the Author.

**THE COMPLEAT ANGLER.** By Izaak Walton and Charles Cotton. With 14 Plates and 77 Woodcuts in the Text.

**THE PICKWICK PAPERS.** By Charles Dickens. With the 43 Illustrations by Seymour and Phiz, the two Buss Plates, and the 32 Contemporary Onwhyn Plates.

## Junior Examination Series

Edited by A. M. M. STEDMAN, M.A. *Fcap. 8vo. 1s.*

**JUNIOR FRENCH EXAMINATION PAPERS.** By F. Jacob, M.A. *Second Edition.*

**JUNIOR ENGLISH EXAMINATION PAPERS.** By W. Williamson, B.A.

**JUNIOR ARITHMETIC EXAMINATION PAPERS.** By W. S. Beard. *Fourth Edition.*

**JUNIOR ALGEBRA EXAMINATION PAPERS.** By S. W. Finn, M.A.

**JUNIOR GREEK EXAMINATION PAPERS.** By T. C. Weatherhead, M.A. *KEY, 3s. 6d. net.*

**JUNIOR LATIN EXAMINATION PAPERS.** By C. G. Botting, B.A. *Fifth Edition.* *KEY, 3s. 6d. net.*

**JUNIOR GENERAL INFORMATION EXAMINATION PAPERS.** By W. S. Beard. *KEY, 3s. 6d. net.*

**JUNIOR GEOGRAPHY EXAMINATION PAPERS.** By W. G. Baker, M.A.

**JUNIOR GERMAN EXAMINATION PAPERS.** By A. Voegelin, M.A.

**Methuen's Junior School-Books**

Edited by O. D. INSKIP, LL.D., and W. WILLIAMSON, B.A.

- A CLASS-BOOK OF DICTATION PASSAGES. By W. Williamson, B.A. *Fourteenth Edition.* Cr. 8vo. 1s. 6d.
- THE GOSPEL ACCORDING TO ST. MATTHEW. Edited by E. Wilton South, M.A. With Three Maps. Cr. 8vo. 1s. 6d.
- THE GOSPEL ACCORDING TO ST. MARK. Edited by A. E. Rubie, D.D. With Three Maps. Cr. 8vo. 1s. 6d.
- A JUNIOR ENGLISH GRAMMAR. By W. Williamson, B.A. With numerous passages for parsing and analysis, and a chapter on Essay Writing. *Fourth Edition.* Cr. 8vo. 2s.
- A JUNIOR CHEMISTRY. By E. A. Tyler, B.A., F.C.S. With 78 Illustrations. *Fourth Edition.* Cr. 8vo. 2s. 6d.
- THE ACTS OF THE APOSTLES. Edited by A. E. Rubie, D.D. Cr. 8vo. 2s.
- A JUNIOR FRENCH GRAMMAR. By L. A. Sornet and M. J. Acator. *Second Edition.* Cr. 8vo. 2s.
- ELEMENTARY EXPERIMENTAL SCIENCE. PHYSICS by W. T. Clough, A.R.C.S. CHEMISTRY by A. E. Dunstan, B.Sc. With 2 Plates and 154 Diagrams. *Sixth Edition.* Cr. 8vo. 2s. 6d.
- A JUNIOR GEOMETRY. By Noel S. Lydon. With 276 Diagrams. *Sixth Edition.* Cr. 8vo. 2s.
- ELEMENTARY EXPERIMENTAL CHEMISTRY. By A. E. Dunstan, B.Sc. With 4 Plates and 109 Diagrams. *Third Edition.* Cr. 8vo. 2s.
- A JUNIOR FRENCH PROSE. By R. R. N. Baron, M.A. *Third Edition.* Cr. 8vo. 2s.
- THE GOSPEL ACCORDING TO ST. LUKE. With an Introduction and Notes by William Williamson, B.A. With Three Maps. Cr. 8vo. 2s.
- THE FIRST BOOK OF KINGS. Edited by A. E. Rubie, D.D. With Maps. Cr. 8vo. 2s.
- A JUNIOR GREEK HISTORY. By W. H. Sprague, M.A. With 4 Illustrations and 5 Maps. Cr. 8vo. 2s. 6d.
- A SCHOOL LATIN GRAMMAR. By H. G. Ford, M.A. Cr. 8vo. 2s. 6d.
- A JUNIOR LATIN PROSE. By H. N. Asman, M.A., B.D. Cr. 8vo. 2s. 6d.

**Leaders of Religion**

Edited by H. C. BEECHING, M.A., Canon of Westminster. *With Portraits.* Cr. 8vo. 2s. net.

- CARDINAL NEWMAN. By R. H. Hutton.
- JOHN WESLEY. By J. H. Overton, M.A.
- BISHOP WILBERFORCE. By G. W. Dadiell, M.A.
- CARDINAL MANNING. By A. W. Hutton, M.A.
- CHARLES SIMON. By H. C. G. Mole, D.D.
- JOHN KNOX. By F. MacCunn. *Second Edition.*
- JOHN HOWE. By R. F. Horton, D.D.
- THOMAS KEN. By F. A. Clarke, M.A.
- GEORGE FOX, THE QUAKER. By T. Hodgkin, D.C.L. *Third Edition.*
- JOHN KEEBLE. By Walter Lock, D.D.
- THOMAS CHALMERS. By Mrs. Oliphant.
- LANCELOT ANDREWES. By R. L. Outley, D.D. *Second Edition.*
- AUGUSTINE OF CANTERBURY. By E. L. Cutis, D.D.
- WILLIAM LAUD. By W. H. Hutton, M.A. *Third Edition.*
- JOHN DONNE. By Augustus Jessopp, D.D.
- THOMAS CRANMER. By A. J. Mason, D.D.
- BISHOP LATIMER. By R. M. Carlyle and A. J. Carlyle, M.A.
- BISHOP BUTLER. By W. A. Spooner, M.A.

**The Library of Devotion**

With Introductions and (where necessary) Notes.  
*Small Pott 8vo, cloth, 2s.; leather, 2s. 6d. net.*

- THE CONFESSIONS OF ST. AUGUSTINE. Edited by C. Bigg, D.D. *Sixth Edition.*
- THE IMITATION OF CHRIST : called also the Ecclesiastical Music. Edited by C. Bigg, D.D. *Fifth Edition.*
- THE CHRISTIAN YEAR. Edited by Walter Lock, D.D. *Fourth Edition.*
- LYRA INNOCENTIVM. Edited by Walter Lock, D.D. *Second Edition.*
- THE TEMPLE. Edited by E. C. S. Gibson, D.D. *Second Edition.*
- A BOOK OF DEVOTIONS. Edited by J. W. Stanbridge, B.D. *Second Edition.*
- A SERIOUS CALL TO A DEVOUT AND HOLY LIFE. Edited by C. Bigg, D.D. *Fourth Ed.*
- A GUIDE TO ETERNITY. Edited by J. W. Stanbridge, B.D.
- THE INNER WAY. By J. Tauler. Edited by A. W. Hutton, M.A.
- ON THE LOVE OF GOD. By St. Francis de Sales. Edited by W. J. Knox-Little, M.A.
- THE PSALMS OF DAVID. Edited by B. W. Randolph, D.D.
- LYRA APOSTOLICA. By Cardinal Newman and others. Edited by Canon Scott Holland, M.A., and Canon H. C. Beeching, M.A.
- THE SONG OF SONGS. Edited by B. Blaxland, M.A.
- THE THOUGHTS OF PASCAL. Edited by C. S. Jettam, M.A.
- A MANUAL OF CONSOLATION FROM THE SAINTS AND FATHERS. Edited by J. H. Burn, B.D.

[Continued.]

## THE LIBRARY OF DEVOTION—continued.

THE DEVOTIONS OF ST. ANSELM. Edited by C. C. J. Webb, M.A.

GRACE ABOUNDING TO THE CHIEF OF SINNERS. By John Bunyan. Edited by S. C. Freer, M.A.

BISHOP WILSON'S SACRA PRIVATA. Edited by A. E. Burn, B.D.

LYRA SACRA: A Book of Sacred Verse. Edited by Canon H. C. Beeching, M.A. *Second Edition, revised.*

A DAY BOOK FROM THE SAINTS AND FATHERS. Edited by J. H. Burn, B.D.

A LITTLE BOOK OF HEAVENLY WISDOM. A Selection from the English Mystics. Edited by E. C. Gregory.

LIGHT, LIFE, and LOVE. A Selection from the German Mystics. Edited by W. R. Inge, M.A.

AN INTRODUCTION TO THE DEVOUT LIFE. By St. Francis de Sales. Translated and Edited by T. Barnes, M.A.

THE LITTLE FLOWERS OF THE GLORIOUS MESSIAH ST. FRANCIS AND OF HIS FRIARS. Done into English by W. Heywood. With an Introduction by A. G. Ferrers Howell.

MANCHESTER AL MONDO: a Contemplation of Death and Immortality. By Henry Montagu, Earl of Manchester. With an Introduction by Elizabeth Waterhouse, Editor of 'A Little Book of Life and Death.'

THE SPIRITUAL GUIDE, which Disentangles the Soul and brings it by the Inward Way to the Fruition of Perfect Contemplation, and the Rich Treasure of Internal Peace. Written by Dr. Michael de Molinos, Priest. Translated from the Italian copy, printed at Venice, 1685. Edited with an Introduction by Kathleen Lytelton. And a Note by Canon Scott Holland.

DEVOTIONS FOR EVERY DAY OF THE WEEK AND THE GREAT FESTIVALS. By John Wesley. Edited, with an Introduction by Canon C. Bodington.

PRECES PRIVATÆ. By Lancelot Andrewes, Bishop of Winchester. Selections from the Translation by Canon F. K. Brightman. Edited, with an Introduction, by A. E. Burn, D.D.

## Little Books on Art

*With many Illustrations. Demy 16mo. 2s. 6d. net.*

Each volume consists of about 200 pages, and contains from 30 to 40 Illustrations, including a Frontispiece in Photogravure.

GREEK ART. H. B. Walters. *Fourth Edition.*

BOOKPLATES. E. Almack.

REYNOLDS. J. Sime. *Second Edition.*

ROMNEY. George Paston.

WATTS. R. E. D. Sketchley.

LEIGHTON. Alice Corkran.

VELASQUEZ. Wilfrid Wilberforce and A. R. Gilbert.

GREUZE AND BOUCHER. Eliza F. Pollard.

VANDYCK. M. G. Smallwood.

TURNER. Frances Tyrrell-Gill.

DÜRER. Jessie Allen.

HOLBEIN. Mrs. G. Fortescue.

BURNE-JONES. Fortunée de Lisle. *Third Edition.*

HOPFNER. H. P. K. Skipton.

REMBRANDT. Mrs. E. A. Sharp.

COROT. Alice Pollard and Ethel Birnstingl.

RAPHAEL. A. R. Dryhurst.

MILLET. Netta Peacock.

ILLUMINATED MSS. J. W. Bradley.

CHRIST IN ART. Mrs. Henry Jenner.

JEWELLERY. Cyril Davenport.

CLAUDE. E. Dillon.

THE ARTS OF JAPAN. E. Dillon.

ENAMELS. Mrs. Nelson Dawson.

MINIATURES. C. Davenport.

CONSTABLE. H. W. Tompkins.

OUR LADY IN ART. Mrs. H. L. Jenner.

## The Little Galleries

*Demy 16mo. 2s. 6d. net.*

Each volume contains 20 plates in Photogravure, together with a short outline of the life and work of the master to whom the book is devoted.

A LITTLE GALLERY OF REYNOLDS.

A LITTLE GALLERY OF ROMNEY.

A LITTLE GALLERY OF HOPFNER.

A LITTLE GALLERY OF MILLENS.

A LITTLE GALLERY OF ENGLISH PORTRAITS.

## The Little Guides

With many Illustrations by E. H. NEW and other artists, and from photographs.

*Small Pott 8vo, cloth, 2s. 6d. net.; leather, 3s. 6d. net.*

The main features of these Guides are (1) a handy and charming form; (2) illustrations from photographs and by well-known artists; (3) good plans and maps; (4) an

adequate but compact presentation of everything that is interesting in the natural features, history, archaeology, and architecture of the town or district treated.

**CAMBRIDGE AND ITS COLLEGES.** By A. Hamilton Thompson. *Second Edition.*

**OXFORD AND ITS COLLEGES.** By J. Wells, M.A. *Eighth Edition.*

**ST. PAUL'S CATHEDRAL.** By George Clinch.

**WESTMINSTER ABBEY.** By G. E. Troutbeck. *Second Edition.*

**THE ENGLISH LAKES.** By F. G. Brabant, M.A.

**THE MALVERN COUNTRY.** By B. C. A. Windle, D.Sc., F.R.S.

**SHAKESPEARE'S COUNTRY.** By B. C. A. Windle, D.Sc., F.R.S. *Third Edition.*

**NORTH WALES.** By A. T. Story.

**BUCKINGHAMSHIRE.** By E. S. Roscoe.

**CHESHIRE.** By W. M. Gallichan.

**CORNWALL.** By A. L. Salmon.

**DERBYSHIRE.** By J. Charles Cox, LL.D., F.S.A.

**DEVON.** By S. Baring-Gould.

**DORSET.** By Frank R. Heath. *Second Ed.*

**HAMPSHIRE.** By J. C. Cox, LL.D., F.S.A.

**HERTFORDSHIRE.** By H. W. Tompkins, F.R.H.S.

**THE ISLE OF WIGHT.** By G. Clinch.

**KENT.** By G. Clinch.

**KERRY.** By C. P. Crane.

**MIDDLESEX.** By John B. Firth.

**NORFOLK.** By W. A. Dutt.

**NORTHAMPTONSHIRE.** By Wakeling Dry

**OXFORDSHIRE.** By F. G. Brabant, M.A.

**SOMERSET.** By G. W. and J. H. Wade.

**SUFFOLK.** By W. A. Dutt.

**SURREY.** By F. A. H. Lambert.

**SUSSEX.** By F. G. Brabant, M.A. *Second Edition.*

**THE EAST RIDING OF YORKSHIRE.** By J. E.

Morris.

**THE NORTH RIDING OF YORKSHIRE.** By J. E.

Morris.

**BRITTANY.** By S. Baring-Gould.

**NORMANDY.** By C. Scudamore.

**ROME.** By C. G. Ellaby.

**SICILY.** By F. Hamilton Jackson.

## The Little Library

With Introductions, Notes, and Photogravure Frontispieces.

*Small Pott 8vo. Each Volume, cloth, 1s. 6d. net; leather, 2s. 6d. net.*

**anon.** A LITTLE BOOK OF ENGLISH LYRICS.

**Austen (Jane).** PRIDE AND PREJUDICE. Edited by E. V. Lucas. *Two Vols.*

**NORTHANGER ABBEY.** Edited by E. V. Lucas.

**Bacon (Francis).** THE ESSAYS OF LORD BACON. Edited by EDWARD WRIGHT.

**Barham (R. H.).** THE INGOLDSBY LEGENDS. Edited by J. B. ATLAY. *Two Volumes.*

**Barnett (Mrs. P. A.).** A LITTLE BOOK OF ENGLISH PROSE. *Second Edition.*

**Beckford (William).** THE HISTORY OF THE CALIPH VATHEK. Edited by E. DENISON ROSS.

**Blake (William).** SELECTIONS FROM WILLIAM BLAKE. Edited by M. PERUGINI.

**Borrow (George).** LAVENGRO. Edited by F. HINDE'S GROOMF. *Two Volumes.*

**THE ROMANY RYE.** Edited by JOHN SAMPTON.

**Browning (Robert).** SELECTIONS FROM THE EARLY POEMS OF ROBERT BROWNING. Edited by W. HELL GRIFFIN, M.A.

**Canning (George).** SELECTIONS FROM THE ANTI-JACOBIN: with GEORGE CANNING'S additional Poems. Edited by LLOYD SANDERS.

**Cowley (Abraham).** THE ESSAYS OF ABRAHAM COWLEY. Edited by H. C. MINCHIN.

**Crabbe (George).** SELECTIONS FROM GEORGE CRABBE. Edited by A. C. DEANE.

**Craik (Mrs.).** JOHN HALIFAX, GENTLEMAN. Edited by ANNIE MATHESON. *Two Volumes.*

**Crashaw (Richard).** THE ENGLISH POEMS OF RICHARD CRASHAW. Edited by EDWARD HULTON.

**Dante (Alighieri).** THE INFERNO OF DANTE. Translated by H. F. CARY. Edited by PAGET TOYNBEE, M.A., D.Litt.

**THE PURGATORIO OF DANTE.** Translated by H. F. CARY. Edited by PAGET TOYNBEE, M.A., D.Litt.

**THE PARADISO OF DANTE.** Translated by H. F. CARY. Edited by PAGET TOYNBEE, M.A., D.Litt.

**Darley (George).** SELECTIONS FROM THE POEMS OF GEORGE DARLEY. Edited by R. A. STREATHFIELD.

**Deane (A. C.).** A LITTLE BOOK OF LIGHT VERSE.

**Dickens (Charles).** CHRISTMAS BOOKS. *Two Volumes.*

**Ferrier (Susan).** MARRIAGE. Edited by A. GOODRICH-FREER and LORD IDDESLEIGH. *Two Volumes.*

**THE INHERITANCE.** *Two Volumes.*

**Gaskell (Mrs.).** CRANFORD. Edited by E. V. Lucas. *Second Edition.*

**Hawthorne (Nathaniel).** THE SCARLET LETTER. Edited by PERCY DRAEMER.

**Henderson (T. F.).** A LITTLE BOOK OF SCOTTISH VERSE.

**Kents (John).** POEMS. With an Introduction by L. BRYNON, and Notes by J. MASEFIELD.

**Kinglake (A. W.).** EOTHEN. With an Introduction and Notes. *Second Edition.*

[Continued.]

## THE LITTLE LIBRARY—continued.

- Lamb (Charles).** ELIA, AND THE LAST ESSAYS OF ELIA. Edited by E. V. LUCAS.
- Locker (F.).** LONDON LYRICS. Edited by A. D. GODLEY, M.A. A reprint of the First Edition.
- Longfellow (H. W.).** SELECTIONS FROM LONGFELLOW. Edited by L. M. FAITHFULL.
- Marvell (Andrew).** THE POEMS OF ANDREW MARVELL. Edited by E. WRIGHT.
- Milton (John).** THE MINOR POEMS OF JOHN MILTON. Edited by H. C. BEECHING, M.A., Canon of Westminster.
- Moir (D. M.).** MANSIE WAUCH. Edited by T. F. HENDERSON.
- Nichols (J. B. B.).** A LITTLE BOOK OF ENGLISH SONNETS.
- Rochevoucauld (La).** THE MAXIMS OF LA ROCHEVOUCAULD. Translated by Dean STANHOPE. Edited by G. H. POWELL.
- Smith (Horace and James).** REJECTED ADDRESSES. Edited by A. D. GODLEY, M.A.
- Sterne (Laurence).** A SENTIMENTAL JOURNEY. Edited by H. W. PAUL.

- Tennyson (Alfred, Lord).** THE EARLY POEMS OF ALFRED, LORD TENNYSON. Edited by J. CHURTON COLLINS, M.A.
- IN MEMORIAM.** Edited by Canon H. C. BEECHING, M.A.
- THE PRINCESS.** Edited by ELIZABETH WORDSWORTH.
- MAUD.** Edited by ELIZABETH WORDSWORTH.
- Thackeray (W. M.).** VANITY FAIR. Edited by S. GWYNN. *Three Volumes.*
- PENDENNIS.** Edited by S. GWYNN. *Three Volumes.*
- ESMOND.** Edited by S. GWYNN.
- CHRISTMAS BOOKS.** Edited by S. GWYNN.
- Vaughan (Henry).** THE POEMS OF HENRY VAUGHAN. Edited by EDWARD HUTTON.
- Walton (Izaak).** THE COMPLETE ANGLER. Edited by J. BUCHAN.
- Waterhouse (Elizabeth).** A LITTLE BOOK OF LIFE AND DEATH. Edited by *Eleventh Edition.*
- Wordsworth (W.).** SELECTIONS FROM WORDSWORTH. Edited by NOWELL C. SMITH.
- Wordsworth (W.) and Coleridge (S. T.).** LYRICAL BALLADS. Edited by GEORGE SAMPSON.

## The Little Quarto Shakespeare

Edited by W. J. CRAIG. With Introductions and Notes

*Poll 16mo. In 40 Volumes. Leather, price 1s. net each volume.*

*Mahogany Revolving Book Case. 10s. net.*

## Miniature Library

Reprints in miniature of a few interesting books which have qualities of humanity, devotion, or literary genius.

- EUPHRANOR: A Dialogue on Youth.** By Edward FitzGerald. From the edition published by W. Pickering in 1851. *Demy 32mo. Leather, 2s. net.*
- OLONIUS: or Wise Saws and Modern Instances.** By Edward FitzGerald. From the edition published by W. Pickering in 1852. *Demy 32mo. Leather, 2s. net.*
- THE RUBAIYAT OF OMAR KHAYYAM.** By Edward FitzGerald. From the 1st edition of 1859, *Fourth Edition. Leather, 1s. net.*

- THE LIFE OF EDWARD, LORD HERBERT OF CHERBURY.** Written by himself. From the edition printed at Strawberry Hill in the year 1764. *Demy 32mo. Leather, 2s. net.*
- THE VISIONS OF DOM FRANCISCO QUEVEDO VILLEGAS, Knight of the Order of St. James.** Made English by R. L. From the edition printed for H. Herringman, 1668. *Leather, 2s. net.*
- POEMS.** By Dora Greenwell. From the edition of 1848. *Leather, 2s. net.*

## Oxford Biographies

*Fcap. 8vo. Each volume, cloth, 2s. 6d. net; leather, 3s. 6d. net.*

- DANTE ALIGHIERI.** By Paget Toynbee, M.A., D.Lit. With 12 Illustrations. *Third Edition.*
- GIROLAMO SAVONAROLA.** By E. L. S. Horsburgh, M.A. With 12 Illustrations. *Second Edition.*
- JOHN HOWARD.** By E. C. S. Gibson, D.D., Bishop of Gloucester. With 12 Illustrations.
- ALFRED TENNYSON.** By A. C. BENSON, M.A. With 9 Illustrations. *Second Edition.*
- SIR WALTER RALEIGH.** By I. A. Taylor. With 12 Illustrations.
- ERASMUS.** By E. F. H. Capey. With 12 Illustrations.
- THE YOUNG PRETENDER.** By C. S. Terry. With 12 Illustrations.

- ROBERT BURNS.** By T. F. Henderson. With 12 Illustrations.
- CHATHAM.** By A. S. M'Dowall. With 12 Illustrations.
- FRANCIS OF ASSISI.** By Anna M. Stodart. With 16 Illustrations.
- CANNING.** By W. Alison Phillips. With 12 Illustrations.
- BEACONSFIELD.** By Walter Sichel. With 12 Illustrations.
- JOHANN WOLFGANG GOETHE.** By H. G. Atkins. With 16 Illustrations.
- FRANÇOIS FENELON.** By Viscount St Cyres. With 12 Illustrations.

**School Examination Series**

Edited by A. M. M. STEDMAN, M.A. *Cr. 8vo. 2s. 6d.*

**FRENCH EXAMINATION PAPERS.** By A. M. M. Stedman, M.A. *Fourteenth Edition.*  
Key. *Sixth Edition. 6s. net.*  
**LATIN EXAMINATION PAPERS.** By A. M. M. Stedman, M.A. *Fourteenth Edition.*  
Key. *Sixth Edition. 6s. net.*  
**GREEK EXAMINATION PAPERS.** By A. M. M. Stedman, M.A. *Ninth Edition.*  
Key. *Fourth Edition. 6s. net.*  
**GERMAN EXAMINATION PAPERS.** By R. J. Morich. *Seventh Edition.*  
Key. *Third Edition. 6s. net.*

**HISTORY AND GEOGRAPHY EXAMINATION PAPERS.** By C. H. Spence, M.A. *Third Edition.*  
**PHYSICS EXAMINATION PAPERS.** By R. E. Steel, M.A., F.C.S.  
**GENERAL KNOWLEDGE EXAMINATION PAPERS.** By A. M. M. Stedman, M.A. *Sixth Edition.*  
Key. *Fourth Edition. 7s. net.*  
**EXAMINATION PAPERS IN ENGLISH HISTORY.** By J. Tail Plowden-Wardlaw, B.A.

**School Histories**

*Illustrated. Crown 8vo. 1s. 6d.*

**A SCHOOL HISTORY OF WARWICKSHIRE.** By B. C. A. Windle, D.Sc., F.R.S.  
**A SCHOOL HISTORY OF SOMERSET.** By Walter Raymond. *Second Edition.*  
**A SCHOOL HISTORY OF LANCASHIRE.** By W. E. Rhodes.

**A SCHOOL HISTORY OF SURREY.** By H. E. Malden, M.A.  
**A SCHOOL HISTORY OF MIDDLESEX.** By V. Plarr and F. W. Walton.

**Methuen's Simplified French Texts**

Edited by T. R. N. CROFTS, M.A.

*One Shilling each.*

**L'HISTOIRE D'UNE TULIPE.** Adapted by T. R. N. Crofts, M.A. *Second Edition.*  
**ABDALLAH.** Adapted by J. A. Wilson.  
**LE DOCTEUR MAIRIEUX.** Adapted by W. P. Fuller.  
**LA BOUILLIE AU MIR.** Adapted by P. H. Ingham.  
**JEAN VALJEAN.** Adapted by F. W. M. Draper.

**LA CHANSON DE ROIAND.** Adapted by H. Rieu, M.A. *Second Edition.*  
**MÉMOIRES DE CADICHON.** Adapted by J. F. Rhoades.  
**L'EQUIPAGE DE LA BELLE-NIVERNAISE.** Adapted by T. R. N. Crofts.  
**L'HISTOIRE DE PIERRE ET CAMILLE.** Adapted by J. B. Patterson.

**Methuen's Standard Library**

*Cloth, 1s. net; double volumes, 1s. 6d. net.*

*Paper, 6d. net; double volume, 1s. net.*

**THE MEDITATIONS OF MARCUS AURELIUS.** Translated by R. Graves.  
**SENSE AND SENSIBILITY.** Jane Austen.  
**ESSAYS AND COUNSELS and THE NEW ATLANTIS.** Francis Bacon, Lord Verulam.  
**RELIGIO MEDICI and URN BURIAL.** Sir Thomas Browne. The text collated by A. R. Waller.  
**THE PILGRIM'S PROGRESS.** John Bunyan.  
**REFLECTIONS ON THE FRENCH REVOLUTION.** Edmund Burke.  
**THE POEMS AND SONGS OF ROBERT BURNS.** Double Volume.  
**THE ANALOGY OF RELIGION, NATURAL AND REVEALED.** Joseph Butler.  
**MISCELLANEOUS POEMS.** T. CHATTERTON.  
**TOM JONES.** Henry Fielding. Treble Vol.  
**CRANFORD.** Mrs. Gaskell.  
**THE HISTORY OF THE DECLINE AND FALL OF THE ROMAN EMPIRE.** E. Gibbon. Text and Notes revised by J. B. Bury. Seven double volumes.  
**THE CASE IS ALTERED. EVERY MAN IN HIS HUMOUR. EVERY MAN OUT OF HIS HUMOUR.** Ben Jonson.

**THE POEMS AND PLAYS OF OLIVER GOLDSMITH.**  
**CYNTHIA'S REVELS.** POETASTER. Ben Jonson.  
**THE POEMS OF JOHN KEATS.** Double volume. The Text has been collated by E. de Selincourt.  
**ON THE IMITATION OF CHRIST.** By Thomas à Kempis. Translation by C. Bigg.  
**A SERIOUS CALL TO A DEVOUT AND HOLY LIFE.** W. Law.  
**PARADISE LOST.** John Milton.  
**EIKONOKLASTES and THE TENURE OF KING- AND MAGISTRATES.** John Milton.  
**UTOPIA and POEMS.** Sir Thomas More.  
**THE REPUBLIC OF PLATO.** Translated by Sydenham and Taylor. Double Volume. Translation revised by W. H. D. Rouse.  
**THE LITTLE FLOWERS OF ST. FRANCIS.** Translated by W. Heywood.  
**THE WORKS OF WILLIAM SHAKESPEARE.** In 10 volumes.  
**PRINCIPAL POEMS, 1815-1818.** Percy Bysshe Shelley. With an Introduction by C. D. Locock.  
**THE LIFE OF NELSON.** Robert Southey.  
**THE NATURAL HISTORY AND ANTIQUITIES OF SELBORNE.** Gilbert White.

## Textbooks of Science

Edited by G. F. GOODCHILD, M.A., B.Sc., and G. R. MILLS, M.A.

*Fully Illustrated.*

- PRACTICAL MECHANICS. S. H. Wells. *Fourth Edition.* Cr. 8vo. 3s. 6d.  
 PRACTICAL CHEMISTRY. Part I. W. French, M.A. Cr. 8vo. *Fourth Edition.* 1s. 6d.  
 PRACTICAL CHEMISTRY. Part II. W. French and T. H. Boardman. Cr. 8vo. 1s. 6d.  
 EXAMPLES IN PHYSICS. By C. E. Jackson, B.A. Cr. 8vo. 2s. 6d.  
 TECHNICAL ARITHMETIC AND GEOMETRY. By C. T. Millis, M.I.M.E. Cr. 8vo. 3s. 6d.  
 PLANT LIFE, Studies in Garden and School. By Horace F. Jones, F.C.S. With 320 Diagrams. Cr. 8vo. 3s. 6d.  
 THE COMPLETE SCHOOL CHEMISTRY. By F. M. Oldham, B.A. With 126 Illustrations. Cr. 8vo. 4s. 6d.  
 ELEMENTARY SCIENCE FOR PUPIL TEACHERS. PHYSICS SECTION. By W. T. Clough, A.R.C.S. (Lond.), F.C.S. CHEMISTRY SECTION. By A. E. Dunstan, B.Sc. (Lond.), F.C.S. With 2 Plates and 10 Diagrams. Cr. 8vo. 2s.  
 EXAMPLES IN ELEMENTARY MECHANICS, Practical, Graphical, and Theoretical. By W. J. Dobbs, M.A. With 51 Diagrams. Cr. 8vo. 5s.  
 OUTLINES OF PHYSICAL CHEMISTRY. By George Senter, B.Sc. (Lond.), Ph.D. With many Diagrams. Cr. 8vo. 3s. 6d.  
 AN ORGANIC CHEMISTRY FOR SCHOOLS AND TECHNICAL INSTITUTES. By A. E. Dunstan, B.Sc. (Lond.), F.C.S. With many Illustrations. Cr. 8vo. 2s. 6d.  
 FIRST YEAR PHYSICS. By C. E. Jackson, M.A. With 51 diagrams. Cr. 8vo. 1s. 6d.

## Textbooks of Technology

Edited by G. F. GOODCHILD, M.A., B.Sc., and G. R. MILLS, M.A.

*Fully Illustrated.*

- HOW TO MAKE A DRESS. By J. A. E. Wood. *Fourth Edition.* Cr. 8vo. 1s. 6d.  
 CARPENTRY AND JOINERY. By F. C. Webb. *Fifth Edition.* Cr. 8vo. 3s. 6d.  
 MILLINERY, THEORETICAL AND PRACTICAL. By Clare Hill. *Fourth Edition.* Cr. 8vo. 2s.  
 INSTRUCTION IN COOKERY. A. P. THOMSON. 2s. 6d.  
 AN INTRODUCTION TO THE STUDY OF TEXTILE DESIGN. By Aldred F. Barker. Demy 8vo. 7s. 6d.  
 BUILDERS' QUANTITIES. By H. C. Grubb. Cr. 8vo. 4s. 6d.  
 RÉPOUSSE METAL WORK. By A. C. Hor... Cr. 8vo. 2s. 6d.  
 ELECTRIC LIGHT AND POWER: An Introduction to the Study of Electrical Engineering. By K. E. Brooks, B.Sc. (Lond.) and W. H. N. James, A.R.C.S., A.I.E.E. Cr. 8vo. 4s. 6d.  
 ENGINEERING WORKSHOP PRACTICE. By C. C. Allen. Cr. 8vo. 3s. 6d.

## Handbooks of Theology

- THE XXXIX. ARTICLES OF THE CHURCH OF ENGLAND. Edited by E. C. S. Gibson, D.D. *Sixth Edition.* Demy 8vo. 12s. 6d.  
 AN INTRODUCTION TO THE HISTORY OF RELIGION. By F. B. Jevons, M.A., Litt.D. *Fourth Edition.* Demy 8vo. 10s. 6d.  
 THE DOCTRINE OF THE INCARNATION. By R. L. Ottley, D.D. *Fourth Edition revised.* Demy 8vo. 12s. 6d.  
 AN INTRODUCTION TO THE HISTORY OF THE CREEDS. By A. E. Burn, D.D. Demy 8vo. 10s. 6d.  
 THE PHILOSOPHY OF RELIGION IN ENGLAND AND AMERICA. By Alfred Caldecott, D.D. Demy 8vo. 10s. 6d.  
 A HISTORY OF EARLY CHRISTIAN DOCTRINE. By J. F. Bethune-Baker, M.A. Demy 8vo. 10s. 6d.

## The Westminster Commentaries

General Editor, WALTER LOCK, D.D., Warden of Keble College, Dean Ireland's Professor of Exegesis in the University of Oxford.

- THE BOOK OF GENESIS. Edited with Introduction and Notes by S. R. Driver, D.D. *Sixth Edition.* Demy 8vo. 10s. 6d.  
 THE BOOK OF JOB. Edited by E. C. S. Gibson, D.D. *Second Edition.* Demy 8vo. 6s.  
 THE ACTS OF THE APOSTLES. Edited by R. B. Rackham, M.A. Demy 8vo. *Third Edition.* 10s. 6d.  
 THE FIRST EPISTLE OF PAUL THE APOSTLE TO THE CORINTHIANS. Edited by I. L. Goudge, M.A. Demy 8vo. 6s.  
 THE EPISTLE OF ST. JAMES. Edited with Introduction and Notes by R. J. Knowling, D.D. Demy 8vo. 6s.  
 THE BOOK OF EZEKIEL. Edited by I. A. Redpath, M.A., D Litt. Demy 8vo. 10s. 6d.  
 A COMMENTARY ON EXODUS. By A. H. M'Neill, B.D. With a Map and 3 Plans. Demy 8vo. 10s. 6d.

## PART II.—FICTION

- Albanesi (E. Maria).** SUSANNAH AND ONE OTHER. *Fourth Edition.* Cr. 8vo. 6s.
- THE BLUNDER OF AN INNOCENT.** *Second Edition.* Cr. 8vo. 6s.
- CAPRICIOUS CAROLINE.** *Second Edition.* Cr. 8vo. 6s.
- LOVE AND LOUISA.** *Second Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- PETER, A PARASITE.** Cr. 8vo. 6s.
- THE BROWN EYES OF MARY.** *Third Edition.* Cr. 8vo. 6s.
- I KNOW A MAIDEN.** *Third Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- Austen (Jane).** PRIDE AND PREJUDICE. *Medium 8vo.* 6d.
- Bagot (Richard).** A ROMAN MYSTERY. *Third Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- THE PASSPORT.** *Fourth Edition.* Cr. 8vo. 6s.
- TEMPTATION.** *Fifth Edition.* Cr. 8vo. 6s.
- LOVE'S PROXY.** *A New Edition.* Cr. 8vo. 6s.
- BANNA DIANA.** *Second Edition.* Cr. 8vo. 6s.
- CASTING OF NETS.** *Twelfth Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- Balfour (Andrew).** BY STROKE OF SWORD. *Medium 8vo.* 6d.
- Baring-Gould (S.).** ARMINELL. *Fifth Edition.* Cr. 8vo. 6s.
- URITH.** *Fifth Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- IN THE ROAR OF THE SEA.** *Seventh Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- MARGERY OF QUETHER.** *Third Edition.* Cr. 8vo. 6s.
- THE QUEEN OF LOVE.** *Fifth Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- JACQUETTA.** *Third Edition.* Cr. 8vo. 6s.
- KITTY ALONE.** *Fifth Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- NOEMI.** *Illustrated.* *Fourth Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- THE BROOM-SQUIRE.** *Illustrated.* *Fifth Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- DARTMOOR JEWELS.** Cr. 8vo. 6s.
- THE PENNYCOMEQUICKS.** *Third Edition.* Cr. 8vo. 6s.
- GUAVAS THE TINNER.** *Illustrated.* *Second Edition.* Cr. 8vo. 6s.
- BLADYS OF THE STEWPONEY.** *Illustrated.* *Second Edition.* Cr. 8vo. 6s.
- PABO THE PRIEST.** Cr. 8vo. 6s.
- WINEFRED.** *Illustrated.* *Second Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- ROYAL GEORGIE.** *Illustrated.* Cr. 8vo. 6s.
- CHRIS OF ALL SORTS.** Cr. 8vo. 6s.
- IN DEWISLAND.** *Second Ed.* Cr. 8vo. 6s.
- THE FROBISHERS.** *Crown 8vo.* 6s.
- Also *Medium 8vo.* 6d.
- DOMITIA.** *Illus.* *Second Ed.* Cr. 8vo. 6s.
- MRS. CURGENVEN OF CURGENVEN.** *Crown 8vo.* 6s.
- LITTLE TUPPENNY.** *A New Edition.* *Medium 8vo.* 6d.
- FURZE BLOOM.** *Medium 8vo.* 6d.
- Barnett (Edith A.).** A WILDERNESS WINNER. *Second Edition.* Cr. 8vo. 6s.
- Barr (James).** LAUGHING THROUGH A WILDERNESS. Cr. 8vo. 6s.
- Barr (Robert).** IN THE MIDST OF ALARMS. *Third Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- THE COUNTESS TEKLA.** *Fourth Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- THE MUTABLE MANY.** *Third Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- THE TEMPESTUOUS PETTICOAT.** *Illustrated.* *Third Edition.* Cr. 8vo. 6s.
- THE STRONG ARM.** *Second Edition.* Cr. 8vo. 6s.
- JENNIE BAXTER JOURNALIST.** *Medium 8vo.* 6d.
- Begbie (Harold).** THE CURIOUS AND DIVERTING ADVENTURES OF SIR JOHN SPARROW; or, THE PROGRESS OF AN OPEN MIND. With a Frontispiece. *Second Edition.* Cr. 8vo. 6s.
- Bellloc (Hilaire), M.P.** FEMANUEL BURDEN, MERCHANT. With 36 Illustrations by G. K. CHESTERTON. *Second Ed.* Cr. 8vo. 6s.
- Benson (E. F.).** DODO: A DETAIL OF THE DAY. *Fifteenth Edition.* Cr. 8vo. 6s. Also *Medium 8vo.* 6d.
- THE VINTAGE.** *Medium 8vo.* 6d.
- Benson (Margaret).** SUBJECT TO VANITY. Cr. 8vo. 3s. 6d.
- Birmingham (George A.).** THE BAD TIMES. *Second Edition.* *Crown 8vo.* 6s.
- Bowles (G. Stewart).** A GUN-ROOM DITTY BOX. *Second Ed.* Cr. 8vo. 1s. 6d.
- Bretherton (Ralph Harold).** THE MILL. Cr. 8vo. 6s.
- Brontë (Charlotte).** SHIRLEY. *Medium 8vo.* 6d.
- Burke (Barbara).** BARBARA GOES TO OXFORD. With 16 Illustrations. *Third Edition.* Cr. 8vo. 6s.
- Burton (J. Bloundelle).** ACROSS THE SALT SEAS. *Medium 8vo.* 6d.
- Caffyn (Mrs.) ('Iota').** ANNE MAULVERER. *Medium 8vo.* 6d.
- Campbell (Mrs. Vere).** FERRISBY. *Second Edition.* Cr. 8vo. 6s.



- Capes (Bernard).** THE EXTRAORDINARY CONFESSIONS OF DIANA PLEASE. *Third Edition.* Cr. 8vo. 6s.  
**A JAY OF ITALY.** *Fourth Ed.* Cr. 8vo. 6s.  
**LOAVES AND FISHES.** *Second Edition.* Cr. 8vo. 6s.  
**A ROGUE'S TRAGEDY.** *Second Edition.* Cr. 8vo. 6s.  
**THE GREAT SKENE MYSTERY.** *Second Edition.* Cr. 8vo. 6s.  
**THE LAKE OF WINE.** Medium 8vo. 6d.  
**Carey (Wymond).** LOVE THE JUDGE. *Second Edition.* Cr. 8vo. 6s.  
**Castle (Agnes and Egerton).** FLOWER O' THE ORANGE, and Other Tales. With a Frontispiece in Colour by A. H. Buckland. *Third Edition.* Cr. 8vo. 6s.  
**Charlton (Randal).** M A V E. *Second Edition.* Cr. 8vo. 6s.  
**THE VIRGIN WIDOW.** Cr. 8vo. 6s.  
**Chesney (Weatherby).** THE TRAGEDY OF THE GREAT EMERALD Cr. 8vo. 6s.  
**THE MYSTERY OF A BUNGALOW.** *Second Edition.* Cr. 8vo. 6s.  
**Clifford (Mrs. W. K.).** THE GETTING WELL OF DOROTHY. Illustrated by GORDON BROWNE. *Second Edition.* Cr. 8vo. 7s. 6d.  
**A FLASH OF SUMMER.** Medium 8vo. 6d.  
**MRS. KEITH'S CRIME.** Medium 8vo. 6d.  
**Conrad (Joseph).** THE SECRET AGENT: A Simple Tale. *Fourth Ed.* Cr. 8vo. 6s.  
**Corbett (Julian).** A BUSINESS IN GREAT WATERS. Medium 8vo. 6d.  
**Corelli (Marie).** A ROMANCE OF TWO WORLDS. *Twenty-Ninth Ed.* Cr. 8vo. 6s.  
**VENDETTA.** *Twenty-Sixth Ed.* Cr. 8vo. 6s.  
**THELMA.** *Thirty-Eighth Ed.* Cr. 8vo. 6s.  
**ARDATH: THE STORY OF A DEAD SELF.** *Eighteenth Edition.* Cr. 8vo. 6s.  
**THE SOUL OF LILITH.** *Fifteenth Edition.* Cr. 8vo. 6s.  
**WORMWOOD.** *Sixteenth Ed.* Cr. 8vo. 6s.  
**BARABBAS: A DREAM OF THE WORLD'S TRAGEDY.** *Forty-Third Edition.* Cr. 8vo. 6s.  
**THE SORROWS OF SATAN.** *Fifty-Fourth Edition.* Cr. 8vo. 6s.  
**THE MASTER CHRISTIAN.** *Eleventh Edition.* 174th Thousand. Cr. 8vo. 6s.  
**TEMPORAL POWER: A STUDY IN SUPREMACY.** 150th Thousand. Cr. 8vo. 6s.  
**GOD'S GOOD MAN: A SIMPLE LOVE STORY.** *Thirteenth Edition.* 150th Thousand. Cr. 8vo. 6s.  
**THE MIGHTY ATOM.** *Twenty-seventh Edition.* Cr. 8vo. 6s.  
**BOY: a Sketch.** *Tenth Edition.* Cr. 8vo. 6s.  
**CAMEOS.** *Thirteenth Edition.* Cr. 8vo. 6s.  
**Cotes (Mrs. Everard).** See Sara Jeannette Duncan.  
**Cotterell (Constance).** THE VIRGIN AND THE SCALES. Illustrated. *Second Edition.* Cr. 8vo. 6s.  
**Crockett (S. R.).** Author of 'The Raiders,' etc. LOCHINVAR. Illustrated. *Third Edition.* Cr. 8vo. 6s.  
**THE STANDARD BEARER.** Cr. 8vo. 6s.  
**Croker (B. M.).** THE OLD CANTONMENT. Cr. 8vo. 6s.  
**JOHANNA.** *Second Edition.* Cr. 8vo. 6s.  
**Also Medium 8vo. 6d.**  
**THE HAPPY VALLEY.** *Fourth Edition.* Cr. 8vo. 6s.  
**A NINE DAYS' WONDER.** *Third Edition.* Cr. 8vo. 6s.  
**PEGGY OF THE BARTONS.** *Seventh Ed.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**ANGEL.** *Fourth Edition.* Cr. 8vo. 6s.  
**Also Medium 8vo. 6d.**  
**A STATE SECRET.** *Third Edition.* Cr. 8vo. 7s. 6d. Also Medium 8vo. 6d.  
**Crosbie (Mary).** DISCIPLES. *Second Ed.* Cr. 8vo. 6s.  
**Cuthell (Edith E.).** ONLY A GUARD. ROOM DOOR. Illustrated by W. PARKINSON. Crown 8vo. 7s. 6d.  
**Dawson (Warrington).** THE SCAR. *Second Edition.* Cr. 8vo. 6s.  
**THE SCOURGE.** Cr. 8vo. 6s.  
**Deakin (Dorothea).** THE YOUNG COLUMBINE. With a Frontispiece by LEWIS BAUMER. Cr. 8vo. 6s.  
**Deane (Mary).** THE OTHER PAWN. Cr. 8vo. 6s.  
**Doyle (A. Conan).** ROUND THE RED LAMP. *Tenth Edition.* Cr. 8vo. 6s.  
**Also Medium 8vo. 6d.**  
**Dumas (Alexandre).** See page 39.  
**Duncan (Sara Jeannette) (Mrs. Everard).** THOSE DELIGHTFUL AMERICANS. Medium 8vo. 6d.  
**A VOYAGE OF CONSOLATION.** Illustrated. *Third Edition.* Cr. 8vo. 6s.  
**Also Medium 8vo. 6d.**  
**Eliot (George).** THE MILL ON THE FLOSS. Medium 8vo. 6d.  
**Erskine (Mrs. Stewart).** THE MAGIC PLUMES. Cr. 8vo. 6s.  
**Fenn (G. Manville).** SYD BEITON; or, The Boy who would not go to Sea. Illustrated by GORDON BROWNE. *Second Ed.* Cr. 8vo. 7s. 6d.  
**Findlater (J. H.).** THE GREEN GRAVES OF BALGOWRIE. *Fifth Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**THE LADDER TO THE STARS.** *Second Edition.* Cr. 8vo. 6s.  
**Findlater (Mary).** A NARROW WAY. *Third Edition.* Cr. 8vo. 6s.  
**OVER THE HILLS.** Cr. 8vo. 6s.  
**THE ROSE OF JOY.** *Third Edition.* Cr. 8vo. 6s.  
**A BLIND BIRD'S NEST.** With 8 Illustrations. *Second Edition.* Cr. 8vo. 6s.  
**Fitzpatrick (K.).** THE WE'NS AT ROWALLAN. Illustrated. *Second Edition.* Cr. 8vo. 6s.  
**Francis (M. E.). (Mrs. Francis Blundell).** STEPPING WESTWARD. *Second Edition.* Cr. 8vo. 6s.  
**MARGERY O' THE MILL.** *Third Edition.* Cr. 8vo. 6s.  
**Fraser (Mrs. Hugh).** THE SLAKING OF THE SWORD. *Second Edition.* Cr. 8vo. 6s.

- IN THE SHADOW OF THE LORD.** *Third Edition. Crown 8vo. 6s.*  
**Fry (B. and C.B.). A MOTHER'S SON.** *Fifth Edition. Cr. 8vo. 6s.*  
**Fuller-Maitland (Ells). BLANCHE ESMEAD.** *Second Edition. Cr. 8vo. 6s.*  
**Gallon (Tom). RICKERBY'S FOLLY.** *Medium 8vo. 6d.*  
**Gaskell (Mrs.). CRANFORD.** *Medium 8vo. 6d.*  
**MARY BARTON.** *Medium 8vo. 6d.*  
**NORTH AND SOUTH.** *Medium 8vo. 6d.*  
**Gates (Eleanor). THE PLOW-WOMAN.** *Cr. 8vo. 6s.*  
**Gerard (Dorothea). HOLY MATRIMONY.** *Medium 8vo. 6d.*  
**MADE OF MONEY.** *Cr. 8vo. 6s.*  
**Also Medium 8vo. 6d.  
**THE IMPROBABLE IDYL.** *Third Edition. Cr. 8vo. 6s.*  
**THE BRIDGE OF LIFE.** *Cr. 8vo. 6s.*  
**THE CONQUEST OF LONDON.** *Medium 8vo. 6d.*  
**Gissing (George). THE TOWN TRAVELLER.** *Second Edition. Cr. 8vo. 6s.*  
**Also Medium 8vo. 6d.  
**THE CROWN OF LIFE.** *Cr. 8vo. 6s.*  
**Also Medium 8vo. 6d.  
**Glasville (Ernest). THE INCA'S TREASURE.** *Illustrated. Cr. 8vo. 3s. 6d.*  
**Also Medium 8vo. 6d.  
**THE KLOOF BRIDE.** *Illustrated. Cr. 8vo. 3s. 6d.*  
**Also Medium 8vo. 6d.  
**Gleig (Charles). BUNTER'S CRUISE.** *Illustrated. Cr. 8vo. 3s. 6d.*  
**Also Medium 8vo. 6d.  
**Grimm (The Brothers). GRIMM'S FAIRY TALES.** *Illustrated. Medium 8vo. 6d.*  
**Hamilton (M.). THE FIRST CLAIM.** *Second Edition. Cr. 8vo. 6s.*  
**Harraden (Beatrice). IN VARYING MOODS.** *Fourteenth Edition. Cr. 8vo. 6s.*  
**THE SCHOLAR'S DAUGHTER.** *Fourth Edition. Cr. 8vo. 6s.*  
**HILDA STRAFFORD and THE REMITTANCE MAN.** *Twelfth Ed. Cr. 8vo. 6s.*  
**Harrod (F.) (Frances Forbes Robertson). THE TAMING OF THE BRUTE.** *Cr. 8vo. 6s.*  
**Herbertson (Agnes G.). PATIENCE DEAN.** *Cr. 8vo. 6s.*  
**Hichens (Robert). THE PROPHET OF HERKELEY SQUARE.** *Second Edition. Cr. 8vo. 6s.*  
**TONGUES OF CONSCIENCE.** *Third Edition. Cr. 8vo. 6s.*  
**FELIX.** *Sixth Edition. Cr. 8vo. 6s.*  
**THE WOMAN WITH THE FAN.** *Sixth Edition. Cr. 8vo. 6s.*  
**BYEWAYS.** *Cr. 8vo. 6s.*  
**THE GARDEN OF ALLAH.** *Seventeenth Edition. Cr. 8vo. 6s.*  
**THE BLACK SPANIEL.** *Cr. 8vo. 6s.*  
**THE CALL OF THE BLOOD.** *Seventh Edition. Cr. 8vo. 6s.*  
**Hope (Anthony). THE GOD IN THE CAR.** *Tenth Edition. Cr. 8vo. 6s.*************
- A CHANGE OF AIR.** *Sixth Ed. Cr. 8vo. 6s.*  
**Also Medium 8vo. 6d.  
**A MAN OF MARK.** *Fifth Ed. Cr. 8vo. 6s.*  
**Also Medium 8vo. 6d.  
**THE CHRONICLES OF COUNT ANTONIO.** *Sixth Edition. Cr. 8vo. 6s.*  
**Also Medium 8vo. 6d.  
**PHROSO.** *Illustrated by H. R. MILLAR. Seventh Edition. Cr. 8vo. 6s.*  
**Also Medium 8vo. 6d.  
**SIMON DALE.** *Illustrated. Eighth Edition. Cr. 8vo. 6s.*  
**THE KING'S MIRROR.** *Fourth Edition. Cr. 8vo. 6s.*  
**QUISANTE.** *Fourth Edition. Cr. 8vo. 6s.*  
**THE DOLLY DIALOGUES.** *Cr. 8vo. 6s.*  
**Also Medium 8vo. 6d.  
**A SERVANT OF THE PUBLIC.** *Illustrated. Fourth Edition. Cr. 8vo. 6s.*  
**TALES OF TWO PEOPLE.** *With a Frontispiece by A. H. BUCKLAND. Third Ed. Cr. 8vo. 6s.*  
**Hope (Graham). THE LADY OF LYTE.** *Second Edition. Cr. 8vo. 6s.*  
**Hornung (E. W.). DEAD MEN TELL NO TALES.** *Medium 8vo. 6d.*  
**Housman (Clemence). THE LIFE OF SIR AGLOVALE DE GALIS.** *Cr. 8vo. 6s.*  
**Hueffer (Ford Madox). AN ENGLISH GIRL: A ROMANCE.** *Second Edition. Cr. 8vo. 6s.*  
**Hutten (Baroness von). THE HALO.** *Fifth Edition. Cr. 8vo. 6s.*  
**Hyne (C. J. Cutcliffe). MR. HORROCKS, PURSER.** *Fourth Edition. Cr. 8vo. 6s.*  
**PRINCE RUPERT, THE BUCCANEER.** *Illustrated. Third Edition. Cr. 8vo. 6s.*  
**Ingraham (J. H.). THE THRONE OF DAVID.** *Medium 8vo. 6d.*  
**Jacobs (W. W.). MANY CARGOES.** *Thirtieth Edition. Cr. 8vo. 3s. 6d.*  
**SEA URCHINS.** *Fifteenth Edition. Cr. 8vo. 3s. 6d.*  
**A MASTER OF CRAFT.** *Illustrated by WILL OWEN. Eighth Edition. Cr. 8vo. 3s. 6d.*  
**LIGHT FREIGHTS.** *Illustrated by WILL OWEN and Others. Seventh Edition. Cr. 8vo. 3s. 6d.*  
**THE SKIPPER'S WOOING.** *Ninth Edition. Cr. 8vo. 3s. 6d.*  
**AT SUNWICH PORT.** *Illustrated by WILL OWEN. Ninth Edition. Cr. 8vo. 3s. 6d.*  
**DIALSTONE LANE.** *Illustrated by WILL OWEN. Seventh Edition. Cr. 8vo. 3s. 6d.*  
**ODD CRAFT.** *Illustrated by WILL OWEN. Seventh Edition. Cr. 8vo. 3s. 6d.*  
**THE LADY OF THE BARGE.** *Eighth Edition. Cr. 8vo. 3s. 6d.*  
**James (Henry). THE SOFT SIDE.** *Second Edition. Cr. 8vo. 6s.*  
**THE BETTER SORT.** *Cr. 8vo. 6s.*  
**THE AMBASSADORS.** *Second Edition. Cr. 8vo. 6s.*  
**THE GOLDEN BOWL.** *Third Edition. Cr. 8vo. 6s.*  
**Keays (H. A. Mitchell). HE THAT EATETH BREAD WITH ME.** *Cr. 8vo. 6s.***********

- Kester (Vaughan).** THE FORTUNES OF THE LANDRAYS. Illustrated. *Cr. 8vo. 6s.*  
**Lawless (Hon. Emily).** WITH ESSEX IN IRELAND. *Cr. 8vo. 6s.*  
**Le Queux (William).** THE HUNCHBACK OF WESTMINSTER. *Third Ed. Cr. 8vo. 6s.*  
 Also *Medium 8vo. 6d.*  
**THE CROOKED WAY.** *Second Edition. Cr. 8vo. 6s.*  
**THE CLOSED BOOK.** *Third Ed. Cr. 8vo. 6s.*  
**THE VALLEY OF THE SHADOW.** Illustrated. *Third Edition. Cr. 8vo. 6s.*  
**BEHIND THE THRONE.** *Third Edition. Cr. 8vo. 6s.*  
**Levett-Yeats (S. K.).** ORRAIN. *Second Edition. Cr. 8vo. 6s.*  
**THE TRAITOR'S WAY.** *Medium 8vo. 6d.*  
**Linton (E. Lynn).** THE TRUE HISTORY OF JOSHUA DAVIDSON. *Medium 8vo. 6d.*  
**London (Jack).** WHITE FANG. With a Frontispiece by CHARLES RIVINGTON BULL. *Sixth Edition. Cr. 8vo. 6s.*  
**Lucas (E. V.).** LISTENER'S LURE: An Oblique Narration. *Fourth Edition. Cr. 8vo. 6s.*  
**Lyall (Edna).** DERRICK VAUGHAN, NOVELIST. *42nd Thousand. Cr. 8vo. 3s. 6d.* Also *Medium 8vo. 6d.*  
**Maartens (Maarten).** THE NEW RELIGION: A MODERN NOVEL. *Third Edition. Cr. 8vo. 6s.*  
**M'Carthy (Justin H.).** THE LADY OF LOYALTY HOUSE. Illustrated. *Third Edition. Cr. 8vo. 6s.*  
**THE DRYAD.** *Second Edition. Cr. 8vo. 6s.*  
**THE DUKE'S MOTTO.** *Third Edition. Cr. 8vo. 6s.*  
**Macdonald (Ronald).** A HUMAN TRINITY. *Second Edition. Cr. 8vo. 6s.*  
**Macnaughtan (S.).** THE FORTUNE OF CHRISTINA M'NAB. *Fourth Edition. Cr. 8vo. 6s.*  
**Malet (Lucas).** COLONEL ENDERBY'S WIFE. *Fourth Edition. Cr. 8vo. 6s.*  
**A COUNSEL OF PERFECTION.** *New Edition. Cr. 8vo. 6s.*  
 Also *Medium 8vo. 6d.*  
**THE WAGES OF SIN.** *Fifteenth Edition. Cr. 8vo. 6s.*  
**THE CARISSIMA.** *Fifth Ed. Cr. 8vo. 6s.*  
 Also *Medium 8vo. 6d.*  
**THE GATELESS BARRIER.** *Fifth Edition. Cr. 8vo. 6s.*  
**THE HISTORY OF SIR RICHARD CALMADY.** *Seventh Edition. Cr. 8vo. 6s.*  
**Mann (Mrs. M. E.).** OLIVIA'S SUMMER. *Second Edition. Cr. 8vo. 6s.*  
**A LOST ESTATE.** *A New Ed. Cr. 8vo. 6s.*  
 Also *Medium 8vo. 6d.*  
**THE PARISH OF HILBY.** *A New Edition. Cr. 8vo. 6s.*  
**THE PARISH NURSE.** *Fourth Edition. Cr. 8vo. 6s.*  
**GRANMA'S JANE.** *Cr. 8vo. 6s.*  
**MRS. PETER HOWARD.** *Cr. 8vo. 6s.*  
 Also *Medium 8vo. 6d.*
- A WINTER'S TALE.** *A New Edition. Cr. 8vo. 6s.*  
**ONE ANOTHER'S BURDENS.** *A New Edition. Cr. 8vo. 6s.*  
 Also *Medium 8vo. 6d.*  
**ROSE AT HONEYPOT.** *Third Ed. Cr. 8vo. 6s.*  
**THERE WAS ONCE A PRINCE.** Illustrated by M. B. MANN. *Cr. 8vo. 3s. 6d.*  
**WHEN ARNOLD COMES HOME.** Illustrated by M. B. MANN. *Cr. 8vo. 3s. 6d.*  
**THE EGLAMORE PORTRAITS.** *Third Edition. Cr. 8vo. 6s.*  
**THE MEMORIES OF RONALD LOVE.** *Cr. 8vo. 6s.*  
**THE SHEEP AND THE GOATS.** *Third Edition. Cr. 8vo. 6s.*  
**A SHEAF OF CORN.** *Second Edition. Cr. 8vo. 6s.*  
**THE CEDAR STAR.** *Medium 8vo. 6d.*  
**Marchmont (A. W.).** MISER HOADLEY'S SECRET. *Medium 8vo. 6d.*  
**A MOMENT'S ERROR.** *Medium 8vo. 6d.*  
**Marriott (Charles).** GENEVRA. *Second Edition. Cr. 8vo. 6s.*  
**Marryat (Captain).** PETER SIMPLE. *Medium 8vo. 6d.*  
**JACOB FAITHFUL.** *Medium 8vo. 6d.*  
**Marsh (Richard).** THE TWICKENHAM PEERAGE. *Second Edition. Cr. 8vo. 6s.*  
 Also *Medium 8vo. 6d.*  
**THE MARQUIS OF PUTNEY.** *Second Edition. Cr. 8vo. 6s.*  
**IN THE SERVICE OF LOVE.** *Third Edition. Cr. 8vo. 6s.*  
**THE GIRL AND THE MIRACLE.** *Third Edition. Cr. 8vo. 6s.*  
**THE COWARD BEHIND THE CURTAIN.** *Cr. 8vo. 6s.*  
**A METAMORPHOSIS.** *Medium 8vo. 6d.*  
**THE GODDESS.** *Medium 8vo. 6d.*  
**THE JOSS.** *Medium 8vo. 6d.*  
**Marshall (Archibald).** MANY JUNES. *Second Edition. Cr. 8vo. 6s.*  
**Mason (A. E. W.).** CLEMENTINA. Illustrated. *Second Edition. Cr. 8vo. 6s.*  
 Also *Medium 8vo. 6d.*  
**Mathers (Helen).** HONEY. *Fourth Ed. Cr. 8vo. 6s.* Also *Medium 8vo. 6d.*  
**GRIFF OF GRIFFITHSCOURT.** *Cr. 8vo. 6s.* Also *Medium 8vo. 6d.*  
**THE FERRYMAN.** *Second Edition. Cr. 8vo. 6s.*  
**TALLY-HO!** *Fourth Edition. Cr. 8vo. 6s.*  
**SAM'S SWEETHEART.** *Medium 8vo. 6d.*  
**Maxwell (W. B.).** VIVIEN. *Ninth Edition. Cr. 8vo. 6s.*  
**THE RAGGED MESSLENGER.** *Third Edition. Cr. 8vo. 6s.*  
**FARULOUS FANCIES.** *Cr. 8vo. 6s.*  
**THE GUARDED FLAME.** *Seventh Edition. Cr. 8vo. 6s.*  
**ODD LENGTHS.** *Second Ed. Cr. 8vo. 6s.*  
**THE COUNTESS OF MAYBURY: BETWEEN YOU AND I.** Being the Intimate Conversations of the Right Hon. the Countess of Maybury. *Fourth Edition. Cr. 8vo. 6s.*

**Mende (L. T.).** DRIFT. *Second Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**RESURGAM.** Cr. 8vo. 6s.  
**VICTORY.** Cr. 8vo. 6s.  
**A GIRL OF THE PEOPLE.** Illustrated by R. BARNET. *Second Ed.* Cr. 8vo. 3s. 6d.  
**HEPSY GIPSY.** Illustrated by E. HOPKINS. Crown 8vo. 2s. 6d.  
**THE HONOURABLE MISS: A STORY OF AN OLD-FASHIONED TOWN.** Illustrated by E. HOPKINS. *Second Edition.* Crown 8vo. 3s. 6d.  
**Melton (R.).** CÆSAR'S WIFE. *Second Edition.* Cr. 8vo. 6s.  
**Meredith (Ellis).** HEART OF MY HEART. Cr. 8vo. 6s.  
**Miller (Esther).** LIVING LIES. *Third Edition.* Cr. 8vo. 6s.  
**Mitford (Bertram).** THE SIGN OF THE SPIDER. Illustrated. *Sixth Edition.* Cr. 8vo. 3s. 6d. Also Medium 8vo. 6d.  
**IN THE WHIRL OF THE RISING.** *Third Edition.* Cr. 8vo. 6s.  
**THE RED DERELICT.** *Second Edition.* Cr. 8vo. 6s.  
**Molesworth (Mrs.).** THE RED GRANGE. Illustrated by GORDON BROWN. *Second Edition.* Cr. 8vo. 3s. 6d.  
**Montgomery (K. L.).** COLONEL KATE. *Third Edition.* Cr. 8vo. 6s.  
**Montresor (F. F.).** THE ALIEN. *Third Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**Morrison (Arthur).** TALES OF MEAN STREETS. *Seventh Edition.* Cr. 8vo. 6s.  
**A CHILD OF THE JAGO.** *Fifth Edition.* Cr. 8vo. 6s.  
**CUNNING MURRELL.** Cr. 8vo. 6s.  
**THE HOLE IN THE WALL.** *Fourth Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**DIVERS VANITIES.** Cr. 8vo. 6s.  
**Nesbit (E.).** (Mrs. H. Bland). THE RED HOUSE. Illustrated. *Fourth Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**Norris (W. E.).** HARRY AND URSULA: A STORY WITH TWO SIDES TO IT. *Second Edition.* Cr. 8vo. 6s.  
**HIS GRACE.** Medium 8vo. 6d.  
**GILES INGILBY.** Medium 8vo. 6d.  
**THE CREDIT OF THE COUNTY.** Medium 8vo. 6d.  
**LORD LEONARD THE LUCKLESS.** Medium 8vo. 6d.  
**MATTHEW AUSTIN.** Medium 8vo. 6d.  
**CLARISSA FURIOSA.** Medium 8vo. 6d.  
**Oliphant (Mrs.).** THE LADY'S WALK. Medium 8vo. 6d.  
**SIR ROBERT'S FORTUNE.** Medium 8vo. 6d.  
**THE PRODIGALS.** Medium 8vo. 6d.  
**THE TWO MARYS.** Medium 8vo. 6d.  
**Ollivant (Alfred).** OLD BOB, THE GREY DOG OF KENMUIR. With a Frontispiece. *Eleventh Edition.* Cr. 8vo. 6s.  
**Oppenheim (E. Phillips).** MASTER OF MEN. *Fourth Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.

**Oxenham (John).** A WEAVER OF WEBS. With 8 Illustrations by MAURICE GREIF-FENHAGEN. *Second Edition.* Cr. 8vo. 6s.  
**THE GATE OF THE DESERT.** With a Frontispiece in Photogravure by HAROLD COPPING. *Fifth Edition.* Cr. 8vo. 6s.  
**PROFIT AND LOSS.** With a Frontispiece in photogravure by HAROLD COPPING. *Fourth Edition.* Cr. 8vo. 6s.  
**THE LONG ROAD.** With a Frontispiece in Photogravure by HAROLD COPPING. *Fourth Edition.* Cr. 8vo. 6s.  
**Pain (Barry).** LINDLEY KAYS. *Third Edition.* Cr. 8vo. 6s.  
**Parker (Gilbert).** PIERRE AND HIS PEOPLE. *Sixth Edition.* Cr. 8vo. 6s.  
**MRS. FALCHION.** *Fifth Edition.* Cr. 8vo. 6s.  
**THE TRANSLATION OF A SAVAGE.** *Third Edition.* Cr. 8vo. 6s.  
**THE TRAIL OF THE SWORD.** Illustrated. *Ninth Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**WHEN VALMOND CAME TO PONTIAC:** The Story of a Lost Napoleon. *Sixth Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**AN ADVENTURER OF THE NORTH.** The Last Adventures of 'Pretty Pierre.' *Fourth Edition.* Cr. 8vo. 6s.  
**THE SEATS OF THE MIGHTY.** Illustrated. *Sixteenth Edition.* Cr. 8vo. 6s.  
**THE BATTLE OF THE STRONG:** a Romance of Two Kingdoms. Illustrated. *Sixth Edition.* Cr. 8vo. 6s.  
**THE POMP OF THE LAVIETTES.** *Third Edition.* Cr. 8vo. 3s. 6d. Also Medium 8vo. 6d.  
**Pemberton (Max).** THE FOOTSTEPS OF A THRONE. Illustrated. *Third Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**I CROWN THEE KING.** With Illustrations by Frank Dadd and A. Forrestier. Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**Phillipotts (Eden).** LYING PROPHETS. *Third Edition.* Cr. 8vo. 6s.  
**CHILDREN OF THE MIST.** *Fifth Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**THE HUMAN BOY.** With a Frontispiece. *Sixth Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**SONS OF THE MORNING.** *Second Edition.* Cr. 8vo. 6s.  
**THE RIVER.** *Third Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.  
**THE AMERICAN PRISONER.** *Fourth Edition.* Cr. 8vo. 6s.  
**THE SECRET WOMAN.** *Fourth Edition.* Cr. 8vo. 6s.  
**KNOCK AT A VENTURE.** With a Frontispiece. *Third Edition.* Cr. 8vo. 6s.  
**THE PORTREEVE.** *Fourth Ed.* Cr. 8vo. 6s.  
**THE POACHER'S WIFE.** *Second Edition.* Cr. 8vo. 6s. Also Medium 8vo. 6d.

- THE STRIKING HOURS.** *Second Edition.*  
*Crown 8vo. 6s.*  
**THE FOLK AFIELD.** *Crown 8vo. 6s.*  
**Pickthall (Marmaduke).** **SAID THE FISHERMAN.** *Seventh Ed. Cr. 8vo. 6s.*  
**BRENDLE.** *Second Edition. Cr. 8vo. 6s.*  
**THE HOUSE OF ISLAM.** *Third Edition. Cr. 8vo. 6s.*  
**'Q' (A. T. Quiller Couch).** **THE WHITE WOLF.** *Second Edition. Cr. 8vo. 6s.*  
*Also Medium 8vo. 6d.*  
**THE MAYOR OF TROY.** *Fourth Edition. Cr. 8vo. 6s.*  
**MERRY GARDEN AND OTHER STORIES.** *Cr. 8vo. 6s.*  
**MAJOR VIGOUREUX.** *Third Edition. Cr. 8vo. 6s.*  
**Rawson (Maud Stepany).** **THE ENCHANTED GARDEN.** *Fourth Edition. Cr. 8vo. 6s.*  
**Rhys (Grace).** **THE WOOING OF SHEILA.** *Second Edition. Cr. 8vo. 6s.*  
**Ridge (W. Pett).** **LOST PROPERTY.** *Medium 8vo. 6d.*  
**ERB.** *Second Edition. Cr. 8vo. 6s.*  
**A SON OF THE STATE.** *Second Edition. Cr. 8vo. 3s. 6d. Also Medium 8vo. 6d.*  
**A BREAKER OF LAWS.** *A New Edition. Cr. 8vo. 3s. 6d.*  
**MRS. GALER'S BUSINESS.** *Illustrated. Second Edition. Cr. 8vo. 6s.*  
**THE WICKHAMSES.** *Fourth Edition. Cr. 8vo. 6s.*  
**NAME OF GARLAND.** *Third Edition. Cr. 8vo. 6s.*  
**GEORGE and THE GENERAL.** *Medium 8vo. 6d.*  
**Ritchie (Mrs. David G.).** **MAN AND THE CASSOCK.** *Second Edition. Crown 8vo. 6s.*  
**Roberts (C. G. D.).** **THE HEART OF THE ANCIENT WOOD.** *Cr. 8vo. 3s. 6d.*  
**Robins (Elizabeth).** **THE CONVERT.** *Third Edition. Cr. 8vo. 6s.*  
**Rosenkrantz (Baron Palle).** **THE MAGISTRATE'S OWN CASE.** *Cr. 8vo. 6s.*  
**Russell (W. Clark).** **MY DANISH SWEETHEART.** *Illustrated. Fifth Edition. Cr. 8vo. 6s.*  
*Also Medium 8vo. 6d.*  
**THIS ISLAND PRINCESS.** *Illustrated. Second Edition. Cr. 8vo. 6s.*  
*Also Medium 8vo. 6d.*  
**ABANDONED.** *Second Edition. Cr. 8vo. 6s.*  
*Also Medium 8vo. 6d.*  
**MR ROCKAFELLAR'S VOYAGE.** *Edited by GORDON BROWNE. Third Edition. Cr. 8vo. 3s. 6d.*  
**MARRIAGE AT SEA.** *Medium 8vo. 6d.*  
**Mr (Marah Ellis).** **FOR THE SOUL OF RAFAEL.** *Cr. 8vo. 6s.*  
**Sergeant (Adeline).** **THE MYSTERY OF THE MOAT.** *Second Edition. Cr. 8vo. 6s.*
- THE PASSION OF PAUL MARILIER.** *Crown 8vo. 6s.*  
**THE QUEST OF GEOFFREY DARRELL.** *Cr. 8vo. 6s.*  
**THE COMING OF THE RANDOLPHS.** *Cr. 8vo. 6s.*  
**THE PROGRESS OF RACHAEL.** *Cr. 8vo. 6s.*  
**BARBARA'S MONEY.** *Cr. 8vo. 6s.*  
*Also Medium 8vo. 6d.*  
**THE MASTER OF BEECHWOOD.** *Medium 8vo. 6d.*  
**THE YELLOW DIAMOND.** *Second Ed. Cr. 8vo. 6s. Also Medium 8vo. 6d.*  
**THE LOVE THAT OVERCAME.** *Medium 8vo. 6d.*  
**Shannon (W. F.).** **THE MESS DECK.** *Cr. 8vo. 3s. 6d.*  
**Shelley (Bertha).** **ENDERBY.** *Third Ed. Cr. 8vo. 6s.*  
**Sidgwick (Mrs. Alfred).** **THE KINSMAN.** *With 8 Illustrations by C. E. Brock. Third Edition. Cr. 8vo. 6s.*  
**Smith (Dorothy V. Horace).** **MISS MONA.** *Cr. 8vo. 3s. 6d.*  
**Sonnichsen (Albert).** **DEEP-SEA VAGABONDS.** *Cr. 8vo. 6s.*  
**Sunbury (George).** **THE HA'PENNY MILLIONAIRE.** *Cr. 8vo. 3s. 6d.*  
**Surtees (R. S.).** **HANDLEY CROSS.** *Illustrated. Medium 8vo. 6d.*  
**MR. SPONGE'S SPORTING TOUR.** *Illustrated. Medium 8vo. 6d.*  
**ASK MAMMA.** *Illus. Medium 8vo. 6d.*  
**Urquhart (M.).** **A TRAGEDY IN COMMONPLACE.** *Second Ed. Cr. 8vo. 6s.*  
**Vorst (Marie Van).** **THE SENTIMENTAL ADVENTURES OF JIMMY BULSTRODE.** *Cr. 8vo. 6s.*  
**Waineman (Paul).** **THE BAY OF LILACS;** *A Romance from Finland. Second Edition. Cr. 8vo. 6s.*  
**THE SONG OF THE FOREST.** *Cr. 8vo. 6s.*  
**Walford (Mrs. L. B.).** **MR. SMITH.** *Medium 8vo. 6d.*  
**THE BABY'S GRANDMOTHER.** *Medium 8vo. 6d.*  
**COUSINS.** *Medium 8vo. 6d.*  
**Wallace (General Lew).** **BEN-HUR.** *Medium 8vo. 6s.*  
**THE FAIR GOD.** *Medium 8vo. 6d.*  
**Watson (H. B. Marriott).** **CAPTAIN FORTUNE.** *Third Edition. Cr. 8vo. 6s.*  
**TWISTED EGLANTINE.** *With 8 Illustrations by FRANK CRAIG. Third Edition. Cr. 8vo. 6s.*  
**THE HIGH TOBY;** *Being further Chapters in the Life and Fortunes of Dick Ryder, otherwise Galloping Dick, sometime Gentleman of the Road. With a Frontispiece by CLAUDE SHEPPERTON. Third Edition. Cr. 8vo. 6s.*  
**A MIDSUMMER DAY'S DREAM.** *Third Edition. Crown 8vo. 6s.*

**THE PRIVATEERS.** With 8 Illustrations by CYRUS CUNEO. *Second Edition.* Cr. 8vo. 6s.  
**A POPPY SHOW: BEING DIVERS AND DIVERSE TALES.** Cr. 8vo. 6s.  
**THE ADVENTURERS.** *Medium 8vo.* 6d.  
**Weekes (A. B.). THE PRISONERS OF WAR.** *Medium 8vo.* 6d.  
**Wells (H. G.). THE SEA LADY.** Cr. 8vo. 6s. Also *Medium 8vo.* 6d.  
**Weyman (Stanley). UNDER THE RED ROBE.** With Illustrations by R. C. WOOD VILLE. *Twenty-First Edition.* Cr. 8vo. 6s.  
**White (Percy). THE SYSTEM.** *Third Edition.* Cr. 8vo. 6s.  
**A PASSIONATE PILGRIM.** *Medium 8vo.* 6d.  
**Williams (Margery). THE BAR.** Cr. 8vo. 6s.  
**Williamson (Mrs. C. N.). THE ADVENTURE OF PRINCESS SYLVIA.** *Second Edition.* Cr. 8vo. 6s.  
**THE WOMAN WHO DARED.** Cr. 8vo. 6s.  
**THE SEA COULD TELL.** *Second Edition.* Cr. 8vo. 6s.  
**THE CASTLE OF THE SHADOWS.** *Third Edition.* Cr. 8vo. 6s.

**PAPA.** Cr. 8vo. 6s.  
**Williamson (C. N. and A. M.). THE LIGHTNING CONDUCTOR: The Strange Adventures of a Motor Car.** With 16 Illustrations. *Seventeenth Edition.* Cr. 8vo. 6s.  
**THE PRINCESS PASSES: A Romance of a Motor.** With 16 Illustrations. *Ninth Edition.* Cr. 8vo. 6s.  
**MY FRIEND THE CHAUFFEUR.** With 16 Illustrations. *Ninth Edit.* Cr. 8vo. 6s.  
**LADY BETTY ACROSS THE WATER.** *Tenth Edition.* Cr. 8vo. 6s.  
**THE CAR OF DESTINY AND ITS ERRAND IN SPAIN.** With 17 Illustrations. *Fourth Edition.* Cr. 8vo. 6s.  
**THE BOTOR CHAPERON.** With a Frontispiece in Colour by A. H. BUCKLAND, 16 other Illustrations, and a Map. *Fifth Edition.* Cr. 8vo. 6s.  
**SCARLET RUNNER.** With a Frontispiece in Colour by A. H. BUCKLAND, and 8 other Illustrations. *Third Ed.* Cr. 8vo. 6s.  
**Wyllarde (Dolf). THE PATHWAY OF THE PIONEER (Nous Autres).** *Fourth Edition.* Cr. 8vo. 6s.  
**Yeldham (C. C.). DURHAM'S FARM.** Cr. 8vo. 6s.

### Books for Boys and Girls

*Illustrated. Crown 8vo. 3s. 6d.*

**THE GETTING WELL OF DOROTHY.** By Mrs. W. K. Clifford. *Second Edition.*  
**ONLY A GUARD-ROOM DOG.** By Edith F. Cuthell.  
**MASTER ROCKAFELLAR'S VOYAGE.** By W. Clark Russell. *Third Edition.*  
**SYD BELTON: Or, the Boy who would not go to Sea.** By G. Manville Penn. *Second Ed.*

**THE RED GRANGE.** By Mrs. Molesworth.  
**A GIRL OF THE PEOPLE.** By L. T. Meade. *Second Edition.*  
**HAPPY GIPSY.** By L. T. Meade. *2s. 6d.*  
**THE HONOURABLE MISS.** By L. T. Meade. *Second Edition.*  
**THERE WAS ONCE A PRINCE.** By Mrs. M. E. Mann.  
**WHEN ARNOLD COMES HOME.** By Mrs. M. E. Mann.

### The Novels of Alexandre Dumas

*Medium 8vo. Price 6d. Double Volumes, 1s.*

COMPLETE LIST ON APPLICATION.

### Methuen's Sixpenny Books

*Medium 8vo.*

**Albanesi (E. Maria). LOVE AND LOUISA.**  
**I KNOW A MAIDEN.**  
**Austen (J.). PRIDE AND PREJUDICE.**  
**Bagot (Richard). A ROMAN MYSTERY.**  
**CASTING OF NETS.**  
**Balfour (Andrew). BY STROKE OF SWORD.**  
**Baring-Gould (S.). FURZE BLOOM.**  
**CHEAP JACK ZITA.**  
**KITTY ALONE.**  
**URITH.**  
**THE BROOM SQUIRE.**  
**IN THE REAR OF THE SEA.**  
**NOEMI.**  
**A BOOK OF FAIRY TALES.** Illustrated.

**LITTLE TUPPENNY.**  
**WINEFRED.**  
**THE FROBISHERS.**  
**THE QUEEN OF LOVE.**  
**Barr (Robert). JENNIE BAXTER.**  
**IN THE MIDST OF ALARMS.**  
**THE COUNTLESS TEKLA.**  
**THE MUTABLE MANY.**  
**Benson (E. F.). DODO.**  
**THE VINTAGE.**  
**Brontë (Charlotte). SHIRLEY.**  
**Brownell (C. L.). THE HEART OF JAPAN.**  
**Burton (J. Bloundelle). ACROSS THE SALT SEAS.**  
**Caffyn (Mrs.). ANNE MAULEVERER.**

Capes (Bernard). THE LAKE OF WINE.  
 Clitherd (Mrs. W. K.). A FLASH OF SUMMER.  
 MRS. KEITH'S CRIME.  
 Corbett (Julian). A BUSINESS IN GREAT WATERS.  
 Croker (Mrs. B. M.). ANGEL. A STATE SECRET.  
 PEGGY OF THE BARTONS.  
 JOHANNA.  
 Dante (Alighieri). THE DIVINE COMEDY (Cary)  
 Doyle (A. Conan). ROUND THE RED LAMP.  
 Duncan (Sara Jeannette). A VOYAGE OF CONSOLATION.  
 THOSE DELIGHTFUL AMERICANS.  
 Elliot (George). THE MILL ON THE FLOSS.  
 Findlater (Jane H.). THE GREEN GRAVES OF BALGOWRIE.  
 Gallon (Tom). RICKERBY'S FOLLY.  
 Gaskell (Mrs.). CRANFORD.  
 MARY BARTON.  
 NORTH AND SOUTH.  
 Gerard (Dorothea). HOLY MATRIMONY.  
 THE CONQUEST OF LONDON.  
 MADE OF MONEY  
 Gissing (G.). THE TOWN TRAVELLER.  
 THE CROWN OF LIFE.  
 Glanville (Ernest). THE INCA'S TREASURE.  
 THE KLOOF BRIDE.  
 Gleig (Charles). HUNTER'S CRUISE.  
 Grimm (The Brothers). GRIMM'S FAIRY TALES  
 Hope (Anthony). A MAN OF MARK  
 A CHANGE OF AIR  
 THE CHRONICLES OF COUNT ANTONIO.  
 PHROSIO.  
 THE DOLLY DIALOGUES.  
 Hornung (E. W.). DEAD MEN TELL NO TALES.  
 Ingraham (J. H.). THE THRONE OF DAVID.  
 Le Queux (W.). THE HUNCHBACK OF WESTMINSTER.  
 Lovett-Yeats (S. K.). THE TRAITOR'S WAY.  
 Linton (E. Lynn). THE TRUE HISTORY OF JOSHUA DAVIDSON.  
 Lyall (Edna). DERRICK VAUGHAN.  
 Malet (Lucas). THE CARISSIMA.  
 A COUNSEL OF PERFECTION.  
 Mann (Mrs.). MRS. PETER HOWARD.  
 A LOST ESTATE.  
 THE CEDAR STAR.  
 ONE ANOTHER'S BURDENS.  
 Marchmont (A. W.). MISER HOADLEY'S SECRET.  
 A MOMENT'S ERROR.  
 Marryat (Captain). PETER SIMPLE.  
 JACOB FAITHFUL.

Marsh (Richard). A METAMORPHOSIS.  
 THE TWICKENHAM PEERAGE.  
 THE GODDESS.  
 THE JOSS.  
 Mason (A. E. W.). CLEMENTINA.  
 Mathers (Helen). HONEY.  
 GRIFF OF GRIFFITHSCOURT  
 SAM'S SWEETHEART.  
 Meade (Mrs. L. T.). 'DRIFT'.  
 Mitford (Bertram). THE SIGN OF THE SPIDER.  
 Montresor (F. F.). THE ALIEN.  
 Morrison (Arthur). THE HOLE IN THE WALL.  
 Nesbit (E.). THE RED HOUSE.  
 Norris (W. E.). HIS GRACE.  
 GILES INGILBY.  
 THE CREDIT OF THE COUNTY.  
 LORD LEONARD THE LUCKLESS.  
 MATTHEW AUSTIN.  
 CLARISSA FURIOSA.  
 Oliphant (Mrs.). THE LADY'S WALK.  
 SIR ROBERT'S FORTUNE.  
 THE PRODIGALS.  
 THE TWO MARYS.  
 Oppenheim (E. P.). MASTER OF MEN.  
 Parker (Gilbert). THE POMP OF THE LAVIETTES.  
 WHEN VALMOND CAME TO PONTIAC.  
 THE TRAIL OF THE SWORD.  
 Pemberton (Max). THE FOOTSTEPS OF A THRONE.  
 I CROWN THEE KING.  
 Philippotts (Eden). THE HUMAN BOY.  
 CHILDREN OF THE MIST.  
 THE POACHER'S WIFE.  
 THE RIVER.  
 'Q' (A. T. Oulifer Couch). THE WHITE WOLF.  
 Ridge (W. Pett). A SON OF THE STATE.  
 LOST PROPERTY.  
 GEORGE and THE GENERAL.  
 Russell (W. Clark). ABANDONED.  
 A MARRIAGE AT SEA.  
 MY DANISH SWEETHEART.  
 HIS ISLAND PRINCESS.  
 Sergeant (Adeline). THE MASTER OF BEECHWOOD.  
 BARBARA'S MONEY.  
 THE YELLOW DIAMOND.  
 THE LOVE THAT OVERCAME.  
 Surtees (R. S.). HANDLEY CROSS  
 MR. SPONGE'S SPORTING TOUR.  
 ASK MAMMA.  
 Walford (Mrs. L. B.). MR. SMITH.  
 COUSINS.  
 THE BABY'S GRANDMOTHER  
 Wallace (General Lew). BEN-HUR.  
 THE FAIR GOD.  
 Watson (H. B. Marriott). THE ADVENTURERS.  
 Weekes (A. B.). PRISONERS OF WAR.  
 Wells (H. G.). THE SEA LADY.  
 White (Percy). A PASSIONATE PILGRIM.











